SCHEDULE OF FINISHES

SL. NO.	NAME OF ROOM	FLOOR											WALL INT	WALL EXT	SKIRTING					DADO			CEILING		ROOF			SURFACE FINISHES							REMARKS
		75MM THICK PCC M 20 TYPE A1 (NOMINAL MIX) LAID OVER 100 MM THICK PCC M 7.5 TYPE D2 (NOMINAL MIX) LAID OVER 100 MM THICK HARD CORE OVER APPROVED WELL RAMMED EARTH FILLING. FINISHED WITH A COAT OF CURING COMPOUND AND PROVIDED WITH TRANSVERSE SMOOTH SURFACE OF VACUUM DEWATERING METHOD WITH BROOMING.	100 MM THICK PCC M 7.5 TYPE D2 (NOMINAL MIX) LAID OVER 150 MM THICK HARD COVER RAMMED EARTH FILLING.	40 MM THICK PCC M15 TYPE B0 NOMINAL MIX OVER RCC SLABS/BRICK STEPS.	600 x 600 x 8-10 MM VITRIFIED (DOUBLE CHARGED) COLOURED RECTIFIED TILES LAID OVER 15 MM THICK SCREED BED IN CM 1:4 OVER 20 MM THICK PCC M15 TYPE B0 (NOMINAL MIX) OVER 75MM THICK PCC M 7.5 SUB BASE TYPE D2 (NOMINAL MIX) OVER 100 MM THICK HARD CORE OVER APPROVED WELL RAMMED EARTH FILLING.	18-20 MM THICK GREEN MARBLE IN SINGLE PIECE OVER 15MM THICK CM 1:4 FOR TREADS, RISERS AND NOT MORE THAN TWO PIECES IN LANDINGS.	50 MM TH PCC 1:2:4 TYPE B1 FINISH EVEN & SMOOTH OVER RCC SLAB.	600 x 600 x 8-10 MM COLORED DESIGN CERAMIC RECTIFIED TILES LAID OVER 15 MM THICK SCREED BED IN CM 1:4 OVER 22 MM PCC M 15 TYPE B0 (NOMINAL MIX) LAID OVER 75 MM PCC SUB BASE IN M 7.5 TYPE D2 (NOMINAL MIX) LAID OVER 100 MM HARD CORE OVER APPROVED WELL RAMMED EARTH FILLING.	600 x 600 x 8-10 MM DESIGN GLAZED RECTIFIED COLORED CERAMIC TILES LAID OVER 10 MM THICK SCREED BED IN CM 1:4 OVER RCC SLAB.	400 x 400 x 7-8 MM COLORED NON-SKID RECTIFIED CERAMIC TILES LAID OVER 15 MM THICK SCREED BED IN CM 1:4 OVER 22 MM PCC M 15 TYPE B0 (NOMINAL MIX) LAID OVER 75 MM PCC SUB BASE IN M 7.5 TYPE D2 (NOMINAL MIX) LAID OVER 100 MM HARD CORE OVER APPROVED WELL RAMMED EARTH FILLING.	400 x 400 x 7-8 MM COLORED NON-SKID CERAMIC TILES LAID OVER 10 MM THICK SCREED BED IN CM 1:4 LAID OVER RCC SLAB.		RENDERING 10 MM TH IN CM 1:6 ON OVER PCC BLOCK WALLS & CONTIGUOUS CONCRETE SURFACES FINISHED EVEN AND SMOOTH ALL AS SPECIFIED ABOVE SKIRTINGDADO.	RENDERING (15 MM THICK IN TWO LAYERS) ON PCC BLOCK WALLS & CONTIGUOUS CONCRETE SURFACES WITH 2 COATS OF APPROVED WATER PROOFING COMPOUND OVER 10 MM THICK IN CM 1:4 FINISHED EVEN & SMOOTH ALL AS SPECIFIED.	100 MM HIGH, 5 MM THICK SETTING COAT IN CM 1:2 FINISHED FAIR AND EVEN USING EXTRA CEMENT OVER 10 MM THICK IN CM 1:4.	SKIRTING OF 100 MM HIGH COLORED DESIGN CERAMIC TILES 7-8 MM THICK OVER BACKING COAT 10 MM THICK IN CM (1:3).	SKIRTING OF 100 MM HIGH WITH POLISHED GREEN MARBLES OVER BACKING COAT 10MM THICK IN CM 1:3	SKIRTING OF 100 MM HIGH VITRIFIED (DOUBLE CHARGED) TILES 9-10 MM THICK OVER BACKING COAT 10 MM THICK IN CM (1:3).		450 x 300 x 6-7 MM DESIGN RECTIFIED GLAZED CERAMIC TILES OVER 10 MM THICK BACKING COAT IN CM 1:3.						RCC ROOF LAID TO SLOPE WITH APP WATER PROOFING MEMBRANE TREATMENT FOR NON-ACCESSIBLE ROOF ALL AS SPECIFIED AND SHOWN ON DRGS.	RCC ROOF LAID TO SLOPE WITH CHINA MOSAIC TILES LAID OVER SCREED BED OVER APP WATER PROOFING MEMBRANE TREATMENT ON ACCESSIBLE ROOFS ALL AS SPECIFIED AND SHOWN ON DRGS.		EXTERNAL SURFACES WALL/GRAJJA ALL AS SPECIFIED.	INTERNAL SURFACES OF WALL AS SPECIFIED.	ALL CEILING SURFACES ALL AS SPECIFIED.	ALL WOODEN SURFACES ALL AS SPECIFIED.	ALL STEEL SURFACES ALL AS SPECIFIED.			
1	2	3	4	5	6	7	8	9	9a	10	10a	10b	11	12	13	14	15	16	16a	17	17a	17b	18	18a	19	20	20a	21	22	23	24	25	26	27	
	GROUND FLOOR																																		
1.	PARKING FOR JCO'S AND HAV/ORS		X												X													T3	T1	T2	T4	T5			
2.	HARD STANDINGS		X																																
3.	RAMP		X																																
4.	STEPS, ENTRANCE VERANDAH, LOBBY AND PLATFORM					X							X	X			X			X								T3	T1	T2	T4	T5			
5.	STAIR CASE 1 & 2					X							X	X			X											T3	T1	T2	T4	T5			
6	LIFT						X						X	X														T3	T1	T2	T4	T5			
7.	CONNECTING PASSAGE TO CYCLE REPAIR, GROCERY SHOP AND PARKING	X											X	X	X													T3	T1	T2	T4	T5			
8.	CLOTHING STORE	X											X	X	X													T3	T1	T2	T4	T5			
9.	RATION STORE	X											X	X	X													T3	T1	T2	T4	T5			
10.	SPORTS STORE							X					X	X		X												T3	T1	T2	T4	T5			
11.	COMPANY STORE							X					X	X		X												T3	T1	T2	T4	T5			
12	GROCERY SHOP							X					X	X		X												T3	T1	T2	T4	T5			
13	BARBER SHOP							X					X	X		X												T3	T1	T2	T4	T5			
14	TAILOR SHOP							X					X	X		X												T3	T1	T2	T4	T5			
15	FUEL STORE (PART)	X											X	X	X													T3	T1	T2	T4	T5			
16	BOOT MAKER SHOP	X											X	X	X													T3	T1	T2	T4	T5			
17	CYCLE REPAIR	X											X	X	X													T3	T1	T2	T4	T5			
18	PLATFORM, 1500 WIDE PLATFORM					X							X	X			X											T3	T1	T2	T4	T5			
19	CABLE SHAFT	X											X	X														T3	T1		T4	T5			
20	FIRE SHAFT	X											X	X														T3	T1		T4	T5			
21	SHAFT	X											X	X														T3	T1		T4	T5			
22	LANDSCAPE AREA	X											X	X														T3	T1		T4	T5			
23	TOILET FOR DISABLED									X			X	X						X								T3	T1	T2	T4	T5			
24	LADIES TOILET									X			X	X						X								T3	T1	T2	T4	T5			
25	REST ROOM FOR SERVICE STAFF							X					X	X		X												T3	T1	T2	T4	T5			
26	**ARMOURIES AND ARMOURER SHOP**	X											X	X	X													T3	T1	T2	T4	T5			
26a	VERANDAH, STEPS	X											X	X	X													T3	T1	T2	T4	T5			
27	**SUMP CUM PUMP HOUSE** (PUMP HOUSE, RAMP AND PLATFORM)	X											X	X	X													T3	T1	T2	T4	T5			
28	OPEN AND INACCESSIBLE TERRACE FOR ARMOURIES, ARMOURER SHOP & PUMP HOUSE																								X			T3							
	FIRST FLOOR																																		
1	STAIRCASE 1& 2					X							X	X			X											T3	T1	T2	T4	T5			
2	LOBBY							X	X				X	X		X				X								T3	T1	T2	T4	T5			
3	COVERED CONNECTING CORRIDOR							X	X				X	X		X												T3	T1	T2	T4	T5			
4	LIFT												X	X																					
5	COVERED CORRIDOR							X	X				X	X		X												T3	T1	T2	T4	T5			
6	DINING HALL							X	X				X	X		X				X								T3	T1	T2	T4	T5			
7	KITCHEN							X	X				X	X		X				X								T3	T1	T2	T4	T5			
8	SERVERY							X	X				X	X		X				X								T3	T1	T2	T4	T5			
9	PAN WASH						X						X	X						X								T3	T1	T2	T4	T5			
10	MEAT STORE							X	X				X	X		X				X								T3	T1	T2	T4	T5			
11	FRESH STORE							X	X				X	X		X												T3	T1	T2	T4	T5			
12	DRY STORE						X						X	X	X													T3	T1	T2	T4	T5			
13	COOK ROOM							X	X				X	X		X												T3	T1	T2	T4	T5			
14	TOILET										X		X	X						X								T3	T1	T2	T4	T5			
15	CORRIDOR							X	X				X	X		X												T3	T1	T2	T4	T5			
16	WASH AREA							X	X				X	X		X												T3	T1	T2	T4	T5			
17	JCO MESS, CLUB ROOM AND RECREATION & TV ROOM							X	X				X	X		X												T3	T1	T2	T4	T5			
18	CABLE AND FIRE SHAFT												X	X														T3	T1		T4	T5			
19	OPEN AND ACCESSIBLE TERRACE																									X		T3							
20	**JCO'S SINGLE LIVING ACCOMMODATION**																																		
20 a	LIVING ROOM							X					X	X		X												T3	T1	T2	T4	T5			
20 b	BED ROOM							X					X	X		X												T3	T1	T2	T4	T5			
20 c	TOILET										X		X	X						X								T3	T1	T2	T4	T5			
20 d	SHAFT												X	X														T3	T1		T4	T5			

SURFACE FINISHES

T-1	MIN TWO COATS OF ACRYLIC WASHABLE DISTEMPER (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER OVER WHITE CEMENT BASED PUTTY ON WALLS USING SMART PAINTING METHOD.
T-2	MIN TWO COATS OF ACRYLIC WASHABLE DISTEMPER (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON CEILING USING SMART PAINTING METHOD.
T-3	MIN TWO COATS OF WEATHER PROOF EXTERNAL EMULSION PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE. OVER A COAT OF EXTERIOR PRIMER ON WALLS.
T-4	MIN TWO COATS OF SYNTHETIC ENAMEL PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON WOODEN SURFACES.
T-5	MIN TWO COATS OF SYNTHETIC ENAMEL PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON STEEL SURFACES.

UPTO HT 2.4 MTR

NOTE: IN CASE OF LOBBY 18 TO 20MM TH. POLISHED GREEN MARBLE (SINGLE PIECE LENGTH 1.500M TO 2.080M) CLADDING OVER 15MM. TH. BACKING COAT IN CM 1:3 ALROUND LIFT OPENING UPTO SOFFIT OF SLAB / BEAM SHALL BE PROVIDED.

NOTES:-

1. CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS BEFORE EXECUTION OF THE WORK.
2. ALL DIMENSIONS ARE GIVEN IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
3. ALL DRAWINGS OF ARCHITECTURAL,STRUCTURAL,ELECTRICAL AND SANITARY PLUMBING ETC. FORMING PART OF THE CONTRACT SHALL BE READ IN CONNECTION WITH EACH OTHER.ANY DISCREPENCY FOUND TO BE BROUGHT TO THE NOTICE OF SITE ENGINEER BEFORE EXECUTION.

SL NO	DATE	DESCRIPTION	INITIAL

REVISIONS

PROVISION OF DEFICIENT 287 SINGLE INLIVING ACCN ASSOCIATED FACILITIES FOR DSC AT NAVAL DOCKYARD, VISAKHAPATNAM (BD NO AMWP 46/2020)

SCHEDULE OF FINISHES

DATE	11 - 06 - 2022	CHIEF ENGINEER (NAVY) VISAKHAPATNAM ZONE	SHEET NO 14 / 24
DRN	SUVRO		
TCD	—		
CKD			
SCALE	—	REF DRG. NO. CEVZ/2022/WD-2110	

AAD (ARCH)

JT DIR (PLG)

DIR (PLG) FOR CHIEF ENGINEER