SCHEDULE OF FINISHES

SL. NO.	NAME OF ROOM	FLOOR											WALL		SKIRTING					DADO			CEILING		ROOF			SURFACE FINISHES							REMARKS
													INT	EXT																					
		75MM THICK PCC IN 2/3 TYPE A1 (NOMINAL MIX) LAID OVER 100 MM THICK PCC IN 7 & TYPE D2 (NOMINAL MIX) LAID OVER 100 MM THICK HARD CORE RAMMED WELL ON APPROVED WELL RAMMED EARTH FILLING FINISHING OF PCC BY VACUUM DEWATERING METHOD TO MAKE THE SURFACE SMOOTH	100 MM THICK PCC IN 3:7 TYPE B1 (NOMINAL MIX) LAID OVER 100 MM THICK PCC IN 7 & TYPE D2 (NOMINAL MIX) LAID OVER 100 MM THICK HARD COVER RAMMED EARTH FINISHING OF PCC BY VACUUM DEWATERING METHOD TO MAKE THE SURFACE SMOOTH.	40 MM THICK PCC M15 TYPE B6 NOMINAL MIX OVER RCC SLABBRICK STEPS.		18-20 MM THICK GREEN MARBLE OVER 15MM THICK CM 1:4 FOR TREADS, LANDINGS AND RISERS.	50 MM TH PCC 1:2:4 TYPE B1 FINISH EVEN & SMOOTH OVER RCC.	600 x 600 x 8-10 MM DESIGN GLAZED RECTIFIED COLORED CERAMIC TILES LAID OVER 10 MM THICK SCREED BED IN CM 1:4 OVER RCC SLAB.	300 X 600 X 7-8 MM DESIGN GLAZED RECTIFIED COLORED NON-SKID CERAMIC TILES LAID OVER 10 MM THICK SCREED BED IN CM 1:4 OVER RCC SLAB.				RENDERING 10 MM TH IN CM 1:6 ON OVER BRICK WALLS/ CONCRETE SURFACES FINISHED EVEN AND SMOOTH ALL AS SPECIFIED ABOVE SKIRTING/DADO.	RENDERING (15 MM THICK IN TWO LAYERS) ON BRICK WALLS/CONCRETE SURFACES WITH 8 MM THICK IN CM 1:4 USING WATER PROOFING CEMENT OVER 10 MM THICK IN CM 1:3 FINISHED EVEN & SMOOTH ALL AS SPECIFIED.	150 MM HIGH, 6 MM THICK SEETING COAT IN CM 1:2 FINISHED FAIR AND EVEN USING EXTRA CEMENT OVER 10 MM THICK IN CM 1:4.	SKIRTING OF 100 MM HIGH COLORED CERAMIC TILES 7-8 MM THICK OVER BACKING COAT 10 MM THICK IN CM (1:3).	SKIRTING OF 100MM HIGH WITH POLISHED/ GREEN MARBLES OVER BACKING COAT 15MM THICK IN CM 1:3	SKIRTING OF 100 MM HIGH VITRIFIED (DOUBLE CHARGED) TILES 9-10 MM THICK OVER BACKING COAT 10 MM THICK IN CM (1:3).		400 x 300 x 6-7 MM DESIGN GLAZED RECTIFIED GLAZED CERAMIC TILES OVER 10 MM THICK BACKING COAT IN CM 1:3.					RCC ROOF LAID TO SLOPE WITH APP WATER PROOFING MEMBRANE TREATMENT FOR NON-ACCESSIBLE ROOF ALL AS SPECIFIED AND SHOWN ON DRGS.	RCC ROOF LAID TO SLOPE WITH CHINA MOSAIC TILES LAID OVER SCREED BED OVER APP WATER PROOFING MEMBRANE TREATMENT ON ACCESSIBLE ROOF ALL AS SPECIFIED AND SHOWN ON DRGS.		EXTERNAL SURFACES WALL/CHAJJA ALL AS SPECIFIED.	INTERNAL SURFACES OF WALL AS SPECIFIED.	ALL CEILING SURFACES ALL AS SPECIFIED.	ALL WOODEN SURFACES ALL AS SPECIFIED.	ALL STEEL SURFACES ALL AS SPECIFIED.			
1	2	3	4	5	6	7	8	9	10	10a	10b	10c	11	12	13	14	15	16	16a	17	17a	17b	18	18a	19	20	20a	21	22	23	24	25	26	27	
	SECOND FLOOR																																		
1.	STAIR CASE 1 & 2					✕							✕	✕			✕											T3	T1	T2	T4	T5			
2.	LOBBY							✕					✕	✕		✕				✕								T3	T1	T2	T4	T5			
3.	LIFT												✕	✕																					
4.	COVERED CORRIDOR							✕					✕	✕														T3	T1	T2	T4	T5			
5.	COMMON AND STUDY ROOM							✕					✕	✕		✕												T3	T1	T2	T4	T5			
6.	STORE ROOM					✕		✕					✕	✕	✕													T3	T1	T2	T4	T5			
7.	OR INSTITUTE							✕					✕	✕		✕												T3	T1	T2	T4	T5			
8.	TOILET BLOCK -1 & TOILET BLOCK -2								✕				✕	✕						✕								T3	T1	T2	T4	T5			
9.	WC,UR AND WHB								✕				✕	✕						✕								T3	T1	T2	T4	T5			
10.	BATH								✕				✕	✕						✕								T3	T1	T2	T4	T5			
11.	SPACE FOR WATER COOLER								✕				✕	✕						✕								T3	T1	T2	T4	T5			
12	SERVICE BALCONY								✕				✕	✕		✕												T3	T1	T2	T4	T5			
13	CORRIDOR							✕					✕	✕		✕												T3	T1	T2	T4	T5			
14	OPEN AND ACCESSIBLE TERRACE							✕					✕	✕		✕										✕		T3	T1	T2	T4	T5			
15	SERVICE BALCONY								✕				✕	✕		✕																			
16	CABLE SHAFT												✕	✕															T1		T4	T5			
17	FIRE SHAFT												✕	✕															T1		T4	T5			
18	**JCO SINGLE LIVING ACCOMMODATION**																																		
18 a	LIVING ROOM							✕					✕	✕		✕												T3	T1	T2	T4	T5			
18 b	BED ROOM							✕					✕	✕		✕												T3	T1	T2	T4	T5			
18 c	TOILET								✕				✕	✕						✕								T3	T1	T2	T4	T5			
18 d	SHAFT												✕	✕														T3	T1		T4	T5			
	THIRD FLOOR																																		
1.	STAIR CASE 1 & 2					✕							✕	✕			✕											T3	T1	T2	T4	T5			
2.	LOBBY							✕					✕	✕		✕				✕								T3	T1	T2	T4	T5			
3.	LIFT												✕	✕																					
4.	COVERED CORRIDOR							✕					✕	✕		✕												T3	T1	T2	T4	T5			
5.	CORRIDOR							✕					✕	✕		✕												T3	T1	T2	T4	T5			
6	02 HAV							✕					✕	✕		✕												T3	T1	T2	T4	T5			
7.	12 OR AND 06 OR							✕					✕	✕		✕												T3	T1	T2	T4	T5			
8.	TOILET BLOCK -1 & TOILET BLOCK -2								✕				✕	✕						✕								T3	T1	T2	T4	T5			
9.	WC,UR,WHB AND BATH								✕				✕	✕						✕								T3	T1	T2	T4	T5			
10.	SPACE FOR WATER COOLER								✕				✕	✕						✕								T3	T1	T2	T4	T5			
11.	SERVICE BALCONY								✕				✕	✕		✕												T3	T1	T2	T4	T5			
12.	CABLE SHAFT												✕	✕															T1		T4	T5			
13.	FIRE SHAFT												✕	✕															T1		T4	T5			
13λ	OPEN AND INACCESSIBLE TERRACE																									✕									
14	**JCO SINGLE LIVING ACCOMMODATION**																																		
14 a	LIVING ROOM							✕					✕	✕		✕												T3	T1	T2	T4	T5			
14 b	BED ROOM							✕					✕	✕		✕												T3	T1	T2	T4	T5			
14 c	TOILET								✕				✕	✕						✕								T3	T1	T2	T4	T5			
14 d	SHAFT												✕	✕														T3	T1		T4	T5			

SURFACE FINISHES

T-1	MIN TWO COATS OF ACRYLIC WASHABLE DISTEMPER (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER OVER WHITE CEMENT BASED PUTTY ON WALLS USING SMART PAINTING METHOD.
T-2	MIN TWO COATS OF ACRYLIC WASHABLE DISTEMPER (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON CEILING USING SMART PAINTING METHOD.
T-3	MIN TWO COATS OF WEATHER PROOF EXTERNAL EMULSION PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF EXTERIOR PRIMER ON WALLS.
T-4	MIN TWO COATS OF SYNTHETIC ENAMEL PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON WOODEN SURFACES.
T-5	MIN TWO COATS OF SYNTHETIC ENAMEL PAINT (LOW VOC CONTENT) AND LEAD FREE WITH UNIFORM FINISHED SURFACE OVER A COAT OF PRIMER ON STEEL SURFACES.

NOTE: IN CASE OF LOBBY 18 TO 20 MM TH POLISHED GREEN MARBLE (SINGLE PIECE LENGTH 1·5000 M TO 2·000 M) CLADDING OVER 15 MM TH. BACKING COAT IN CM 1:3 ALROUND LIFT OPENING UPTO SOFFIT OF SLAB/BEAM SHALL BE PROVIDED.

NOTES:-

1. CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS BEFORE EXECUTION OF THE WORK.
2. ALL DIMENSIONS ARE GIVEN IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
3. ALL DRAWINGS OF ARCHITECTURAL,STRUCTURAL,ELECTRICAL AND SANITARY PLUMBING ETC. FORMING PART OF THE CONTRACT SHALL BE READ IN CONNECTION WITH EACH OTHER.ANY DISCREPENCY FOUND TO BE BROUGHT TO THE NOTICE OF SITE ENGINEER BEFORE EXECUTION.

SL NO	DATE	DESCRIPTION	INITIAL
		REVISIONS	

PROVISION OF DEFICIENT 287 SINGLE INLIVING ACCN ASSOCIATED FACILITIES FOR DSC AT NAVAL DOCKYARD, VISAKHAPATNAM (BD NO AMWP 46/2020)

SCHEDULE OF FINISHES

DATE	11 - 06 - 2022	CHIEF ENGINEER (NAVY) VISAKHAPATNAM ZONE	SHEET NO 15 / 24
DRN	SUVRO		
TCD	—		
CKD			
SCALE	—	REF DRG. NO. CEVZ/2022/WD-2110	

AAD (ARCH)

JT DIR (PLG)

DIR (PLG) FOR CHIEF ENGINEER