



GROUND FLOOR PLAN

NOTES:-

- CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS BEFORE EXECUTION OF THE WORK.
- FIGURED DIMENSIONS SHALL BE FOLLOWED.
- ALL DIMENSIONS ARE GIVEN IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
- EXECUTIVE AUTHORITY SHALL CHECK THIS DRG BEFORE TAKING EXECUTION IN HAND.
- ALL DRAWINGS OF ARCHITECTURAL, STRUCTURAL, ELECTRICAL AND SANITARY PLUMBING ETC. FORMING PART OF THE CONTRACT SHALL BE READ IN CONNECTION WITH EACH OTHER ANY DISCREPANCY FOUND TO BE BROUGHT TO THE NOTICE OF SITE ENGINEER BEFORE EXECUTION.
- DR - INDICATES ALUMINIUM DRAPERY ROD WITH UPVC COATED OF FOR SAILORS CREW ROOM AND SS DRAPERY ROD WITH STD. BRACKET SHALL BE PROVIDED FOR OFFICERS CREW ROOM AND BRIEFING ROOM.
- FOR LIST OF DRG REFER DRG NO. CEVZ / 2022 / LD-2120, SHEET NO.1/1.
- WALLS BELOW FFL SHALL BE AS PER FDN DETAILS.
- SLOPE OF THE TOILET FLOOR SHALL BE MAINTAINED TOWARDS NT FOR PROPER DRAINAGE.
- WALL SHALL BE OF 200 / 100 PCC BLOCK MASONRY.

- ALL EXTERNAL WALL SHALL BE 200TH AND INTERNAL SHALL BE 100TH IF NOT SHOWN IN THE DRG.
- 100 TH WALL TO REST DIRECTLY ON PCC SUB BASE / RCC SLAB.
- ALL WALLS TO BE TAKEN UPTO SOFFIT OF RCC SLAB / BEAM UNLESS OTHERWISE SPECIFIED.
- ALL WINDOW CILLS SHALL BE PROJECTED OUTSIDE AS PER TYP DETAILS.
- ALL WINDOWS CILL SHALL BE PROVIDED WITH MIN. 20TH POLISHED MARBLE CILL OF SINGLE PIECE INCLUDING 25MM BEARING ON EITHER SIDES. IN CASE OF MORE THAN 1500MM WIDE OPENING NUMBER OF MARBLE CILL PIECE SHALL BE DECIDED BY ENGINEER-IN-CHARGE AT THE TIME OF EXECUTION.
- ALL SANITARY PIPES / RWPS ARE NOT SHOWN IN THE ELEVATIONS / SECTIONS ARE TO BE PROVIDED AS PER DETAIL DRGS.
- CAPACITY OF WATER TANK SHALL BE AS PER SCHEMATIC WATER SUPPLY DRGS.
- IRRESPECTIVE OF WHATEVER SHOWN IN ARCHITECTURAL DRGS ALL STRUCTURAL ELEMENTS SHALL BE FOLLOWED AS PER STRUCTURAL DRGS.
- ALL CHAJJAS HAVE BERING OF 150MM ON BOTH SIDES UNLESS OTHERWISE SPECIFIED.
- WHEREVER REF DIMENSIONS NOT GIVEN IN PLANS FOR WINDOWS AND VENTILATORS OPENINGS SHALL BE PROVIDED IN THE CENTRE OF RESPECTIVE BAY.
- SURFACE OF ALL STAINLESS STEEL MEMBERS SHALL BE SMOOTH, FAIR FINISH.

- GAUGE FOR STAINLESS STEEL MEMBERS SHALL BE NOT LESS THAN 1.6 mm TH.
- SS RAILING TYPE - 1 FOR STAIRCASE REF. (TD NO. CEVZ / 2022 / TD - 20 SHEET NO. 1/2 TO 2/2).
- SS RAILING TYPE - 1 SHALL BE PROVIDED FOR VERANDAH / BALCONY REF. (TD NO. CEVZ / 2022 / TD - 21 SHEET NO. 1/2 TO 2/2).
- FOR ALL ALUMINIUM SLIDING WINDOWS & VENTILATORS REF TD NO CEVZ/2022/TD-13, SHEET NO 1/4 TO 4/4.
- GRC JALI TYPE-M SHALL BE 1092 X 2000 IN LIEU OF 1092 X 2100.
- 02 NOS OF MOTORIZED ROLLING SHUTTERS OF SIZE 6000 X 4000 SHALL BE PROVIDED IN EACH OF AC STOWAGE SPACE FOR OPERATIONALLY READY ADRs AND 02 NOS OF GEAR OPERATED ROLLING SHUTTERS OF SIZE 2500 X 2400 SHALL BE PROVIDED IN AC STOWAGE SPACE FOR STORAGE OF EAT (BANSHEE). DETAILS SHALL BE AS PER MANUFACTURERS INSTRUCTIONS.
- CONVEYORSS ROLLERS SHALL BE PROVIDED IN BOTH THE AC STOWAGE ROOMS AND ADR PACKING AND RIGGING AREA AS SHOWN IN THE PLAN AND DETAILS SHALL BE AS PER MANUFACTURERS INSTRUCTIONS.
- 6MM TH GLASS SHALL BE USED IN ALV IRRESPECTIVE WHATEVER SHOWN IN TD.

PROVN OF HANGAR AND ANNEXE BUILDING
AT INS DEGA VISAKHAPATNAM
HANGAR AND ANNEXE BUILDING
GROUND FLOOR PLAN

DATE	28 FEB 2023	SHEET NO.	1R/13
DRN	S B SAHOO	CHIEF ENGINEER (NAVY)	
TCD		VISAKHAPATNAM ZONE	
CKD			
SCALE	1:100	REF DRG NO : CEVZ / 2022 / WD - 2120	

01. 04-10-23 DRG CORRECTED UPTO DATE.

S.NO.	DATE	DESCRIPTION	INITIAL
		REVISIONS	

AD(ARCH)

JT. DR (ARCH)

DIRECTOR (ARCH)
FOR CHIEF ENGINEER