

NOTICE INVITING TENDER
ADVERTISED TENDER ENQUIRY
GOVT OF INDIA, MINISTRY OF HOME AFFAIRS

VIII.11014/9355/HQ IGAR(N)/Engr/2026

Dated : 28 Apr 2026

1. Online e-tender with tender fees are hereby invited on behalf of President of India from Assam Rifles approved contractors and enlisted contractors working with other Central Government department/organization meeting eligibility criteria for selection of contractor for the following work: -

<u>Ser</u>	<u>Name of Work</u>	<u>Approximate Cost (in Rs)</u>	<u>Earnest Money (In Rs)</u>	<u>Tender Fee (In Rs)</u>
1.1	Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn	1,94,52,312/-	3,89,100/-	1,500/-

2. Last date for uploading the tender documents by bidders duly completed in all respect is at **as per CPP Portal**.

3. The lump sum / item rate amount to be quoted for the entire work by the tenderers shall **include all taxes including GST, ESIC, and EPF and LWC** etc as **applicable at the time of awarding of contract and during the execution of work till completion**.

4. Tender fee is required to be submitted through SBI in the form of Account payee, Demand Draft, Banker's cheque or e-payment and treasury challan etc in favour of **DGAR, c/o 99 APO as application of SBI under Head of Account 0055 Police (A-5) Assam Rifles, Misc Tender Fee**.

5. The Directorate General Assam Rifles as the Competent Financial Authority (CFA) reserves the right to reject or accept any application/tender without assigning any reasons.

Note: The complete tender document can be accessed & downloaded from CPP portal <http://eprocure.gov.in/eprocure/app> please check regularly the website for any change/modification/amendment in the tender enquiry (TE). This TE is being issued with no. financial commitment and DGAR reserves the right to change or vary any part thereof at any stage. He also reserves the right to withdraw the TE, should it become necessary at any stage.

6. Assam Rifles registered/enlisted contractors are exempted from submitting following documents however they have to upload the recent valid enlistment letter issued by HQ DGAR: -

- 6.1 Affidavit for constitution of firm or power of attorney.
- 6.2 Work executed or Performance statement of the firm in the last 03 years
- 6.3 Affidavit for employment of Engineers.

(Sandesh Dabholkar)
Lt Col
SO1 (Works)
for DGAR

Distribution :-

1. HQ DGAR
Signal Br (EDP Cell)
Shillong-10 - You are requested to pub above tender notice on AR website.
Soft copy of this tender notice is forwarded through ARMS.
2. All IGAR/Sector/ARTC & S, - For info and wide publicity please.
3. Notice board
4. Est Branch (Internal) - You are requested to detail a BOO for opening of e-tender **1130 h**
on 18 May 2026 and subsequent days.
5. Office Copy

**NOTICE INVITING TENDER
ADVERTISED TENDER ENQUIRY
GOVT OF INDIA, MINISTRY OF HOME AFFAIRS**

VIII.11014/9355/HQ IGAR(N)/Engr/2026

Dated: 28 Apr 2026

1 For and on behalf of the President of India, the Headquarter DGAR, Engr Branch invites online tenders on the prescribed form, for the execution of the following work as given in this schedule to tender: -

Ser	Description of Works Required	Quantity
1.1	Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn	One Job

2. If you are in a position to quote for the execution of work in accordance with the requirements stated in the attached schedule to tender, all documents attached herewith should be filled in, and submitted through e-Procurement site <http://eprocure.gov.in/eprocure/app>.

3. You are requested to study the tender document completely and ensure all documents pages and annexure to the tender are completely and correctly filled in duly signed and stamped where applicable and then upload on CPP Portal.

4. This online Tender is NOT transferable.

5. This tender enquiry has the following chapters and appx: -

Schedule To Online Tender			Page No.
5.1	Chapter-I	Instructions to Bidders/Tenderers	02 to 07
5.2		Notice Inviting Tender	08 to 10
		Authority Letter	11
		Schedule 'A' (Part – I to XIII) with tech specification and drawing	12 to 14
		Schedule of Work	15
		General Summary	16
		Schedule 'B' Store	17
		Schedule 'C'	18
		Schedule 'D'	19
		Stages of Payment	20
		List of Drawings	21
		Tender	22
		Appendix 'A'	23
		Acceptance	24
		Certificate (Standard Forms to be uploaded by bidders)	25-26
5.3	Appendix 1	Performance Statement Format for last three years	27
5.4	Appendix 2	Certificate to be signed by tenderer	28
5.5	Appendix 3	Proforma for "e-payment"	29
5.6	Appendix 4	Non-Black listing certificate	30
5.7	Appendix 5	Form of Solvency from a Scheduled Bank	31
5.8	Appendix 6	Guarantee/Warranty	32
5.9	Appendix 7	Undertaking for no use of undue influence	33
5.10	Appendix 8	Earnest Money Deposit (EMD) Instrument	34
5.11	Appendix 9	Enlistment/Renewal letter of Assam Rifles approved contractors and enlisted contractors working with other central Government department/organization meeting eligibility criteria contractor in any Govt Department (to be uploaded)	35
5.12	Appendix 10	Amendment of tender document	36-37
5.13	Appendix 11	GSTIN Registration Certificate	38
5.14	Appendix 12	Site Visit Certificate	39
5.15	Appendix 13	Special Conditions of Contract	40-80
5.16			
	Appendix 14	Drawings	81-88

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Chapter-I
Instructions to Bidders/Tenderers

(THIS TENDER SET IS NOT TRANSFERABLE)

6. All Tender documents attached with this invitation to tender including the specifications are SACROSANCT for considering any offer as complete offer, it is therefore important that Tender Acceptance Letter which is a written undertaking that all the terms and condition of the tender are understood and accepted should be signed and submitted only through e-procurement site <http://eprocure.gov.in/eprocure/app>.

7. Tenderers are advised to carefully go through all the conditions and documents attached with this tender enquiry, before uploading the e-tender.

8. All e-tender documents must be duly completed, signed by authorized signatory on each page and uploaded.

9. Tenderers must ensure this complete set is signed on each page and uploaded with their offer, as it is, without any modification/alteration.

10. In case of any difference between the conditions mentioned in schedule to e-tender and the specifications/QRs, the condition given in the specifications will be binding.

11. Name of work : As given in Schedule

12. Tender Cost : Rs **1,500/-**

13. Those who download the tender set from the CPP website must submit the cost of e-tender (non-refundable) through SBI in the form of account payee, demand draft, banker cheque or E- payment and treasury challan etc. a scanned copy of the tender fee of Rs 1000.00 (Rupees one thousand only) upto work value Rs 50.00 Lakh and above Rs 1500.00 (Rupees one thousand five hundred only) to be deposited in favour of DGAR. Original to be submitted as per para 12 of the page No. 02. Tender Fee to be deposited in favour of DGAR at the time submission of e-Tender. e-Tender documents submitted without the tender cost will be rejected. (Original payment instruments in respect of tender fee and EMD are to be deposited either by person in the tender box placed in tender room of HQ DGAR or by post to the Engineer Branch (HQ DGAR) at least one hour (i.e., **time-1130hours**) prior to the time of opening of technical bids (**Time-1230 hours**). Late/Delayed/Non submission of original would result in rejection of bid during online bid opening.

14. Earnest Money (2% of value of tender) : **₹ 3,89,100.00**

15. Date of issue/publishing NIT : **as per CPP portal**

16. Document download start date : **as per CPP portal**

17. Document download end date : **as per CPP portal**

18. Last date & time for uploading of online Tender : **as per CPP portal**

19. Opening of Technical bid : **as per CPP portal**

20. Opening of Financial bid : **Subsequently on approval of Technical Bid**

Note: The onus of ensuring that the above mentioned tender fee and EMD dispatched by post reaches the above said office address is that of the bidder/contractor

21. **A power of attorney in favour of signatory and signatories or the tenderer in case the tender is signed by a person or persons other than the actual tenderer or on behalf of a firm / company and his/ her / their signature attested by Notary / Class-I Gazetted Officer.**

22. Financial Stability Certificate issued during current financial year for a minimum value of appropriate class from the scheduled bank where the firm is operating its current account as per Appendix '5' (format attached).

23. Latest Income tax clearance certificate issued by concerned authority must be produced with supporting PAN Number.

24. Full name and status of the person signing the tender documents must be clearly mentioned in the tender.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

25. Tenderer must quote the rate in terms of **Per No/Set/Sqm/Cum/Lump sum** etc only. **All taxes/other charges should be clearly indicated in the Schedule. No extra charges / taxes over and above the quoted rate in any form will be borne by the Department. The rate quoted will be firm and final and no amendment / alternation to the rate quoted in the tender will be accepted at a later date. No representation will be entertained for change in tenderer's name quoted or any other alternation in respect of any of the contracted articles / goods during the currency of the contract or if any fresh duty or tax is levied.** Conditional discounts if any will not be considered and have no effect on the evaluation of tenders.

26. Paying Authority.

Pay & Account Office Assam Rifles
(Old DGAR Complex)
Laitumukhrah, Shillong - 793011

27. Director General, Assam Rifles, reserves the right to cancel/reject any or all the tenders without assigning any reasons.

28. **Clarification on Specifications/ Qualitative Requirements.** In case any prospective bidder requires clarification(s) on technical specifications/ Qualitative Requirements (QR), the same is to be submitted online. No change in price or substance of the bid will be sought, offered or permitted. No post-bid clarification on the initiative of the bidder will be entertained.

29. **Testing and Inspection Criteria.** The tenderers will have to abide by the testing and inspection criteria formulated by the user confirming to CPWD guidelines.

30. The Department (Users) : DG Assam Rifles, Ministry of Home Affairs,
Govt. of India

31. Inspection Authority : Authorised person detailed by The
Director General, Assam Rifles
Headquarter DGAR, Shillong -10

32. Inspection Officer : Board of officers at Consignee location during critical
stages of work / after completion of work

33. Works required at (Consignee) : As stated in NIT

34. **Execution of Works.** Execution of works at the site given by the Engineer-in-Charge.

35. **Guarantee/ Warranty Terms.**

(a) If not specified in quantity of rate/ specification, **minimum one-year warranty** is required. Warranty period will start from the date of completion of work. In case works/part of works are found defective/damaged during inspection after completion of work, the contractor will re-execute the work under warranty at consignee's location free of cost. Defect liability period is one year. The security deposit amount will be released with confirmation of user.

(b) For RCC roof slab:- Water proofing treatment for roof slab shall be carried out by an approved specialized firm. Ten years guarantee shall be given by the specialized firm and the contractor on non judicial stamp paper of Rs 50/- (Rupees fifty only) for the effectiveness of water proofing treatment.

36. **Rejected Works.** If the appointed contractor fails to remove the bad/ damaged/ rejected works of above items whatever the case may be from sites/location where installed, within the reasonable period i.e., seven (07) days from the date of issue of letter to contractor, the Director General Assam Rifles or his representative shall dispose off the rejected works without assigning any further notice.

37. **Work at the Risk and Cost.** In case of rejection of the item by the Site Engineer in case of neglect, failure or delay on the part of the contractor on work order placed by the Engineer in charge, Headquarter DGAR/ respective HQ IGAR/ HQ Sector Assam Rifles, may without prejudice to any other action which the department may take under the terms of the contract will be at liberty to execute such work at the risk and expense of the contractor. Any amount (which may include transportation and other incidental charges) incurred in excess of the contracted rate shall be borne by the contractor or recovered from his security deposit and/or from any amount which may be due to him by the Directorate General Assam Rifles. The right to risk and cost the work under this clause will entitle right to purchase after expiry of time of delivery or replacement of unfit work, without any warning or further information to contractor. The risk and cost work will be approved by CFA.

38. **Option Clause.** The department reserves the right to increase/decrease the Quantity by 10% at the rates quoted by the successful tenderer at the time of placement of contract (Item rate contract).

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

39. If the tenderer is in a position to quote for the work in accordance with requirements stated in the attached schedule to tender, all documents attached herewith should be duly filled in, signed and stamped and are required to be **UPLOADED**.

40. If the exigencies of work so demand, the Engineer-in-Charge may allow payment to third party, who is creditor to the contractor, after fulfilling certain conditions

(a) The contractor gives an auth letter addressed to the Engr-in-Charge on non judicial stamp paper of Rs.100/- in format given below:-

I/we authorize the **SO-1 (Wks), HQ DGAR** to pay directly on my/our behalf to (name of third party) an amount of `.....(Rupees In words) for the work done or supplies made by (name of third party). I/We shall be responsible for the quality and quantity of the same under the provisions of agreement No.....

(b) The total payment to third party shall not exceed 10% of agreement amount of work.

(c) Full reasons for proposing such third party payment shall be recorded and prior written approval of the next higher auth shall be obtained before making such payments.

41. The item rate/lump sum contract in the case of successful tenderers should conform to tender work accepted in performance evaluation in all respect besides specifications mentioned in CPWD guidelines. The successful tenderer will be asked as applicable to give drawing/schedules prior to commencement of work.

42. Any change in Address/Telephone/Fax/e-mail should be immediately informed. The state of non-communication by the firm will make the offer liable for rejection.

43. Any query/representation be addressed to CE/ SO-1 (Works), HQ DGAR/ SO-1 Works of HQ IGAR(N)

44. **Jurisdiction & Arbitration.** This tender and subsequent contract if any are subject to the jurisdiction of Indian Laws and Courts at the place of issue of the schedule. In the event of any question dispute or difference arising under these conditions or any special conditions of contract, or in connection with this contract (except as to any matters the decision of which is specially provided for by these special condition) the same shall be referred to the Sole Arbitration of the Director General Assam Rifles or some other person appointed by him. There will be no objection that the Arbitrator is a Government Servant that he had to deal with the matters in which the contract is related or that in the course of his duties as Government Servant he has expressed views on all or any of the matters in dispute or difference. The award of the Arbitrator shall be final and binding on the parties to this contract. Further that all disputes arising out of the contract, Shillong Court shall have exclusive jurisdictions. The tenderers submitting the tenders shall render a certificate to have agreed to this clause.

45. Implementation of EPF and ESI for Contract labour.

(a) The ESI and EPF contributions on the part of employer in respect of this contract shall be paid by the contractor. These contributions on the part of employer paid by the contractor shall be reimbursed by the Engineer-in-Charge to the contractor on actual basis post submission of proof of payments.

(b) The contractor whose bid is accepted will also be required to furnish either copy of application/licenses/registrations or proof of applying for obtaining labour licenses, registration with EPFO, ESIC and BOCW welfare board and programme chart (Time and Progress) within the period specified.

(c) No Running Account Bill shall be paid for the work till the application labour licenses, registration with EPFO, ESIC and BOCW welfare board, whatever applicable are submitted by the contractor to the Engineer-in-Charge.

46. **Submission of the tender in Two Bid System.** All bidders are required to submit their offers in two bid system as under:-

DOCUMENTS TO BE SUBMITTED ONLINE WHICH WILL FORM PART OF PQC

(a) **Technical Bid.** The tech bid should contain the following:-

(i) Tender documents duly completed and signed and stamped on each pages but WITHOUT QUOTING RATE AS PER SCHEDULE-A (PART-I) to be uploaded along with other documents.

(ii) Power of Attorney: A power of attorney in favour of signatory and signatories or the tenderer in case the tender is signed by a person or persons other than the actual tenderer or on behalf of a firm/company duly attested by class I Gazetted Officer.

(iii) Compliance to specifications applicable as per CPWD works manual 2022, AR-2249 and General Conditions of Contract 2020.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

(iv) Scanned copy of GST Registration Certificate issued by the concerned authority with supporting PAN / TIN to be uploaded.

(v) **Past Experience.** Minimum two years ending 31st March of preceding financial year of advertised tender. Copies of relevant and authenticated documents (work order/LOI) supporting the same issued by Department of Central Govt/State Govt or Public Sector Unit, where the bidder has successfully concluded the ibid contract, should be enclosed with the tender.

(vi) **Past Performance.** The bidder/OEM should have executed project for supply and installation/commissioning of same or similar category products during preceding three Financial years (i.e current year and three previous financial years) as on opening of bid as per following criteria:-

- (a) Three similar completed works each costing not less than 40% of the estimated cost put to tender, or
- (b) Two similar completed works each costing not less than 60% of the estimated cost put to tender, or
- (c) One similar completed works each costing not less than 80% of the estimated cost put to tender

(vii) **Proof of Completion.** Completion report certificate duly signed by the concerned department/authority.

(viii) Non Blacklisting Certificate as per Appx 4 of Chapter-I to be submitted.

(ix) Certificate of Acceptance of Terms and Conditions of NIT as per Appx 2 of Chapter-I to be submitted.

(x) **Financial Stability Certificate (FSC).** Latest audited balance sheet and Annual Turnover certificate of last two years duly signed by licensed Chartered Accountant to be submitted. These documents should contain **Unique Document Identification Number (UDIN)**. Financial capability of the bidder should be at least 30% of the value of the contract.

(xi) **Bank Solvency.** The contractor is required to submit latest bank solvency certificate (**not older than 120 days**) issued by scheduled bank, preferably a nationalized bank. The bank solvency should meet the eligibility criteria required for the Class of contractor for which he is registered. If the contractor is found not suitable to undertake the work as per bank solvency, he/she will be rejected in the Technical Bid.

(xii) **Enlistment / Renewal Letter.** Enlistment / Renewal letter of contractor in Assam Rifles / any Govt Department (scan copy to be uploaded) giving category and financial limit for Tendering shall be uploaded.

(xiii) **Earnest Money Deposit / Tender Fee.** Scanned copy of Tender Fee and **EMD @ 2% (two percentage) of the tender value** to be deposited through Demand Draft/Bank Draft / Fixed Deposit Receipt/TDR duly pledged in favour of HQ DGAR from a schedule bank preferably a nationalized bank. EMD should be valid for a period of 45 days beyond the fixed Bid Validity period. **Original EMD and Tender Fee to be submitted as per Para 12 of page No 02.**

MSME are exempted for goods and services but MSME exemption cannot be extended to construction works as it cannot be treated as service rendered or supply of goods.

(xiv) Affidavit from contractor for employment of Engineers with last three years experience and degree / diploma certificate of Engineers. No overlap of Engineers for any other work under execution by the contractor is acceptable.

(b) **DOCUMENTS TO BE SUBMITTED BY BIDDERS BUT WILL NOT FORM PART OF PQC**

- (i) Performa for e-payment as per Appx 3 of Chapter-I.
- (ii) Warranty / Guarantee certificate as per Appx 6 of Chapter-I (if required).
- (iii) Undertaking for No Use of Undue Influence as per Appx 7 of Chapter-I.
- (iv) **Implementation of EPF and ESI for Contract Labour.**

(aa) The ESI and EPF contributions on the part of employer in respect of this contract shall be paid by the contractor. These contributions on the part of the employer paid by the contractor shall be reimbursed by the Engineer-in-charge to the contractor on actual basis on submission of proof of payments.

(ab) The contractor whose bid is accepted will also be required to furnish either copy of applicable licenses/ registrations or proof of applying for obtaining labour licenses, registration with EPFO, ESIC and BOCW Welfare Board and Programme chart (Time and Progress) within the period specified.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

(ac) No Running Account Bill shall be paid for the work till the applicable labour licenses, registration with EPFO, ESIC and BOCW Welfare Board, whatever applicable are submitted by the contractor to the Engineer-in-Charge.

(v) **Site Visit.** It is preferable that, the contractor or his/her authorized representative to visit the work site where the work is going to be executed. The contractor will enclose a certificate duly signed by the SO-1 (Wks) of HQ Inspector General Assam Rifles (North) wherein the date of site visit by the contractor / his representative is endorsed.

(c) **Commercial Bid (Cost Bid) (Schedule 'A').** Cost bid of only technically qualified tender will be opened by a board of officer, date of opening of cost bids will be intimated to the valid tenderers and posted on the website after evaluation of Technical Bids. **Cost bid should contain following:-**

(i) Commercial bid forms given in a standard Bill of Quantity (BOQ) format (.xls file) provided with tender document should only be used to fill up the commercial bid.

(ii) **Bidder are to note that submission of financial bids be done in the format provided and no other format is acceptable.** Bidders are required to download the Bill of Quantity file, open it and complete the coloured (unprotected cells with their respective financial quotes and other details viz. name of bidder). No other columns should be changed. Once the details have been completed, the bidder should save it and submit it online without changing the file name. **If the Bill of Quantity file template is found to be modified by the bidder, the bid will be considered invalid and liable to be rejected.**

(iii) The cost is to be indicated for each item(s) and it should be the execution of work/ execution of item, inclusive of carrying charges and all taxes, as applicable.

(iv) **Rates will not be indicated in the technical Bid Schedule 'A' and if indicated, then the tender will be considered invalid.**

(v) Tenders should quote the rate both in words and figures in the online tender form available at www.eprocure.gov.in for each variety. In case of variation in rate quoted in words and in figures, the quoted rate in words will be considered as valid.

47. **Evaluation of the Proposal.** A two stage procedure will normally be adopted as mentioned below:-

(a) **Stage-I : Evaluation of Technical Bids**

(i) A Technical Evaluation Committee (TEC) constituted by the Directorate General Assam Rifles will examine the technical bids. This would be a paper evaluation comprising of scrutiny of all documents required to be submitted for the Technical Bid.

(ii) The TEC reserves the right to verify authenticity of all documents submitted by the firm through internet / telephone or other similar means.

(b) **Stage-II : Financial Evaluation**

(i) The cost bids of only technically qualified enlisted tenderers will be opened whose documents as per schedule of requirement have been found meeting the laid down specifications/ quantity rate/ item rate/lumpsum rate depend upon schedule and the Price Bid will be evaluated accordingly.

(ii) L1 will be decided based on the lowest overall cost of complete work/job including taxes or any other charges.

(iii) The commercial bid uploaded by bidder will be evaluated by a Board of Officers constituted by the Directorate General Assam Rifles and further accessed by a Tender Processing Committee (TPC) for realistic prices. Depending upon the acceptance of the comparative statement of tenders (final prices) by the Competent Financial Authority (CFA), a work order may be placed to the successful bidders. The bidders will be required to accept the work order, enter into a contract for execution of work and execution of project as per terms and conditions mentioned in this Tender Enquiry.

(iv) **Acceptance/ Rejection of Tenders.** Directorate General Assam Rifles reserves the right to accept or reject any or all tenders without assigning any reason.

48. **Insurance.**

- (a) Contractor shall produce character certificate, ITI/ experience certificate of the staff employed.
- (b) Contractor shall be responsible for any discipline cases of staff employed.
- (c) Contractor shall be responsible for any accident/insurance claim of staff employed.
- (d) **Proper documents to be maintained for Salary disbursement of the staff employed.**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

INSTRUCTIONS FOR TENDERERS

1. The Tenderer is required to quote his rates in figures and words against each items of Schedule 'A' in respect of "to be quoted schedules" and amounts and derived percentages in figures and words against each Schedule in General Summary in respect of "pre priced Schedule". The tenderer shall quote his rates/ amounts on the Schedule 'A' and General Summary pages only.

(a) Name of work being tendered for as given in NIT.

(b) Name and address of tenderer along with his seal duly signed by, auth signatory of Firm as in letter head.

2. Wherever the tenderer is required to write both in figures and words, he should ensure that there is no discrepancy between figures and words. The word 'Only' should be added immediately after the last word of rate/ amount/ percentage mentioned in words. In case of discrepancy amount in words shall be considered.

3. In case of partnership concern/ firm or a limited company, signatory to offer shall ensure that he is competent to bind the contractor/firm (through partnership deed, general power of attorney or memorandum and articles of Association of a Company) in all the matters pertaining to the contracts with Union of India including arbitration clause. An attested copy of the documents confirming of such authority shall be attached with the offer, if not submitted earlier. In case of Sole proprietorship, self-sworn affidavit is required to be produced.

4. Conditional tenders will be treated as invalid tenders and will not be considered.

5. **Bid Validity.** A bid shall be valid for **180 days (one hundred eighty days)** unless otherwise specified from the date of opening of the tender. A bid valid for shorter period can be rejected by the user, as being nonresponsive.

6. **Earnest Money.**

(a) The tender should be accompanied by Earnest Money to be submitted duly pledged in favour of **Director General Assam Rifles, Shillong-10**. The EMD may be accepted in the form of Account payee Demand draft, Fixed Deposit Receipt, TDR from a bank preferably a nationalised bank. EMD should be valid for a period of 45 days beyond the fixed Bid Validity period.

(b) Firms submitting EMD through Bank Guarantee are required to ensure authenticity of the same through digitally signed secured e-mail from issuing banks to official e-mail ID of **SO-1 (Works), Engineer Branch, HQ Inspector General Assam Rifles (North)**.

7. **Performance Bank Guarantee (PBG).**

(a) To ensure due performance of the contract, Performance Bank Guarantee is to be obtained from the successful bidder awarded the contract. Performance Bank Guarantee is to be obtained from every successful bidder irrespective of its registration status etc. The contractor shall submit an irrevocable **Performance Bank Guarantee of 5% (Five Percent)** of the value of contract. Performance Bank Guarantee may be furnished in the form of an Account payee Demand Draft, Fixed Deposit Receipt, Bank Guarantee from a recognised bank in an acceptable form safeguarding the department interest in all respect. Getting confirmation through digitally signed secured e-mail from issuing Bank.

(b) Performance Bank Guarantee should remain valid for a period of **sixty days** beyond the date of completion of all contractual obligations of the contractor.

(c) Online verification of company portal with user ID and password followed by 2nd stage authentication system generated One Time Password (OTP) on portal for reconfirmation.

(d) e-mail confirmation followed by 2nd stage authentication by system generated SMS through registered mobile and reconfirmation through SMS to the verifying Office.

8. **Forfeiture of Earnest Money (if applicable):-**

(i) If any tenderer withdraws his tender or makes any modification in the terms & conditions of the tender which is not acceptable to the Dept within 07 days after last date of submission of bids, then the Govt shall without prejudice to any other right or remedy, be at liberty to forfeit 50% of earnest money absolutely irrespective of letter of acceptance for the work is issued or not.

(ii) If any tenderer withdraws his tender or makes any modification in the terms & conditions of the tender which is not acceptable to the Dept after expiry of 07 days after last date of submission of bids, then the Govt shall without prejudice to any other right or remedy, be at liberty to forfeit 100% of earnest money absolutely irrespective of letter of acceptance for the work is issued or not

9. Release of EMD / Refund of EMD. The tenderer except the lowest tenderer shall be refunded immediately within a week from the date of acceptance of successful bidder. EMD in respect of the L1 (lowest) tenderer shall be refunded on receipt of Performance Bank Guarantee.

10. This INSTRUCTIONS FOR TENDERER along with Particular Specifications shall form part of the tender documents.

11. "Accepting Officer" means the duly authorised officer who signs the contract on behalf of the President of India as duly designated by CFA.

12. Tender value is inclusive of GST, EPF, ESIC & LWC. In case of any amendment made by Government during the course of contract towards GST, EPF, ESIC & LWC charges same has to be borne by Contractors.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

NOTICE INVITING TENDER

1. A tender is invited for the work as given in **Appendix 'A'**.
 - (a) The work is estimated to cost as given in **Appendix 'A'**. This estimate however is not guaranteed and is merely given as a rough guidance and if the work costs more or less, a tenderer will have no claim on that account.
 - (b) The Tenderer shall calculate his own unit rates from the specifications and other information furnished in the tender documents for each item as given in **Schedule 'A'**.
2. The work is to be completed within the period given in **Appendix 'A'** (in accordance with the phasing if any, indicated in the tender) from the date of handing over the site, which will be within 30 days after acceptance of tender and submission of Performance Security Deposit.
3. Contractors registered with Director General Assam Rifles may deposit Bank Challan & purchase tenders. Contractors registered with other Govt organisations may also upload tender however their eligibility for tender participation will be subject to submission of Financial and personal credential of Registration as Govt department Contractor duly authenticated by an officer not below Executive Engineer / Superintending Engineer of the concerned department with whom contractor is registered along with the tender documents. This will include:-
 - (a) Registration documents with validity copy.
 - (b) Financial and Solvency limit issued by a Bank.
 - (c) Personal Details of Firms.
- 3.1 Not more than one tender / bid shall be submitted / uploaded by one contractor or one firm of contractor(s). Under no circumstances will a father and his son(s) or other close relation who have business dealing with one another be allowed for the same contract as separate competitors. A breach of this condition will render the tenders of both parties liable to rejection.
4. **Earnest Money (Bid Security).**
 - (a) The Earnest Money as stated in para 6 of Instruction for tenderers will be accepted in the Form of Account payee Demand Draft, Fixed Deposit Receipt, Bankers cheque or Bank Guarantee.
 - (b) It should be ensured that the Earnest Money from any Commercial bank is pledged in favour of **Director General Assam Rifles**.
 - (c) If the banks are closed on the last date of receipt of tenders, the date shall be postponed suitably.
- 4.1 **Validity Period of EMD.** Earnest Money shall be valid for a period of 180 days (bid validity) plus 45 days (Tender duration) i.e. total **225 days** (minimum).
- 4.2 The Director General Assam Rifles as the CFA will release/refund the earnest money, wherever applicable, to all unsuccessful tenderers after expiry of the Final bid validity and latest on or before the 30th day after the award of the contract by endorsing an authority on the deposit receipt for its refund on production by the tenderer of a certificate of the Accepting Officer that a bonafied tender was received and all documents are returned.
- 4.3 The Director General Assam Rifles as the CFA concerned will either return the Earnest Money to the successful tenderer by endorsing an authority on the 'Deposit Receipt' for its refund, on receipt of an appropriate amount of Security Deposit or will retain the same in part or full on account of Security Deposit, if such a transaction is feasible.
5. **Security Deposit.**
 - (i) Security Deposit, in the form of an Account payee Demand Draft, Fixed Deposit Receipt, Bank Guarantee from a recognised bank, preferably nationalised is required to be submitted by the successful bidder for whom work order has been placed and the work has been completed by him/her. This should remain valid for a period of **sixty days** beyond the date of completion of defect liability period / warranty period. The contractor shall submit an irrevocable Security Deposit **of 5% (Five Percent)** of the value of contract.
 - (ii) Payment for Final bill of the successful bidder after completion of work, shall be made subject to receipt of Security Deposit / a renewed PBG covering the entire defect liability period.
 - (ii) Firms submitting Security Deposit through Bank Guarantee are required to ensure authenticity of the same through digitally signed secured e-mail from issuing banks to official e-mail **ID of Engr Branch, HQ DG Assam Rifles (enrbr3@gmail.com)**.
6. Documents pertaining to the work (Signed for the purpose of identification by the Accepting Officer or his accredited representative) and samples of materials and works to be supplied by the contractor will be opened for inspection by the tenderer at the office of Accepting Officer concerned during working hours.
7. The tenderers are advised to visit site by making prior appointment with the Staff Officer-I (Works) concerned in sufficient time.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer

8. A Tenderer shall be deemed to have full knowledge of all relevant documents, samples, site etc whether he has inspected them or not.
9. Any tender which proposed any alteration to any of the condition laid down or which proposes any other condition or description, what so ever, is liable to be rejected.
10. **The submission of tender by a tenderer implies that he has read this Notice and Conditions of Contract and has made himself aware of the scope and specifications of the work to be done and of the condition and rates of works, tools and plants etc. that will be issued to him and local conditions and other factors bearing on the execution of the work.**

11. **Compensation for delay (Liquidated Damages).**

(a) If the contractor fails to maintain the required progress as per contract agreement or to complete the work and clear the site on or before contract completion or extended date of completion, he shall, without prejudice to any other right or remedy available under the law be liable to the Government on account of such breach and pay as agreed compensation, the amount calculated at the rates stipulated below, duly approved by CFA (whose decision in writing shall be final and binding) who may decide on the amount of tendered value of the work for every completed day/month (as applicable) that the progress remains below that specified in Contract Agreement.

(b) This will also apply to items or group of items for which a separate period of completion has been specified.

(c) **Compensation for Delay of Work:** With max rate @ 1% (one percent) per month for delay to be computed on per day basis based on quantum of damage suffered due to stated delay on the part of Contractor. Provided always that the total amount of compensation for delay to be paid under this condition shall not exceed 10% (ten percent) of the accepted Tendered Value of work or of the accepted Tendered Value.

(d) The amount of compensation may be adjusted or set-off against any sum payable to the contractor under this or any other contract with the Government. In case, the contractor does not achieve a particular milestone mentioned as per Contract Agreement, or the re-scheduled milestone(s), the amount shown against that PDC shall be withheld, to be adjusted against the compensation levied at the final grant of Extension of Time. With-holding of this amount on failure to achieve a PDC, shall be automatic without any notice to the contractor. However, if the contractor catches up with the progress of work on the subsequent milestone, the withheld amount shall be released. In case the contractor fails to make up for the delay in subsequent milestone(s), amount mentioned against each milestone missed subsequently also shall be withheld. However, no interest, whatsoever, shall be payable on such withheld amount.

12. **Time and Extension for Delay**

(a) The time allowed for execution of the works as specified in the Contract Agreement/ work order or the extended time in accordance with these conditions shall be the essence of the Contract. The execution of the works shall commence from such time period as mentioned in work order or from the date of handing over of the site whichever is later. If the contractor commits default in commencing the execution of the work as aforesaid, Government shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the earnest money & performance guarantee absolutely alongwith cancellation of work for retendering.

(b) As soon as possible, after the Contract is let or any substantial Work Order is placed and before work under it is begun, the SO-1 (Works) / Contract operating authority and the Contractor shall agree upon a time and progress chart. The Chart shall be prepared in direct relation to the time stated in the contract documents or the work order for completion of the individual items thereof and/or the Contract or work order as a whole. It shall indicate the forecast of the dates for commencement and completion of the various trade processes or sections of the work and shall be amended as may be required by agreement between the SO-1 (Works) / Contract operating authority and the Contractor within limitation of time imposed in the contract documents or work order. If the works be delayed:-

- (i) By force majeure, or
- (ii) By reason of abnormally bad weather, or
- (iii) By reason of serious loss or damage by fire, or
- (iv) By reason of civil commotion, local commotion of workmen, strike or lockout, affecting any of the trades employed on the work, or
- (v) By reasons of delay on part of nominated sub-contractors, or nominated contractor, which the Contractor has, in the opinion of SO-1 (Works)/Contract operating authority, taken all practicable steps to avoid or reduce, or
- (vi) By reason of delay on the part of Contractors or tradesmen engaged by Government in executing works not forming part of the contract, or
- (vii) By reason of any other cause, which in the absolute discretion of the Accepting Officer is beyond the Contractor's control.

(c) Then, in such case the Accepting Officer may make fair and reasonable extension in the completion dates of individual items or groups of items of work for which separate periods of completion are mentioned in the contract documents or work order as applicable.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

(d) **Upon the happening any such event causing delay, the Contractor shall immediately, but not later than 14 days of the happening of the event,** give notice thereof in writing to the SO1(Works)/Contract operating authority but shall nevertheless use constantly his best endeavor to prevent or make good the delay and shall do all that may reasonably be required to the satisfaction of the SO1(Works)/Contract operating authority to proceed with the works for which SO1(Works) will monitor details on record. Extension of time shall be approved by the CFA.

(e) **In case the Contractor fails to notify the SO-1 (Works) / Contract operating authority of happening of an event(s) causing delay within the period of 30 days stipulated above, he shall forfeit his right to claim extension of time for the delay caused due to such event(s).**

(f) If the work is delayed by reason of non-availability of Government stores shown in Schedule 'B', then, in any such event notwithstanding the herein fore contained, the CFA may in his discretion grant such extension of time as may appear reasonable to him and the same shall be communicated to the Contractor by the SO-1(Works)/Contract operating authority in writing. The decision so communicated shall be final and binding and the Contractor shall be bound to complete the works within such extended time.

(g) **No claim in respect of compensation or otherwise, howsoever arising, as a result of extensions granted under conditions above shall be admitted.**

(h) No RARs shall be processed for payment if the PDC of the said work / job is expired. Extension of Time (EOT) for PDC shall be processed and sanction be obtained prior to processing of RARs.

13. **Cancellation, Foreclosure and Termination of Contract.** If the contractor:-

(a) Makes default in commencing the works within a reasonable time from the date of the handing over the site and continues in that state after a reasonable notice from SO-1 (Works) / Contract operating authority.

or

(b) In the opinion of the SO1(Works)/Contract operating authority at any time, whether before or after the date or extended date for completion, makes default in proceeding with the works, with due diligence and continues in that state after a reasonable notice from SO-1 (Works) / Contract operating authority.

or

(c) Fails to comply with any of the terms and conditions of the Contract, or after reasonable notice in writing with orders properly issued there under,

or

(d) Fails to complete the works, work order and items of works, with individual dates for completion, and clear the site on or, before the date of completion.

13. The Director General Assam Rifles as the CFA may, without prejudice to any other right or remedy which shall have accrued or shall occurred thereafter to Govt, cancel the contract as a whole or only such work order (s) or items of work in default from the contract: whenever the Director General Assam Rifles as the CFA exercises his authority to cancel the contact as a whole or in part under this condition he may complete the work by any means at contractor's risk and cost.

14. The Director General Assam Rifles as the CFA does not bind himself to accept the lowest or any tender or to give any reasons for not doing so.

15. The Director General Assam Rifles as the CFA reserves his right to accept a tender submitted by a Public Sector Under taking giving a price preference over other tender which may be lower or as admissible under the Govt Policy. No claim for any compensation or otherwise will be admissible from such tenderers whose tenders may be rejected on account of the said policy.

16. **Handing / Taking over of work site will be completed within maximum of four weeks after issue of Work Order in all respect.**

17. The change of site will not be accepted after Administrative Approval. In case of unavoidable circumstances, the concurrence of the Director General Assam Rifles as the CFA is essential before commencement of work.

18. **The completion report will be addressed to the Accepting Officer. The contractor will make sure that work will be completed in all respect as per Schedules, drawings and specification.**

19. The work order duly completed in all aspect will be issued within a week after approval of works by Director General Assam Rifles as the CFA.

20. This **NOTICE OF TENDER INCLUDING APPENDIX 'A'** shall form part of the tender documents.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

AUTHORITY LETTER

(To be used in conjunction with General Condition of Contracts, CPWD)

HQ DGAR
Laitkor
Shillong - 793010

VIII.11014/9355/HQ IGAR(N)/Engr/2026

Dated: _____ Apr 2026

LUMP SUM / ITEM RATE CONTRACTS FOR THE WORKS REQUIRED IN THE WORK:

**MITIGATE LANDMASS SUBSIDENCE AT ACTIVE SLIDING ZONE TO SAFEGUARD ROAD
CONNECTIVITY AT KOHIMA GRN**

Shri/ M/S _____ of
_____ is/are hereby authorized to tender for the above work. The tender is to be submitted through
e-Procurement site <http://eprocure.gov.in/eprocure/app> by 1100 hours on _____ 2026.

Any correspondence concerning this tender should be addressed as indicated at the top of this sheet quoting the reference as given.

**THE PRESIDENT OF INDIA DOES NOT BIND HIMSELF/HERSELF
TO ACCEPT THE LOWEST OR ANY TENDER**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SCHEDULE 'A' NOTES
LIST OF WORKS AND PRICES

Name of Work: - **Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn**

1. This schedule consists of **08 (Eight)** parts as detailed below:-

Ser	Sch	Description of Works Required
1.1	PART- I	RCC Retaining wall 4 mtr height 30 mtr long
1.2	PART- II	Gabion retaining wall 4.25 mtr height 30 mtr long
1.3	PART- III	Random rubble masonry retaining wall 1.5mtr height 50 mtr long
1.4	PART- IV	RCC Retaining wall 5 mtr height 30 mtr long
1.5	PART- V	Bituminous Road 3.50 mtr wide 90 mtr long
1.6	PART- VI	Drain (Brick masonry) 400mm wide 150 mtr long
1.7	PART- VII	Vertical Drain 11 mtr depth (03 Nos)
1.8	PART- VIII	Chain link Fencing 40 mtr long

2. The description of building works and services given in various parts of Schedule 'A' are in brief. These are deemed to be amplified and read in conjunction with special conditions, particular specifications, drawing (including notes thereon), specifications for materials and workmanship given in CPWD specification 2019 Volume I and II and amendments thereafter.

3. Entire work under this contract shall be completed within the period of "**06 Months**" after the date of handing over the site as indicated in the first work order as under.

4. Pre-priced rates inserted under Column "Unit rate" of schedule 'A' are deemed to be at par with the rates contained in the Delhi Schedule Rates or analogous rates there to. Contractor's attention is invited to condition of clauses 13.2.8 & 13.2.9 of CPWD Works Manual 2014, wherein the lump sum price shall be worked out by him independently of the prices or rates inserted by Assam Rifles in the tender and irrespective of any errors or inaccuracies therein. The percentage to be inserted by tenderer against a particular part of schedule 'A' shall be derived by him from the amount tendered by him against the particulars part of schedule 'A' as compared to the amount inserted by Assam Rifles against each part of schedule 'A'.

5. In case, details in respect of items shown on main drawings are not given in the drawings referred to in the main drawings, then the same shall be followed from any other drawing included in the list of drawings. Any drawings mentioned in the contract/contract drawings but inadvertently not included in the list of drawings shall also be deemed to form part of the contract.

6. Probable distribution of various items of internal/external services are indicated on drawing. These are tentative and may be varied as per site requirement, where necessary at the discretion of the Engineer-in-Charge. The effect of such changes/variations in quantities due to realignment or re-siting shall deemed to be included in the rates quoted and no price adjustment on this account shall be allowed.

7. Layout of buildings indicated in the site plan are tentative and no price adjustment shall be made on account of any change in final approved layout within the site of work.

8. **The tenderers are advised to visit the work site after taking prior appointment with Engineer-in-Charge before submission of tender.** The tenderer shall have no claim what-so ever on this account at a later stage whether he has actually inspected the work site or not.

9. The lump sum / item rate quoted by the tenderer shall be deemed to include for all minor details of construction which are not specifically shown on drawing or specified in particular specification but which are essential for execution or work /services in workman like manner and sound construction. In case of differences in opinion of the contractor and the Engineer-in-charge as to whether or not a certain item of work constitutes minor details of construction, the decision of Accepting Officer shall be final, conclusive and binding.

10. Cost of testing including transportation of materials or equipment or items, provision of all facilities for testing in accordance with specifications and / or IS shall be borne by the contractor unless otherwise mentioned.

11. The materials used for construction should be of best quality duly approved by user and as per approved list of products by the Assam Rifles (Refer Item/Product list attached as **Appx 'B'**). TMT bars used for construction should be from Primary manufactures. Irrespective of whatever shown on drawings or specified elsewhere in the tender documents, the product shall be duly approved by Engineer-in-Charge.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

12. **Lab Test report.** Lab test reports of items mentioned at Para 1 are required to be submitted by the L1 bidder. The lab test reports shall fulfil fwg conditions :-

- 12.1 Duly approved by Govt/NABL Labs.
- 12.2 Should not be more than 1 year old from the date of bid uploading.
- 12.3 Should have Name of seller /OEM and date of test
- 12.4 Test report should be relevant to the items mentioned in the bid
- 12.5 The lab report may be sent for verification to lab to establish authenticity at discretion of buyer.

13. Unit rates quoted shall be deemed to be inclusive of all taxes and levies of Govt. so applicable such as Sales Tax/VAT/WCT/GST, EPF, ESIC & LWC on works contract, excise duty, toll tax, entry tax, income tax, worker's welfare tax/cess, etc and nothing extra shall be paid on this account. Necessary deduction at source shall be made by the Accepting Officer as applicable as per the mandatory statutory requirement of Central and State Government.

14. The lump sum / item rate quoted against all items of schedule 'A' shall be deemed to include for all items of works complete as specified in particular specifications and shown on drawings, notes thereon for completion of work and all minor details though not specifically shown on drawings or specified in particular specification except works covered under schedule 'A' or unless specifically stated elsewhere in the tender documents.

15. Cutting and forming chases in masonry/concrete work etc. including cutting and or leaving holes/recesses, sinking etc. where required and as directed by the Engineer-in-Charge shall be done as far as possible while the work is in progress. The cost of materials and labour for cutting and/or forming chases, cutting or leaving hole/recesses, sinking and making good in cement mortar (1:3) for filling up to 20 mm and in PCC (1:2:4) type B-1 concrete for filling more than 20 mm shall deemed to be included in the lump sump quoted by the contractor. In addition, cutting or forming chases, cutting or leaving hole/recesses, sinking and making good in cement mortar 1:3/PCC 1:2:4 type B-1 in connection with the work required in plumbing, internal water supply, internal electrification etc shall deemed to be included in the unit rates of respective building works in Schedule 'A'. However, no price adjustment shall be made for any variation in the items/quantities of chases/holes/recesses etc. consequent upon changes in quantities of plumbing, internal water supply, internal electrification works etc.

16. The buildings under this contract have been designed for SBC of soil as indicated in structural drawings. Variation in SBC of soil, if found at site and required redesigning of the foundation, the same shall be regularised through proper deviation order, for which Approval in Principle will be taken before execution is commenced

17. **Safety Measures, Precautions, Risks etc.**

(a) The Work shall be carried out with utmost care to ensure that no damage to Existing/Adjoining Work/Fittings is done failing which the damage, if any done shall be rectified by the Contractor to match with the Existing/ Adjoining Work /Fittings to the entire satisfaction of Engineer-in-Charge under Contractor's own arrangement and at his own expenses.

(b) Suitable Tools, Plants, Equipments, Mechanism, etc., as considered necessary shall be adopted during execution of the Work. The Contractor shall take all Precautions, Safety Measures, etc., to avoid any Damage, Miss-happening, Accident, etc., to the Workmen engaged by him to carry out the Work. The UNIT RATES quoted by Contractor shall be deemed to have included the Element of adopting Safety Measures, Precautions and also the Risks, etc. involved in Work and nothing EXTRA shall be admissible on this account.

(c) Segregation of site with suitable material (CGI sheet, Hessian cloth, etc.) to prevent any access of any unauthorized / unwanted person(s), to be carried out by the contractor under own arrangement without any cost effect.

18. Government shall not Pay anything Extra, if the Contractor has to Pay Royalty to the State Government for the Earth brought to Site by him from Outside burrow. In case any Royalty is required to be Paid by the Contractor for bringing Approved Earth from Outside burrow, the Rate quoted shall be deemed to include for the same and nothing Extra shall be Paid to the Contractor by the Department.

19. The Rate quoted for Rough Excavation is independent of the Actual Method of Excavation permitted by the Private Land Owners and nothing Extra shall be Paid by the Department.

20. **All quantities are PROVISIONAL. Any variation in quantities if considered necessary due to site requirement/any other technical reasons as decided by the Engineer-in-Charge may be executed to the extent as specified in condition of CPWD General Conditions of Contract clauses 12.**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

21. Unless otherwise specified the unit rate of each item of work inserted by Assam Rifles or quoted by tenderer shall be deemed to include for "Materials and labours" / "Supplying and fixing" / "Supplying, laying, jointing and testing including commissioning" etc complete unless otherwise specifically mentioned. Condition in CPWD Specifications 2019 Volume I and II and amendments thereafter and the preambles to the items given in Delhi Schedule Rates 2019 under respective trades shall be applicable. If any provision in the description of items of Schedule 'A' and particular specification is at variance with the provision laid down in the condition of Schedule and preambles to Schedule item, the provision in description of items of Schedule 'A' and provision in particular specification shall take precedence.

22. In Schedule 'A' the rates for various items shall be inserted by the tenderer both in figures and words under columns and the amount shall be extended. The total amount of this Schedule 'A' shall be carried over to general summary.

23. Rates quoted in different schedules for similar items if varies then lowest quoted rate shall be applicable for calculation of L-1.

24. **Inspection of the Works (Defects Liability Period).** The Defects liability period for the scope of work(s) covered under the contract is **TWELVE CALENDAR MONTHS** from the date of completion of the work or handing over of the work executed to user whichever is later. Any defects in the work noticed during this period shall be rectified by the contractor forthwith, on demand in writing from the Staff Officer-I(Works) specifying the area affected not withstanding that the work executed might have been inadvertently passed, certified and paid. The contractor shall carry out the rectification of the defects notified at his own expense during the defects liability period and in event of his failure to do within a period to be specified by the Staff Officer-I(Works) in his demand, the Staff Officer-I(Works) shall undertake such rectification work at the risk and expense of the contractor.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SCHEDULE 'A'

Unit/Fmn : **HQ Inspector General Assam Rifles (North), C/O 99 APO**
Name of work : **Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn**

SCHEDULE 'A'/ BOQ UPLOADED SEPERATELY

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Name of work:- Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn

GENERAL SUMMARY

Ser No.	Description of Schedule "A" Part	Amount (Incl all taxes)
1	<u>SCHEDULE 'A' PART-I</u> RCC Retaining wall 4 mtr height 30 mtr long	₹ _____ (Rupees _____ _____ only)
2	<u>SCHEDULE 'A' PART-II</u> Gabion retaining wall 4.25 mtr height 30 mtr long	₹ _____ (Rupees _____ _____ only)
3	<u>SCHEDULE 'A' PART-III</u> Random rubble masonry retaining wall 1.5mtr height 50 mtr long	₹ _____ (Rupees _____ _____ only)
4	<u>SCHEDULE 'A' PART-IV</u> RCC Retaining wall 5 mtr height 30 mtr long	₹ _____ (Rupees _____ _____ only)
5	<u>SCHEDULE 'A' PART-V</u> Bituminous Road 3.50 mtr wide 90 mtr long	₹ _____ (Rupees _____ _____ only)
6	<u>SCHEDULE 'A' PART-VI</u> Drain (Brick masonry) 400mm wide 150 mtr long	₹ _____ (Rupees _____ _____ only)
7	<u>SCHEDULE 'A' PART-VII</u> Vertical Drain 11 mtr depth (03 Nos)	₹ _____ (Rupees _____ _____ only)
8	<u>SCHEDULE 'A' PART-VIII</u> Chain link Fencing 40 mtr long	₹ _____ (Rupees _____ _____ only)
	<u>Grand Total</u>	₹ _____ (Rupees _____ _____ only)

Rupees _____

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SCHEDULE 'B'**ISSUE OF WORKS, ETC. TO THE CONTRACTOR**
(SEE CONDITION 26.1 OF CPWD)

Serial No	Particulars	Rate at which materials will be issued to the contractor		Place of issue (by name)	Remarks
		Unit	Qty		
I		-Nil-			

NOTES: (To be filled as applicable or scored out)

1. This Schedule consists of Nil items only.
2. It will be the responsibility of the contractor to submit in writing his demand for materials SEVEN DAYS in advance of his requirement.
3. Material listed above shall be issued solely for the purpose of incorporation in the work.
4. Recovery will be made for the gross quantity issued and not for the measured quantity of finished work.
5. If the contractor requires store listed above issued to him for making good any loss or damage to work arising from any cause what-so-ever other than the accepted risk and the Govt. issues the same to him, the rates of issue for such items of works shall be the Assam Rifles all stock book rate or market rate on the date of issue of works or Schedule 'B' rate whichever is higher.
6. Store listed in Schedule 'B' when issued to contractor for rectification of defects notified to him under conditions of clauses 26.1 of CPWD during the defect liability period shall be charged at the rates shown in Schedule 'B'.
7. The items issued FREE FOR FIXING shall be tested at the time of issue in the presence of contractor or contractor's accredited representative and if they are not working after fixing, the contractor shall replace the same at no extra cost to the Government.
8. If the works issued "FREE FOR FIXING" are lost or damaged while in the custody of the contractor, the Govt shall recover the cost thereof at double the market rate as prevailing on the detection of such loss or damage. The decision of Engineer-in-charge with regards to damage to the works issued and relevant market rate shall be final and binding on the contractor.
9. If on completion of work, the contractor fails to return surplus materials out of those supplied by Govt. then in addition to any other liability which the contractor would have incurred, the Engineer-in-Charge may by a written notice to the contractor, require him to pay within a fortnight of receipt of the notice for such un-returned and surplus materials at double the prevailing market rate as decided by the Engineer-in-charge. If however, the contractor is not satisfied with the decision of the same with regard to market rate he shall be entitled to represent the matter to CFA within Seven Days of receipt of Engineer-in-charge's' decision and the decision of the CFA, thereon shall be final and binding.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SCHEDULE 'C'**LIST OF TOOLS AND PLANTS (OTHER THAN TRANSPORT)
WHICH WILL BE HIRED TO THE CONTRACTOR****(See Condition 28.1 of CPWD)**

Serial No	Quantity	Particulars	Details of Assam Rifles crew supplied	Hire charges per unit per working day	Stand by charges per unit per off day	Place of issue (by name)	Remarks
1	2	3	4	5	6	7	8

-NIL-

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SCHEDULE 'D'**(TRANSPORT TO BE HIRED TO THE CONTRACTOR)****(See Conditions GCC of CPWD)**

Serial No	Quantity	Particulars	Rate per unit per working day	Place of issue (by name)	Remarks
1	2	3	4	5	6

NIL

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Name of Work: - Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn

STAGE OF PAYMENT

The payment for **lump sum & items rate and measurable works** under Sch "A" Part – I and VIII will be made after measuring the work done as per the standard method of measurement as under.

(a) **Building Work (lump sum) contract :**

(i)	Stage - I	:	-	-	-
(ii)	Stage - II	:	-	-	-
(iii)	Stage - III	:	-	-	-
(iv)	Stage - IV	:	-	-	-

(b) **Item rate contract :**

(i)	Stage - I	:	Upto 90%	-	As per measurement/ Work Done.
(ii)	Stage - II	:	Balance 10 %	-	Upto 100% completion of work in all respects and rectification of defects and handing/ taking over to Users

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Name of Work: - **Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Garrison HQ IGAR(N)**

LIST OF DRAWINGS

1. The following drawings are included in the tender documents:-

S/No	Description of drawings	Drawing No	Sheet No
1	RCC Retaining wall 4 mtr height	CP and DS Associates HSCL	1/1
2	Gabion retaining wall	NPCCL(NERC)/Kohima/1988	1/1
3	Random rubble masonry retaining wall 1.5mtr height	DMR/ENGR/2017/249	1/1
4	RCC Retaining wall 5 mtr height	DMR/ENGR/2022	1/3 to 3/3
5	Drain (Brick masonry)	DGAR/STD/ENGR/09	1/1
6	Vertical drain	-	1/1
7	Chain link fencing	DMR/Engr/2021/256	1/1

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

TENDER

TO

THE PRESIDENT OF INDIA

Having examined and perused the following documents: -

1. Special Conditions of Contract
2. Particular Specifications signed by SO-1(Works)
3. Drawings detailed in the list of Drawings.
4. Schedule 'A', 'B', 'C' and 'D' attached hereto.
5. **CPWD Specifications 2021** Volume I and II and amendments thereafter and Delhi Schedule **Rates 2021** (here-in-after referred to as the Schedule) together with amendments if any. General Conditions of Contracts of CPWD together with errata and amendments if any.
6. Water and Electricity: **No Water and Electricity will be supplied by the Assam Rifles.**

Should this tender be accepted, I/We agree.

(a) That the sum of Rs. _____ (Rupees _____) forwarded as Earnest Money shall either be retained as part of Security Deposit or refunded by the Government on receipt of the appropriate amount of Security Deposit, all as per Conditions of CPWD.

(b) To execute all the works referred to in the said documents upon the terms and conditions contained or referred to therein and as detailed in the General summary below or at such other rates as may be fixed under the provision of conditions of CPWD and further agree to refer all disputes, as required by conditions of CPWD to the Sole Arbitration of a Serving Officer having degree in Engineering or equivalent or having passed final / direct final examination of Sub-division II of the Institution of Surveyors (India) recognized by the Govt of India to be appointed by the CHIEF ENGINEER ASSAM RIFLES, whose decision shall be final, conclusive and binding.

TOTAL B.F. FROM SERIAL PAGE NO _____ Rs. _____

or the lumpsum of Rs. _____ (Rupees _____

_____) Signature _____ Dated

_____ 2024 in the capacity of _____ duly authorised to sign the tender for and on behalf of _____

SIGNATURE OF WITNESS

NAME _____

POSTAL ADDRESS _____

TELEGRAPHIC

ADDRESS

TELEPHONE NO. _____

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

APPENDIX 'A' TO NOTICE INVITING TENDER1. **Condition No – 1**

(a) Name of Work : **Mitigate landmass subsidence at Active sliding zone to safeguard road connectivity at Kohima Grn**

(b) Estimated Cost : **₹ 1,94,52,312/-**

2. **Condition No – 2**

Period of Completion : 06 Months

3. **Condition No – 3**

(a) Document download start date : **As per CPP Portal**

(b) Earnest Money : **Rs. 3,89,100/-**

(c) Earnest money to be deposited in favour of : Mahanideshalaya Assam Rifles
Directorate General Assam Rifles
Shillong - 793010

(d) Office where drawing & other documents will be available for inspection : SO-1 (Works)
Headquarter Inspector General Assam Rifles (North)
c/o 99 APO

4. **Condition No – 4**

(a) Last date & time for uploading of online tender : **As per CPP Portal**

5. **Condition No – 5** : **Eligibility Criteria**(a) **For DGAR Enlisted Contractors.**

(i) Enlistment in **Class 'A' and above**.

(ii) Shall not carry adverse remarks in **Work Load Return (WLR)** or any other report circulated by Competent Engineer Authority.

(b) **For Non-Enlisted Contractors of DGAR.**

(i) Contractor shall meet the enlistment criteria for at least **Class 'A'**, with regard to satisfactorily completed similar nature and requisite value of work with any Central/State Government department.

(ii) Bank Solvency, Annual turnover, Working Capital along with UDIN.

(iii) Not suspended / debarred / Black listed (permanently / Temporarily) for bidding / any business dealings with Central/State Government department or any Autonomous body/Local body.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

ACCEPTANCE

_____ Alterations have been made in these documents and as evidence that these alterations were made before the execution of the Contract Agreement and these have been initialled by the Contractor and _____ SO-1 (Works).

The said officer is hereby authorised to sign and initial on my behalf the documents forming part of this contract.

The above tender was accepted by me on the _____ day of _____ on behalf of the President of India for the lump sum of ₹. _____ (Rupees _____)

Signature _____ dated this _____ day of _____

Appointment: CFA, Assam Rifles
ACCEPTING OFFICER
(For and on behalf of the President of India)

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

CERTIFICATE
GENERAL CONDITIONS OF CONTRACTS (CPWD)
FOR LUMP SUM / ITEM RATE CONTRACTS

I am in possession of copy of the CPWD General Conditions of Contract. I/we have read and understood the provisions contained in the aforesaid General Conditions of Contracts before submission of this tender and I/we agree that I/we shall abide by the terms and conditions thereof, as modified, if any, elsewhere in these tender documents.

It is hereby further agreed and declared by me/us that the General Conditions of Contracts CPWD form part of these tender documents.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

CERTIFICATE
ASSAM RIFLES CONDITIONS AND PARTICULAR SPECIFICATIONS
FOR LUMP SUM CONTRACTS, TERM CONTRACTS, ITEM RATE
MEASUREMENT CONTRACTS

A copy of the Assam Rifles Special Conditions and Particular Specifications for lump sum contracts, Term Contracts and measurement contracts has been supplied to me/us and is in my/our possession. I/we have read and understood the provisions contained in the aforesaid Assam Rifles Special Conditions and Particular Specifications of Contracts before submission of this tender and I/we agree that I/we shall abide by the terms and conditions thereof, as modified, if any, elsewhere in these tender documents.

It is hereby further agreed and declared by me/us that the Assam Rifles Special Conditions and Particular Specifications form part of these tender documents.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

CERTIFICATE TO BE SIGNED BY THE TENDERER

(TO BE FILLED BY THE TENDERER)

1. It is certified that I have read and understood and will comply all instructions contained in tender enquiry and its schedule. All pages of schedule to tender from page 01 to 96 have been filled properly and signed.
2. The construction/building materials supply/ works once /completed/delivered will be subjected to an inspection by the acceptance board at the given consignee location. The specifications of the items will be in conformity with the details provided by the user and as per given specifications. The date of completion of acceptance board would be deemed date on which the warranty will commence.
3. **We shall provide onsite comprehensive warranty of one year for the items being executed work / supplied.**
4. **We guarantee to provide 100% replacement for the defective item during guarantee/warranty & ten years guarantee for the effectiveness of water proofing treatment of accessible roof and structural members.**
5. **We affirm that we abide by the work schedule as given in tender and elsewhere in the tender enquiry.**
6. **We agree to deposit a Security Deposit equal to FIVE percentage (5%) of the total cost of work as per work order/supply order.** After defect liability period of 12 months, the Security Deposit will affirm be released on receipt of confirmation from concern unit/user along with fresh photographs.
7. We certify that any cost incurred on additional items/systems/components /accessories required would be borne by us.

Signature of tenderer: _____

Name in block letters: _____

Name of firm: _____

Full address: _____

(i) Telephone No _____

(ii) Mobile No _____

(iii) Fax No _____

(iv) Email id _____

(v) Website _____

Company Seal
Place : _____

(Authorised Signatory of Company)

Date : _____

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

**ELECTRONIC CLEARING SERVICE (CREDIT CLEARING/REAL TIME GROSS SETTLEMENT (RTGS)
FACILITY FOR RECEIVING PAYMENTS**

A. DETAILS FOR ACCOUNT HOLDER:-

NAME OF ACCOUNT HOLDER	
COMPLETE CONTACT ADDRESS	
TELEPHONE NUMBER/FAX/EMAIL	

B. BANK ACCOUNT DETAILS:-

BANK NAME	
BRANCH NAME WITH COMPLETE ADDRESS, TELEPHONE NUMBER AND EMAIL	
WHETHER THE BRANCH IS COMPUTERISED	
WHETHER THE BRANCH IS RTGS ENABLED? IF YES , THEN WHAT IS THE BRANCH'S IFSC CODE	
IS THE BRANCH ALSO NEFT ENABLED	
TYPE OF BANK ACCOUNT(SB/CURRENT/CASH CREDIT WITH 10/11/13)	
COMPLETE BANK ACCOUNT NUMBER	
MICR CODE OF BANK	
NAME AND ADDRESS OF THE BENEFICIARY/PAYEE	
IFSC(INDIAN FINANCIAL SYSTEM) CODE	

C. DATE OF EFFECT:-

I hereby declare that the particulars given are correct and complete. If the transaction is delayed or not effected at all for reasons of incomplete or Incorrect Information, I would not hold the user Institution responsible. I have read the option Invitation letter and agree to discharge responsibility expected of me as a participant under the Scheme.

Date: _____
(.....)
Signature of Customer

Certified that the particulars furnished above are correct as per our records.
(Bank's stamp)

Date: _____
(.....)
Signature of the Authorized Official from the Bank

1. Please attach a photocopy of cheque along with the verification obtained from the Bank
2. In case your Bank Branch is presently not "RTGS enabled" then open its upgradation to "RTGS Enabled" branch. Please submit the information again in the above Proforma to the Department at the earliest.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

NON BLACK LISTING CERTIFICATE

1. I _____ Son of Shri _____ age about _____ by
profession proprietor/ partner of M/s _____ having registered office at
_____ do hereby solemnly affirms and declare as under :-

- (a) Undertakes to the effect that any Government Organisation(s) have not blacklisted our firm.
- (b) I am not Proprietor/ Partners/ Director of any other firm or business with whom Government has banned / suspended business dealing.
- (c) I do not have any concern/ subsidiaries, blacklisted by Government Organization.
- (d) **All works have been completed within PDC and no work / works is / are laying pending / sick / delayed.**

Company Seal

(Authorised Signatory of Company)

Place: _____

Date: _____

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

FORM OF SOLVENCY FROM A SCHEDULED BANK

This is to certify that the M/s _____ is maintaining current Account No _____ with us. Proprietor of M/s _____ having address _____, is a respectable customer of this branch. To our information, M/s _____ is considered financially sound for any procurement/engagement up to Rs. _____ (Rupees _____ only).

IFSC Code :

MICR Code :

Bank Seal

(Authorised Signatory of Bank)

Place : _____

Name : _____

Contact No. of Bank: _____

Designation : _____

Date : _____

Employee No : _____

Contact No. : _____

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

GUARANTEE/ WARRANTY

Except otherwise provided in the invitation to tender, the contractor hereby declares that the goods/ works/ articles/ equipment sold/ supplied to the purchaser/ consignee under this contract shall be of **best quality and workmanship and new** in all respects and shall be strictly in accordance with the specification and particulars mentioned/contained in the contract. The contractor hereby guarantees that the said goods/ works/ articles would continue to confirm to the description and quality aforesaid for a period of **SIX MONTHS** from the date of receipt of goods/works/articles/equipment in good condition at site by the consignee in case of supply contract and **TWELVE MONTHS** from the date of installation and satisfactory taking over of the goods/works/articles/equipment at site by consignee where installation and commissioning is involved and notwithstanding the fact and the purchase/inspection authority has inspected and/or approved the said goods/works/articles/equipment or such if during the **TWELVE MONTHS** the said goods / stores / articles / equipment be discovered not to confirm to the description and quality aforesaid or not giving satisfactory performance or have deteriorated and the decision of the purchase/consignee in that behalf shall be final and binding on the contractor/seller and the purchaser shall be entitled to call upon the contractor / seller to rectify the goods / stores / articles / equipment or such portion thereof as is found to be defective by the purchasers within the reasonable period or such specified period as may be allowed by the purchaser in his discretion on application made thereof by the contractor/seller, and in such an event, the above period shall apply to the goods/stores/articles/equipment rectified from the date of rectification mentioned in the warranty thereof, otherwise the contractor /seller shall pay the purchaser such compensation as may arise by reason of the breach of warranty therein contained.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

PENALTY FOR USE OF UNDUE INFLUENCE

The seller should undertake that he has not given, offered or promised to give directly or indirectly any gift, consideration, reward, commission, fees brokerage of inducement to any person in service of the Purchaser or otherwise in procuring, the Contact or Forbearing top do or for having done or forborne to do any act in relation or execution of the Contract or any other Contact with the Government for showing or forbearing to show favor or disfavor to any person in relation to the Contact or any other Contact with the Government. Any breach of the aforesaid undertaking by the seller or any one employed by him or acting on is behalf (whether with or without the knowledge of the seller) or the commission of any offers by the seller or any one employed or acting on his behalf, as defined in Chapter IX of the Indian Penal Code, 1860 or the Prevention of Corruption Act, 1947 or any other Act enacted for the prevention of corruption shall entitle the Purchase to cancel the contact and all or any other Contact with the seller and recover from the Seller the amount of any loss arising from such cancellation. A decision of the Purchaser or his nominee to the effect that a breach of the undertaking had been committed shall be final and binding on the seller.

Giving or offering of any gift, bribe or inducement or any attempt at any such act on behalf of the seller towards any officer/employee of the Purchaser or to any other person in a position to influence any officer/employee of the Purchaser for showing any favor in relation to this or any other contact, shall result in rejection of the bid.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

EARNEST MONEY DEPOSIT (EMD) IN FORM OF FDR/ BANK GUARANTEE/ TDR
(SCAN COPY WITH ONLINE BID/
ORIGINAL COPY TO BE DEPOSITED AS PER PARAGRAPH 12 OF PAGE 2 OF TENDER DOCU)

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Enlistment/Renewal letter of Assam Rifles approved contractor and enlisted contractors working with other Central Government department/organization meeting eligibility criteria of contractor in any Govt Department (to be uploaded)

Appendix-'10'

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

AMENDMENTS IN TENDER DOCUMENTS AND ENLISTED CLASS OF CONTRACTORS

1. Following changes incorporated as suggested vide Ministry of Finance OM No. F.9/4/2020-PPD dt 12 Nov 2020.

(a) **Performance certificate.** Performance Security should be 5% of the value of the contract.

2. Please incorporate the upper tendering limit and bank solvency in the NIT as per para 3 of the SOP of enlistment of the contractors of Assam Rifles reproduced blow:-

<u>Ser</u>	<u>Class</u>	<u>Upper Tendering limit</u>	<u>Bank Solvency</u>
(a)	S	Rs. 800 Lakhs	Rs. 240 Lakhs
(b)	A	Rs. 200 Lakhs	Rs 60 Lakhs
(c)	B	Rs. 100 Lakhs	Rs. 30 Lakhs
(d)	C	Rs. 50 Lakhs	Rs. 15 Lakhs
(e)	D	Rs. 25 Lakhs	Rs. 7.50 Lakhs

3. Past performance to be restricted to 3 years instead of 5 years.

4. Validity of enlistment to be clearly specified in the NIT.

5. Details as per SOP for enlistment of contractor reproduced below:-

<u>Class</u>	<u>Past experience of completed works in last 7 years</u>	<u>Financial Soundness</u>	<u>Engineering Establishment</u>
'S'	Three works costing not less than Rs.320 lakhs each or Two works costing not less than Rs.400 lakhs each or One work costing not less than Rs.640 lakhs each or Average annual turnover for three consecutive years shall not be less than Rs. 240 lakhs	(a) Solvent upto Rs. 240 lakhs or Financially sound for engagement up to Rs.800 lakhs (b) Working capital not less than Rs.40 lakhs	(a) One graduate Engineer from a Government recognized institution with minimum experience of 5 years And (b) Two diploma Engineer from Government recognized institution with minimum experience of 05 years.
'A'	Three works costing not less than Rs.80 lakhs each or Two works costing not less than Rs.100 lakhs each or One work costing not less than Rs.160 lakhs each or Average annual turnover for three consecutive years shall not be less than Rs.60 lakhs	(a) Solvent upto Rs. 60 lakhs or Financially sound for engagement up to Rs.200 lakhs (b) Working capital not less than Rs.10 lakhs	(a) One graduate Engineer from a Government recognized institution with minimum experience of 5 years And (b) One diploma Engineer from Government recognized institution with minimum experience of 05 years.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

<u>Class</u>	<u>Past experience of completed works in last 7 years</u>	<u>Financial Soundness</u>	<u>Engineering Establishment</u>
'B'	Three works costing not less than Rs.40 lakhs each or Two works costing not less than Rs.50 lakhs each or One work costing not less than Rs.80 lakhs each or Average annual turnover for three consecutive years shall not be less than Rs.30 lakhs	(a) Solvent up to Rs.30 lakhs or Financially sound for engagement up to Rs.100 lakhs (b) Working capital not less than Rs.5 lakhs	One graduate Engineer from a government recognized institution with minimum experience of 5 years And One diploma Engineer from Government recognized institution with minimum experience of 05 years.
'C'	Three works costing not less than Rs. 20 lakhs each or Two works costing not less than Rs. 25 lakhs each or One work costing not less than Rs.40 lakhs or Average annual turnover for three consecutive years shall not be less than Rs.15 lakhs	(a) Solvent upto Rs.15 lakhs Or Financially sound for engagement up to Rs.50 lakhs (b) Working capital not less than Rs.2.5 lakhs	One graduate Engineer from a government recognized institution with minimum experience of 3 years Or One diploma Engineer from Government recognized institution with minimum experience of 5 years.
'D'	Three works costing not less than Rs. 10 lakhs each or Two work costing not less than Rs. 12.50 lakhs each or one work costing not less than Rs. 20 lakhs each or Average annual turn over for three consecutive years shall not be less than Rs.7.5 lakhs	(a) Solvent upto Rs.7.5 lakhs Or Financially sound for engagement up to Rs.25 lakhs (b) Working capital not less than Rs.1.25 lakhs	One graduate Engineer from a government recognized institution with minimum experience of 2 years Or One diploma Engineer from Government recognized institution with minimum experience of 3 years.

Appendix-'11'

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

GSTIN REGISTRATION CERTIFICATE (TO BE UPLOADED)

Appendix-'12'

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SITE VISIT CERTIFICATE

It is certified that Sh. / Smt. _____ of
M/s _____ (Name of firm) has visited work site for
“ _____ ” (Name of
work) on _____ (date). He / She has been explained nature of work to be executed on
ground.

(Signature of Contractor / representative)

Signature with Company seal

Date :

(Signature of respective SO-1 (Wks) of location)

Signature with office stamp

Date :

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

SPECIAL CONDITIONS OF THE CONTRACT**1. General.**

(a) The following Special Conditions shall be read in conjunction with the General Conditions of contracts including upto date Errata/Amendments thereto. If any provision(s) in these Special Conditions is at variance with that of the aforesaid documents, the former shall be deemed to take precedence there over.

(b) The Work under this contract shall be carried out in accordance with Schedule 'A', particular specifications, drawings and other provisions given in General summary and general specifications/provisions given in CPWD Specifications 2019 Volume - 1 & Volume - 2.

2. Admission to Site by Contractor to Ascertain His Own Information.

(a) The tenderers shall contact the Staff Officer-I(Works) for the purpose of inspection of site(s) and relevant documents other than those sent herewith, who will give reasonable facilities for this purpose. The tenderers shall also make themselves familiar with working conditions, accessibility of site(s), availability of materials and other cognate conditions which may affect the entire completion of work under this contract.

(b) The tenderers shall be deemed to have visited the site(s) and made themselves familiar with the working conditions, whether they actually inspect the site(s) or not. No extra payment consequent on any mistake or misunderstanding or otherwise on this account shall be allowed.

3. Security and passes.

(a) Contractor shall employ only Indian Nationals after verifying their antecedents and loyalty. The contractor shall on demand by the Engineer-in-Charge, submit list of his agents, employees and work people concerned and shall satisfy the Engineer-in-Charge as to the bonafides of such people.

(b) The Engineer-in-Charge at his discretion has the right to forward the list of personnel's to Commandant (Adm) / Commanding Officer of formation/unit or any appropriate authority for issuing the passes as per rules and regulations of the area in force to control the admission of the contractor, his agents, employees and work people to the site of the work or any part thereof. Passes should be returned at any time on demand by the Engineer-in-Charge and or the authorities concerned and in any case on completion of work.

(c) Verification of antecedents of Contractor's representatives/labour deployed at site in connection with execution of work under the contract, as per security requirement shall be the responsibility of the contractor and all expenses in connection with verification of antecedents by Police Authorities/Security Agency shall be borne by the Contractor. No claim whatsoever on this account shall be entertained by the department.

(d) The contractor and his agents, employees and work people shall observe all the rules promulgated by the authority controlling the area in which the work is to be carried out, e.g., prohibition of smoking and lighting, fire precautions, search of persons on entry and exit, keeping to specific routes, observing specified timing etc. Nothing extra shall be admissible for any man-hours etc lost on this account.

(e) **Identity Cards or Passes.** The contractors, his agents and representatives are required individually to be in possession of an identity card or pass duly verified by the police department. The identity card or pass will be examined by the security staff at the time of entry into or exit from site and also at any time or number of times at site.

(f) Contractor shall be responsible for the conduct and action of his workmen, agents or representative. Thorough search of all persons and transport shall be carried out at each gate and for as many times as a gate is used for entry or exit and may also be carried out at any time or any number of times at the work site.

4. Fire Precautions.

(a) The contractor, his agents, representatives, workmen etc, shall strictly observe the orders pertaining to fire precautions prevailing within the restricted area.

(b) Motor transport vehicles, if any, allowed by authorities to enter the area must be fitted with serviceable fire extinguishers.

5. Minimum Wages Payable.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

(a) The contractor shall not pay wages lower than minimum wages for labour as fixed by the Govt of India/State Govt whichever is higher.

(b) The contractor shall have no claim whatsoever, if any on account of local factor and/or Regulations, he is required to pay the wages in excess of minimum wages as described above during the execution of work.

6. **Royalties.** The contractor shall deposit royalty and obtain necessary permit for supply of bajri, stone, kankar, sand and other materials etc. from the local authorities and quoted rates shall be inclusive of royalty.

7. The rates and prices to be tendered in the BoQ (Bill of Quantities) are for completed and finished items of works and complete in all respects. It will be deemed to include all constructional plant, labour, supervision, materials, transport, all temporary works, erection, maintenance, contractor's profit and establishment/overheads, together with preparation of designs & drawings pertaining to casting yard, shop drawing, fabrication drawing (if required), staging form work, stacking yard, etc. all general risk, all taxes, royalty, duties, cess, octroi and other levies, insurance liabilities and obligations set out or implied in the tender documents and contract.

8. **Water.** Water will not be supplied by Assam Rifles. Good quality portable water suitable for construction purposes as per IS specification shall be used for construction at no extra cost.

9. **Cooperation with Other Agencies.** The contractor shall permit free access and generally afford reasonable facilities to other agencies or departmental workmen engaged by the Govt to carry out their part of the work, if any, under separate arrangements.

10. **Electric Supply.**

(a) Assam Rifles is not bound to supply Electricity to the Contractor for execution of work. However, where feasible, Assam Rifle may provide electricity supply.

(b) The contractor will be charged for the electric energy consumed at commercial rates laid down by the concerned State Electricity department.

(c) No additional payment shall be made to the contractor for any electricity charges paid by him/her for execution of work or otherwise to Assam Rifles or any other agency/department.

(d) The SO-1 (Works) or Engineer-in-Charge or persons authorised by them have free access to inspect all electric installations, connections, devices, appliances etc., and if these are not found satisfactory or not following safety norms, the electricity supply can be disconnected without any advance notice.

(d) Assam Rifles do not guarantee continuity of supply and no compensation whatsoever shall be allowed for supply becoming intermittent or for breakdown in the system.

11. **Time and Progress Chart (CPM Chart).**

(a) The time and progress chart to be prepared as per **Clause 5.1 (b) of General Conditions of Contract 2020 Construction Works of CPWD**, shall consist of detailed network analysis and a time Schedule. The critical path network will be drawn jointly by the Staff Officer-I (Works) and the contractor soon after acceptance of tender. The time scheduling of the activities will be done by the contractor so as to finish the work within the stipulated time. On completion of the time schedule a firm calendar date Schedule will be prepared and submitted by the contractor to the Staff Officer-I (Works) who will approve it after due scrutiny. The schedule will be submitted in four copies within two weeks from the date of handing over of site.

(b) During the currency of work, the contractor will adhere to the time schedule and this adherence will be a part of the contractor's Performance under the contract. During the execution of the work the contractor is expected to participate in the reviews and updating of the network under taken by the Staff Officer-I (Works). These reviews may be undertaken at the discretion of the Staff Officer-I (Works) either as a periodical appraisal measure or when the quantum of work ordered on the contractor is substantially changed through deviation orders or amendments. Any revision of the time schedule as a result of the review will be submitted by the contractor to Staff Officer-I (Works) within a week for the approval after due scrutiny by the authority concerned.

(c) The contractor shall adhere to the revised time schedule thereafter. In case of contractor disagreeing with revised schedule the same will be referred to the Accepting Officer whose decision shall be final, conclusive and binding. Staff Officer-I (Works's approval to the revised schedule resulting in a completion date beyond the stipulated date of completion shall not automatically amount to a grant

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

of extension of time. Extension of time shall be considered and decided by the appropriate authority and separately regulated.

(d) Contractor shall mobilize and employ sufficient resources to achieve the detailed schedule within broad framework of the accepted method of working and safety. No additional payment will be made to contractor for any multiple shift work or other intensive methods contemplated by him in his schedule, even though the time schedule is approved by the Staff Officer-I (Works).

12. **Record of Consumption of Cement.**

(a) The contractor shall maintain a hard bound register with serially numbered pages with all pages initialled by Engineer-in-charge against numbering showing quantities of cement received, incorporated in the work and balance at the end of each day. The form of record shall be as approved by Engineer-in-Charge. The register shall be signed daily by representatives of Assam Rifles and the contractor in token of verification of its correctness and will be checked by Engineer-in-Charge, at least once a week.

(b) The register shall be kept at site in safe custody of the contractor's representative during the progress of the work and shall be produced on demand for verification to the inspecting officer(s).

(c) On completion of the work the contractor shall deposit the cement register with the Engineer-in-Charge for record.

13. **Security of Classified Documents.** The contractor shall not communicate any classified information regarding the work to unauthorised persons without the prior written approval of the Engineer-in-Charge. The contractor shall also not make copies of the design/drawing and other documents furnished to him in respect of work, and shall return all documents on completion of the work or earlier on determination of the contract.

14. **Record of Materials**

(a) The quantity of materials such as paints, water proofing compound and the like, as directed by the Engineer-in-Charge (the quantity of which cannot be checked after incorporation in the works), shall be recorded in measurement books and signed by the contractor and the Engineer-in-Charge as a check to ensure that the required quantity has been brought to site for incorporation in the work.

(b) Materials brought to site shall be stored as directed by the Engineer-in-Charge recorded in Measurement Book and shall be suitably marked for identification.

(c) The contractor shall, on demand, produce to the Staff Officer-I (Works) original receipted vouchers in respect of the supplies. Vouchers so produced and verified shall be stamped by Engineer-in-Charge indicating contract number. The contractor shall ensure that the materials are brought to site in original sealed containers/packing; bearing manufacturer's marking except in the case of the requirement of material(s) being less than smallest packing.

15. **Materials and Samples**

(a) List of approved products / items for inclusion in work is attached as **Appx 'B'**.

(b) Refer Clause 10A of General Conditions of Contract, Construction Works of CPWD- 2020.

(c) The Tender is advised to ascertain the sample of the materials from SO-1 (Works) of formation Headquarters (IGAR HQ / Sector HQ). The Tenderer shall be deemed to have inspected the samples and satisfied himself as to the nature and quality of materials, he is required to incorporate in the work, irrespective of whether he has actually inspected or not. The materials to be incorporated in the work by the contractor shall conform to, or shall be superior in quality to the sample approved and shall comply with the specifications given here-in-after.

(d) The contractor shall not procure materials in bulk unless the samples are first approved by the SO-1 (Wks).

(e) The materials to be used shall comply with the requirement of the latest Indian Standard Code.

(f) The cost of testing of material shall be borne by the contractor and while quoting their rates this aspect shall be kept in mind and nothing extra shall be admissible on the account.

16. **Refund of Performance Security Deposit.** The Performance security deposit may be refunded to contractor after the expiration of the defect liability period by the Staff Officer-1(Works) provided always that the contractor shall first have been paid the final bill and have rendered a no demand certificate (IAFA-451).

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

17. **Official Secret Act.** Refer Condition 24 of IAFW-2249. The contractor's attention is invited to India Official Secret Act 1923 (xxx of 1923) particularly Sec 5 thereof. The contractor shall be bound by the provision of this Act.

18. **Cleaning Down.** The contractor shall clean all floors, walls remove cement, lime, paint marks, drops etc. clean the joinery glass panes etc touch up all painters work and carryout all other necessary items of work in connection there with and leave the whole premises clean and tidy before handing over the building(s) and other works covered under this contract.

19. **Details of Construction.** The quoted rates shall be deemed to include for minor details of construction which are obviously and fairly intended and are essential for completion of the work but may not have specially been referred to in these documents. In the event of disputes the decision of the Accepting Officer shall be final, binding and conclusive.

20. **Damage to Existing Works.** Any damage done to existing structure during the execution of works shall be made good by the contractor at his own cost and site of works left clean and tidy on completion. Rectification or reinstatement making good etc. shall conform to the standard of materials originally used in the finished work shall match with existing work in all respect to the entire satisfaction of the Engineer-in-Charge and SO-1(Works). In case of any dispute on this account, the matter shall be referred to the Chief Engineer whose decision in writing shall be final and binding.

21. **Octroi/Sales Tax/GST and other Duties.** Contractor's rates shall be deemed to be inclusive of all duties such as Octroi, Sales Tax, excise, VAT/GST etc. as given in General Conditions of Contract and state Govt sales tax/GST on works contracts payable under respective statutes pursuant to the Constitution (Forty sixth amendment) Act 1982. Any condition stipulated by the tenderer regarding sales tax/GST on works contracts will not be considered and such tender shall be liable for rejection.

22. **Construction Labour Welfare Tax.** The quoted rates by the tenderers shall be deemed to be inclusive of construction labour welfare tax and no extra payment shall be admissible to the contractor on this account.

23. **Recovery Charge for Testing of Materials.** Where testing of contractor's material is carried out in Zonal/NABL accredited Lab/National Test House/nearest NIT / nearest IIT / Engineering Colleges by the Department, the contractor shall be liable to pay the testing charges, which shall be recovered from the Contractor's Running payment/Final Bill as the case may be.

24. **Force Majeure.**

(a) Should any force majeure circumstances arise, each of the contracting party shall be excused for the non-fulfilment or for the delayed fulfilment of any of its contractual if the affected part within 15 days of its occurrence informs the other party in writing.

(b) Force Majeure shall mean fires, floods, natural calamities or other acts such as war, turmoil, strikes (as not limited to be establishment of the seller), sabotage, explosions, quarantine restrictions beyond the control of either party.

(c) It is understood and agreed between the parties hereto that the right and obligations of the parties shall be deemed to be in suspension during the continuance of the force majeure event as aforesaid and the said rights and obligations shall automatically revive upon the cessation of the intervening forces majeure vent the period within the rights and obligation of the parties shall be in suspension due to force majeure event shall not be considered as a delay with respect to the period of deliver and/or acceptance of delivery under the contract or other to the detriment of either party.

(d) Notwithstanding the provisions of the immediately for clauses it is further understood and agreed between the party hereto that in the event of any force majeure persisting for uninterrupted period exceeding (06) Six months, on their part reserves the right to terminate this contract upon giving prior written notice of 30 (Thirty) days to the other party of the intention terminate without any liability other than reimbursement on the terms provided in their agreement for the goods received.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

PARTICULAR SPECIFICATIONS

1. General Requirements.

1.1. The Work under this CONTRACT shall be carried out in accordance with SCHEDULE 'A' (BOQ), PARTICULAR SPECIFICATIONS, DRAWINGS and General Specifications and other provisions in CPWD Specifications 2019 Volume - 1 & Volume - 2 read in conjunction with each other.

1.1.2. General Specifications referred to/mentioned in GENERAL CONDITIONS OF CONTRACTS mean Specifications including Amendments and Errata as applicable.

1.1.3. Materials & Workmanship required for these Works/Services shall be as described against 'Specifications & Workmanships' in the various Trade/Sections of the CPWD Specifications 2019 duly modified by these Particular Specifications here-in-after.

1.1.4. Reference to some Paragraphs of CPWD Specifications 2019 has been made in these Particular Specifications, but other Paragraphs and Provisions as applicable are also to be followed e.g. reference to Clause No. pertaining to General Workmanship for Brick Masonry, Joinery, Iron and Steel Work, etc. have not been made but provisions therein as required for the work are applicable.

1.1.5. Provisions contained in the CPWD Specifications 2019 Volume – 1 & Volume - 2 in the Preambles to the relevant Items of SCHEDULE 'A' (BOQ) shall also be read in conjunction with the Provisions contained in these documents.

1.1.6. Where Specifications/Provisions for any Item of Work given in these Particular Specifications are at variance with the Provisions/Specifications given in CPWD Schedule, Specifications/Provisions given in these Particular Specifications shall be followed. However, for pricing of Deviation Orders, Rates given in DSR shall be adopted.

1.1.7. Where Specifications for any Item of Work are not given in CPWD Specifications 2019 or in these Particular Specifications, Specifications given in relevant Indian Standard Specifications or Code of Practice shall be followed.

1.1.8. Particular Specifications given here-in-after shall be read in conjunction with the Provisions in the CPWD Specifications 2019 and relevant Bureau of Indian Standards referred to thereto and in these Particular Specifications. In case of any discrepancy, the Provisions in these Particular Specifications shall take precedence.

1.1.9. Materials/Accessories/Equipments for which MAKE have not been specified in these Particular Specifications, shall be of BIS Makes and shall strictly comply with Current Appropriate BIS Specifications, for which BIS Specification has not been issued/available, they shall comply with the Currents BS Specifications or as approved by Engineer-in-Charge.

1.1.10. These Particular Specifications shall deem to be included the APPENDICES attached here-in- after.

2. **Making Good.** The contractor shall cut, leave or form holes, recesses, chases etc, in concrete, brick work, walls, ceiling, floors and in any other situations as required or as directed by the Engineer-in-Charge and finish to match the adjoining surfaces.

3. Scope of Work.

3.1. This Contract includes for the full, final and entire completion of Works described in SCHEDULE 'A' (BOQ) including Schedule 'A' Notes thereon and specified in these Particular Specifications forming part of the Tender documents.

3.2. Tenderers are advised to visit the SITE (S) and ascertain for themselves the exact scope of Work and its Working Conditions, viz Working Hours, Availability of Site(s), etc. and quote their Tenders accordingly. Any Claim whatsoever, on such/these accounts will not be entertained by the Government at a later Date/Stage.

4. Site of Work

4.1. The Works shall be carried out at different Locations/Site(s). The Contractor shall finalize the programme with the Engineer-in-Charge well in advance in such a way that neither the USERS feel inconvenience nor Work is delayed.

4.2. The proposed Location as shown on site plan of Various Works shall be as directed by the Engineer-in-Charge at Site(s) of Works.

5. Visit to Site

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

5.1. The Tenderers are advised to contact Staff Officer-1 (Works) on any Working Day during Working Hours, who will arrange for their visit to work site.

5.2. The Tenderer shall be deemed to have visited the Site of Work before Quoting their UNIT RATES and no Claim for any EXTRA PAYMENT on account of any misunderstanding, etc. will be entertained by the Department, irrespective of the fact whether they have actually visited the Site or not.

6. **Materials**

6.1 **General**

6.1 All Materials to be supplied by the Contractor for incorporation in the Work shall conform to relevant IS Specifications. In case Specification of any Materials needed for incorporation in work is not contained in any of the Contract Documents, the Specification of such Materials/Articles to be incorporated in work shall be got approved in writing from the Staff Officer-1(Works) before their incorporation in work by the Contractor without any Price Adjustment.

6.2. The relevant Bureau of Indian Standards shall be of Latest Revision including Amendments if any. The Contractor shall incorporate in the work Materials complying with the requirements of relevant Bureau of Indian Standards of the Latest Publication (Edition) including all amendments/revision issued by Bureau of Indian Standards on and before bid submission end date, thereof without any Price Adjustment in the Quoted Rate.

6.3. As far as practicable all manufactured Materials/Articles other than those manufactured in Contractor's Workshop at Site shall bear IS Certification Marks. In case, any Article not bearing IS Certification Marks but conforming to relevant Specification is proposed to be incorporated in the Work, Samples of the same shall be got approved in writing from Engineer-In-Charge before their incorporation in work. The Contractor shall submit sufficient evidence to the Staff Officer-1(Works) to show that such Articles conform to the relevant Specifications and no Price Adjustment shall be made on this account.

6.4. Manufactured Materials/Articles shall be brought at Site in Original Sealed Containers/Packing bearing Manufacturer's marking unless the quantity required is a fraction of smallest packing.

6.5. The Contractor shall carry out such Instructions that are given to him in Writing by the Engineer- in-Charge to ensure that Full Quantity of such Materials goes in to Work.

6.6 **Anti-Termite Treatment.**

6.6.1 Materials of Proprietary nature such as Paints, Water Proofing Compound, Chemicals for Anti- Termite Treatment and the like, quantity of which cannot be checked after incorporation in the work shall be measured and recorded in the MEASUREMENT BOOK as soon as those are brought at Site. These Measurements shall be signed both by the Engineer-in-Charge and the Authorised Representative of the Contractor. ORIGINAL STAMP RECEIPTED BILLS along with the relevant INVOICES from the Manufacturers or their Authorised Dealers (if any) in support of having brought the full quantity required for incorporation in the Work, shall be produced to Engineer-in-Charge.

6.6.2 Anti-termite (post treatment only) with minimum 5 years warranty shall be catered in existing / new construction buildings, and for those items which are likely to be infested by termite. Engineer-in-Charge shall witness the process of anti-termite treatment. Proper GST bill along with empty anti-termite containers cans to be deposited with the Engineer-in-Charge for destruction.

7. **Approved Makes/Brand of Materials.**

7.1. Materials/Accessories/Equipment for which MAKE have not been specified in these Particular Specifications, shall be of Standard Makes and shall strictly comply with Current Appropriate BIS Specifications, for which IS Specification has not been issued/available, they shall comply with the Currents BIS Specifications or as approved by SO-1(Wks) of respective HQ IGAR/ HQ Sector Assam Rifles.

7.2. A list of certain items for which specific manufacturers/ make only are to be provided in this contract are given in **Appendix `J`**.

8. **Approved Sources of Local Origin Materials Meeting Provisions of Relevant IS Code.**

8.1. The Sources and Sample for materials such as Bricks, Aggregates, etc., shall generally conform to relevant Specifications given in the Tender documents. all such Materials shall be got approved from SO-1(Wks) of respective HQ IGAR/ HQ Sector Assam Rifles in writing before these Materials are brought at Site in bulk.

8.2. Contractor at his own may procure materials from any other sources without any extra cost to the Department provided that the same conform to respective IS as stated here-in-before.

9. **Approval of Samples/Materials.**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

9.1. Approval of Samples/Materials by Engineer-In-Charge shall be recorded in a Register labelled as 'SAMPLE APPROVAL REGISTER' to be maintained by the Engineer-in-Charge which interalia shall mention Sources of Supply, Name of Manufacturer, Trade Name/Brand (if applicable) and reference to Clause of Tender Documents containing Specifications of Particular Materials.

9.2. Letters conveying Approval of Samples/Materials by Engineer-In-Charge shall interalia mention sources of Supply, Name of Manufacturer, Trade Name/Brand (if applicable) and reference to Clause of Tender documents containing Specifications of Particular Materials.

10. **Testing of Material.** SO-1 (Works) at regular intervals shall carry out random testing of samples of material supplied / construction material being used by the contractor. Material testing will be carried out by the SO-1 (Works) at the site labs established. If site lab established is not capable of testing a particular type of material, SO-1 (Works) will send sample of material to nearest NABL accredited laboratories, National Test House, Regional Research labs, IITs, National Institutes of Technology, Govt Engineering College or any Govt laboratories Government laboratories.

11. **Standard of Quality & Workmanship.**

11.1. **General**

11.2. The Work shall strictly comply with the provisions contained in the Latest Edition of INDIA STANDARD CODE OF PRACTICE and/or IS SPECIFICATION as applicable, Works except where such Regulations and Rules are modified by these Particular Specifications.

11.3. All Works shall be carried out properly by Skilled Tradesmen. The Contractor on demand shall produce such evidence of Qualifications of his Workmen/Skilled Tradesmen/Supervisors / Engineers, either at the commencement of Work or at any time thereafter/during currency of the Contract. The entire Work shall be High Class with the best Workmanship and to the entire satisfaction of Engineer-in-Charge.

12. **Excavation & Earth Work**

12.1. **Excavation in Trenches and Over Areas**

12.1.1. Excavation in Trenches and Over Areas shall be carried out as described in Clause No. 2.13 to 2.18 of CPWD Specifications 2019- Part 1.

12.1.2. Excavation shall be restricted to Dimension as shown on Drawings and as specified in Schedule. Excavation made if any, in excess of required Depth/ Authorised Width shall be made good by the Contractor with Cement Concrete 1:5:10 (40 mm graded crushed stone aggregate) without any Extra Cost to the Govt.

12.1.3. In case of Excavation in Hard Rock, Extra Depth of Excavation in excess to the required Depth shall be made with Cement Concrete 1:4:8 (40 mm graded crushed stone aggregate) without any Extra Cost to the Govt.

12.1.4. Beds of the Trenches/Column shall be watered and well rammed and any depression thus formed shall be filled with approved earth as required and level and slope as directed by the Engineer-in-Charge.

12.1.5. If hard strata are met with, which can neither be treated as the Soft rock nor Hard rock within the definition of CPWD Specifications, the same shall be treated as Hard soil.

12.1.6. If Rock (Soft/Disintegrated and Hard) is met at Site, Contractor shall immediately notify the facts to Engineer-In-Charge in writing.

12.1.7. **Hard Rock.** Blasting is **NOT PERMITTED** at site unless until specified in the Contract Document and approved by the SO-1 (Works).

12.2. **Bailing and Pumping**

12.2.1. A Tenderer shall ascertain himself the Level of Sub-Soil Water at Site of Work to allow in his Tender for any Bailing and Pumping out of Water, etc. as per Site Condition. Bailing and pumping out of Water, if required, will be done as described in Clause No. 2.21.1 of CPWD Specifications 2019 Vol 1. No Extra Payment shall be admissible for the above-mentioned operations. In the event of Deviation, no Adjustment shall be made for Cost of Bailing, Pumping and De-watering as specified here-in-before.

12.2.2 Bailing or pumping out water, accumulated in excavation, due to rains is included under respective items of earthwork and is not to be paid separately.

12.3. **Filling in Trenches.**

12.3.1. Refer Para 2.23 and sub paras of 2.23 of CPWD Specifications 2019 Part

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

12.4. **Removal of Surplus Soil.**

12.4.1. Surplus Soil and/or Rubbish obtained from Excavation shall be disposed unless otherwise specified in Particular Specifications here-in-after, upto a distance as specified in Sch 'A' BOQ items at the Location(s) as directed by Engineer-in-Charge, deposited, spread and levelled.

12.4.2. Soil/earth obtained from excavation shall be used for returning filling in places where any other type of filling like moorum/sand is not specified or shown in drawings after separating it from grass, vegetations and other foreign materials.

13. **Hard Core.**

13.1. Hard core shall consist of broken stone aggregate of gauge not exceeding 63 mm and shall be well graded so that after consolidation it provides a dense and compact sub grade. Hard core shall be spread, watered well rammed and consolidated. The thickness of Hard core shown in Drawings/ Schedule 'A' shall be thickness after consolidation.

14. **Cement Concrete Work.**

14.1. **Materials**

14.2. **Cement.** Refer paras 3.1.2 and sub paras 3.1.2.1 to 3.1.2.6 of CPWD Specifications 2019 Part 1.

14.2.1. **Type of Cement.** Cement shall be Ordinary Portland cement Grade 43 conforming to IS: 8112 of 2013 or Portland Pozzolona cement conforming to IS 1489.

14.2.2. The following checks and procedures shall be followed before the cement supplied by the contractor is accepted and is approved for incorporation in the works.

14.3. **Procurement.**

14.3.1. Cement incorporated by the contractor shall be procured from main producers (OEM) of cement and the date of manufacturing shall be within six weeks from date of delivery at site.

14.3.2. The approved main cement manufacturers companies of OPC and PPC are given as Appendix 'B'.

14.3.3. The following conditions shall have to be satisfied before PPC shall be allowed to be used in the work:-

- (a) PPC should meet the strength criteria of 43 Grade OPC as laid down in IS-8112- 2013.
- (b) The minimum period before striking off form work while using PPC shall be as given in relevant PS clause here-in-after.
- (c) In cold climate regions where temperature is lower than 15^o C only OPC shall be used.
- (d) **Mixing of OPC and PPC shall not be allowed in a work.**
- (e) While procuring PPC, the following requirements are to be ensured and certificate to the effect is to be obtained by the contractor for each batch from the manufacturer and the same shall be submitted to the Staff Officer-1(Works) for approval to procure PPC :-
 - (i) The quality of fly ash is strictly as per IS-1489(Part-I)- 2002.
 - (ii) Fly ash is inter-ground with clinker not mixed with clinker.
 - (iii) Dry fly ash is transported in closed containers and stored in silos. Only pneumatic pumping have been used.
 - (iv) The fly ash received from thermal power plants using high temperature combustion above 1000 o C have been used.

14.3.4 The particulars of the manufacturer /main producer of cement along with the date of manufacture shall be submitted by the contractor for every lot of cement separately. The documents in support of purchases of cement shall be verified by the Engineer-in-Charge and Staff Officer-1 (Works).

14.4. **Storage.**

14.4.1. There will be two separate godowns with proper dunnage provided by contractor at site of works exclusively for storage of cement :-

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

14.4.2. "First Godown" will have the cement lot(s) for which independent testing is to be got done and/or under process.

14.4.3 "Second Godown" will have the cement lot(s) whose independent testing has been got done and which after successful testing stands approved by Staff Officer-1 (Works) for incorporation in the work.

14.4.4 Cement shall be stored over dry platform with gap of 20 cm from walls around and at least 20 Cm high from floor level. Godowns shall have easy access for proper inspection and cement shall be protected from dampness/moisture to minimise storage deterioration or intrusion of foreign matter.

14.4.5 Both the godowns shall be provided with two locks on each door. The key of one lock at each door shall remain with the Engineer-in-Charge or his representative and that of the other lock with the contractors' authorised agent at the site of works so that cement is removed from the godown only according to the requirements for independent testing purposes or for daily consumption purposes with the knowledge of both the parties.

14.5. Testing of Cement

14.5.1. Contractor shall submit particulars of manufacturer of cement along with the date of manufacture for every lot of cement separately. The manufacturer is to carry out inspections and testing of cement in accordance with the relevant BIS provisions. Contractor shall also submit manufacturer's test certificates in original alongwith the test sheet or an authenticated copy thereof giving results of each physical test as applicable and the chemical composition of cement. The documents giving above particulars shall be verified by Engineer-in-Charge and Staff Officer-1(Works) in support of the purchases of cement and these details shall be recorded in the Cement Acceptance Register as per proforma given in Appendix 'D' to the tender documents here-in-after.

14.5.2. The Staff Officer-1 (Works) of respective HQ IGAR / HQ Sector Assam Rifles shall organise independent testing of random samples of cement drawn from the various lots which shall be got tested by the contractor under his own arrangements and the cost of both materials and labour required for sampling, testing, packing, transportation of samples to the testing places and testing charges thereof, and for subsequent identification of cement sampled, shall be borne by the contractor. The independent testing shall be got done from any of the following where facilities exist for all the tests required, viz, National Test House, Regional Research labs, IITs, National Institutes of Technology, NABL laboratories, Govt Engineering College or Any Govt laboratories.

14.5.3. The independent testing shall be got done as per :-

- | | | | |
|-----|----------|---|--|
| (a) | IS--3535 | : | Method of sampling hydraulic cement. |
| (b) | IS-4031 | : | Methods of Physical test for hydraulic cement. |
| (c) | IS-4032 | : | Method of chemical analysis of hydraulic cement. |

The other relevant IS shall also be followed. However the tests shall be restricted to those indicated in Appendix 'E' to the tender documents here-in-after.

14.5.4. The above tests shall be independent tests. The samples shall be taken immediately within one week of delivery at the site of works and all the tests got carried out by contractor within one week of sampling. In case it is not possible to test the samples within one week, the samples shall be packed and stored in air tight containers as decided by Staff Officer-1 (Works) of respective HQ IGAR / HQ Sector Assam Rifles till such time that they are tested.

14.5.5. The entire lot(s) of Cement shall stand rejected; if it does not comply with any of the requirement of IS specifications and the test results on samples are not within the acceptable limits. The rejected lot(s) shall be removed from the site of works by the contractor under their own arrangement and cost. The cost of tests shall be borne by the contractor irrespective of the results.

14.5.6. The contractor shall use only **one type brand** of cement for entire structural/reinforced concrete work. In the event of contractor desiring use of any different brand of cement, fresh design mix shall be carried out and submitted for approval without any extra cost to the Govt.

14.6. Documentation

14.6.1 The contractor shall submit original paid vouchers from the main manufacturers for the total quantity of cement supplied under each consignment brought to the site of work.

14.6.2. All consignments so received at the work site shall be inspected by Engineer-in-Charge alongwith the relevant documents for permitting storage in the "first godown" defined here-in-before.

14.6.3. The original vouchers and the test certificates shall be kept in record in the office of Engineer-In-Charge duly authenticated and with cross reference to the Control Number recorded in the Cement Register as per

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

format given in Appendix 'D' in the tender, maintained for "first godown" duly signed by the Engineer-in-Charge, and the contractor.

14.6.4. After the independent testing has been got done by Staff Officer-1 (Works) and satisfactory results obtained and kept on record, the consignment so got tested shall be removed from the "first godown" and transferred to "second godown" as defined here-in-before. Original vouchers and the test certificates submitted by the contractor alongwith the consignment and test certificates of independent testing shall be defaced by Engineer-in-charge and kept on record of Staff Officer-1 (Works) duly authenticated and with cross reference to the control Number rendered in the cement register maintained for the "Second Godown". This second register shall be termed as "Cement Acceptance Register" which shall be signed by JE (Civ) / Engineer-in-Charge and the contractor. Format of Cement supply and Acceptance register to be maintained is given at **Appendix 'C'** to this tender. Besides this the quantity of cement shall be also suitably recorded in the Measurement Book for record purposes before incorporation in the work and shall be signed by Engineer-in-charge and the contractor.

14.6.5. The Accepting Officer may order a Board of officers in which contractor shall also be a member for random check of cement and verification of connected documents.

14.6.6. Daily inspection shall be carried out by Engineer-in-charge or his representative and contractor's authorised agent and separate register shall be maintained in both the godowns duly indicating on daily basis the inspection carried out and indicating holding in godown at beginning of the day, inward supplies in the day, removal in the day and balance at the close of the day duly signed by above persons. In the removal column particulars of lot removed and purpose for which removed shall be indicated.

14.6.7. The purchase voucher and test certificate of manufacturer shall be linked and are to be defaced by the Engineer-in-Charge.

14.7 **Weighing and Payment for Cement.**

14.7.1. Random sample of 5 bags per 100 bags shall be got weighed by Engineer-in-charge in presence of representative of contractor from each consignment to arrive at average weight per bag for calculating total quantity of cement brought at site for incorporation in the work. All arrangement for weighing of cement bags including labour etc shall be provided by the contractor at their own cost.

14.7.2. The quantity of cement arrived at as aforesaid shall be considered for payment as applicable in accordance with General Conditions of Contracts.

14.7.3. Only when the test results of independent tests carried out on the cement are found satisfactory and it is permitted to be stored in the "Second Godown" and quantity entered in MB, then only this lot shall be considered for payment in RARs.

14.7.4. Payments shall be restricted as per provisions in clause "Advance on Account" of General Conditions of Contracts.

14.7.5 **Curing and Minimum Period for striking off form work when PPC** is used for RCC works in various locations, the minimum period for curing and striking off form work shall be as under:-

- | | | |
|-----|---|------------|
| (a) | Curing :- | |
| | (i) Structural RCC work | : 21 days |
| | (ii) PCC work, plastering etc | : 14 days |
| (b) | Striking off form work | |
| | (i) Walls, columns and vertical sides of beams | : 7 days |
| | (ii) Slabs (Props left under) | : 14 days. |
| | (iii) Beams soffits (Props left under) | : 14 days. |
| (c) | Removal of props to slab/beam | |
| | (i) Spanning upto 6 M Span | : 21 days |
| | (ii) Spanning beyond 6 M Span | : 28 days |
| (d) | For cantilever portion of slab form work with support shall be retained until the completion of the casting of the entire frame work of the building. | |

14.7.6 In case of bad weather, periods mentioned above may be revised at the discretion of the Engineer-in-Charge. The contractor shall be deemed to have considered the above provision before tendering and quote lump sum accordingly. No claim will be entertained if longer periods required for striking off form work and curing and all such effected matters are looked into upon the use of pozzolana cement as a result being issued to the contractor in full or part of for bad weather.

14.7.7 Curing shall be carried out using pump of suitable capacity at no extra cost to the Govt all as directed by Engineer-in-Charge.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

14.8 **Coarse and Fine Aggregate for Plain & Reinforced Cement Concrete**

14.8.1. Coarse aggregate for all concrete shall be graded crushed hard granite, trap or basalt stone as approved by the Staff Officer-1 (Works) and shall conform to the requirements laid down in clause 4.1.1.1(a) and 4.1.1.2 of CPWD Specification Part1. Hand broken stone aggregate shall not be permitted for use in the work. Size and grading of aggregate shall be as per clause 4.1.1.3 of CPWD Specification Part1.

14.8.2 **Grading of Aggregates**

14.8.3 **Grading of Coarse Aggregate**. Grading of Coarse Aggregate for Plain and Reinforced Concrete i.e. Stone Aggregate shall be as per clause 4.1.1.3 of CPWD Specification Part1.

14.8.4 Grading of Coarse Aggregate unless otherwise specified shall be as follows :-

- (a) For Reinforced/Structural Element of depth - 12.5mm or under graded (Max size) /thickness 50mm
- (b) For Reinforced/Structural Element of depth - 20mm graded (Max size) Over 50 mm
- (c) For Plain Cement Concrete thickness exc. - 20mm graded (Max size) 25mm but not exc. 75mm
- (d) For Plain Cement Concrete thickness 75mm - 40mm graded (Max size) and over
- (e) Lime Concrete - 40mm graded (Max size)

14.9 **Fine Aggregate / Sand**. Fine aggregate for all concrete work shall be naturally occurring river sand conforming to the specification in Para 3.1.3 of CPWD Specifications 2019. The maximum quantity of silt shall not exceed 8% by total volume. Fine aggregate / sand Use of sand conforming to grading Zone IV of IS 383 (1970 second revision or as amended) shall not be allowed for RCC works.

14.10 **Water Proofing Compound**

14.10.1 Integral water proofing compound shall conform to IS: 2645. The brand thereto shall be got approved in writing from the Staff Officer-1 (Works) before they are brought to site. Proportion of mix and method of mixing shall be as per manufacturer's printed instructions.

14.11. **Water**

14.11.1 Water shall conform to the requirement stipulated in IS-456. Water shall not contain any harmful chemicals which can adversely affect the strength and durability of RCC.

14.12. **Plasticiser**

14.12.1. Plasticiser shall be used in Design Mix Concrete as per the Manufacturer's instruction without any Extra Cost to achieve the desired Results Strength and Workability. Plasticiser manufactured by M/s SIKA INDIA Pvt. Ltd./ M/s BASF INDIA Ltd. / M/s CICO TECHNOLOGIES Ltd. / FOSROC CHEMICALS Pvt. Ltd. / MC BAUCHEMIE INDIA Pvt. Ltd. shall be used. However Plasticiser should confirm to IS-9103.

14.13. **Mix of Concrete**

14.13.1 **Design Mix Concrete**

14.13.1.1. M-30 Mix Design shall be carried out as per provisions of IS-456:2000/IS 3370/IS 2911 where as applicable and guidelines given in IS- 10262 and SP 23 with the following conditions unless otherwise specified :-

- | | | | |
|------|---|---|--------|
| (i) | Exposure Condition for Mix Design (M-30) | : | Severe |
| (ii) | Degree of Quality Control for Mix Design (M-30) | : | Good. |

14.13.1.2. For Design Mix Concrete of M-30 Grade, the Minimum Cement Content and water cement ratio shall be as per IS 456/IS 3370/IS 2911. The Contractor is required to Design each Grades of Concrete as per IS 456/IS 3370/IS 2911 and IS-10262 to work out the Cement Content of the above Grade of Design Mix.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

14.13.1.3. Design Mix shall be got designed from National Test House, Regional Research labs, IITs, National Institutes of Technology, Govt Engineering College. The Design Mix Concrete shall be approved by the Engineer-in-Charge prior to incorporation in the work.

14.13.1.4. The Design Mix furnished by the laboratory shall include the following details :-

- (a) Grading of individual coarse and fine aggregate used in Design Mix.
- (b) Proportion by weight of each component of aggregate of Design Mix.
- (c) Water cement ratio for recommended proportions of aggregates.
- (d) Slump and compaction factor values for the recommended Design Mix.
- (e) Use of plasticiser/ super plasticiser is permitted as per clause no 10.3.3 of IS 456-200.
- (f) Initial standard deviation to be adopted for acceptance criterion as per IS-456 of 2000.
- (g) 28 days Compressive strength of cement supplied for Design Mix.
- (h) Actual cement content in the Design Mix.
- (j) The maximum free water cement ratio shall be as per table 5 of IS 456-2000. Sampling and acceptance of concrete shall be as per clause 15 & 16 of IS-456 of 2000. The maximum size of aggregate for reinforced cement concrete shall be 20mm.
- (k) Recommendation of mixed proportions at site.

14.13.1.5. Cost of designing the mix shall be borne by the Contractor. All material required for carrying out the design shall be provided by the contractor at the laboratory.

14.13.1.6. In case contractor fails to submit the samples of design mix soon after commencement of work, the delay shall solely be attributable to the contractor and no claim of whatsoever nature shall be admissible on this account.

14.13.1.7. The Tenderer shall quote their Rate for the applicable Items considering the Actual Quantity of Cement required to be incorporated in the Work which is to be assessed by them.

14.13.1.8. No Plus DO (Deviation Order) shall be admissible even if the required/approved quantity of Cement is more than specified in IS 456/IS 3370/IS 2911. Contractor shall be responsible / guarantor to that provides M-25 and M-30 Design Mix Concrete. This shall not be considered as misrepresentation of fact and no claim what so ever on this provision shall be admissible.

14.13.1.9. The Contractor is advised to assess the realistic quantity of Cement for the Design Mix specified above before quoting. If considered necessary, they may get the Design Mix done on their own before quoting the Tender. However, the Design Mix done prior to quoting of Tender shall not be considered for incorporation in the Work after conclusion of Contract and shall have to be done as specified above.

14.13.1.10. A re-verification of Mix proportions for Design mix concrete shall be essential for any different brand of cement. With any change in aggregate source, mix design or grade of cement, fresh design mix shall be done by the contractor. Nothing extra shall be paid on this account. The decision of Staff Officer-1 (Works) regarding the necessity for re verification or redesign of mix will be final and binding.

14.14. **Batching**

14.14.1. Refer Clause No. 4.2.4.1 of CPWD Specifications. In case of batch mixing plant at site the grading of aggregate shall be controlled by obtaining the coarse aggregate in different sizes and blending them in right proportions, the different sizes being stocked in separate stock piles. The material should be stock-piled for several hours preferably a day before use. The grading of coarse and fine aggregate should be checked as frequently as possible, the frequency for a given job being determined by the Engineer-in-Charge to ensure that the specified grading is maintained.

14.14.2. Concrete for all PCC and RCC (design mix and nominal mix) shall be mixed in semi-automatic movable weigh batching machine of capacity as decided by Staff Officer-1 (Works) based on requirement at site. The batching machine shall have digital display weighing gauge with weighing accuracy of + 1% (One Percent). The machine shall be located in the vicinity of the site. The machine shall produce the concrete required as per mix design and complete quality assurance and control shall be maintained by the contractor in accordance to IS-456:2000 and best modern Engineering practice. The record of quality assurance tests shall be submitted to the Engineer-in-Charge for approval and record.

14.14.3. RMC plant shall be put to use in all those geographical areas where ISO certified automated RMC plants are available for RCC work of quantity **3 CUM** or above per day. Where requirement of concrete is less than 3 CUM in a day, the same can be mixed using normal weigh batcher and hopper type mixer.

14.15. **Form Work & Scaffolding**

14.15.1 **General**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

14.15.2 Form work shall comply with the requirements of clause No. 5.2 and subsequent clauses of CPWD Specifications Vol-1 I. The shuttering shall be of steel only except at places where it is not feasible to use steel shuttering on technical grounds plywood shuttering can be used with written approval of Staff Officer-1 (Works).

14.16.1. **Removal of Form Work**

14.16.1.1. Refer Clause No. 5.2.3.7 of CPWD Specifications 2019 Vol-1.

14.16.2.2. In case of Bad Weather, Periods mentioned here-in-above may be revised at the discretion of the Engineer-in-Charge. The Contractor shall be deemed to have considered the above provision before tendering and Quote Rate accordingly. No Claim will be entertained if Longer Periods required for Striking Off Formwork and Curing and all such effected matters is looked into upon the use of Pozzolana Cement as a Result being issued to the Contractor in Full or Part of for Bad Weather.

14.17. **Assembly of Reinforcement**. Refer Clause 5.3.1.1. of CPWD Specifications 2019 Vol-1 (as applicable) and as directed by the Engineer-in-Charge.

14.18. **Cover to Reinforcement**. Refer Clause No. 5.3.3.5 of CPWD Specifications 2019 Vol-1 (as applicable) and as directed by the Engineer-in-Charge as per severe exposure condition.

14.19. **Placing**. Refer Clause No. 5.4.2 and subsequent clauses of CPWD Specifications 2019 Vol-1 (as applicable) and as directed by the Engineer-in-Charge.

14.20. **Compaction**. Refer Clause No. 5.4.3.1 to 5.4.3.3 of CPWD Specifications 2019 Vol-1. Compaction of Concrete in RCC Slab, Beam Walls and Columns shall be done with Approved Mechanical Vibrator. In other Locations Hand Compaction may be permitted by Tamping or Roding as approved by the Engineer-in-Charge.

14.21. **Curing**. Refer Clause No. 5.4.6 of CPWD Specifications 2019 Vol-1 (as applicable) and as directed by the Engineer-in-Charge.

15. **Brick Work**.

15.1. **Materials**.

15.1.1. **Cement** . Cement shall be as specified for Cement Concrete Work here-in-before.

15.1.2. **Sand** . Sand shall be as specified in Cement Concrete Work here-in-before.

15.1.3. **Bricks**.

15.1.3.1. The Common Burnt Clay Bricks shall conform to IS:1077 and shall be hand moulded or machine moulded. They shall be free from nodules of free lime, visible cracks, flaws warpage and organic matter, have a frog 100 mm in length 40 mm in width and 10 mm to 20 mm deep on one of its flat sides. Bricks made by extrusion process and brick tiles may not be provided with frogs. Each brick shall be marked (in the frog where provided) with the manufacturer's identification mark or initials. The bricks should have minimum compressive strength of 75 Kg/Cm² when tested in accordance with clause 26 of IS-1077. The dimension of bricks when tested in accordance with clause no 6.2.1 of IS-1077 shall be within the following tolerance limits per 20 bricks:

For 250x 125x 75 mm	For 230x 115x 75 mm
(a) Length 4920 mm to 5080mm (5000±80 mm)	(a) Length 4520 mm to 4680mm (4600±80 mm)
(b) Width 2460 mm to 2540mm (2500±40 mm)	(b) Width 2260 mm to 2340mm (2300±40 mm)
Height 1460 mm to 1540mm (1500±40 mm)	(c) Height 1460 mm to 1540mm (1500±40 mm)

15.1.3.2. **Compressive Strength**: The bricks when tested in accordance with the procedure laid down in IS-3495 shall have a minimum average compressive strength as 75 Kg/cm² .

15.1.3.3. **Sampling and Tests**. Samples of bricks shall be subjected to the following tests :

- (a) Dimensional tolerance.
- (b) Water absorption.
- (c) Efflorescence.
- (d) Compressive strength.

15.1.3.4 **Sampling**: For carrying out compressive strength, water absorption, efflorescence and dimensional tests, the samples of bricks shall be taken at random according to the size of lot as given in Table above. The sample thus taken shall be stored in a dry place until tests are made. For the purpose of sampling, the following definition shall apply.

(a) **Lot**: A collection of bricks of same class and size, manufactured under relatively similar conditions of production. For the purpose of sampling a lot shall contain a maximum, of 50,000 bricks. In case a

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

consignment has bricks more than 50,000 of the same classification and size and manufactured under relatively similar conditions of production, it shall be divided into lots of 50,000 bricks or part thereof.

(b) **Sample:** A collection of bricks selected for inspection and/or testing from a lot to reach the decision regarding the acceptance or rejection of the lot.

(c) **Defective:** A brick failing to meet one or more of the specified requirements.

15.1.3.5. The samples shall be taken as below:

(a) Sampling from a Stack: When it is necessary to take a sample from a stack, the stack shall be divided into a number of real or imaginary sections and the required number of bricks drawn from each section. For this purpose, bricks in the upper layers of the stack shall be removed to enable units to be sampled from places within the stack.

Note: For other methods of sampling i.e. sampling in motion and sampling from lorries or trucks, IS :5454 may be referred. Scale of sampling and criteria for conformity for visual and dimensional characteristics: —

15.1.3.6. **Water Absorption:** The average water absorption of bricks when tested in accordance with the procedure laid down shall be not more than 20% by weight

15.1.4 **Laying:**

15.1.4.1 Bricks shall be laid in English Bond unless otherwise specified. For brick work in half brick wall, bricks shall be laid in stretcher bond. Half or cut bricks shall not be used except as closer where necessary to complete the bond. Closers in such cases, shall be cut to the required size and used near the ends of the wall. Header bond shall be used preferably in all courses in curved plan for ensuring better alignment.

Note: Header bond shall also be used in foundation footings unless thickness of walls (width of footing) makes the use of headers impracticable. Where thickness of footing is uniform for a number of courses, the top course of footing shall be headers.

15.1.4.2 All loose materials, dirt and set lumps of mortar which may be lying over the surface on which brick work is to be freshly started, shall be removed with a wire brush and surface wetted. Bricks shall be laid on a full bed of mortar, when laying, each brick shall, be properly bedded and set in position by gently pressing with the handle of a trowel. Its inside face shall be buttered with mortar before the next brick is laid and pressed against it. Joints shall be fully filled and packed with mortar such that no hollow space are left inside the joints.

15.1.4.3 The walls shall be taken up truly in plumb or true to the required batter where specified. All courses shall be laid truly horizontal and all vertical joints shall be truly vertical. Vertical joints in the alternate course shall come directly one over the other. Quoin, Jambs and other angles shall be pro-perly plumbed as the work proceeds. Care shall be taken to keep the perpends properly aligned within following maximum permissible tolerances:-

(a) Deviation from vertical within a storey shall not exceed 6 mm per 3 m height.

(b) Deviation in verticality in total height of any wall of building more than one storey in height shall not exceed 12.5 mm.

(c) Deviation from position shown on plan of any brick work shall not exceed 12.5 mm.

(d) Relative displacement between load bearing wall in adjacent storeys intended to be vertical alignments shall not exceed 6 mm.

(e) A set of tools comprising of wooden straight edge, masonic spirit levels, square, 1 metre rule line and plumb shall be kept on the site of work for every 3 masons for proper check during the progress of work.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

15.1.4.4. All quoins shall be accurately constructed and the height of brick courses shall be kept uniform. This will be checked using graduated wooden straight edge or storey rod indicating height of each course including thickness of joints. The position of damp-proof course, window sills, bottom of lintels, top of the wall etc. along the height of the wall shall be marked on the graduated straight edge or storey rod. Acute and obtuse quoins shall be bonded, where practicable in the same way as square quoins. Obtuse quoins shall be formed with squint showing three quarters brick on one face and quarter brick on the other.

15.1.4.5. The brick work shall be built in uniform layers. No part of the wall during its construction shall rise more than one metre above the general construction level. Parts of wall left at different levels shall be raked back at an angle of 45 degrees or less with the horizontal. Tothing shall not be permitted as an alternative to raking back. For half brick partition to be keyed into main walls, indents shall be left in the main walls.

15.1.4.6. All pipe fittings and specials, spouts, hold fasts and other fixtures which are required to be built into the walls shall be embedded, as specified, in their correct position as the work proceeds unless otherwise directed by the Engineer-in-Charge.

15.1.4.7. Top courses of all plinths, parapets, steps and top of walls below floor and roof slabs shall be laid with brick on edge, unless specified otherwise. Brick on edge laid in the top courses at corner of walls shall be properly radiated and keyed into position to form cut (maru) corners as shown in Fig 6.4. Where bricks cannot be cut to the required shape to form cut corners, cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) equal to thickness of course shall be provided in lieu of cut bricks.

15.1.4.8 Bricks shall be laid with frog (where provided) up. However, when top course is exposed, bricks shall be laid with frog down. For the bricks to be laid with frog down, the frog shall be filled with mortar before placing the brick in position.

15.1.4.9. In case of walls one brick thick and under, one face shall be kept even and in proper plane, while the other face may be slightly rough. In case of walls more than one brick thick, both the faces shall be kept even and in proper plane.

15.1.4.10 To facilitate taking service lines later without excessive cutting of completed work, sleeves (to be paid separately) shall be provided, where specified, while raising the brick work. Such sleeves in external walls shall be sloped down outward so as to avoid passage of water inside.

15.1.4.11. Top of the brickwork in coping and sills in external walls shall be slightly tilted. Where brick coping and sills are projecting beyond the face of the wall, drip course/throating (to be paid separately) shall be provided where indicated.

15.1.4.12. Care shall be taken during construction that edges of jambs, sills and projections are not damaged in case of rain. New built work shall be covered with gunny bags or tarpoulin so as to prevent the mortar from being washed away. Damage, if any, shall be made good to the satisfaction of the Engineer-in-Charge.

15.1.4.13. Vertical reinforcement in the form of bars (MS or high strength deformed bars or thermo-mechanically treated bars as per direction of Engineer-in- Charge)), considered necessary at the corners and junction of walls and jamb opening doors, windows etc. shall be encased with cement mortar not leaner than 1:4 (1 cement : 4 coarse sand), or cement concrete mix as specified. The reinforcement shall be suitably tied, properly embedded in the foundation and at roof level. The dia. of bars shall not be less than 8 mm and concrete grade shall be minimum 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).

15.1.4.14. In retaining walls and the like, where water is likely to accumulate, weep holes, 50 to 75 mm square shall be provided at 2 m vertically and horizontally unless otherwise specified. The lowest weep hole shall be at about 30 cm above the ground level. All weep holes shall be surrounded by loose stones and shall have sufficient fall to drain out the water quickly.

15.1.4.15. Work of cutting chases, wherever required to be made in the walls for housing G.I. pipe, CI pipe or any other fixtures shall be carried out in various locations as per guidelines given below :-

- (a) Cutting of chases in one brick thick and above load bearing walls.
 - (i) As far as possible services should be planned with the help of vertical chases. Horizontal chases should be avoided.
 - (ii) The depths of vertical chases and horizontal chases shall not exceed one-third and one-sixth of the thickness of the masonry respectively.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

(iii) When narrow stretches of masonry (or short length of walls) such as between doors and windows, cannot be avoided they should not be pierced with openings for soil pipes or waste pipes or timber joints, etc. Where there is a possibility of load concentration such narrow lengths of walls shall be checked for stresses and high strength bricks in mortar or concrete walls provided, if required.

(iv) Horizontal chases when unavoidable should be located in the upper or lower one-third of height of storey and not more than three chases should be permitted in any stretch of a wall. No continuous horizontal chase shall exceed one metre in length. Where unavoidable, stresses in the affected area should be checked and kept within the permissible limits.

(v) Vertical chases should not be closer than 2 m in any stretch of a wall. These shall be kept away from bearings of beams and lintels. If unavoidable, stresses in the affected area should be checked and kept within permissible limits.

(vi) Masonry directly above a recess, if wider than 30 cm horizontal dimension) should be supported on lintel. Holes in masonry may be provided upto 30 cm width and 30 cm height without any lintel. In the case of circular holes in the masonry, no lintel need be provided for holes upto 40 cm in diameter.

(b) Cutting of chases in half brick load bearing walls. No chase shall be permitted in half brick load bearing walls and as such no recessed conduits and concealed pipes shall be provided with half brick thick load bearing walls.

(c) Cutting of chases in half brick non-load bearing wall: Services should be planned with the help of vertical chases. Horizontal chase should be provided only when unavoidable.

15.1.5 **Joints**

15.1.5.1. The thickness of all types of joints including brick wall joints and cross joints shall be such that four course and three joints taken consecutively shall measure as follows:

(i) In case of modular bricks conforming to IS 1077 specification for common burnt clay buildings bricks, equal to 39 cm.

(ii) In case of non-modular bricks, it shall be equal to 31 cm.

Note : Specified thickness of joints shall be of 1 cm. Deviation from the specified thickness of all joints shall not exceed one-fifth of specified thickness.

15.1.5.2. **Finishing of Joints**: The face of brick work may be finished flush or by pointing. In flush finishing either the face joints of the mortar shall be worked out while still green to give a finished surface flush with the face of the brick work or the joints shall be squarely raked out to a depth of 1 cm while the mortar is still green for subsequently plastering. The faces of brick work shall be cleaned with wire brush so as to remove any splashes of mortar during the course of raising the brick work. In pointing, the joints shall be squarely raked out to a depth of 1.5 cm while the mortar is still green and raked joints shall be brushed to remove dust and loose particles and well wetted, and shall be later refilled with mortar to give ruled finish. Some such finishes are 'flush', 'weathered', ruled, etc.

15.1.5.3. **Curing**. The brick work shall be constantly kept moist on all faces for a minimum period of seven days. Brick work done during the day shall be suitably marked indicating the date on which the work is done so as to keep a watch on the curing period. All brick work shall be built in English bond except in half brick walls which shall be in Stretcher bond.

16. **Wood Work (Carpenter's & Joinery Work)**

16.1. **Materials**

16.1.1. **Timber**. Refer Clause No. 9.1 and clauses 9.1.1 to 9.1.8 of CPWD Specifications 2019 Vol-I.

16.2. **Wooden Chowkats or frame (wherever Specified / Shown In Drawings)**

16.2.1. Refer Clause No. 9.3 of CPWD Specifications 2019 Vol-I for Door Window and Ventilator frames and shall be of Second Class Hard Wood of the species mentioned here-in-before and as approved by Staff Officer-1 (Works).

NOTE: The Surfaces of Wooden Chowkats or Frame. coming in contract with Concrete or Brick Works, etc. shall be treated with Two Coats of Bituminous Paint after thoroughly cleaned from Dirt, Oil, etc. The cost of the same shall deem to be included in the quoted rate by the Tenderer.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

16.3. **Flush Door Shutter**

16.3.1. Flush door shutter shall be provided complete all as specified in Schedule 'A' (BOQ).

16.3.2. Flush door shutter shall be solid core types with block core, and shall conform to IS 2202 (Part I)- 1999, Specification for wooden flush door shutters (solid core type) Part I.

16.3.3. All timber used shall be well seasoned and chemically treated. Adhesive shall be phenol formaldehyde synthetic resin BWP type specified in IS:848-2006. All dimensions shall be finished dimension and Manufacturer's Test Certificate for test specified in IS: 2202 (Part I) shall be rendered.

16.4. **Factory Made Shutters**

16.4.1. Refer Clause No. 9.7 of CPWD Specifications 2019 Vol-I..

16.4.2. All Panelled and Wire Gauge Shutter for doors shall be factory made conforming to IS-1003 manufactured from well selected kiln seasoned, Second class Hardwood chemically treated as per IS-401 for anti-termite. Samples of shutter shall be got approved by the GE before placing the bulk order.

16.4.3. Factory Made Shutters shall be from any of the Approved Manufacturers listed in relevant Appendix to this Tender document here-in-after.

16.4.4. The door shutter shall be tested in the reputed Testing House/Lab as approved by Staff Officer-1 (Works) as per IS-1003. The number of door samples shall be as required by relevant IS-1003. In case, the results are not satisfactory, the entire lot shall be rejected. The cost of the testing and the cost of the door shutter sample is deemed to be included in the rates quoted by the tenderer.

16.5. **Plywood**

16.5.1. Plywood shall conform to IS-303 and shall be ISI marked. Plywood wherever shown on drawing shall be of BWR grade, type 'BB' of thickness as mentioned in drawings.

16.5.2. Refer Clause No. 9.2.2 and subsequent Clause No 9.2.2.1 to 9.2.2.6. thereof of CPWD Specifications Vol I for Plywood as applicable.

16.6. **Veneered Particle Board**

16.6.1. Refer Clause No. 9.2.4 and subsequent clauses 9.2.4.1 to 9.2.4.4 of thereof of CPWD Specifications Vol I.

16.7. **Chemical/Preservative Treatment**

16.7.1. Before painting or French polishing all joinery and timber incorporated in the work to be manufactured at site shall be treated as mentioned in IS-401 by modified hot and cold treatment, the minimum quantity of chemical impregnated in each cubic meter of timber shall be at the rate as specified in table 2 group 5 of said IS and all joinery manufactured at site, which has been exposed by chiseling/planning/cutting after treatment by hot and cold process, except those in factory made paneled shutters, which shall be chemically treated in factory, shall be treated with two coats of any of the approved chemicals such as ASCU etc. as directed by Engineer-in-Charge for protection against termite.

16.7.2. Cost of Anti-termite treatment to wood work shall be deemed to have been included in the quoted rate. The quantity and application of chemicals shall be as per manufacturer's instructions.

16.7.3. Wood work shall be painted or polished as specified in Schedule 'A' (BoQ) after second coat of anti-termite treatment has completely dried.

17. **Steel & Iron Work**

17.1. **General**

17.1.1. All Steels require to incorporate in the Work shall be Contractor's Supply from Primary producers of steel.

17.2. **Types of Steel**

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

17.2.1. **Reinforcement Steel For All Locations.** Steel bars for concrete reinforcement wherever shown on drawings or as specified in Schedule 'A' (BOQ) shall be TMT bars produced by Thermo Mechanical Treatment Process and grade of steel shall be mention on drawing or specified in Schedule 'A' (BOQ), unless other wise the grade of steel is not specified on drawing or specified, the grade of steel shall be (Grade Fe 500D) and meeting all requirement of IS-1786-2008. Where ever mild steel reinforcement bars are shown on drawings these shall be amended to read as TMT bars of same dia or nearest higher dia and accordingly to be provided.

17.2.2. **Structural Steel**

17.2.2.1. **Standard Quality** :- Structural steel except hollow steel sections shall be conform to IS-2062- 2006, E-250(Fe 410W). This steel shall be provided in the location mentioned in the drawings or as specified in Schedule 'A' (BOQ). In case the quality of structural steel i.e. A, B or C is not mentioned in drawings then quality A shall be used.

17.2.2.2. **Ordinary Quality** :- Unless otherwise specified, Mild Steel Members in Grills/Guard Bars, Holdfasts, Door and Window, Frames, Railing, Steel Windows, Steel Doors and the like shall be ordinary quality of Steel conforming to IS-2062-2006, E-165 (Fe 290).

17.2.2.3. **Hollow Steel Sections For Structural Use** :- Hollow steel sections for structural steel section shall be conform to IS-4923-1997 and grade of steel shall be YSt 310. This steel shall be provided in the location mentioned in the drawings or as specified in Schedule 'A' (BOQ).

17.2.3. **Structural Steel (Hollow Steel Sections)** :- Structural hollow steel sections shall be directly procured from TATA (STRUCTURA) /JINDAL STAR/ Steel Authority of India (SAIL) ISI Marked .

17.2.4. **Testing of Steel**

17.2.4.1. The manufacturer is to carry out inspections and testing of steel in accordance with the relevant BIS provisions. The contractor shall submit the manufacturer's test Certificate in original along with the test sheet giving the results of each mechanical test as applicable and the chemical composition of the steel or authenticated copy thereof, fully signed by the manufacturer with each consignment. The Engineer-in-Charge shall record these details in Steel Acceptance Register, as given at Appendix 'F' after due verification and send a certified true copy of test sheet to SO-1 (Wks) DG AR for his records. The SO-1(Wks)/CE shall also organize independent testing of random samples of steel drawn from various lots from National Test House, Regional Research labs, IITs, National Institutes of Technology, NABL Approved laboratories, Govt. Engineering College or Any Govt laboratories as per the recommended minimum frequency shown in para here-in-after. Samples from each lot should be tested for quality and elongation. The elongation shall not be less than 18%. Cost of samples, transportation and testing shall be borne by the Contractor. The records of such checks would be maintained in the steel test register.

17.2.4.2. Nominal mass of any size of finishes bar/section of steel shall be checked as specified in relevant IS code. The nominal mass so determined shall be recorded in steel testing register giving cross reference to consignment number. Nominal mass of any size of finished bar/section of steel if found to be beyond the tolerance limits on minus side as specified in relevant IS code, the same shall be rejected and the contractor shall remove the same at his own cost without any extra cost to the Government. However, if the weight of steel section is beyond the tolerance limit on higher side the same can be provided with approval of the SO-1 (Wks) but without any extra cost to the Government.

17.2.4.3. If any Test Result of any particular size of Bar/Section of steel of any consignment is not found satisfactory as specified in relevant IS, the contractor shall remove the same at his own cost and no claim of contractor shall be entertained on this account.

17.2.4.4. **Type of Testing**

17.2.4.4.1. **Reinforcement Steel**

(a)	High Strength Deformed Steel Bars	- Nominal Mass Test, Tensile Test, Bend Test and Re-bend Test shall be carried out as per Clause No. 8 of IS-1786-1985 and Test Specimens shall be as per Clause No. 10 of IS-1786-1985
(b)	Mild Steel Bars	- Nominal Mass Test, Tensile Test and Bend Test shall be carried out as per Clause No. 9 of IS-432 (Part-I)-1982. Re-bend Test is not required to be carried out for Mild Steel Bars.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

7.2.4.4.2. **Structural Steel**

(a)	Structural Steel (Standard Quality)	- Tensile Test and Bend Test shall be carried out as per Clause No. 6, 7 and 8 of IS-226-1975 for Standard Quality of Steel Sections.
(b)	Structural Steel (Ordinary Quality)	- Tensile Test and Bend Test shall be carried out as per Clause No. 6, 7 and 8 of IS-1977-1975 for Ordinary Quality of Steel Sections.
	Structural Steel (hollow steel sections)	- Tensile Test shall be carried out as per IS-4923-1997 for Standard Quality (Hollow Steel Section) of Steel Sections.

17.2.4.5. **Testing Charges** :- The Unit Rate/Amount quoted by the Contractor in the Tender shall be inclusive of Cost of all sorts of Testing to the extent as specified here in before and in relevant Indian Standards.

17.2.5. **Documentation** :- The contractor shall submit Original Purchase Vouchers and Test Certificate from the Main Producer/ Secondary Producer/BIS marked manufacturer/authorized dealer as applicable for the total quantity of steel supplied under each consignment to be incorporated in the work. All consignments received at the work site shall be inspected by the Engineer-in-Charge alongwith the relevant documents before acceptance. The Original Purchase Vouchers and Test Certificates shall be defaced by the Engineer in Charge and kept on record in the office of the Engineer-in-Charge duly authenticated and with cross reference to the consignment number recorded in the Steel Acceptance Register. The steel Acceptance Register will be signed by the JE (Civil), Engineer-in- Charge, and the, Contractor. The Accepting Officer may order a Board of Officers for random check of steel and verification of connected documents. The entire quantity of steel items shall also be suitably recorded in the measurement book for record purposes as "Not to be abstracted" before incorporation in the work and shall be signed by the Engineer in Charge and the contractor.

17.2.6. **Storage, Accounting, Preservation & Maintenance Of Steel**. The storage, accounting, preservation and maintenance of steel supplied by the contractor shall be done as per standard engineering practice till the same is consumed in the work and the cost of the same shall be deemed to be included in the unit amount quoted by the tenderer. The Staff Officer-1 (Works) shall inspect at regular interval to verify that steel lying at site are stored, accounted, preserved and maintained as per the norms. The steel shall be stored so as to differentiate each consignment separately. If the Staff Officer-1 (Works) is not satisfied with the storage/preservation of any size of bar/section of steel, he may order for any test (s) of steel as applicable for that size of bar/section of steel and as specified in tender documents and relevant Indian Standard to recheck the acceptability criteria for the same. The contractor shall bear the cost of necessary testing(s) in this regard and no claim whatsoever shall be entertained by the Govt.

17.2.7. **Measurements and Payment of Steel.**

17.2.7.1. The entire quantity of all steel items shall also be suitably recorded in the Measurement Book for record purposes as "Not to be Abstracted" before incorporation in the work and shall be signed by the Engineer in Charge and the contractor.

17.2.7.2. The nominal mass conversion factor for various steel sections/size of finished bars as given in relevant IS codes shall be considered standard for measurement.

17.2.7.3. The payment of steel shall only be allowed after production of Original Purchase Vouchers, Test Certificates by the contractor for each consignment of steel and results of testing carried out by the Department are found satisfactory after testing.

17.2.7.4. Format of Steel Supply and Acceptance register to be maintained is given at **Appendix 'D'** to this tender

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

No. P-45021/2/2017-B.E.-II
Government of India
Ministry of Commerce and Industry
Department of Industrial Policy and Promotion

Dated 15th June, 2017
Udyog Bhawan, New Delhi

To

All Central Ministries/Departments/CPSUs/All concerned

ORDER

Subject: Public Procurement (Preference to Make in India), Order 2017

Whereas it is the policy of the Government of India to encourage 'Make in India' and promote manufacturing and production of goods and services in India with a view to enhancing income and employment, and

Whereas procurement by the Government is substantial in amount and can contribute towards this policy objective, and

Whereas local content can be increased through partnerships, cooperation with local companies, establishing production units in India or Joint Ventures (JV) with Indian suppliers, increasing the participation of local employees in services and training them,

Now therefore the following Order is issued :

1. This Order is issued pursuant to Rule 153 (iii) of the General Financial Rules 2017.
2. **Definitions:** For the purposes of this Order:

'Local content' means the amount of value added in India which shall, unless otherwise prescribed by the Nodal Ministry, be the total value of the item procured (excluding net domestic indirect taxes) minus the value of imported content in the item (including all customs duties) as a proportion of the total value, in percent.

'Local supplier' means a supplier or service provider whose product or service offered for procurement meets the minimum local content as prescribed under this Order or by the competent Ministries / Departments in pursuance of this order.

'L1' means the lowest tender or lowest bid or the lowest quotation received in a tender, bidding process or other procurement solicitation as adjudged in the evaluation process as per the tender or other procurement solicitation.

'margin of purchase preference' means the maximum extent to which the price quoted by a local supplier may be above the L1 for the purpose of purchase preference.

'Nodal Ministry' means the Ministry or Department identified pursuant to this order in respect of a particular item of goods or services.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

'Procuring entity' means a Ministry or department or attached or subordinate office of, or autonomous body controlled by, the Government of India and includes Government companies as defined in the Companies Act.

3. **Requirement of Purchase Preference:** Subject to the provisions of this Order and to any specific instructions issued by the Nodal Ministry or in pursuance of this Order, purchase preference shall be given to local suppliers in all procurements undertaken by procuring entities in the manner specified hereunder:
- a. In procurement of goods in respect of which the Nodal Ministry has communicated that there is sufficient local capacity and local competition, and where the estimated value of procurement is Rs. 50 lakhs or less, only local suppliers shall be eligible. If the estimated value of procurement of such goods is more than Rs. 50 lakhs, the provisions of sub-paragraph b or c, as the case may be, shall apply.
 - b. In the procurements of goods which are not covered by paragraph 3a and which are divisible in nature, the following procedure shall be followed:
 - i. Among all qualified bids, the lowest bid will be termed as L1. If L1 is from a local supplier, the contract for full quantity will be awarded to L1.
 - ii. If L1 bid is not from a local supplier, 50% of the order quantity shall be awarded to L1. Thereafter, the lowest bidder among the local suppliers, will be invited to match the L1 price for the remaining 50% quantity subject to the local supplier's quoted price falling within the margin of purchase preference, and contract for that quantity shall be awarded to such local supplier subject to matching the L1 price. In case such lowest eligible local supplier fails to match the L1 price or accepts less than the offered quantity, the next higher local supplier within the margin of purchase preference shall be invited to match the L1 price for remaining quantity and so on, and contract shall be awarded accordingly. In case some quantity is still left uncovered on local suppliers, then such balance quantity may also be ordered on the L1 bidder.
 - c. In procurements of goods not covered by sub-paragraph 3a and which are not divisible, and in procurement of services where the bid is evaluated on price alone, the following procedure shall be followed:
 - i. Among all qualified bids, the lowest bid will be termed as L1. If L1 is from a local supplier, the contract will be awarded to L1.
 - ii. If L1 is not from a local supplier, the lowest bidder among the local suppliers, will be invited to match the L1 price subject to local supplier's quoted price falling within the margin of purchase preference, and the contract shall be awarded to such local supplier subject to matching the L1 price.
 - iii. In case such lowest eligible local supplier fails to match the L1 price, the local supplier with the next higher bid within the margin of purchase preference shall be invited to match the L1 price and so on and contract shall be awarded accordingly. In case none of the local suppliers within the margin of purchase preference matches the L1 price, then the contract may be awarded to the L1 bidder.

Contd. p.3/-

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

4. **Exemption of small purchases:** Notwithstanding anything contained in paragraph 3, procurements where the estimated value to be procured is less than Rs. 5 lakhs shall be exempt from this Order. However, it shall be ensured by procuring entities that procurement is not split for the purpose of avoiding the provisions of this Order.
5. **Minimum local content:** The minimum local content shall ordinarily be 50%. The Nodal Ministry may prescribe a higher or lower percentage in respect of any particular item and may also prescribe the manner of calculation of local content.
6. **Margin of Purchase Preference:** The margin of purchase preference shall be 20% .
7. **Requirement for specification in advance:** The minimum local content, the margin of purchase preference and the procedure for preference to Make in India shall be specified in the notice inviting tenders or other form of procurement solicitation and shall not be varied during a particular procurement transaction.
8. **Government E-marketplace:** In respect of procurement through the Government E-marketplace (GeM) shall, as far as possible, specifically mark the items which meet the minimum local content while registering the item for display, and shall, wherever feasible, make provision for automated comparison with purchase preference and without purchase preference and for obtaining consent of the local supplier in those cases where purchase preference is to be exercised.
9. **Verification of local content.**
 - a. The local supplier at the time of tender, bidding or solicitation shall be required to provide self-certification that the item offered meets the minimum local content and shall give details of the location(s) at which the local value addition is made.
 - b. In cases of procurement for a value in excess of Rs. 10 crores, the local supplier shall be required to provide a certificate from the statutory auditor or cost auditor of the company (in the case of companies) or from a practicing cost accountant or practicing chartered accountant (in respect of suppliers other than companies) giving the percentage of local content.
 - c. Decisions on complaints relating to implementation of this Order shall be taken by the competent authority which is empowered to look into procurement-related complaints relating to the procuring entity.
 - d. Nodal Ministries may constitute committees with internal and external experts for independent verification of self-declarations and auditor's/ accountant's certificates on random basis and in the case of complaints.
 - e. Nodal Ministries and procuring entities may prescribe fees for such complaints.
 - f. False declarations will be in breach of the Code of Integrity under Rule 175(1)(i)(h) of the General Financial Rules for which a bidder or its successors can be debarred for up to two years as per Rule 151 (iii) of the General Financial Rules along with such other actions as may be permissible under law.
 - g. A supplier who has been debarred by any procuring entity for violation of this Order shall not be eligible for preference under this Order for procurement by any other procuring entity for the

Contd. p 4/

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

duration of the debarment. The debarment for such other procuring entities shall take effect prospectively from the date on which it comes to the notice of other procurement entities, in the manner prescribed under paragraph 9h below.

- h. The Department of Expenditure shall issue suitable instructions for the effective and smooth operation of this process, so that:
- i. The fact and duration of debarment for violation of this Order by any procuring entity are promptly brought to the notice of the Member-Convenor of the Standing Committee and the Department of Expenditure through the concerned Ministry /Department or in some other manner.
 - ii. on a periodical basis such cases are consolidated and a centralized list or decentralized lists of such suppliers with the period of debarment is maintained and displayed on website(s).
 - iii. in respect of procuring entities other than the one which has carried out the debarment, the debarment takes effect prospectively from the date of uploading on the website(s) in the such a manner that ongoing procurements are not disrupted.

10. Specifications in Tenders and other procurement solicitations.

- a. Every procuring entity shall ensure that the eligibility conditions in respect of previous experience fixed in any tender or solicitation do not require proof of supply in other countries or proof of exports.
- b. Procuring entities shall endeavour to see that eligibility conditions, including on matters like turnover, production capability and financial strength do not result in unreasonable exclusion of local suppliers who would otherwise be eligible, beyond what is essential for ensuring quality or creditworthiness of the supplier.
- c. Procuring entities shall, within 2 months of the issue of this Order review all existing eligibility norms and conditions with reference to sub-paragraphs 'a' and 'b' above.
- d. If a Nodal Ministry is satisfied that Indian suppliers of an item are not allowed to participate and/ or compete in procurement by any foreign government, it may, if it deems appropriate, restrict or exclude bidders from that country from eligibility for procurement of that item and/ or other items relating to that Nodal Ministry. A copy of every instruction or decision taken in this regard shall be sent to the Chairman of the Standing Committee.
- e. For the purpose of sub-paragraph 10 d above, a supplier or bidder shall be considered to be from a country if (i) the entity is incorporated in that country, or (ii) a majority of its shareholding or effective control of the entity is exercised from that country; or (iii) more than 50% of the value of the item being supplied has been added in that country. Indian suppliers shall mean those entities which meet any of these tests with respect to India.

Contd p 5/-

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

11. **Assessment of supply base by Nodal Ministries:** The Nodal Ministry shall keep in view the domestic manufacturing / supply base and assess the available capacity and the extent of local competition while identifying items and prescribing minimum local content or the manner of its calculation, with a view to avoiding cost increase from the operation of this Order.
12. **Increase in minimum local content:** The Nodal Ministry may annually review the local content requirements with a view to increasing them, subject to availability of sufficient local competition with adequate quality.
13. **Manufacture under license/ technology collaboration agreements with phased indigenization:** While notifying the minimum local content, Nodal Ministries may make special provisions for exempting suppliers from meeting the stipulated local content if the product is being manufactured in India under a license from a foreign manufacturer who holds intellectual property rights and where there is a technology collaboration agreement / transfer of technology agreement for indigenous manufacture of a product developed abroad with clear phasing of increase in local content.
14. **Powers to grant exemption and to reduce minimum local content:** Ministries /Departments of Government of India and the Boards of Directors of Government companies or autonomous bodies may, by written order,
- reduce the minimum local content below the prescribed level;
 - reduce the margin of purchase preference below 20% ;
 - exempt any particular item or procuring or supplying entities or class or classes of items or procuring or supplying entities from the operation of this Order or any part of the Order .

A copy of every such order shall be marked to the Member-Convenor of the Standing Committee constituted under this Order.

15. **Directions to Government companies:** In respect of Government companies and other procuring entities not governed by the General Financial Rules, the administrative Ministry or Department shall issue policy directions requiring compliance with this Order.
16. **Standing Committee:** A standing committee is hereby constituted with the following membership

Secretary, Department of Industrial Policy and Promotion—Chairman
 Secretary, Commerce—Member
 Secretary, Ministry of Electronics and Information Technology—Member
 Joint Secretary (Public Procurement), Department of Expenditure—Member
 Joint Secretary (DIPP)—Member-Convenor

The Secretary of the Department concerned with a particular item shall be a member in respect of issues relating to such item. The Chairman of the Committee may co-opt technical experts as relevant to any issue or class of issues under its consideration.


..... Contd p 6/

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer

17. **Functions of the Standing Committee:** The Standing Committee shall meet as often as necessary but not less than once in six months. The Committee
- shall oversee the implementation of this order and issues arising therefrom, and make recommendations to Nodal Ministries and procuring entities.
 - shall annually assess and periodically monitor compliance with this Order
 - shall identify Nodal Ministries and the allocation of items among them for issue of notifications on minimum local content
 - may require furnishing of details or returns regarding compliance with this Order and related matters
 - may, during the annual review or otherwise, assess issues, if any, where it is felt that the manner of implementation of the order results in any restrictive practices, cartelization or increase in public expenditure and suggest remedial measures
 - may examine cases covered by paragraph 13 above relating to manufacture under license/ technology transfer agreements with a view to satisfying itself that adequate mechanisms exist for enforcement of such agreements and for attaining the underlying objective of progressive indigenization
 - may consider any other issue relating to this Order which may arise.
18. **Removal of difficulties:** Ministries /Departments and the Boards of Directors of Government companies may issue such clarifications and instructions as may be necessary for the removal of any difficulties arising in the implementation of this Order.
19. **Ministries having existing policies:** Where any Ministry or Department has its own policy for preference to local content approved by the Cabinet after 1st January 2015, such policies will prevail over the provisions of this Order. All other existing orders on preference to local content shall be reviewed by the Nodal Ministries and revised as needed to conform to this Order, within two months of the issue of this Order
20. **Transitional provision:** This Order shall not apply to any tender or procurement for which notice inviting tender or other form of procurement solicitation has been issued before the issue of this Order.


 (B. S. Nayak)
 Under Secretary to Government of India
 Ph 23061257

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer

P-45021/21/2024-BE-II (E-197009)
Government of India
Ministry of Commerce & Industry
Deptt. for Promotion of Industry & Internal Trade
(Public Procurement Section)

Udyog Bhawan, New Delhi
Dated: 02.12.2024


OFFICE MEMORANDUM

Subject: Non-compliance of Public Procurement (Preference to Make in India) Order, 2017 while Floating tenders on CPPP and GeM Portal- reg

The undersigned is directed to refer to the above-mentioned subject and to say that the Department for Promotion of Industry and Internal Trade (DPIIT) scrutinizes high-value tenders of Central Government Procuring Entities published on CPPP and GeM Portals for their compliance with Public Procurement (Preference to Make in India) Order, 2017 (PPP-MII Order) last revised on 19.07.2024. Recent assessments reveal that certain conditions articulated in the tender documents by government procuring entities are not in compliance with the PPP-MII Order. This issue is particularly significant among procuring entities within the Ministry of Home Affairs, where 85 tenders (copy enclosed) were found to be non-compliant with the PPP-MII Order. Details of such tenders have been regularly sent by DPIIT to various procuring entities under MHA. Incorporating restrictive and discriminatory eligibility criteria in tenders is violative of PPP-MII Order and also contrary to General Financial Rules.

2. It is stated that the Make in India initiative is a cornerstone of our economic strategy, aimed at fostering a robust domestic manufacturing sector capable of competing on a global scale. To realize this vision, it is essential that our procurement processes be inclusive and equitable, thereby facilitating participation from local manufacturers without imposing unnecessary barriers.

3. In this regard, it is requested that all procuring entities under Ministry of Home Affairs may kindly be directed to ensure complete compliance with PPP-MII Order 2017 while floating tenders and take immediate and decisive action to eliminate any restrictive or discriminatory eligibility criteria from their tender documents. Further Status/ATR to pending grievances may be shared with this Department within 15 days.



(Surendra Singh)

Under Secretary to the Government of India

Email: ssingh.dopt@nic.in

Tel: 23061592

To

1. Secretary, Ministry of Home Affairs

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Appendix BCERTIFICATE FOR ABIDING BY CODE OF INTEGRITY FOR
PUBLIC PROCUREMENT VIDE RULE 175 (1) OF GFR-2017

1. It is hereby certified that I/We Mr/Mrs/Ms _____ (Full name of owner/
proprietor of Bidder Firm) on behalf of M/S _____ (Full Name and address of
Firm) are bidding for this Tender duly adhering to the 'Code of Integrity' vide Rule 175 (1) of
GFR-2017.
2. The under mentioned aspects under 'Code of Integrity' are hereby certified for non-
indulgence in:-
 - (a) Making offers, solicitation towards bribes/ gratification, reward, gift or any material
benefit either directly or indirectly in-exchange for an unfair advantage in the
procurement process or to otherwise influence the procurement process.
 - (b) Omission, or misrepresentation of facts that may mislead or attempt to mislead so
that financial or other benefit may be obtained or an obligation is avoided.
 - (c) Any sort of collusion, bid-rigging or anti-competitive behavior/ act that may impair
transparency, fairness and progress of the procurement process.
 - (d) Improper use of information provided by the procuring entity to the bidders with an
intent to gain unfair advantage in the procurement processes or even for personal gains.
 - (e) Any financial, material or business transactions (including un-official
communication/ correspondence) between the bidder and any official of the procuring
entity related to tender or executing the process of contract, which can affect the
decision(s) of the procuring entity either directly or indirectly.
 - (f) Any coercion or threat to impair or harm, directly or indirectly any official or related
party or its property to influence or affect the procurement process in any manner.
 - (g) Acts or attempts to obstruct or hinder any investigation or auditing of the
procurement process during tendering stage or post supply order stage.
 - (h) Making false declarations/ disclaimers or providing false information for
participation in a Tender process, or to secure a contract or to affect the participation of
other prospective Bidders.
3. The under mentioned aspects under 'Code of Integrity' are hereby certified for
adherence:-
 - (a) Promise on the part of the principal not to seek or accept any benefit, which is not
legally available.
 - (b) Principal to treat all bidders with equity and reason.
 - (c) Promise on the part of bidders not to offer any benefit to the employees of the
Principal not available legally.
 - (d) Bidders not to enter into any undisclosed agreement or understanding with other
bidders with respect to prices, specifications, certifications, subsidiary contracts, etc.
 - (e) Bidders not to pass any information provided by Principal as part of business
relationship to others and not to commit any offence under PC/ IPC Act.
 - (f) Foreign bidders to disclose the name and address of agents and representatives
in India and Indian Bidders to disclose their foreign principals or associates.
 - (g) Bidders to disclose the payments to be made by them to agents/ brokers or any
other intermediary.
 - (h) Bidders to disclose any transgressions with any other company that may impinge
on the anti corruption principle.

Sign:

Date

-2-

(j) A person signing IP shall not approach the Courts while representing the matters to IEMs and he/ she will await their decision in the matter.

(k) In case of a joint venture, all the partners of the joint venture should sign the Integrity Pact. In case of sub-contracting, the Principal contractor shall take the responsibility of the adoption of IP by the sub-contractor. It is to be ensured that all sub-contractors also sign the IP.

4. I/We make the following "Disclosure of Conflict of Interest" in accordance to Rule 5.1.4(ix) of Manual for Procurement of Goods and Services-2017:-

5. I/We make the following "Disclosure of any previous transgressions made in respect of provisions certified vide Para 2 (a) to (h) above with any entity in any country during the last three years or of being debarred/ blacklisted by any other Govt of India procuring agency:-

6. It is fully understood that in case of the aforesaid information provided proved to be false or misleading, I/We are liable to disqualification from the procurement process and the contract, if awarded, is liable to be cancelled. In the event of contract already having been executed, the balance payment be stopped till finalisation of the case and in the event of payment already been made, the Firm/ Concern is liable to be 'Banned from Business by Blacklisting' and recovery of dues already paid with respect to the Contract.

7. Details of Independent External Monitor (IEM) are as under :-

Shri Ashwani Kumar, Ex CMD, Dena Bank
Flat No. 101, 1st Floor,
Plot No. F.P.No. 81, Ruby Bandra West,
Ruby CHSL, 29th Road,
Near Duruoella Convent High School,
Bandra West, Mumbai-400050
Telephone : 9920262626
E-Mail – ashwani_ashwani1@yahoo.co.in

Place :

(Signature & Stamp of Owner/
Proprietor of the Firm/ Concern)

Date :

Note:-

1. In Para 4 above - Bidder to endorse in own handwriting "*I have no conflict of interest with any bidder nor with any official from the procuring entity*".
2. In Para 5 above - Bidder to endorsed in own handwriting "*NO*".
3. In case of any conflict of interest, bidder to mention same accordingly in Para 4 and 5 above.

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer

Appendix 'A'

(Refer Para 1 of Vigilance Branch,
HQ DGAR letter No I.12015/Policy/
Vig/2020/ 83 O dt 12-Feb 2020

**CERTIFICATE OF CONFIRMATION ON RULE 175 (1) (II) OF GENERAL FINANCIAL
RULES-2017 AND PARAGRAPH 5.1.4 (IX) OF MANUAL FOR PROCUREMENT
OF GOODS-2017**

- 1 It is hereby certified that as per Rule 175 (1) (II) of General Financial Rules-2017 there are no 'Conflicts of Interests' pertaining to this Firm/ Company/ Proprietorship/ Concern.
2. As per Para 5.1.4 of (ix) of Manual for Procurement of Goods 2017, it is certified that my/ our firm/ company/ proprietorship/ concern:-
- (a) Do not have controlling partner(s) in common who are Participants/ Bidders in the Tender.
 - (b) Do not receive or have received any direct or indirect subsidy/ financial stake from any of these bidders.
 - (c) Do not have the same legal representative/ agent with other common bidders for purpose of this bid.
 - (d) Do not have relationship with each other, directly or through common third parties for this Tender.
 - (e) Have not participated in more than one bid of the Tender (Participation by a bidder in more than one bid will result in the disqualification of all bids in which the parties are involved. However, this does not limit the inclusion of the components/ sub-assembly/ assemblies from one bidding manufacturer in more than one bid).
 - (f) Have not quoted as agent/ agents in offshore procurements on behalf of their principal manufacturers, is/ are aware that one agent cannot represent two manufacturers or quote on their behalf in a particular tender enquiry. Is/ Are aware that one manufacturer can also authorise only one agent/ dealer and that there can be only one bid from the following:-
 - (i) The principal manufacturer directly or through one Indian Agent on his behalf.
 - (ii) Indian/ Foreign Agent on behalf of only one principal.
 - (g) Have not as Bidder or any of its affiliates participated as a Consultant in the preparation of the design or technical specifications of the said contract/ NIT that is the subject of this Bid/ Tender.
 - (h) As a holding company/ firm/ concern do not have more than one independently manufacturing units, or more than one unit having common business ownership/ management and have only one unit quoting the Bid. Declare proactively that such sister concern/ common business/ management unit in same/ similar line of business have not participated in the said Bid/ Tender.
3. It is fully understood that in case of the aforesaid information provided proved to be false or misleading, the contract if allotted is liable to be cancelled. In the event of contract already having been executed the balance payment be stopped till finalisation of the case and in the event of payment already been made, the Firm/ Concern is liable to be 'Banned from Business' with Assam Rifles.

Place .


Date .

(Signature & Stamp of Owner/
Proprietor of the Firm/ Concern)

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer



Supdt B & R-I
ASSAULT RIFLES

SD-1 (WKS)
HOIGAR (North)

Good For Construction


ENGR B R T D G A R
114.1.1.1
2026-04-24 15:16:46

LENGTH - 30 Mtrs

Signature of the tenderer & Stamp

Date 2026


SD- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer



Signature of the tenderer & Stamp

Date 2026

Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer



NOTES :-

1. Contractor to check and verify all dimensions before execution of the work.
2. All dimensions are given in millimeters unless otherwise mentioned.
3. Figured dimensions shall be followed.
4. Do not scaled out dimensions from drawing, follow written dimensions only.

RETAINING WALL


DRN	Jayachandran K	ENGR BRANCH
CKD	<i>[Signature]</i>	HQ 27 SECTOR
DATE	Dec 2017	ASSM RIFLES
Drg No.	DMR/ENGR/2017/ 249	Sheet No. 1/1

[Signature]
 LT COL
 SO1 (Wks)

Signature of the tenderer & Stamp

Date _____ 2026


Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer



Signature of the tenderer & Stamp

Date _____ 2026


Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer



Signature of the tenderer & Stamp

Date 10/11/2026


Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer



Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
(Sandesh Dabholkar)
Lt Col
Staff Officer-I (Wks)
for Accepting Officer



Not to Scale

ENGRBR7
 114.1.7.1
 2026-04-24


 Lt Col
 SC-1 (Wks)
 HQ IGAR (Wks)

Signature of the tenderer & Stamp

Date _____ 2026

Sd/- xx xx xx
 (Sandesh Dabholkar)
 Lt Col
 Staff Officer-I (Wks)
 for Accepting Officer

