



DOOR & WINDOW MASONRY OPENING SCHEDULE						
SL.NO.	ITEM	TYPE	SIZE	SILL LEV. FROM. FL.	LINTEL LEV.	REMARK
1	DOOR	D1	1500 X 2100	-	2100	MS DOOR
2	WINDOW	W1	1250X 1200	900	2100	ALUMINIUM

NOTES:

- All dimensions are in millimetres (mm) unless otherwise specified. Levels are in metres (m).
- Drawings are not to be scaled. Written dimensions shall govern in all cases.
- If any discrepancy is found in this drawing, the same may be brought to the notice of this office immediately and get it reconciled before execution.
- All drawings shall be read in conjunction with relevant structural, electrical and other services drawings.
- All works shall be carried out in accordance with approved drawings, technical specifications and directions of the Engineer-in-Charge.
- Contractor shall verify all dimensions, levels and site conditions before commencement of work.
- No deviation from the approved drawings shall be made without prior written approval of the Engineer-in-Charge & the Consultant.
- All openings and cut-outs(if any) required for services shall be coordinated with the respective services drawings before the execution.
- RCC, masonry, plastering, finishing and waterproofing works shall be executed strictly as per approved details and specifications.
- Statutory requirements and safety norms shall be complied with at all stages of construction.
- Drawings are issued for the specific work mentioned and shall not be used for any other purpose.
- All finished surfaces shall be true to line, level, and plumb.
- All materials shall be new, first-class quality and approved by the Engineer-in-Charge before use.
- Proper setting out, alignment, and levelling shall be ensured before starting any work.
- Work shall proceed only after proper curing of RCC and masonry as per specifications.
- Finishing works shall commence only after services rough-ins are completed and approved.

PLINTH AREA-25.72 SQM
(INCLUDING STAIRCASE)

REVISION:	DESCRIPTION:	DATE:
-----------	--------------	-------

STATUS: TENDER DRAWING

CLIENT:
**CCE(R&D)ESTATES SOUTH,
HYDERABAD**

CONSULTANT:
 **CREATIVE CORPORATION**
We find ways...
New colony,Lane-3,chunvati road,Gopalgaon,
Balsore,Odisha-756001
E-Mail: creativecorporation@gmail.com

PROJECT:

CONSULTANCY SERVICES FOR CIVIL WORK FOR
INSTALLATION AND OPERATION OF GRS-III
TELEMETRY STATION AT P1 SITE,KONARK,ITR

BUILDING NAME:

ANTENNA ROOM

TITLE:

GROUND FLOOR PLAN

DATE:	DRAWN: JAGADISH	CHECKED: JYOTI	REVISION:
-------	--------------------	-------------------	-----------

SHEET SIZE: A2	DRAWING NO: CC/CCE(R&D)ESTS/TD/GRS-III/P1/AR/A-01
-------------------	--