

कार्यालय अधीक्षण अभियन्ता
सिंचाई कार्य मण्डल, पिथौरागढ़

अपलोड किये गये BOQ को योजनावार माप निम्नानुसार है।

1. कार्य का नाम :-मा0 मुख्यमन्त्री घोषणा सं0- 243/2022 विधानसभा क्षेत्र चम्पावत के अन्तर्गत बूम से टनकपुर तक शारदा नदी के दायें पार्श्व पर (तटबन्ध) बाढ सुरक्षा निर्माण कार्य। (शारदा नदी के दायें पार्श्व बूम, व उचौलीगोट, मे बाढ सुरक्षा कार्य) पार्ट-3

S.N	Item of Work	Qty	Unit
1	Excavation in Ordinary Rock using Hydraulic Excavator and Tippers with disposal upto 1000 m Excavation for roadway in ordinary rock with hydraulic excavator of 3.3 Cum bucket capacity including cutting and loading in tippers, transporting to embankment site with a lift upto 1.5 m and lead upto 1000 m, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per MoRD 3-8-3	14926.00	Cum
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 11-4-1 P.C.C grade M 10 Nominal mix 1:3:6 11-4-1-1 (MoRD)	19175.00	Cum
3	Dewatering from foundation of abutments and wing walls (with pump capacity 4000 lit per Hr.) including wages of operator and fuel including supply of all material, labour and T&P required for proper completion of the work.	11520.00	Hrs
4	Providing and laying of wire crates 3.00x1.50x1.50 in size with GI wire conforming to IS: 280 & IS:4826 in 150mm x 150mm mesh laid with stone boulders, as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)	4050.00	Cum
5	Hand Packed stone filling in back of wall including cost of all materials, royalty, T&P etc. complete as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)	1620.00	Cum

2. कार्य का नाम :—मा0 मुख्यमन्त्री घोषणा सं0— 243 / 2022 विधानसभा क्षेत्र चम्पावत के अन्तर्गत बूम से टनकपुर तक शारदा नदी के दायें पार्श्व पर (तटबन्ध) बाढ सुरक्षा निर्माण कार्य। (शारदा नदी के दायें ग्राम बसानी गोठ, सुवागोठ एवं गैण्डाखाली न0—3 की सुरक्षा हेतु) पार्ट—4

S.No.	Particulars of Item	Quantity	Unit
1	Excavation in Ordinary Rock using Hydraulic Excavator and Tippers with disposal upto 1000 m Excavation for roadway in ordinary rock with hydraulic excavator of 0.9 Cum bucket capacity including cutting and loading in tippers, transporting to embankment site with a lift upto 1.5 m and lead upto 1000 m,	28075.00	Cum
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 11-4-1 P.C.C grade M 10 Nominal mix 1:3:6	41235.00	Cum
3	Dewatering from foundation of abutments and wing walls (with pump capacity 4000 lit per Hr.) including wages of operator and fuel including supply of all material, labour and T&P etc. required for proper completion of the work.	12000.00	Hrs
4	Hand Packed stone filling in back of walls including cost of all materials, royalty, T&P etc. complete as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)	1332.00	Cum
5	Providing and laying of wire crates 3.00x1.50x1.50 in size with GI wire conforming to IS: 280 & IS:4826 in 150mm x 150mm mesh laid with stone boulders, as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications) GI wire 8 gauge BWG	8167.00	Cum

3. कार्य का नाम :—मा0 मुख्यमन्त्री घोषणा सं0— 243 / 2022 विधानसभा क्षेत्र चम्पावत के अन्तर्गत बूम से टनकपुर तक शारदा नदी के दायें पार्श्व पर (तटबन्ध) बाढ सुरक्षा निर्माण कार्य। (शारदा नदी के दायें पार्श्व 28 हैक्टेयर, चिलियाघोल, की सुरक्षा हेतु) पार्ट—5

S.No.	Particulars of Item	Quantity	Unit
1	Excavation in Ordinary Rock using Hydraulic Excavator and tippers with disposal upto 1000 m Excavation for roadway in ordinary rock with hydraulic excavator of 0.9 Cum bucket capacity including cutting and loading in tippers, transporting to embankment site with a lift upto 1.5 m and lead upto 1000 m, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per Technical Specification Clause 302.3.5	23625.00	Cum
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 11-4-1 P.C.C grade M 10 Nominal mix 1:3:6	8590.00	Cum
3	Dewatering from foundation of abutments and wing walls (with pump capacity 4000 lit per Hr.) including wages of operator and fuel including supply of all material, labour and T&P etc. required for proper completion of the work.	3600.00	Hrs
4	Providing weepholes in brick masonry/stone masonry plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	6300.00	Rmt
5	12-4 Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 cement mortar (1:5)	9113.00	Cum

नोट— निविदा से सम्बन्धित पूर्ण जानकारी हेतु उत्तराखण्ड सरकार की वेबसाईट <http://uktenders.gov.in> पर लॉगऑन करें।

(एच०सी०सिंह)
अधीक्षण अभियन्ता