

BRIHANMUMBAI MUNICIPAL CORPORATION

(HYDRAULIC ENGINEER'S DEPARTMENT)

900 MLD WTP, Bhandup Complex

Minutes of Pre-Bid Meeting

Subject :- The work of design, supply, installation, testing and commissioning of 3437.5 m³/h capacity centrifugal Pump Set along with other accessories at 900 MLD Pumping Station Bhandup Complex.

Venue :- Hydraulic Engineer's Office, Worli Engineering Hub, Mumbai-400018.

Meeting Date:- 07.04.2026

Time :- 12.30 pm

Tender ID :2026_MCGM_1286968_1

Tender due on :24.04.2026

No.	Contractor's name	Contractor's Queries	B.M.C's reply to Queries
1	KRAJESH & COMPANY	Soft starter is to be provided for Trimmer pump in this contract. Kindly clarify.	Existing electrical feeders of all motors do not have Soft Starters. Spare electrical feeder has been provided in existing electrical panel which is supposed to be used for subject work. Hence, to maintain similarity in electrical network no Soft Starter is proposed. Tender Condition prevails
2	KRAJESH & COMPANY	Kindly provide us with the I/O count list and P&ID drawings for the panel.	I/O Signal/Data required to be processed are enlisted at page no 145 to 147 in Tender Document under Technical specifications. P&ID diagram is to be prepared by the contractor considering the I/O Signal/Data needs to be processed as approval and as build drawings. Tender Condition prevails.

No.	Contractor's name	Contractor's Queries	B.M.C's reply to Queries
3	KRAJESH & COMPANY	<p>Page No. 144 CABLE (H.T. Cables: 3.3 kV, 3C x150 sq.mm Copper armored XLPE cables) - We have already raised this point in the earlier tender, wherein most manufacturers clearly stated that they do not manufacture such small quantities for HT copper cable and have instead suggested to kindly use higher-grade HT Aluminum 11 kV or 22 kV cables as the same will also satisfactorily function and is being used for HT work PAN India.</p> <p>Hence, we request that if the work is awarded to us, we shall first try to procure Copper Armored XLPE cables, In case of non-availability, we request to allow Aluminum cables for 11 kV / 22 kV as on alternate option.</p>	<p>900 MLD Water Treatment Plant at Bhandup Complex is a important and vital installation and hence copper cable is to be laid for feeding HT motors.</p> <p>Tender Condition prevails</p>

Sd/-
E.E.(900 MLD WTP)B.C.

Sd/-
Dy. H.E. (M & E)B.C.

Sd/-
H. E.