



[1]  
**M.P. POWER GENERATING COMPANY LIMITED**  
**OFFICE OF THE ADDL. CHIEF ENGINEER (P&W)**  
**SHREE SINGAJI THERMAL POWER PROJECT, MPPGCL,**  
**DongaliaDisttKhandwa (MP)-450112**  
**An ISO 9001:2015, ISO 14001:2015, ISO 45001:2018 certified station**  
**E-mail: [sepnw.sstpp1@gmail.com](mailto:sepnw.sstpp1@gmail.com)**  
**Official Website: [mppgcl.mp.gov.in](http://mppgcl.mp.gov.in)**



**No. 515-1700/ET&I-I/SSTPP/WT-2951/T-2026\_MPPGC\_478871\_1/ 510 Dongalia, Dtd: 21.04.2026**

**Sub:-“Work contract for Construction of aluminium partition wall with door & related work at 2<sup>nd</sup> floor service building for establishment office of SE(ET&I)-I & BOP area of EMD-I, PH-I, SSTPP, MPPGCL, Khandwa.”**

**TENDER SCHEDULE**

SL. No.	Particular of work	Qty.	Unit
1.00	Work contract for Construction of aluminium partition wall with door & related work at 2 <sup>nd</sup> floor service building for establishment office of SE(ET&I)-I & BOP area of EMD-I, PH-I, SSTPP, MPPGCL, Khandwa		
1.01	Providing & fixing of partition panel made with heavy duty aluminium section 44.5mmX100mm size, with minimum 12mm thick novapan laminated sheet (4 ft height) or non-transparent glass (3 ft height) and from 2 mtr height up-to false ceiling level clear glass, providing one door including all required material, labour, T&P etc. 1. For completion the work in all respect for establishment office of SE(ET&I)-I, PH-1 at 2nd floor service building. 2. For completion the work in all respect for EMD BOP partition including fabrication of ceiling/roof at 15 ft height from ground with fabrication of staff cabin at, PH-1 Compressor House building.	129Mtr <sup>2</sup>  { (i) O/o. SE(ET&I)-I: 29 Mtr <sup>2</sup> ii) EMD-I: 100 Mtr <sup>2</sup> }	Sq. Mtr
1.02	Supply, installation & fixing of following electrical items in above partition ( <i>establishment office of SE(ET&amp;I)-I, PH-1 at 2<sup>nd</sup> floor service building-1 &amp; EMD BOP partition at, PH-1 Compressor House building</i> ) along with required wiring, material, consumables etc. i) Wall mounted fan 400mm size of reputed make with ISI mark. <b>-1 No.</b> ii) Power supply point (socket with switches complete 16 Amp 230VAC) mounted on modular switchboard. <b>-1No.</b> iii) Power supply points (socket with switches complete 06 Amp 230VAC) for computer & other peripherals. <b>-4No.</b> iv) Call bell with switch. <b>-1No.</b> v) LED tube light (18 watt, 230VAC) <b>-2No.</b>	3 Set  (For O/o. SE(ET&I)-I: 01 For EMD BOP part: 01 For EMD staff cabin: 01)	Set

**SCOPE OF WORK**

- 1) The quantity mentioned above is tentative and may vary. The payment shall be made as per actual work carried out.
- 2) The material may be inspected by the competent authority, at your work/site before starting of work.
- 3) For competing above job all required T&P shall be in scope of contractor.
- 4) Any other work related to complete the above job and not mentioned above is in scope of contractor.

**Terms & Conditions**

- **Safety:** The contractor shall provide safety appliances (as applicable) to all of his workers including supervisor and ensure that safety appliances are used by his workers. Following appliances shall be necessarily available with all employees of contractor:  
Safety Boot, Safety Helmet, Safety Belt, Insulated hand gloves
- Accident: In case of accident (Fatal/non-fatal) during work all responsibility of the deceased / injured person shall rest with the contractor, MPPGCL shall not be responsible for any compensation.
- All to-&- fro charges & local transportation charges for men, material, T&P items and others will be in scope of contractor/bidder.

**TENDER SPECIFIC CONDITION**

1. **Contract Period/Work Completion Period:**-The firm should have capability to complete the work within 01 month from the actual date of commencement of work as per directives of Controlling Officer. The order shall be valid for one year. If any work remains balance due to some reasons then that balance work will be carried out later within the order validity period. However the contract period shall be valid for 12 months from the actual date of commencement of work as per directives of Controlling Officer. The contract period may also be extended subsequently for a period of 3 months or up to 50% of original contract value if required by MPPGCL and contractor is bound to accept the same.
2. **PENALTY:**- In addition to the clause no. 2.26 of Instructions to Bidders “PENALTY” , following shall also be applicable :-
  - (i) In case, if any worker is observed not following the safety rules and regulations as per requirement of factory act and other relevant law, penalty as deemed fit. (Not exceeding Rs. 500/- per day) shall be imposed on contractor by Engineer-in-charge and /or safety officer.
  - (ii) The contractor will be liable for the due observation and implementation of the statutory conditions and requirements of Factory Act and other labour laws as applicable to his workmen. If any penalty is imposed on Factory occupier / Factory Manager due to non compliance of labour laws the same shall be borne by the contractor.
  - (iii) All the statutory penalties imposed by the state / central government authorities shall be borne by the contractor.
3. **Clause 2.7 of General Conditions of Contract “EXECUTION OF AGREEMENT” shall be read as:** The successful bidder must assign & submit the acceptance of LOI/Order within 15 days from the date of issuance by MPPGCL. The bidder should present himself or his duly authorized representative in person within 15 days after acceptance of order to execute an agreement as per prescribed proforma as per annexure -VI on non judicial stamp paper (as per gazette notification of GoMPdtd. 09.09.2025) With revenue stamp of Rs.2 affixed on it before commencement of work for the due and faithful fulfillment of the contract as under:-

S. No.	Contract value (in Rs.)	Worth of non judicial stamp paper (in Rs.)
1.	Upto 50,00,000/-	1000/-
2.	Above 50,00,000/-	0.2 % percent of contract value subject to a maximum of 10,00,000/-

The cost of stamp papers shall be borne by the contractor/his authorized representative.

--sd--

**(Rajesh Sahriya)**  
Superintending Engineer (Works)  
SSTPP, MPPGCL, Dongalia