

SCHEDULE 'B' & 'C'

22

Name of Work :-

NAME OF WORK :: CONSTRUCTION OF SAMAJBHAVAN AT MOUZA PALSAD TAL KAMPTEE

S.No.	Name of Work	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	2	3	4	5	6	7
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary	67.41	207.00	Rupees two hundred seven and paise nil only	Cum	13954.00
2	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary	40.44	258.00	Rupees two hundred fifty-eight and paise nil only	Cum	10434.00
3	Transportation of material obtained from debris of various sorts including necessary excavation/ loosing including loading, unloading and conveying and disposing as directed.	0.00	252.00	Rupees two hundred fifty-two and paise nil only	Cum	0.00
4	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	6.74	2092.25	Rupees two thousand ninety-two and paise twenty-five only	Cum	14102.00
5	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be	4.50	6563.70	Rupees six thousand five hundred seventy three and seventy paise only	Cum	29537.00
6	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. Layers including watering and compacting etc. complete.	0.00	120.00	Rupees one hundred twenty and paise nil only	Cum	0.00
7	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	51.00	929.75	Rupees nine hundred twenty-nine and paise seventy-five only	Cum	47417.00
8	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions	30.36	7702.05	Rupees seven thousand seven hundred two and paise five only	Cum	233834.00



2	Name of Work	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
3	4	5	6	7		
	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed	6.49	14381.05	Rupees fourteen thousand three hundred eighty-one and paise five only	Cum	93333.00
10	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compactionand	9.97	12867.05	Rupees twelve thousand eight hundred sixty-seven and paise five only	Cum	128284.00
11	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to	1.75	14530.05	Rupees fourteen thousand five hundred thirty and paise five only	Cum	25428.00
12	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces	13.29	14530.05	Rupees fourteen thousand five hundred thirty and paise five only	Cum	193104.00
13	Providing and fixing during laying in RCC Slab rectangular 2 mm thick M.S. sheet fan hook box of size 180x100 mm with required depth with holes or notches as required, bottom and top sides of 1.6 mm M.S. sheet fixed with 3.5 mm dia. round headed screws together with 12 mm dia. M.S. bar	4.00	397.00	Rupees three hundred ninety-seven and paise nil only	Cum	1588.00
14	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and	4.77	90077.15	Rupees ninety thousand seventy-seven and paise fifteen only	Cum	429817.00
15	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C.coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering,	0.44	7788.05	Rupees seven thousand seven hundred eighty-eight and paise five only	Cum	3427.00
16	Providing and applying water proofing treatment using acrylic polymer modified cement based water proofing coating with fibre glass mesh mixing at the rate of powder to liquid (2:1) by weight covering 9 to 10 Square Metre /Kilogram with two coat using approved chemicals	0.00	615.00	Rupees six hundred fifteen and paise nil only	Cum	0.00
17	Providing and laying mechanical protective layer over water proofing membrane with cement screed plaster 1:5 after laying chicken mesh over membrane including curing etc. complete 20 mm thick with cost of chicken mesh etc. complete and covering 7 years guarantee on court	0.00	390.00	Rupees three hundred ninety and paise nil only	Cum	0.00

2	Name of Work	Quantity 3	Rate		Unit 6	Amount 7
			In Fig. 4	In Words 5		
	Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete.	4.08	7441.35	Rupees seven thousand four hundred forty-one and paise thirty-five only	Cum	30361.00
19	Providing fly ash brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	16.16	7663.35	Rupees seven thousand six hundred sixty-three and paise thirty-five only	Cum	123840.00
20	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.	105.08	277.15	Rupees two hundred seventy-seven and paise fifteen only	Cum	29123.00
21	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the	139.36	649.05	Rupees six hundred forty-nine and paise five only	Cum	90452.00
22	Providing and applying impression 24 carrat Luxury paint of approved make & approved brand Emulsion paint to interior walls and ceilings of approved quality, colour and shade to new surface in two coats, including sub surface preparation by Acrylic putty and Acrylic primer coats including	105.08	200.00	Rupees two hundred and paise nil only	Cum	21016.00
23	Providing and applying antipeel paint of approved make & approved brand exterior Emulsion paint of approved quality, colour and shade to old and new surface in two coats, including exterior acrylic primer coat, scaffolding, preparing the surface etc. complete (Heat	139.36	200.00	Rupees two hundred and paise nil only	Cum	27872.00
24	Providing and fixing Country cut teak wood double or single leaf panelled shutters, 35 mm thick style top and freze rail 95 x 35 thick with lock and bottam rail 195 x 25 mm thick and panels without ventilator as per detailed drawing excluding the door frame, stainless steel fixtures	9.60	9542.00	Rupees nine thousand five hundred forty-two and paise nil only	Cum	91603.00
25	Providing and fixing frame with / without ventilator of size as specified with Country cut teak wood for doors and windows including chamfering, rounding, rebating, iron holdfast of size 300mm x 40mm x 5mm with oil painting, etc. complete	0.11	200050.00	Rupees two lakhs fifty and paise nil only	Cum	22006.00
26	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/ One Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.	18.00	2097.00	Rupees two thousand ninety-seven and paise nil only	Cum	37746.00

Name of Work	Quantity	Rate		Unit	Amount
		In Fig.	In Words		
2	3	4	5	6	7
Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc.	83.60	1293.45	Rupees one thousand two hundred ninety-three and paise forty-five only	Cum	108132.00
28 Providing and laying machine cut machine polished machine cut Kota stone slabs 20 to 25 mm thick for treads and risers of steps and staircases, with rounded nosing for the treads on a bed of 1:4 cement mortar including cement float, filling joints with neat cement slurry, curing, polishing and	16.31	1619.10	Rupees one thousand six hundred nineteen and paise ten only	Cum	26408.00
29 Providing Mirror polishing to Kota Stone including using all necessary stones and equipments cleaning, washing etc. complete. For Flooring	80.00	149.00	Rupees one hundred forty-nine and paise nil only	Cum	11920.00
30 Providing Mirror polishing to Kota Stone including using all necessary stones and equipments cleaning, washing etc. complete. For Skirting	1.80	79.00	Rupees seventy-nine and paise nil only	Cum	142.00
31 Providing and fixing heavy duty inter locking concrete Rubber mould glossy paving blocks of 80 mm thickness of having a strength of 400 Kilogram/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints	0.00	1408.40	Rupees one thousand four hundred eight and paise forty only	Cum	0.00
32 Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on	8.00	569.00	Rupees five hundred sixty-nine and paise nil only	Cum	4552.00
33 Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on	8.00	569.00	Rupees five hundred sixty-nine and paise nil only	Cum	4552.00
34 Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window of two tracks with rectangular pipe having overall dimension ?63.50 x 38.10 x 1.02 mm at weight 0.547 Kilogram/One Running Metre. and window frame bottom track section	18.90	4864.00	Rupees four thousand eight hundred sixty-four and paise nil only	Cum	91930.00
Total Rs.					1945914.00

[Signature]
Sub Divisional Engineer
Z.P.(W) Sub Dn, Mouda

Part B
Part C

[Signature]
Approved
Executive Engineer
Zilla Parishad, Mouda

36874.00
359995.00
2342783.00