

**TENDER NO NOTIFICATION**

<b>Tender No.</b> 79	:-	MPPKVVCL/Tender No. - 05/05/2026
<b>Announcement Date</b>	:-	
<b>Work No.</b>	:-	
<b>Name of Work</b>	:-	Construction & renovation of Control room at AKVN S/S Waidhan, Distt. Singrauli.
<b>Title</b>	:-	Notice Inviting Tender
<b>Stage</b>	:-	Three Stage, General Bid-Technical Bid, Cost Bid
<b>Location/Division/Basin</b>	:-	Rewa Civil Circle
<b>Estimated Cost Rs.</b>	:-	1003248.00
<b>Cost of Document in Rs.</b>	:-	1180.00
<b>EMD in Rs.</b>	:-	10032.00
<b>Execution Period</b>	:-	4 Month
<b>Tender Category</b>	:-	Works
<b>SOR</b>	:-	PWD with effect from 01/12/2020
<b>Purchase of Tender Start Date</b>	:-	05-05-2026
<b>Bid Submission End Date</b>	:-	18-05-2026
<b>Opening Date (Document)</b>	:-	(Envelope A) Open 18-05-2026, 05:30 PM, Technical Proposal (Envelope B) Open 18-05-2026, 05:30 PM, Financial Bid (Envelope C) Open 18-05-2026, 05:30 PM
<b>Tender Opening Date</b>	:-	20-05-2026, 10:30 AM
<b>Tender No Hosted By</b>	:-	<u>secivilrewa@gmail.com</u>
<b>Contact No.</b>	:-	9425824994

  
**Executive Engineer (Civil)**  
**MPPKVVCL, Rewa**

Name:- Construction & renovation of Control room at AKVN S/S Waidhan, Distt. Singrauli.

Item	Item Details	Qty.	Unit	Rate	Amount
2.2	clearing jungle...	1995	SQM	4.14	8259.3
2	2.7.2 Earthwork in excavation by mechanical means..... All kinds of soil	45	CUM	402	18090
3	4.1.2.3 Providing & Laying P.C.C. 1:4:8 with 40 mm aggregate.	10	CUM	3474	34740
4	5.16.3 Reinforcement for R.C.C.....etc complete.	3590	kg	62.9	225811
5	5.9.1 Centering and shuttering.....	18	SQM	190.6	3430.8
6	5.1.1 Providing & Laying R.C.C.M20 with 20 mm aggregate.	13.8	CUM	5796	79984.8
7	5.2.1 Providing & Laying R.C.C.M20 with 20 mm aggregate.	12	CUM	5865	70380
8	5.3.1 Providing & Laying R.C.C.M20 with 20 mm aggregate.	20	CUM	6155	123100
9	5.9.6 Centering & shuttering i/c strutting, proping for columns	25	SQM	471.2	11780
10	5.9.5 Centering & shuttering i/c strutting, proping for lintels, Beams girders & cantilevers	55	SQM	356	19580
11	5.9.3 Centering & shuttering i/c strutting, proping for Suspended floors	90	SQM	439.6	39564
12	6.5.2 Brick work with open bhatta bricks CM 1:6	4.7	CUM	4155	19528.5
13	6.6.2 Brick work with open bhatta bricks CM 1:6	20	CUM	4350	87000
14	11.77.1 Providing & Fixing vitrified tile 600x600mm	7	sqm	940	6580
15	11.76.1 Providing & Fixing vitrified tile 600x600mm	80	SQM	950	76000
16	6.14.2 Half brick work CM1:4	15	SQM	522	7830
17	10.27.1 P & Fixing glass panes 4mm thick	10.5	SQM	792	8316
18	11.49 Ceramic glazed tile wall	13	sqm	776	10088
19	11.48 Ceramic glazed tile floor	5.5	sqm	670	3685
20	17.1.1 P/F w.c. Seat	1	Nos	2995	2995
21	17.2.1 P/F european seat	1	Nos	3036	3036
22	19.49 P/Placing.....on terrace water tank	500	LIT	7	3500
23	18.9.2.1 P/F CPVC pipe .....	10	RM	297	2970
24	18.9.2.2 P/F CPVC pipe .....	15	RM	428	6420
25	17.58.2 P/Fixing soil waste pipe.....110mm dia	10	RM	195	1950
26	17.59.3.2 PVC T-110mm	3	Nos	346	1038
27	18.35.3 BALL wall brass	2	Nos	516	1032
28	18.51.1 P/F brass bib cock 15mm	5	Nos	234	1170
29	19.5.1 P/Laying in position cc 1:3:6 aal around pipe	3	RM	576	1728
30	3.1.1 Point wiring .....SHORT POINT	9	Nos	282	2538
31	3.1.2 Point wiring .....medieme POINT	12	Nos	487	5844
32	3.1.3 Point wiring .....long POINT	5	Nos	737	3685
33	3.1.3.1 3/6 amp 5 pin seprate board sp	1	Nos	393	393
34	3.1.3.2 3/6 amp 5 pin seprate board mp	4	Nos	637	2548
35	3.6.1 Circuit wiring.....2x2.5 sqmm	90	RM	69	6210
36	3.6.2 Circuit wiring.....4x2.5 sqmm	70	RM	116	8120
37	10.1.B Point wireing 16 a sp	4	Nos	577	2308

10.1.a	Point wiring 16 amp	2	Nos	949	1898
27.8.1.2	MCB C series	4	Nos	136	544
27.11.2	MCB BOX	1	Nos	617	617
30.1.2	Ceiling fan 1200mm sweep	3	Nos	1668	5004
29.23	Electronic regulator 100 Watt	3	Nos	168	504
31.3.1	Electronic tube light	10	Nos	502	5020
13.8.1	6MM thick cement plaster of mix CM 1:3	100	SQM	96	9600
13.3.2	20MM thick cement plaster of mix CM 1:6	200	SQM	197	39400
46	13.9 6MM thick cement plaster of mix CM 1:3 with heat cem..	100	SQM	171	17100
47	13.65 Painting with synthetic enamel paint.....	75	SQM	77	5775
48					0
49	18.3.4 Supplying & Fixing .....6module.	5	Each	138	690
50	18.2.1 Supplying & Fixing .....1 OR 2module.	5	Each	92	460
51	9.65.2 P/Fixing ISI marked stainless steel sliding door bolts .... 250x16mm	14	Each	326	4564
52	9.69.1 P/Fixing ISI marked stainless steel handles 125mm	14	Each	60	840
					1003248.4



A.E. (Civil)  
MPPKVCL, Rewa