

TENDER NO NOTIFICATION

Tender No.	96	:-	MPPKVCL/Tender No. - 01/08/05/2020
Announcement Date		:-	
Work No.		:-	
Name of Work		:-	Construction of boundary wall, yard metalling & levelling and main gate & wicket gate, Bore well and Control room Renovation at 33/11kv S/s Bela, Amarpatan. Distt. <u>Sadma</u> .
Title		:-	Notice Inviting Tender
Stage		:-	Three Stage, General Bid-Technical Bid, Cost Bid
Location/Division/Basin		:-	Rewa Civil Circle
Estimated Cost Rs.		:-	816388.00
Cost of Document in Rs.		:-	1180.00
EMD in Rs.		:-	8164.00
Execution Period		:-	2-Month
Tender Category		:-	Works
SOR		:-	PWD with effect from 01/12/2020
Purchase of Tender Start Date		:-	08-05-2026
Bid Submission End Date		:-	22-05-2026
Opening Date (Document)		:-	(Envelope A) Open 22-05-2026, 05:30 PM, Technical Proposal (Envelope B) Open 22-05-2026, 05:30 PM, Financial Bid (Envelope C) Open 22-05-2026, 05:30 PM
Tender Opening Date		:-	25-05-2026, 10:30 AM
Tender No Hosted By		:-	<u>secivilrewa@gmail.com</u>
Contact No.		:-	9425824994


Executive Engineer (Civil)
MPPKVCL, Rewa

Name:-

Construction of boundary wall, yard metalling & levelling and main gate & wicket gate, Borewell and Control room Renovation at 33/11kv S/s Bela, Amarpatan. Distt. Satna.

No.	Item Code	Item Details	Qty.	Unit	Rate	Amount
1	2.6	Earth work in excavation by mechanical means (blasting prohibited) all kind of soil	42.18	Sqm	129	5441.22
2	4.1.2.3	Providing & laying PCC 1:4:8 with 40mm aggregate	3.5	Cum	3474	12159
3	5.16.3	Reinforcement for RCC etc complete	1400	Kg	62.9	88060
4	5.9.1	Centering and shuttering	35	Sqm	190.6	6671
5	5.1.1	Providing & laying RCC M20 with 20mm aggregate.	12	Cum	5796	69552
6	5.3.1	Providing & laying RCC M20 with 20mm aggregate.	10	Cum	6155	61550
7	5.9.6	Centering and shuttering i/c structting, proping for columns	18	Sqm	471.2	8481.6
8	2.27.1	Supplying and filling in plinth-----not exceeding 20cm	28	cum	300	8400
9	6.5.2	Brick work with open bhatta brick CM 1:6	5	Cum	4150	20750
10	13.3.2	20mm thick cement plaster of mix CM 1:6	100	Sqm	197	19700
11	5.9.5	Centering & shuttering i/c structting, proping for lintels, beams girders & cantilevers	50	Sqm	356	17800
12	6.6.2	Brick work cm 1:6 above plinth	15	Cum	4350	65250
13	13.52	Finishing wall by any mechanical-----acrylic paint	350	Sqm	138	48300
14	5.9.3	Centering & shuttering i/c structting, proping for suspended floors	30	Sqm	439.6	13188
15	42.88.1	Collection and spreading ---- dust	40	cum	897	35880
16	42.88.3	Collection and spreading ---- 40mm metal	50	Cum	1036	51800
17	15.48	Dismantalling of old plaster---	55	Sqm	13	715
18	14.1.1	Repairing to plaster --12 to 20mm thk	25	Sqm	180	4500
19	13.9	6mm plaster with floting coat--	30	Sqm	171	5130
20	39.1.13	Supplying and installation of..... 2HP With 25 Stage	1	Each	26295	26295
21	22.24	Supplying and applying fiber and -----	30	Sqm	365	10950
22	14.30	Removing dry or oil bound or -----water proofing	160	Sqm	6	960
23	13.41	White cement based putty---	160	Sqm	74	11840
24	13.46	Wall painting by any -----	160	Sqm	64	10240
25	13.65	Painting with synthetic enamel paint-----	30	Sqm	77	2310
26	10.27	P/F glass panes/steel sheet-----	2	Sqm	792	1584
27	39.3.1	Supplying and laying of submersible flat cable.... 2.5 sqr mm	100	Rm	78	7800
28	39.5	Supplying and laying of nylon roap 12MM thick..... Motor	105	Rm	76	7980
29	39.4.2	Supplying and laying of HDPE Pipe 32 mm OD	85	Rm	88	7480
30	16.9.2	P/F and M.S. Clamp---150mm dia	1	Each	1129	1129
31	16.8.2	P/F suitable size bore cap 150MM dia	1	Each	366	366
32	10.14.1	Steel work in built up ----- Hot finished	300	kg	108	32400
33	13.57	Painting on GS Sheet -----mordant solution	4.5	Sqm	55	247.5
34	19.49	P/Placing on terrace water tank	1000	Lit	7	7000
35	18.9.2.1	P/F CPVC Pipe	40	Rm	297	11880
36	18.9.2.2	P/F CPVC Pipe	15	Rm	428	6420
37	18.35.3	Ball brass	3	Nos	516	1548
38	18.51.1	P/F brass bib cock 15mm	10	Nos	234	2340
39	8.1.1	Point wiring - short point	3	Nos	282	846
40	8.1.2	Point wiring - medium point	6	Nos	487	2922
41	3.2	3/5 amp 5 pin seprate board MP	4	Nos	637	2548

5.3	Circuit wiring 2x2.5 sqmm	20	Rm	69	1380
19.1.1.2	Circuit wiring 2x1.5 sqmm	20	Rm	23	460
10.1.4	Point wiring 16 A MP	3	Nos	949	2847
27.5.1.2	MCB C series	4	Nos	136	544
27.11.2	MCB Box	1	Nos	617	617
30.1.2	Ceiling fan 1200mm sweep	1	Nos	1668	1668
29.23	Electronic regulator 100 watt	1	Nos	168	168
31.3.1	Electronic tube light	6	Nos	502	3012
30.4.5	Exhaust fan 300mm sweep	1	Nos	1410	1410
18.3.1	Supplying and fixing of ----PVC Box 1 or 2 module	3	Each	76	228
18.3.6	Supplying and fixing of ----PVC Box 12 module	1	Each	223	223
28.5.1	Labour charge for fixing-----	1	Each	367	367
28.4.1	Fixing of MCB/MCCB-----	4	Each	8	32
16.1.1.2	Boring/drilling----- all type of soils	31	Rm	413	12803
16.1.2.2	Boring/drilling----- all type of rocky strata upto 90 mtr	59	Rm	625	36875
16.1.4.2	Boring/drilling----- all type of rocky strata beyond 90 mtr	20	Rm	656	13120
16.3.2	Supplying assembling lowering---	30.5	Rm	551	16805.5
39.1.9	Supplying and installation of..... 1.5 HP With 20 Stage	1	Each	23415	23415

816387.82



A.E. (Civil)
MPPKVCL, Satna