

**NIT SCHEDULE OF ANNUAL REPAIR WORK OF DIFFERENT WORK UNDER
SUB DIVISION NARSINGHPUR
MPPWD SOR Road & Bridge wef 11.04.2025**

NIT AMOUNT 16.73 LAKH

S. No.	SOR Item No./Page No.	Item Description	Quantity	Rate	Unit	Amount
1	17.20 / 141	Removal and refixing of existing pipe railing before and after rains including transportation of material from bridge to store place which is provided by the department as per guidance of department.	3860	200	RM	772000
2	12.1 / 96	Excavation for structures: Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom as per relevant clauses of section 300 & 2100.	8019	79	CUM	633501
3	17.1 / 139	Removal of existing cement concrete wearing coat including its disposal complete as per technical specification without causing any detrimental effect to any part of the bridge structure and removal of dismantled material with all lifts and lead up to 1000m (Thickness 75 mm).	46.38	283	CUM	13124.97
4	14.1 / 116	Providing and placing reinforced/prestressed cement concrete in super-structure excluding reinforcement as per drawing and technical specification and as per relevant clauses of section 1500, 1700 and 2300 in RCC Grade M30: (i) Solid Slab 1 Height up to 5 m	46.38	5475	CUM	253919.55
		Total				1672545.52
		PAC AMOUNT Say (Lakh)				16.73


Sub Engineer

PWD, Bridge Construction,
Sub Division, Narsinghpur


Sub Div Officer,

PWD, Bridge Construction,
Sub Division, Narsinghpur


Executive Engineer,

PWD, Bridge Construction,
Sub Division, Jabalpur