

N I T SCHEDULE

CONSTRUCTION OF PARKING STAND IN DISTRICT COURT KATNI

PAC - Rs. 3.88 LACS

S O R 01 01 2024

S. No.	S O R ITEM No.	DETAIL OF WORKS	QTY	RATE	UNIT	AMOUNT
1	2.26	Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering, ramming and compacting in layers not exceeding 20cm in depth and dressing complete				
			60.00	672	CUM	40320
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level : PCC M-20				
			60.00	4933	CUM	295980
3	5.9	Centering and shuttering including strutting, propping etc. and removal of form for:				
		5.9.1 Foundations, footings, bases of columns, etc. for concrete upto plinth level				
			15	190.60	SQM	2859
4	6.7	Brick work with fly ash lime bricks (FALG Bricks) conforming to IS:12894-2002, in super structure above plinth level up to floor two level in : Having 50 kg / cm ² average compressive strength. Cement mortar 1:4 (1 cement : 4 sand)				
			8	5158.00	CUM	41676.64
5	13.1	12 mm cement plaster of mix : 1:4 (1 cement : 4 sand)				
			40	173.00	SQM	6920
						387756



SUB ENGINEER
P W D - KATNI-I

S D O P.W.D. (B/R)
SUB DIV.- KATNI I



EXECUTIVE ENGINEER
P W D (B/R)
DIVISION-KATNI