

**NIT Schedule for White wash/ Colour Wash, painting in PWD Colony
Residential Building Rajgarh Under Sub Division Rajgarh**

PAC in Lakh 5.00

S.No.	Description of item	Qty.	Rate	Unit	Amount
1	2	3	4	5	6
	SOR Item No. 14.30				
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	1800	sqm	6.00	10800
	SOR Item No. 14.49.1				
2	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 liters/10 sqm complete including cost of Priming coat.	1500	sqm	42.00	63000
	SOR Item No. 13.41				
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand over the plastered wall surface to prepare the surface even and smooth i/c all cost of material, labour and scaffold etc in all position complete. Note : Putty shall be applied only on the internal walls, for application on the exterior walls prior permission of APD/Chief Engineer will be required.	1600	sqm	74.00	118400
	SOR Item No. 13.54.3				
4	Finishing walls by any mechanical or manual means with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :	1300	sqm	81.00	105300
	SOR Item No. 14.27				
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	2500	sqm	5.00	12500
	SOR Item No. 14.53.1				
6	Finishing walls with DeluxeMulti surface paint system for interiors and exteriors using Primer as per manufacturers specifications : One or more coats applied on walls @ 0.85 ltr/10 sqm.	1300	sqm	58.00	75400

S.No.	Description of item	Qty.	Rate	Unit	Amount
1	2	3	4	5	6
	SOR Item No. 13.42				
7	Providing and applying special putty in two coats based materials varnish, Belgium chalk, turpentine oil, white paint, safeda including sand papering for making the surface smooth for applying any or vinyl paints including all cost of material and labour etc complete.	850	sqm	52.00	44200
	SOR Item No. 14.37				
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	640.2	sqm	35.00	22407
	SOR Item No. 13.45				
9	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 grams/ltr of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coat on new work.	250	sqm	75.00	18750
	SOR Item No. 14.29				
10	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: Old work (one or more coats).	200	sqm	21.00	4200
	SOR Item No. 13.67.3				
11	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	1045	sqm	24.00	25080

500037

5.00

Sub Engineer
P.W.D. (B&R)
Rajgarh

Sub Divisional Officer
P.W.D. (B&R) Sub Division
Rajgarh

Executive Engineer
P.W.D. (B&R) Division
Rajgarh