


**N.I.T. Schedule for Painting & Washing of Govt. Non Residential Building
Under Sub division Khilchipur PWD (B/R) Division Rajgarh (M.P.)**

P.A.C. RS. - 7.00 Lacs

| S.N. | SOR Item No. | Description | Qty | Unit | Rate | Amount |
|--------------------|--------------|---|----------|------|-------|------------------|
| 1 | 14.27 | Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete | 10000.00 | Sqm | 5.00 | 50000.00 |
| 2 | 14.29 | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : | | | | |
| | 14.29.1 | Old work (one or more coats) | 5200.00 | Sqm | 21 | 109200.00 |
| 3 | 14.26 | White washing with lime to give an even shade : | | | | |
| | 14.26.1 | Old work (two or more coats) | 3114.00 | Sqm | 7.00 | 21798.00 |
| 4 | 14.36 | Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade : | | | | |
| | 14.36.1 | One or more coats on old work. | 6000.00 | Sqm | 41.00 | 246000.00 |
| 5 | 14.37 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : | | | | |
| | 14.37.1 | One or more coats on old work. | 800.00 | Sqm | 35.00 | 28000.00 |
| 6 | 13.67. | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content | | | | |
| | 13.67.3 | With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre | 2500.00 | Sqm | 24.00 | 60000.00 |
| 7 | 13.41 | Providing and applying white cement based putty of average thickness 1 mm, of approved brand over the plastered wall surface to prepare the surface even and smooth i/c all cost of material, labour and scaffold etc in all position complete. Note : Putty shall be applied only on the internal walls, for application on the exterior walls prior permission of APD/Chief Engineer will be required | 2500.00 | Sqm | 74.00 | 185000.00 |
| TOTAL = | | | | | | 699998.00 |
| Sai in Lacs | | | | | | 7.00 Lacs |

Sub Engineer
P.W.D. (B/R)
Khilchipur


Sub Divisional Officer
P.W.D. (B/R)
Sub Division Khilchipur

Executive Engineer
P.W.D. (B/R)
Division Rajgarh