

**Office of The Executive Engineer**  
**U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.**  
 (Ex.- U.P. SAMAJ KALYAN NIRMAN NIGAM LTD.)

**106, Aruna Nagar, Etah.**

**E-Tender Notice**

Notice No. 03/M.L.A-Patiyali/Kasganj/2026-27

Dated :- 14-05-2026

U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. 106, Aruna Nagar, Etah.. Invites Percentage E-Tender from eligible Registered contractors/firms/company for the following work given below:-

S. N.	Name of Works	Cost of Tender (Rs)	Under Vidhyak Nidhi	Cost of BOQ (In Lacs)	Earnest Money (in Lacs)	Time of Completion	Address of unit & Tender Receiving office
1	2	3	4	5	6	7	8
1	ग्राम रम्पुरा ब्लॉक पटियाली में बारातघर का निर्माण	1652.00 With GST	M.L.A Patiyali	13.76	0.28	4 Month or within one month as per release of second installment from DRDA .	Executive Engineer UPSCIDC 106 Aruna Nagar Etah

The tender can be downloaded from the website [www.etender.up.nic.in](http://www.etender.up.nic.in) as per schedule given below

S.N	DESCRIPTION	DATE	TIME
1	Document downloading start date	14.05.2026	03.00 PM
2	Document downloading end date	21.05.2026	11.00 AM
3	Bid submission start date	14.05.2026	03.30 PM
4	Online bid submission closing date	21.05.2026	11.00 AM
5	Bid opening date	21.05.2026	11.30 AM

**Terms & Condition:-**

- Only Registered contractor/firm/company in UPSCIDCO Etah "D" class is eligible for this work
- All Documents included demand draft of Tender Fees and Earnest Money, Character certificate, Solvency certificate, Pan Card of Registered firm /owner / Proprietorship , Registration certificate and GST Registration Certificate must be uploaded at website (<https://e-tender.up.nic.in>) on or before 11.00 AM on Dated 21.05.2026 and Bid will be open on 21.05.2026 at 11.30 AM
- Hard Copy of Technical and financial bid complete in all aspect in two separate envelope sealed and duly signed should be submitted in the office of Executive Engineer, UPSCIDC 106, Aruna Nagar Etah On or before 11.00 AM on 21.05.2026 along with earnest money and cost of tender Fee, through DD/Banker Cheque of Nationalize bank payable in favour of U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD or UPSCIDC Payable at Etah
- Any bidder who is having criminal record is not allowed to participate in E-Tender process
- Quantity of work shown on BOQ may vary and quantity will be paid as per actual measurement at site
- The rates should be quoted as per specification. GST will be paid extra as applicable
- The lowest rates quoted will be analyzed by a committee of officers of UPSCIDC and work order will be issued to successful bidder subject to acceptance/Recommendation of rates by the committee. If the bidder is not able to work as per agreement and specification in time. Work order will be canceled and security will be forfeited



अधिकाारी अभियंता  
 कूपी० स्टेट कांस्ट्रक्शन एण्ड  
 इन्फ्रास्ट्रक्चर डेवलेपमेंट कारपोरेशन लिमिटेड  
 एटा

8. Executive Engineer UPSCIDC reserves the right to accept or reject any or all tenders or in part there of without assigning any reason what so ever at any time and without any legal obligation thereof The decision of undersigned will be final and binding to all Bidder.
9. The contractor shall be completely responsible for any mishap at site due to in sufficient safety measures.
10. In respect of all labor directly or indirectly employed in the work by the contractor is a part of this contract. The contractor shall comply with all rules framed by govt. from time to time for the protection of the health and Sanitary arrangement for workers employed by the contractor
11. For any substandard quality of work. The suitable deduction of payment will be made from contractor as per direction of Engineer in Charge
12. The successful bidder will have to execute an agreement on Rs. 100.00 non judicial stamp paper with in One Week and Work to be started just after of Agreement.
13. All the work shall be carried out as per detailed specification of UPPWD/CPWD and as per direction of Engineer in Charge.
14. In case of any damage/loss of Nigam Property at site. The cost of the same shall be deducted from the contractor bill.
15. TDS & other deduction will be done as per applicable Rules.
16. Quoted rates more than bid rates shall not be accepted.
17. The tendered cost in the form of bank guarantee/FDR of any nationalized Bank or Demand Draft. If the rates quoted by the bidder is below more than 5% of BOQ Amount than additional security will have to be deposited with reference to G.O No 622/23/12-2012-2 Audit/08 T.C-2 Dt. 08.06.12 of UPPWD – Anubhag 12 as per following  
0.50% per 1.00% below up to 10% below of BOQ Amount  
1.00% per 1.00% below , above 10% below of BOQ Amount
18. Evaluation of Tender carried out in three stages as below:-
  - i) Evaluation of Tender Fees and Earnest money with respect to upload documents.
  - ii) Technical Evaluation with respect to required documents uploaded as per NIT.
  - iii) Financial bid shall be opened of successful Bidders firm/Contractor in Technical Bid.
19. The work will be completed by successful bidder In time as per Column No-7
20. Payment will be made on G.S.T. Bill which in raised by bidder for work done as per Abstract of cost Prepared by contractor on the basis of Actual Measurement of work done and up to fund available for the work and checked by Corporation Engineers.
21. Due to Covid-19 pandemic the Guideline issued from Govt of India /Govt of UP/District Authority time to time is to be strictly followed by successful contractor during the time of construction /execution of work
22. It is requested to contractor to regularly watched on website (<https://e-tender.up.nic.in> for any amendment related to NIT/E-tender.
23. Tender value may be credit in Our Union Bank of India , G.T Road Etah by RTGS/NEFT/D.D A/c No. - 594002010004460 IFSC Code is – UBIN0559407 and earnest money may be Credit in our Bank Mentioned above threw F.D/D.D/R.T.G.S/NEFT.

  
Executive Engineer  
UPSCIDCO Etah

अधिसारी अभियंता  
यूपीएच स्टेट कॉरपोरेशन एण्ड  
इन्फ्रास्ट्रक्चर डेवलपमेंट कारपोरेशन लिमिटेड  
एटा

U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD ETAN  
(Erstwhile:-U.P.SAMAJ KALYAN NIRMAN NIGAM LTD)

BILL OF QUANTITY

कार्य का नाम :- ग्राम रमपुरा ब्लॉक पटियाली में बारातघर का निर्माण।

ANALYSIS FOR SEPTIC TANK FOR 25 USERS

S.N	DESCRIPTION OF WORK	No.	L	B	H	QTY	UNIT	Rate	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic Excavator )/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.								
	Septic Tank	1	3.46	2.46	1.80	15.32			
					Total	15.32	Cum	177.50	2,719.46
2/ 4.1.8	Providing and laying in cement concrete 1:4:8 (1 cement :4 coarse sand :8 graded stone aggregate 40 mm nominal size) and curing complete,including cost of form- work, in foundation and floors.								
	septic tank	1	3.46	2.46	0.10	0.85			
					Total	0.85	Cum	6812.00	5,798.10
3/ 6.1.1	Class M-150 brick work in 1:4 cement coarse sand mortar i/c supply of all material labour T&P complete of work in foundation .								
	Septic Tank	2	3.46	0.23	2.05	3.26			
		2	2.00	0.23	2.05	1.89			
					Total	5.15	Cum	7370.65	37,949.86
4/ 5.1.2	R.C.C. works with cement approved coarse sand and 20 mm approved stone aggregate in the proportion 1 : 1.5:3 (1 cement: 1.5 coarse sand : 3 stone aggregate ) excluding supply Of reinforcement and its bending & binding. with binding wire including supply of all material T&P complete.								
		1	3.46	2.46	0.10	0.85			
					Total	0.85	Cum	9045.75	7,699.38
5/ 5.22.6	M.S work in RCC work								
		1	1.17	0.015	7850.00	137.77			
					Total	137.77	Kg	107.85	14,858.22
6/ 13.9.2	20 mm thick 1:3 cement coarse sand mortar plaster with NCF.								
		1	10.00	2.05		20.50			
		1	11.84	0.25		2.96			
					Total	23.46	Sqm	587.20	13,775.71
							Total Rs		82,800.73

*Handwritten signature/initials*

*Handwritten signature/initials*

U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. ETAA  
(Erstwhile:-U.P. SAMAJ KALYAN NIRMAN NIGAM LTD)

BILL OF QUANTITY

कार्ड का नाम - ग्राम रम्पुरा ब्लॉक पटियाली में बारातघर का निर्माण।

S.N	DSR 2023	Description of item	Qty	Unit	Rate	Amount in Rs
1	2.31	Cleaning of Jungel & grass uprooting complete for layout surface area	150.00	Sqm	17.60	2640.00
2	2.6.1	Earth work in excavation by mechanical means (Hydraulic Excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 cum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	41.12	Cum	177.50	7298.80
3	4.1.8	Providing and Laying in cement concrete 1:4:8 (1 cement :4 Coarse sand :8 Graded Stone Ballast 40mm nominal size) and curing complete, including cost of form work in foundation and floors.	8.26	Cum	6812.00	56235.29
4	6.1.2	Class-150 (Non Modular) brick work in Foundation including supply of all materials, labour and T&P etc. required for proper completion of the work. : In 1:6 cement and coarse sand mortar.	21.00	Cum	7132.25	149770.15
5	4.1.3	RCC work in 1:2.4::C:C/S &S/G 12 to 20 mm Plinth Bend & Lintel Bena	4.25	Cum	7878.50	33517.98
6		Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement				
		1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)				
	5.3	Beam & Sun shade	1.58	Cum	11505.50	18141.87
	5.3	Roof Slab	11.48	Cum	11505.50	132027.34
7	5.22 A	Reinforcement of Reinforced concrete (when not included in and an over all rates) brought to required shape as necessary including bending for proper completion of the work and including the supply of steel and its wastage, bend, hooks, binding wire and authorized over lapping shall be measured upto floor two level.	1747.55	Kg	107.85	188472.90
8	6.4.2	Class-150 brick work in 1:6 C:S in Super structure i/c all material, labour, T&P etc. complete. (230MM Wall)	26.54	Cum	9105.95	241688.45
9		B/W in 1:4::C:C/S mortar In Super Structure.				
	6.13.2	115 mm thick wall	23.12	Sqm	1123.80	25980.51
10	13.9.2	20 mm thick bearing & roof plaster in 1:3::C:C/S	12.06	Sqm	587.20	7082.34
11	13.9.2	20 mm thick cement plaster in 1:3::C:C/S mortar i/c water proofing compound and N.C.F. top of roof.	91.80	Sqm	587.20	53905.66
12		P/F of M.S iron work				
	10.31	Door Chaukhat	71.50	Kg	130.50	9330.75
	10.11.1	M.S Z-section window/ventilator openable	265.82	Kg	131.05	34836.24

*Handwritten signature/initials*

*Handwritten signature/initials*

U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. ETAH  
(Erstwhile:-U.P.SAMAJ KALYAN NIRMAN NIGAM LTD)

BILL OF QUANTITY

कार्य का नाम :- ग्राम रम्पुरा ब्लॉक पटियाली में बारातघर का निर्माण।

S N	DSR 2023	Description of item	Qty	Unit	Rate	Amount in Rs
13	13.4.2	12 mm thick plaster in 1:6 cement & c/sand mortar over smooth surface including supply of all material, labour, T&P etc.	211.98	Sqm	343.65	72846.98
14	13.5.2	15 mm thick plaster in 1:6 cement & c/sand mortar over smooth surface including supply of all material, labour, T&P etc.	184.83	Sqm	395.35	73073.73
15	11.3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone of size 12.5mm nominal size) laid in one layer finished with floating coat of neat cement (40mm thick floor)	27.34	Sqm	614.20	16789.77
16	8.2.2.2	Providing and Laying 18mm thick Black Granite Stone Gnag Saw Cut Premoulded and prepolished machine cut in water quash and in platform over 20mm thick base of cement mortar 1:4 Cement :coarse sand laid and jointed with white cement slurry including rubbing and polishing complete.	78.10	Sqm	5136.30	401125.51
17	11.37A	P/Fxing of white glazed tiles in 1:3 cement coarse sand i/c finished with white cement.	12.99	Sqm	1112.70	14453.97
18	11.26.1	20 mm thick Dado/skirting in 1:3::C:C/S mortar i/c NCF.	2.46	Sqm	1948.25	4798.54
19	2.25A	Supply and filling of Earth brought from outside not exceeding 20m in depth, consolidation each deposited layer rammed with hammer or by mechanical means including cartage upto 5 km and loading & unloading including cost of earth etc. complete	75.69	Cum	700.50	53021.06
20	13.62.1	Two coat enamel paint with one coat of primer in . Window	30.75	Sqm	226.25	6957.87
21	13.62.1	Two coat enamel paint with one coat of Wood primer over door shutters i/c chaukhat.	19.66	Sqm	226.25	4447.17
22	13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	211.98	Sqm	156.05	33079.50
23	13.41	Two coat of Oil bound distemper i/c one coat of primer.	396.81	Sqm	185.65	73668.36
24	5.3	Making drip course in 1:3::C:C/S mortar.	29.56	Rmt	78.40	2317.50
25	5.3	Making groove in plaster 10 to 12 mm thick.	171.12	Rmt	57.09	9769.24
26	6.4.1	M-150 class brick work in 1:4 cement & Fine sand mortar in Foundation in Plinth including supply of all material, labour and T&P etc	0.79	Cum	9344.35	7343.82
27	13.4.1	12 mm thick plaster in 1:4 cement & c/sand mortar over smooth surface including supply of all material, labour, T&P etc.	14.19	Sqm	357.35	5070.80
28	9.21.1	P/Fxing Flush door 35 mm thick single door	8.19	Sqm	2392.65	19595.80
29	10.30.1	Providing and fixing glass panes of 4.00mm thickness	9.36	sqm	1064.65	9965.12
30	ANA	Providing and fixing Conduite Pipe	6.00	No	521.04	3126.24
31	17.3.1	European Type WC pan with white Plastic seat	1.00	each	8006.60	8006.60

*Handwritten signature/initials*

*Handwritten signature/initials*

**U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. ETAN**

(Erstwhile:-U.P.SAMAJ KALYAN NIRMAN NIGAM LTD)

**BILL OF QUANTITY**

कार्य का नाम :- ग्राम रम्पुरा ब्लॉक पटियाली में बारातघर का निर्माण।

S.N	DSR 2023	Description of item	Qty	Unit	Rate	Amount in Rs
32	18.49.1	P/F CP brass bib cock of approved quality conforming to IS:8931	1.00	each	506.80	506.80
33	18.48A	Water Tank 1000L	1000.00	ltr	11.00	11000.00
34	17.1.1	White Viterous China Wash Basin Size 630*450mm with a pair of 15mm CP brass pillar tap	1.00	No	2648.85	2648.85
35	17.28	P/F PVC waste pipe for Wash Basin	1.00	No	116.70	116.70
36	17.31	P/F 600*450 beveled edge mirror	1.00	No	1607.95	1607.95
37	17.73.2	P/F CP brass towel rod	2.00	No	708.95	1417.90
38	12.41.2	P/F PVC rain Water pipe 110mm	20.00	Mtr	377.40	7548.00
39	ANA	Const of Septic & Soak Pit	1.00	No	82800.73	82800.73
					Rs	1805233.06
		Less Rates DSR 2023 Amount *.735*106/107			Rs	1314445.14
40	MR	Electrification Work	1.00	Job	50000.00	50000.00
41	MR	Writing Name of School over wall.	1.00	Job	5000.00	5000.00
42	MR	P/F of sign board	1.00	Job	6800.00	6800.00
					Rs	1376245.14

*[Handwritten signature]*

*[Handwritten signature]*