

**U.P. STATE CONSTRUCTION AND INFRASTRUCTURE DEVELOPMENT
CORPORATION LTD.**

**(A Govt. of U.P. Undertaking)
(AN ISO 9001:2000 certified Organisation)**

Reg. Office : Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow

Short Terms Notice Inviting E-Tender

Tender Notice No- 59 /S.E/LKO-Region/ E-Tender /2026-27 Dated: 14-05.2026

1. U.P. State Construction & Infrastructure Development Corporation Ltd, Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow (U.P.) invites in 2 bids system online tenders on percentage rate bids from eligible and registered contractors in "B" class or above class in U.P. State Construction and Infrastructure Development Corporation Ltd. Bidders are advised to note the minimum criteria.

S. N.	Name of work	Estimated Cost (Rs. in lacs)	Earnest Money (Rs. in lacs)	Cost of Bid Document in Rs.	Time of Completion (in month)	Address of sale of tenders	Place of submission of tender
1	2	3	4	5	6	7	8
1.	Renovation of Fisheries Department Head office, Lucknow.	172.55	3.45	Rs.3540.00 (including GST)	06 Months	To be downloaded from the e-tender portal of nic "etender.up.nic.in"	To be uploaded on e-tender portal of nic


2. The contractors who fulfill the following requirements shall be eligible to apply.
- (i) Should have successfully completed similar works with some Central Government Department/ State Government Department/Central Autonomous Body/Central or State Public Sector undertaking during the last five years from the date of publication satisfying either of the following.
- (a) Three similar completed works each costing not less than 40 % of Tendered cost.
or
- (b) Two similar completed works each costing not less than 60% of Tendered cost.
or
- (c) One similar completed work costing not less than 80% of Tendered Cost.
- (ii) Should have an average annual financial turnover of 50% of estimated cost on construction work of similar nature during last three years, ending 31st March 2025 with UDIN (Copy of certificate from C.A. to be submitted).
- (iii) Should not have incurred any loss in more than two years during the last three years. Solvency certificate form Bankers issued within 06month from the date of NIT or issued by District Magistrate to be submitted.
- (vi) Should have a solvency of minimum 40% of the estimated cost put to tender, in support of which a certificate will be submitted.
- (iv) Character certificate form issued by District Magistrate to be submitted.
- (v) Information regarding projects in hand, current litigation, orders regarding exclusion, expulsion or black listing, if any should be submitted/uploaded.
- (vi) Registration of Labour, PAN No, GSTIN should be uploaded.
- (vii) Certificate issued by C.A. for detail of GSTR-1 and GST-3B ending Financial Year March 2025 should be uploaded.
- (viii) Security shall be deducted @ 5% from the payment amount from each running bills.
- (ix) G.S.T. shall be paid as sanctioned or as per approval by client.
- (x) The bidder shall mandatorily upload a bar chart for completion of the work within the stipulated time.
- (xi) Payment shall be made as per Availability of Fund from Client.
- (xii) Handing over to client department of project after completion will be the responsibility of contractor.

3. The bids shall remain valid for acceptance for a period of 180 (one hundred eighty days) days from the last date of submission of bids.
4. Bidders shall upload two separate covers marked "technical bid" and fee in PDF format and "financial bid" in cover "b" in Excel format.
5. Financial bids shall be opened of those bidder whose bids are technically qualified, Tender fee and E.M.D. properly submitted and other required documents uploaded found eligible. Scanned copy of E.M.D/Tender Fee to be uploaded with technical bid. In financial bid, rates shall be quoted by contractor Exclusive of taxes (GST as applicable shall be paid extra).
6. A set of Bidding documents may be downloaded from the e-tender portal of NIC as mentioned in column-7 between dated mentioned in N.I.T.
7. A Pre bid meeting shall be held in the office of the Superintending Engineer, U.P. State construction and Infrastructure Development Corporation Ltd., Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow. on dateNIL.....2026.
8. Bid will be uploaded on e-tender portal of NIC on date ..14.5.2026 at ..5.00..AM/PM and shall be submitted up to ..23.05.2026 at ..12....AM/PM. The technical bids will be opened on ..23.05.2026 at ..1....AM/PM in the office of Superintending Engineer, U.P.State construction and Infrastructure Development Corporation Ltd., Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow and the name of qualified bidders Shall be uploaded to portal, The financial bids shall be opened on dated mentioned in N.I.T. of NIC portal and name of successful bidder shall be uploaded and displayed.
9. The tenderer must be transfer the tender fee online and earnest money via RTGS to the U.P. State Construction and Infrastructure Development Corporation Limited, Lucknow bank name **Bank of India**, Account number **685210110006452**, IFSC Code **BKID0006852**, Indira Nagar Branch, Lucknow. A photocopy of the receipt/UTR number confirming the transfer of the tender fee and security deposit must be uploaded with the tender.
10. No Engineer of gazetted rank or other Gazetted officer employed in Engineering or Administrative duties in an Engineering Department of the state/ Central Government is allowed to work as a contractor for a period of two years after his retirement from government service, without Government permission. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government as aforesaid before submission of the tender or engagement in the contractor's service.
11. Any bidder who is having criminal record is not allowed to participate in the bidding process. photo attested by gazetted officer.
12. Any bidder who is registered with the state bar council is not allowed to participate in the bidding process.
13. The successful bidder will have to submit 5% performance guarantee of the tendered cost in the form of bank guarantee or FDR/DD of nationalized bank/Scheduled bank (HDFC/ICICI/AXIS BANK only).If the rates quoted by the bidder is below the BOQ, additional performance guarantee will have to be deposited with reference to G.O. No. 622/23/12-2012-2 Audit/08 T.C. -2 Dt. 08-06-2012 of UPPWD-Anubhag-12, as per following:-
 - (a) 0.50% per 1.00% below up to 10%, below of BOQ.
 - (b) 1.00% per 1.00% below, above 10%, below of BOQ.
14. UPSCIDCO reserve the right to accept or reject any or all tenders or in part thereof without assigning any reason whatsoever. UPSCIDCO also reserve the right to increase or decrease the quantity to be ordered.
15. All document including demand draft and certificate must be uploaded at website (<https://etender.up.nic.in>) and L1 have to verify uploaded documents by hard copy at the office of Superintending Engineer, U.P.State construction and Infrastructure Development Corporation Ltd., Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow.
16. The required papers uploaded as tender Fee, EMD. Affidavit etc. for qualification should be uploaded with Seal & signature.
17. The required papers uploaded for tender should be proper readable with Seal & signature Blurred or misprint paper will not be acceptable.
18. Construction work must be completed by contractor in all respect.



19. Bid Capacity (on Rs100 Non-Judicial Stamp papers) should be uploaded with duly verified by C.A/C.M.A. in format Form-A1,A2 as attached in Pre-Qualification document and should be Sign and Seal by both C.A. and Bidder.
20. Other general conditions of contract can be seen at UPSCIDCO Raebareli office in any working day between 10.00 AM to 5.00 PM.
21. All guide lines of M.H.A for Building Construction work to be followed in all respect.
22. L1 Bidder Should Receive all drawing and layout from the office of Executive Engineer, U.P.State construction and Infrastructure Development Corporation Ltd., Lekhraj Market-1st, 3rd floor Indira Nagar Lucknow.
23. The affidavit is to be typed on stamp paper worth Rs. 100/- duly signed and notarized with date, affixing a revenue stamp of Rs. 2/- only.
24. A duly signed agreement (" the Agreement") shall be executed between L1 qualified bidder and the corporation. The N.I.T will be deemed to be part of the Agreement.
Note:-If the tender fee is not deposited online by the registered firm then firm will be disqualified.
25. प्रतिभाग करने वाली फर्म द्वारा नयी पंजीकरण व्यवस्था के अनुसार हैसियत प्रमाण पत्र श्रेणीवार ए+, ए, बी, सी, डी के अनुसार क्रमशः 300.00 लाख, 150.00 लाख, 80.00 लाख, 40.00 लाख एवं 10.00 लाख अपलोड किया जाना अनिवार्य होगा अन्यथा तकनीकी बिड अस्वीकृत कर दी जायेगी जिसकी पूर्ण जिम्मेदारी फर्म की होगी।
26. सभी आवश्यक शपथ पत्र रू0 100.00 के स्टाम्प पेपर पर नोटरी सहित टेण्डर आई0डी0 एवं कार्य का नाम अंकित करना अनिवार्य होगा तथा सभी शपथ पत्र निविदा प्रकाशन की तिथि के बाद के होना अनिवार्य है। सभी शपथ पत्र में प्रथम पक्ष व द्वितीय पक्ष अंकित होना अनिवार्य होगा।
27. निविदा दाता द्वारा साइट निरीक्षण एवं दस्तावेजीकरण के सन्दर्भ में निम्न बिन्दुओ को भी संज्ञान में लिया जाना है:-
 1. साइट निरीक्षण अनिवार्यता :-ठेकेदार अथवा ठेकेदार द्वारा अधिकृत प्रतिनिधि द्वारा निविदा प्रकाशन की तिथि के पश्चात् साइट का भली-भाँति निरीक्षण करना अनिवार्य होगा।
 2. नाम पट्टिका का प्रदर्शन :-निरीक्षण के दौरान ठेकेदार अथवा ठेकेदार द्वारा अधिकृत प्रतिनिधि एवं फर्म का नाम पट्टिका स्पष्ट रूप से प्रदर्शित की जानी चाहिए।
 3. जी0पी0एस0 आधारित फोटोग्राफी :-निरीक्षण के दौरान साइट की जी0पी0एस0 लोकेशन सहित फोटोग्राफी करना अनिवार्य होगा। फोटोग्राफ में साइट का स्पष्ट दृश्य और कार्य का नाम स्पष्ट रूप से प्रदर्शित होना चाहिए। साइट निरीक्षणकर्ता का आधार एवं साइट निरीक्षण प्रमाण पत्र अपलोड करना अनिवार्य होगा।
 4. फोटोग्राफ का अपलोड करना :-निरीक्षण के उपरान्त ली गयी जी0पी0एस0 फोटोग्राफ को निर्धारित पोर्टल/प्लेटफार्म पर अपलोड करना अनिवार्य होगा ताकि यह सुनिश्चित हो सके कि साइट का निरीक्षण किया गया है।
 5. प्रमाण प्रस्तुत करना :-ठेकेदार को साइट निरीक्षण की पुष्टि हेतु जी0पी0एस0 फोटोग्राफ और कार्यस्थल का विवरण तकनीकी विड के साथ अपलोड करना होगा।
 6. अनुपालन की पुष्टि:-निविदा प्राधिकारी निरीक्षण दस्तावेजो और फोटोग्राफ की पुष्टि करेगा, यदि निरीक्षण का पालन नहीं किया जाता है तो ठेकेदार की विड अस्वीकार कर दीजायेगी।

Note:-1-Any addendum of corrigendum or any other update shall be available on <https://e-tender.up.nic.in>. Therefore Bidders are requested to refer to the e-Tender portal from time to time for any addendum /corrigendum/other documents updated regarding the e-tender.


 Executive Engineer
 UPSCIDCO, LUCKNOW

Renovation of Fisheries Department Head office,
Lucknow.

Site Location

(1) Lat 26.871148° Long 80.935833°



(ए०के० शुक्ला)
रिटेनर (तकनीकी/सिविल)
यूपीसिडको, लखनऊ इकाई-प्रथम



(बाबू राम)
प्र० अधिशापी अभियन्ता
यूपीसिडको, लखनऊ-प्रथम

Summary of Cost (E-Tender)

Name of Work :- Renovation of Fisheries Department Head Office Uttar Pradesh
Lucknow

Sno.	Particular of work	Amount
1	Cost of Repairing & Renovation of Communication, Ministerial Association and First Floor Main Office Building .	
A	Cost of Civil Work	2592198.92
B	Cost of Internal & External Sewerage and Sanitary Work	493984.64
C	Cost of Electrical Work (Internal & External)	0.00
2	Cost of Repairing & Renovation of (डास्प भवन) Office Building.	
A	Cost of Civil Work	1885083.72
B	Cost of Internal & External Sewerage and Sanitary Work	510100.62
3	Cost of Repairing & Renovation of Left side(नियोजन शाखा) Office Building.	
A	Cost of Civil Work	2451141.74
B	Cost of Electrical Work (Internal & External)	0.00
4	Cost of Repairing & Renovation of (मत्स्य चेतना केंद्र) Office.	
A	Cost of Civil Work	4414572.08
B	Cost of Internal & External Sewerage and Sanitary Work	524064.29
C	Cost of Electrical Work	0.00
5	Cost of 80mm thick Interlocking Tile & Rain Water Harvesting. Work.	
A	Cost of 80mm thick Interlocking Tile work	712539.99
B	Cost of Rain Water Harvesting Work	1008173.35
6	Cost of 110 mm thick Cement Concrete Road of Existing C.C. Road in Campus.	553072.71
7	Construction Cost of Damage Boundary in Back Side of (मत्स्य चेतना केंद्र) .	667447.84
8	Cost of 2 mm thick Bituminous membranes Waterproofing Work of Office Building Terrace.	717411.95
9	Cost of Boaring work submersible pump 5H.P.K.S.B. make.	567760.87
10	Cost of Glow Sinage Board for Main Entrence of Main Building and मत्स्य चेतना केंद्र Office.	157374.72
	Total	17254927.44
	Say in Lacs	172.55


(ए.के. शुक्ला)
सिटेनर (लकनौकी/सिविल)
यूपीसिडको, लखनऊ इकाई-प्रथम


(बाबू राम)
प्र० अधिशाषी अभिरक्षता
यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity

Name of Work :- Repairing & Renovation of Communication, Ministerials Association and First Floor Attached Main Office Building Matsya Nideshalay 7 Ayodhya Road Babuganj Lucknow.

S.No.	P.W.D.SI No.	115		Unit	Quantity	Rate	Amount
		Particulars					
1	15.56	Dismantling of Existing old Plaster including disposal of dismantled materials up to 60 mt directed by Engineer Incharge.		SqM	1766.09	41.01	72427.35
2	14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.		SqM	1766.09	54.37	96022.31
3	13.5.1	15 mm thick 1:4 cement :C/Sand Plaster including Supply of all material ,Labour T &P etc.		SqM	1766.09	309.00	545721.81
4	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08%and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand),jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.		SqM	372.85	1165.79	434664.80
5	13.80	Providing & Applying Two Coat White Cement Based Wall care Putty For Given Smooth surface for Outer side wall & ceiling.		Sqmt	3195.44	117.11	374217.98
6	13.41.1	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats.		Sqmt	2980.57	139.32	415253.01
7	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint withSilicone additives of required shade:13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqmover and including priming coat of exterior primer applied@ 2.20 kg/10 sqm)		SqM	214.87	128.40	27589.31
8	13.62.1	Two Coat Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade.		SqM	66.78	169.79	11338.58
9	15.2.1	Dismantling of Existing Toilet C.C Flooring including disposal of dismantled materials directed by Engineer Incharge within a distance of		Cub mt	3.32	1826.79	6064.94
10	MR	Removal of Cinder in Existing Toilet Sunken Portion including disposal of materials directed by Engineer Incharge within a distance of 60 meter .		Job	2.00	3325.00	6650.00
11	Aly	Dismantling of Brick Work with Window including New B/W 1:4 Cement / coarse Sand including of sides repairing 1:4 Cement / coarse Sand.		Sqmt	19.80	1497.16	29643.77
12	4.1.2	Providing & Laying of P.C.C. M- 20 Toilet Flooring 1:1.5:3 (1 Cement : 1.5 Coarse Sand : 3 Stone gritt 20mm Nominal Size) including all Material Labour T&P etc.		Cub mt	3.32	6259.44	20781.34
13	9.147.A4.1	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame,sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile),After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. Providing and fixing factory made uPVC white colour casement/casement including 4 & 5mm. thick Plain Glass as required complete in all Respect as directed by enginee-incharge.		Sqmt	19.80	8250.17	163353.37


 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम


14	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. (8.31)	SqM	108.10	951.54	102861.47
15	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ including pointing the joints with white cement and matching pigments etc., complete. (11.40)	SqM	33.24	1080.21	35906.18
16	26.86.7	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Decorative windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/ cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm ² , modulus of elasticity 900 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately). Frame size 65 x 100 mm	Rmt	34.90	1228.99	42891.75
17	26.87.1	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size and fire retardant. WPC to be laminated with PVC foil of minimum 14 microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately) 35 mm thick	SQM	11.55	3262.01	37676.22
18	Aly	Providing and fixing of 110mm. Dia 6 kg/cmsq. Rain Water Pipe including all material Labour T&P etc.	Rmt	40.80	517.75	21124.20
19	Aly	Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes 6Kg. PSI 110 mm Shoe	Nos	16.00	289.75	4636.00
20	22.3	Providing and laying water proofing treatment to vertical & horizontal surfaces of depressed portions of W.C., Bath and the consisting of: Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 and IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface.	SQM	38.26	577.55	22097.06
21	MR	Supply & Filling of Cinder including All Material Labour T&P etc. directed by Engineer Incharge within a distance of 60 meter .	Cub mt	5.97	4275.00	25521.75

(ए.के. शुक्ला)
रिटेनर (तकनीकी/सिविल)
यूपीसिडको, लखनऊ इकाई-प्रथम

(बाबू राम)
प्र. अधिशाषी अभियन्ता
यूपीसिडको, लखनऊ-प्रथम

22	15.60	Disposal of dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cub mt	52.98	198.08	10494.28
23	10.3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm diasteel pulleys, complete.	Sqmt	5.28	8584.91	45328.32
24	Aly	Providing and fixing of 2mm. Thick Section Powder Coated aluminium work for D.L. Door with extruded built up standard tubular sections and other sections of approved make fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete	Sqmt	5.28	7563.09	39933.12
Total						2592198.92


 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम


Bill of Quantity

Name of Work :- Repairing & Renovation of Communication, Ministerials Association and First Floor Attached Main Office Building Matsya Nideshalay 7 Ayodhya Road Babuganj Lucknow.


Internal & External Sewerage and Sanitary Work


S. No.	PWD Sl.No.	115 Particulars	Unit	Qty.	Rate	Amount
1		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00m spacing. includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.	RMt	74.00	403.45	29855.30
A	18.8.2	20 mm dia. nominal bore	RMt	49.80	470.72	23441.86
B	18.8.3	25 mm dia. nominal bore				
2	17.1.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests.	Nos	1.00	5078.63	5078.63
3	17.3.1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	Nos	6.00	6008.60	36051.60
4	17.4.2	Providing and fixing white vitreous china flat back or wall corner type tipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :	Nos	8.00	7213.68	57709.44
5	17.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	Nos	7.00	1987.85	13914.95
6	MR	Providing & fixing of C.P. Long body Bib Cock including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1159.00	6954.00
7	MR	Providing and fixing C.P. brass angle valve for basin and Cistren points of approved quality. Make Parry Were.	Nos	20.00	845.50	16910.00
8	MR	Providing and fixing C.P. brass Two Way Bib Cock for Fosest points of approved quality. Make Parry Were.	Nos	6.00	1453.50	8721.00
9	MR	Providing & fixing of Health Fosest including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1567.50	9405.00
10	18.21.2	Providing and fixing uplasticised PVC connection pipe with brass unions :	Nos	15.00	89.34	1340.10
11	17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Nos	7.00	1206.70	8446.90
12	MR	Providing & Fixing of C.P. Jali including All materials, labour T&P. Complete of work	Nos	15.00	266.00	3990.00
13	17.28.2 I	Providing & Fixing of Waste pipe including All materials, labour T&P. Complete of work	Nos	10.00	89.72	897.20
14	MR	Providing & Fixing C.p. Soap Dish in Proper Position.	Nos	7.00	1425.00	9975.00
15	MR	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	Nos	7.00	2185.00	15295.00
16	Aly.	Providing and fixing 110 mm P.V.C. Pipe 6kg. Pis including all Material, Labour T&P. Complete of work.	RMt	110.00	517.75	56952.50


(ए०क० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


(बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

	Aly.	Providing and fixing 90 mm P.V. C. Pipe 6kg.Pis including all Material, Labour T.&P. Complete of work.	Mtr	25.00	460.75	11518.75
18	Aly.	Providing and fixing P.V. C. 110 mm Nahani Trap including all Material, Labour T.&P. Complete of work.	Nos	12.00	237.50	2850.00
19	18.17.1	Providing and fixing of Gate Valve (25 mm Dia) including all Material, Labour T.&P. Complete of work.	Nos	6.00	467.09	2802.54
20	18.62.3	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./H.P.H.D.plastic ball. 18.62.3 25 mm nominal bore, 152mm long, weighing not less than 440 gms	Nos	2.00	393.09	786.18
21	Aly.	Making of Plate Form for Storage Tank including All Material Labour T.&P Complete of Work.	Nos	1.00	5584.14	5584.14
22	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Nos	1000.00	8.26	8260.00
23	18.33.1	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10(1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :18.33.1 With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	Nos	7.00	8151.75	57062.25
24	Aly.	Providing & Laying of 200 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	20.00	1338.55	26771.00
25	Aly.	Providing & Laying of 160 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	15.00	988.95	14834.25
26	Aly.	Providing & Laying of 110 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	20.00	804.65	16093.00
27	MR	Supply & Fixing of light duties exhaust fan 12"dia ISI double ball bearing metallic Usha / Crompton/Bajaj make	Each	7.00	4275.00	29925.00
28	MR	Supply & Fixing of exhaust fan luvors 12"dia	Each	7.00	950.00	6650.00
29	9.83	Supply & Fixing of Door Closer including all material labour T&P etc.	Each	7.00	844.15	5909.05
Total						493984.64



 (रक्षे शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity


**Name of Work :- Repairing & Renovation of (डास्प भवन) Office Building Matsya Nideshalay 7
Ayodhya Road Babuganj Lucknow.**


S.No.	P.W.D.SI No.	Particulars	Unit	Quantity	Rate	Amount
1	15.56	Dismantling of Existing old Plaster including disposal of dismantled materials up to 60 mt directed by Engineer Incharge.	SqM	1006.56	41.01	41279.03
2	14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	SqM	1006.56	54.37	54726.67
3	15.2.1	Dismantling of Existing Toilet C.C Flooring including disposal of dismantled materials directed by Engineer Incharge within a distance of 60 meter .	Cub mt	2.92	1826.79	5334.23
4	M.R	Removal of Cinder in Existing Toilet Sunken Portion including disposal of materials directed by Engineer Incharge within a distance of 60 meter .	Job	4.00	3325.00	13300.00
5	Aly.	Dismantling of Brick Work with Door Window including New B/W 1:4 Cement / coarse Sand including of sides repairing 1:4 Cement / coarse Sand.	Sqmt	69.44	1497.16	103962.79
6	4.1.2	Providing & Laying of P.C.C. M- 20 Toilet Flooring 1:1.5:3 (1 Cement : 1.5 Coarse Sand : 3 Stone gritt 20mm Nominal Size) including all Material Labour T&P etc.	Cub mt	2.92	6259.44	18277.56
7	13.5.1	15 mm thick 1:4 cement :C/Sand Plaster including Supply of all material ,Labour T &P etc.	SqM	664.35	309.00	205284.15
8	9.147.A4 1	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame,sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.Providing and fixing factory made uPVC white colour casement/casement including 4 & 5mm. thick Plain Glass as required complete in all Respect as directed by enginee-incharge.	SqM	69.44	8250.17	572891.80
9	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming toIS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm,including pointing in white cement mixed with pigment of matching shade complete. (8.31)	SqM	207.27	951.54	197225.70
10	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades,except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry@ including pointing the joints with white cement and matching pigments etc., complete.(11.40)	SqM	58.10	1080.21	62760.20


 (ए.के. शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

11	26.86.7	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Ceostory windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58- 60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately).Frame size 65 x 100 mm	Rmt	40.10	1228.99	49282.50
12	26.87.1	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size and fire retardant. WPC to be laminated with PVC foil of minimum 14microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note:stainless steel butt hinges and necessary S.S screws shall be paid separately) 30 mm thick	SQM	13.65	3262.01	44526.44
13	13.80	Providing & Applying Two Coat White Cement Based Wall care Putty For Given Smooth surface for Outer side wall & ceiling.	Sqmt	1637.41	117.11	191757.09
14	13.41.1	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats.	Sqmt	1041.56	139.32	145110.14
15	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqmover and including priming coat of exterior primer applied@ 2.20 kg/10 sqm)	SqM	595.85	128.40	76507.14
16	13.62.1	Two Coat Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade.	SqM	123.09	169.79	20899.45
17	Aly.	Providing and fixing of 110mm. Dia 6 kg/cmsq. Rain Water Pipe including all material Labour T&P etc.	Rmt.	33.30	517.75	17241.08
18	Aly.	Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes 6Kg. PSI 110 mm Shoe	Nos	14.00	289.75	4056.50
19	22.3	Providing and laying water proofing treatment to vertical & horizontal surfaces of depressed portions of W.C., Bath and the consisting of: 1st course of applying cement slurry @ 4.4 kg/sqm mixed with water	Sqmt	45.60	577.55	26336.28
20	M.R	Supply & Filling of Cinder including All Material Labour T&P etc.directed by Engineer Incharge within a distance of 60 meter .	Cub mt	6.49	4275.00	27744.75
21	15.60	Disposal of dismantled or waste materials by mechanical means, including loading,transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cub mt	33.22	198.08	6580.22
Total						1885083.72


 (रमेश चंद्रा)
 सिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity

**Name of Work :- Repairing & Renovation of (डास्य भवन) Office Building Matsya Nideshalay 7
Ayodhya Road Babuganj Lucknow.**


Internal & External Sewerage and Sanitary Work


S. No.	PWD Sl.No.	115 Particulars	Unit	Qty.	Rate	Amount
1		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00m spacing. includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
A	18.8.2	20 mm dia. nominal bore	RMt	96.00	403.45	38731.20
B	18.8.3	25 mm dia. nominal bore	RMt	78.00	470.72	36716.16
2	17.1.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests.	Nos	2.00	5078.63	10157.26
3	17.3.1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	Nos	6.00	6008.60	36051.60
4	17.4.2	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :	Nos	6.00	7213.68	43282.08
5	17.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	Nos	6.00	1987.85	11927.10
6	MR	Providing & fixing of C.P. Long body Bib Cock including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1159.00	6954.00
7	MR	Providing and fixing C.P. brass angle valve for basin and Cistren points of approved quality Make Parry Were.	Nos	15.00	845.50	12682.50
8	MR	Providing and fixing C.P. brass Two Way Bib Cock for Foset points of approved quality Make Parry Were.	Nos	6.00	1453.50	8721.00
9	MR	Providing & fixing of Health Foset including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1567.50	9405.00
10	18.21.2	Providing and fixing uplasticised PVC connection pipe with brass unions :	Nos	15.00	89.34	1340.10
11	17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Nos	6.00	1206.70	7240.20
12	MR	Providing & Fixing of C.P. Jali including All materials, labour T& P. Complete of work	Nos	12.00	266.00	3192.00
13	17.28.2.1	Providing & Fixing of Waste pipe including All materials, labour T& P. Complete of work	Nos	10.00	89.72	897.20
14	MR	Providing & Fixing C.p. Soap Dish in Proper Position.	Nos	6.00	1425.00	8550.00
15	MR	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	Nos	6.00	2185.00	13110.00
16	Aly.	Providing and fixing 110 mm P.V. C. Pipe 6kg. Pis including all Material, Labour T&P. Complete of work.	RMt	76.00	517.75	39349.00

(एनके शुक्ला)
रिटेनर (तकनीकी/सिविल)
यूपीसिडको, लखनऊ इकाई-प्रथम

(बाबू राम)
प्र० अधीशापी अभियन्ता
यूपीसिडको, लखनऊ-प्रथम

17	Aly.	Providing and fixing 90 mm P.V. C. Pipe 6kg.Pis including all Material, Labour T.&P. Complete of work.	Mtr	30.00	460.75	13822.50
18	Aly.	Providing and fixing P.V. C. 110 mm Nahani Trap including all Material, Labour T.&P. Complete of work.	Nos	15.00	237.50	3562.50
19	18.17.1	Providing and fixing of Gate Valve (25 mm Dia) including all Material, Labour T.&P. Complete of work.	Nos	4.00	467.09	1868.36
20	18.62.3	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D.plastic ball.18.62.3 25 mm nominal bore, 152mm long, weighing not less than 440 gms	Nos	2.00	393.09	786.18
21	Aly.	Making of Plate Form for Storage Tank including All Material Labour T&P Complete of Work.	Nos	2.00	5584.14	11168.28
22	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Liter	2000.00	8.26	16520.00
23	18.33.1	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size), i/c necessary excavation, foundation concrete 1:5:10(1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :18.33.1 With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	Nos	8.00	8151.75	65214.00
24	Aly.	Providing & Laying of 200 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T &P. complete of work.	Rmt.	25.00	1338.55	33463.75
25	Aly.	Providing & Laying of 160 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T &P. complete of work.	Rmt.	15.00	988.95	14834.25
26	Aly.	Providing & Laying of 110 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T &P. complete of work.	Rmt.	30.00	804.65	24139.50
27	MR	Supply & Fixing of light duties exhaust fan 12"dia ISI double ball bearing metallic Usha / Crompton/Bajaj make	Each	6.00	4275.00	25650.00
28	MR	Supply & Fixing of exhaust fan luvvers 12"dia	Each	6.00	950.00	5700.00
29	9.83	Supply & Fixing of Door Closer including all material labour T&P etc.	Each	6.00	844.15	5064.90
Total (A)						510100.62



 (रमेश कुमार)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (रामेश कुमार)
 प्र० अधिशाषी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity


Name of Work :- Repairing & Renovation of Left side (नियोजन शाखा) Office Building Matsya Nideshalay 7 Ayodhya Road Babujanj Lucknow.


S.No.	P.W.D.SI No.	115 Particulars	Unit	Quantity	Rate	Amount
1	15.56	Dismantling of Existing old Plaster including disposal of dismantled materials up to 60 mt directed by Engineer Incharge.	SqM	1948.56	41.01	79910.45
2	14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	SqM	1948.56	54.37	105943.21
3	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	Cub mt	4.08	2665.05	10868.07
4	Aly.	Dismantling of Brick Work with Door Window including New B/W 1:4 Cement / coarse Sand including of sides repairing 1:4 Cement / coarse Sand.	Sqmt	87.36	1497.16	130791.90
5	5.3	R.C.C. works with cement approved coarse sand and 2 cm. (3/4") gauge approved stone ballast in the proportion 1:1.5:3 (1cement:6aggregate) in lintels of doors and windows excluding supply of reinforcement and its bending& binding. With 24BWG binding wire including supply of all labours, tools and plants etc required for proper completion of the works. Strength of the concrete shall not be less than M-20	Cub mt	3.61	8634.37	31166.62
6	5.22.6	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.	Kg	431.52	80.94	34927.23
7	5.9.5	Centering and shuttering including strutting, propping etc. and removal of form for :	Sqm	36.88	552.63	20378.78
8	13.5.1	15 mm thick 1:4 cement :C/Sand Plaster including Supply of all material ,Labour T &P etc.	SqM	1948.56	309.00	602105.04
9	11.27	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3coarse sand) and jointed with grey cement slurry mixed with pigment tomatch the shade of the slabs, including rubbing and polishing complete.	SqM	77.55	1767.09	137037.83
10	9.147.A.4.1	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame,sash and mullion (where ever required) extruded profiles duly reinforced with 1 60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM gasket, stainless steel (SS 304 grade) friction hinges, zinc alloy (whitepowder coated) casement handles, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Providing and fixing factory made uPVC white colour casement/casement including 4 & 5mm. thick Plain Glass as required complete in all Respect as directed by enginee-incharge.	SqM	86.40	8250.17	712814.69
11	13.80	Providing & Applying Two Coat White Cement Based Wall care Putty For Given Smooth surface for Outer side wall & ceiling.	Sqmt	1948.56	117.11	228195.86


 (ए० ई० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

12	13.41.1	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats.	Sqmt	1312.45	139.32	182850.53
13	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: 13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	SqM	636.11	128.40	81676.52
14	13.62.1	Two Coat Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade.	SqM	100.80	169.79	17114.83
15	Aly.	Providing and fixing of 110mm. Dia 6 kg/cmsq. Rain Water Pipe including all material Labour T&P etc.	Rmt.	102.60	517.75	53121.15
16	Aly.	Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes 6Kg. PSI 110 mm Shoe	Nos	34.00	289.75	9851.50
17	15.60	Disposal of dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cub mt	62.54	198.08	12387.53
Total						2451141.74



 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशाषी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity


Name of Work :- Repairing & Renovation of (मत्स्य चेतना केंद्र) Office Building Matsya Nideshalay 7 Ayodhya Road Babuganj Lucknow.


S.No.	P.W.D.SI No.	115				
		Particulars	Unit	Quantity	Rate	Amount
1	15.56	Dismantling of Existing old Plaster including disposal of dismantled materials up to 60 mt directed by Engineer Incharge.	SqM	420.13	41.01	17229.53
2	14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	SqM	420.13	54.37	22842.47
3	15.2.1	Dismantling of Existing Toilet C.C Flooring including disposal of dismantled materials directed by Engineer Incharge within a distance of 60 meter .	Cub mt	2.48	1826.79	4530.44
4	15.23.1	Dismantling tile work in Toilet in cement mortar including stacking material within 50 metres lead. 15.23.1 For thickness of tiles 10 mm to 25 mm	Sqmt	55.16	55.08	3038.21
5	M.R	Removal of Cinder in Existing Toilet Sunken Portion including disposal of materials directed by Engineer Incharge within a distance of 60 meter .	Job	2.00	3325.00	6650.00
6	Aly.	Dismantling of Brick Work with Door Window including New B/W 1:4 Cement / coarse Sand including of sides repairing 1:4 Cement / coarse Sand.	Sqmt	119.30	1497.16	178611.19
7	6.4.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	Cub mt	19.48	6833.61	133118.72
8	13.8.2	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix :For Apron & Drain	Sqmt	491.10	358.64	176128.10
9	4.1.2	Providing & Laying of P.C.C. M- 20 Toilet Flooring 1:1.5:3 (1 Cement : 1.5 Coarse Sand : 3 Stone gritt 20mm Nominal Size) including all Material Labour T&P etc.	Cub mt	6.88	6259.44	43064.95
10	13.5.1	15 mm thick 1:4 cement :C/Sand Plaster including Supply of all material ,Labour T &P etc.	SqM	420.13	309.00	129820.17
11	9.147.A4.1	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame,sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.Providing and fixing factory made uPVC white colour casement/casement including 4 & 5mm. thick Plain Glass as required complete in all Respect as directed by enginee-incharge.	SqM	135.96	8250.17	1121693.11
12	12.52	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm,both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mmthick (minimum) sheet, spaced at 1200 mm center to center .bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				0.00


 (ए.के. मुकुला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशाषी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम


12.52.3	12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part 1 and laminated with white 0.16 mm thick fire retardant PVC film on the face side and 12 micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	Sqm.	195.16	1662.37	324428.13	
13	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	SqM	638.77	1165.79	744671.68
14	11.27	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	SqM	123.75	1767.09	218677.39
15	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. (8.31)	SqM	216.93	951.54	206417.57
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ including pointing the joints with white cement and matching pigments etc., complete. (11.40)	SqM	52.43	1080.21	56635.41
17	26.86.7	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Coosetory windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58- 60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately). Frame size 65 x 100 mm	Rmt	40.10	1228.99	49282.50
18	26.87.1	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size and fire retardant. WPC to be laminated with PVC foil of minimum 14 microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In-Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately) 30 mm thick	SQM	13.65	3262.01	44526.44
19	13.80	Providing & Applying Two Coat White Cement Based Wall care Putty For Given Smooth surface for Outer side wall & ceiling.	Sqmt	3198.31	117.11	374554.08
20	13.41.1	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats.	Sqmt	2046.22	139.32	285079.37
21	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: 13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	SqM	1152.09	128.40	147928.36
22	13.62.1	Two Coat Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade.	SqM	150.81	169.79	25606.03
23	Aly.	Providing and fixing of 110mm. Dia 6 kg/cmsq. Rain Water Pipe including all material Labour T&P etc.	Rmt.	52.50	517.75	27181.88


 (संकु शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

24	Aly.	Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes 6Kg. PSI 110 mm Shoe	Nos	22.00	289.75	6374.50
25	22.3	Providing and laying water proofing treatment to vertical & horizontal surfaces of depressed portions of W.C., Bath and the consisting of: 1st course of applying cement slurry @ 4.4 kg/sqm mixed with water	Sqmt	39.71	577.55	22934.51
26	M.R	Supply & Filling of Cinder including All Material Labour T&P etc.directed by Engineer Incharge within a distance of 60 meter .	Cub mt	8.24	4275.00	35226.00
27	15.60	Disposal of dismantled or waste materials by mechanical means, including loading,transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cub mt	42.01	198.08	8321.34
Total						4414572.08


 (ए.के. सुवर्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम


Bill of Quantity

Name of Work :- Repairing & Renovation of (मत्स्य चेतना केंद्र) Office Building Matsya Nideshalay 7 Ayodhya Road Babujanj Lucknow.


Internal & External Sewerage and Sanitary Work


S. No.	PWD Sl.No.	115 Particulars	Unit	Qty.	Rate	Amount
1		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00m spacing, includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
A	18.8.2	20 mm dia. nominal bore	RMt	86.00	403.45	34696.70
B	18.8.3	25 mm dia. nominal bore	RMt	70.00	470.72	32950.40
2	17.1.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests.	Nos	2.00	5078.63	10157.26
3	17.3.1	Providing and fixing white vitreous china pedestal type water closet(European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	Nos	5.00	6008.60	30043.00
4	17.4.2	Providing and fixing white vitreous china flat back or wall corner type tipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :	Nos	7.00	7213.68	50495.76
5	17.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	Nos	6.00	1987.85	11927.10
6	MR	Providing & fixing of C.P. Long body Bib Cock including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1159.00	6954.00
7	MR	Providing and fixing C.P. brass angle valve for basin and Cistren points of approved quality Make Parry Were.	Nos	15.00	845.50	12682.50
8	MR	Providing and fixing C.P. brass Two Way Bib Cock for Foset points of approved quality Make Parry Were.	Nos	6.00	1453.50	8721.00
9	MR	Providing & fixing of Health Foset including all Material labour T&P etc. Make Parry Were.	Nos	6.00	1567.50	9405.00
10	18.21.2	Providing and fixing uplasticised PVC connection pipe with brass unions :	Nos	15.00	89.34	1340.10
11	17.31	Providing and fixing 600x450 mm beveled edge mirror of superiorglass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Nos	6.00	1206.70	7240.20
12	MR	Providing & Fixing of C.P. Jali including All materials ,labour T&P. Complete of work	Nos	12.00	266.00	3192.00
13	17.28.2.1	Providing & Fixing of Waste pipe including All materials ,labour T&P. Complete of work	Nos	10.00	89.72	897.20
14	MR	Providing & Fixing C.p. Soap Dish in Proper Position.	Nos	6.00	1425.00	8550.00
15	MR	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	Nos	8.00	2185.00	17480.00
16	Aly.	Providing and fixing 110 mm P.V. C. Pipe 6kg. Pis including all Material, Labour T&P. Complete of work.	RMt	66.00	517.75	34171.50


 (रंके शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

18	Aly.	Providing and fixing 90 mm P.V.C. Pipe 6kg.Pis including all Material, Labour T.&P. Complete of work.	Mtr	30.00	460.75	13822.50
19	Aly.	Providing and fixing P.V.C. 110 mm Nahani Trap including all Material, Labour T.&P. Complete of work.	Nos	12.00	237.50	2850.00
20	18.17.1	Providing and fixing of Gate Valve (25 mm Dia) including all Material, Labour T.&P. Complete of work.	Nos	6.00	467.09	2802.54
20	18.62.3	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./H.P.H.D.plastic ball.18.62.3 25 mm nominal bore, 152mm long, weighing not less than 440 gms	Nos	2.00	393.09	786.18
21	Aly.	Making of Plate Form for Storage Tank including All Material Labour T&P Complete of Work.	Nos	2.00	5584.14	11168.28
22	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Nos	1000.00	8.26	8260.00
23	18.33.1	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size), i/c necessary excavation, foundation concrete 1:5:10(1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design : 18.33.1 With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	Nos	12.00	8151.75	97821.00
24	Aly.	Providing & Laying of 200 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	30.00	1338.55	40156.50
25	Aly.	Providing & Laying of 160 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	20.00	988.95	19779.00
26	Aly.	Providing & Laying of 110 mm. Dia P.V.C. pipe 6kgcm Sewer Line including excavation of Tranch Providing 1:4:8 cement Concrete P.C.C. Base including all Labour, T.&P. complete of work.	Rmt.	19.10	804.65	15368.82
27	MR	Supply & Fixing of light duties exhaust fan 12"dia ISI double ball bearing metallic Usha / Crompton/Bajaj make	Each	5	4275.00	21375.00
28	MR	Supply & Fixing of exhaust fan luvors 12"dia	Each	5	950.00	4750.00
29	9.83	Supply & Fixing of Door Closer including all material labour T&P etc.	Each	5	844.15	4220.75
		Total (A)				524064.29



 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 सूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 सूपीसिडको, लखनऊ-प्रथम

Bill of Quantity

Bill of Work :-Providing & Laying of 80mm thick Interlocking Tile work of Infront of Main Building Lawn of Matsya Nideshalay 7 Campuss Ayodhya Road Babujanj Lucknow.

S. No.	P.W.D S I No.	Particulars	Unit	Quantity	Rate	Amount
115						
1	2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood,trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqmt	251.86	13.20	3324.55
2	4.1.8	Providing and laying in P.C.C 1:4:8 (cement C/sand graded Stone ballast 40 mm Nominal Size) and curing complete, including all Material Labour T&P etc.	Cub mt	39.00	5112.10	199371.90
3	16.19	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	Sqmt	468.20	819.12	383511.98
4	6.4.2	Class- 150 brick work in 1:6 cement and C.sand mortar in Super Structure including supply of all materials, labour and T & P etc. required for proper completion of work.	Mtr.	13.07	6833.61	89315.28
5	13.9.2	20 mm cement plaster 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement on the surface.	Sqmt	84.00	440.67	37016.28
Total						712539.99



 (इ. इं. सुकला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity


Rain Water Harvesting Size- 4.00X3.00X 2.30 Mt.


S.No.	Particulars	No.	L	B	D/H	Qty	Unit	Eff.Rate	Amount
115									
2.6.1	Earth work in Excavation in trenches for foundations pipes cable etc in ordinary soil (Loam, clay or sand) including lift up to 1.50M and lead upto 50M and dressing of sides and ramming of bottom and disposal of surplus excavated earth as directed by the Engineer i.c. within a lead of 30 m. up to 1.50mtr.	1	4.50	3.56	2.25	36.05	Cum.	133.21	4802.22
2	4.1.8 Providg and laying cement concrete 1:4:8 (1cement:4fine sand: 8 Brick Ballast 40mm. nominal size) including supply of all materials, labour and T&P etc. required for proper completion of the work and curing complete also including cost of form work in foundation and floors.	1	4.70	3.80	0.15	2.68	Cum.	5112.10	13700.43
3	6.4.1 Class- 150 brick work in 1:4 cement and C.sand mortar in Super Structure including supply of all materials, labour and T & P etc. required for proper completion of work.	2	4.70	0.35	1.20	3.89			
		2	3.00	0.35	1.20	2.48			
		2	4.46	0.23	1.15	2.36			
	Partition	2	3.00	0.23	1.15	1.59			
		1	3.00	0.23	1.50	1.04			
						11.36	Cum.	7012.52	79662.23
4	5.3 R.C.C. works with cement approved coarse sand and 20mm gauge approved stone grit in the proportion 1:2:4 (1cement:6aggregate) in lintels of doors and windows excluding supply of reinforcement and its bending & binding. but including its fixing and binding the same with 24 BWGGI binding wire and including necessary centering and shuttering etc. and also including supply of all materials, labours, tools and plants etc required for proper completion of the works. Binding wire cost being included in the item	1	4.46	3.46	0.15	2.31	Cum.	8634.37	19945.39
5	5.2.2.6 Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.								
	Steel 10 mm Dai (2X 41 Nos)	82	3.45	0.62		175.40			
	Steel 10 mm Dai (2X 24 Nos)	48	4.45	0.62		132.43			
						307.83	Kg.	80.94	24915.76
6	13.9.2 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement on the surface.								
		2	4.00		2.35	18.80			
		2	3.00		2.35	14.10			
		2	3.00		1.50	9.00			
		2	4.46		0.25	2.23			
		3	3.00		0.25	2.25			
		2	4.46		0.60	5.35			
		2	3.46		0.60	4.15			
		1	4.90		3.50	17.15			
						73.03	Sqm	440.67	32183.89
7	4.10 40 mm. Thick C.C. Flooring 1:2:4 Cement:C.sand:20 mm. Stone grit with Floting coat of neat cement including supply of all Materials Labour and T & P etc. Complete of Work.								
		1	4.00		3.65	14.60			
		1	2.00		3.00	6.00			
						20.60	Sqm	308.32	6351.39
8	23.5 Supply & Filling , Spreading & Leveling stone boulders of size range 5cm to 20 cm inrecharge pit in the required thickness for all leads & left all complete as per direction of engineer in charge.	1	2.00	3.00	0.90	5.80	Cum.	1133.04	6571.63


 (ए०के० कुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको लखनऊ इन्फ्रास्ट्रक्चर


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

		Supply & Filling, Spreading & Leveling stone boulders of size range 5mm to 10 mm in recharge pit in the required thickness for all leads & left all complete as per direction of engineer in charge.	1	2.00	3.00	0.60	4.50	Cum.	1154.39	5194.76
		Drilling of 250mm. Dia bore hole manually.	1	100.00			100.00	mtr.	617.50	61750.00
		supply and fixing of nylon jali around the sloted pipes complet as required	1	1.00			1.00	Job	2850.00	2850.00
23.7		Supply & Filling, Spreading & Leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit in the required thickness for all leads & left all complete as per direction of engineer in charge..	1	4.00			4.00	Cum.	1154.39	4617.56
13	MIR	transport of Boring tools other required equipments and instalation at site							7600.00	7600.00
14	Analysis	Supply & Lowering of 160mm dia sloted Plane/rigid PVC pipe (6kg./sqcm pressure rating) and accessories	1	90.00			90.00	mtr.	745.75	67117.50
15	Analysis	Providing & Laying of Rainwater pipe 160 mm Dia pipe 6 kg/ cm sq. in Mainhole Chamber including all Material Labour T&P etc.								
		Front	1	52.00			52.00			
		Right	1	45.00			45.00			
		Left	1	45.00			45.00			
		Back	1	58.00			58.00			
		Total					200.00	mtr.	781.22	156244.00
16	DSR 19.2.2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design:								
		Front	1	55.00			55.00			
		Right	1	50.00			50.00			
		Left	1	50.00			50.00			
		Back	1	58.00			58.00			
		Total					213.00	mtr.	885.43	188596.59
17	18.33.1	Constructing brick masonry Mainhole (600x600) upto hight 1.20 mt in cement mortar 1:4 (1 cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat\ of neat cement, foundation concrete 1:3:6 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size), a finished with a floating coat of neat cement, all complete as per standard design.	1	40.00			40.00	Nos	8151.75	326070.00
		Total								1008173.35



 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Abstract of Cost

Work :- Providing & Laying of 110 mm thick Cement Concrete Road of Existing C.C. Road of Matsya Nideshalay 7 Campuss Ayodhya Road Babujanj Lucknow.

115		Unit	Quantity	Rate	Amount	
Particulars						
6.1.2	Class- 150 brick work in 1:6 cement and C.sand mortar in Foundation including supply of all materials, labour and T & P etc. required for proper completion of work.	Cum mt	36.90	5352.43	197504.67	
5.33.1.1	Providing and laying M- 25 Grade C. C. in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland , admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge;	Cum mt	38.15	7132.89	272119.75	
3	16.45	Providig and fixing pre - moulded joint filler in expansion joint of C.C. pavements after making the joints dust free with high pressure air jet Cleaners all complete as per direction of the Engineer in Charge.	Rmt	104.60	3.98	416.31
4	16.46	Providig and filling in position rubberesd bitumen hot sealing compound for sealing of expansion joints in C.C. pavements all complete as per direction of the Engineer in Charge.	Rmt	104.60	6.49	678.85
5	MR	Tremix on C.C. Road surface by Power trowel floater machine.	Sqmt	346.75	237.50	82353.13
Total						553072.71



 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशाधी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Bill of Quantity

**Work :- Construction of Damage Boundary Wall and Plaster & Painting of Existing
Balance Boundary Wall at Matsya Nideshalay 7 Ayodhya Road Babuganj Lucknow.
(Back Side)**

P.W.D S.No.	115	Particulars	Unit	Quantity	Rate	Amount
2.31		Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqmt	60.00	13.20	792.00
15.7.4		Dismantling Brick Work cement mortar including stacking of dismantled materials as directed by Engineer Incharge within a distance of 60 meter (200 feet)	Cub mt	7.25	1546.09	11209.15
Any.		Construction of Boundrywall with R.C.C. Column 1:1.5:3 Cement:c.sand:stone gritt & Brickwork Both side 15mm. Thick Plaster with Height 2.10 mtr.	Mtr.	30.00	18595.54	557866.20
13.5.1		15 mm thick 1:4 cement :C/Sand Plaster including Supply of all material ,Labour T &P etc.	Sqmt	170.80	309.00	52777.20
13.80		Providing & Applying Two Coat White Cement Based Wall care Putty For Given Smooth surface for Outer/ inner side wall & ceiling.	Sqmt	170.80	117.11	20002.39
13.47.1		Finishing walls with Premium Acrylic Smooth exterior paint withSilicone additives of required shade:13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqmover and including priming coat of exterior primer applied@ 2.20 ke/10 sqm)	Sqmt	170.80	128.40	21930.72
15.60		Disposal of Boundary Wall dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cub mt	14.49	198.08	2870.18
Total						667447.84



 (ए०के० शुक्ला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम



 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Abstract of Cost

Work :- Waterproofing Work of Office Building Terrace At Matsya Nideshalay 7
Campuss Ayodhya Road Babujanj Lucknow.

115		Unit	Quantity	Rate	Amount
P.W.D S/No.	Particulars				
	Providing & Laying of 2 mm thick Bituminous membranes Waterproofing Work including Scraping & Cleaning of surface and one coat of bituminous primer then laying of membrane sheet and seal lapping Joint of complete of Work.	Sqmt	1024.07	631.75	646956.22
2	15.1 Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	Cum mt	18.61	639.02	11892.16
3	22.3 Providing and laying water proofing treatment to Roof surfaces of Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions and IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion	Sqmt	101.40	577.55	58563.57
Total					717411.95



(रंके शुक्ला)
रिटेनर (तकनीकी/शिवािल)
यूपीसिडको, लखनऊ इकाई-प्रथम



(बाबू राम)
प्र० अधिशापी अभियन्ता
यूपीसिडको, लखनऊ-प्रथम

ABSTRACT OF COST (Boring)

Name of Work :- Boaring work of Matsya Nideshalay Campus Ayodhya Road Babuganj Lucknow.


Sl. No.	DSR	DESCRIPTION OF ITEM	Qty.	UNIT	RATES	AMOUNT
1	23.2.1.	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machinerles required for the Job, all complete as per direction of Engineer-in-charge, upto 150 metre depth below ground level.300mm. dia	150	mtr.	619.65	92947.50
2	23.3.2	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 150mm. dia	90	Mtr.	595.30	53577.00
3	23.4.3	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge.200mm. dia	50	mtr.	942.34	47117.00
4	23.8	Gravel Packing in Tubewell Construction accordanse With IS 4097	5	Cum.	1519.30	7596.50
5	23.12	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.	72	Hours	814.28	58628.16
6	23.14.3	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tubewell as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. Supply & Laying	1	No.	1721.29	1721.29
7	23.15.3	Providing and fixing Bail plug/ Bottom plug of required dia to the bottom of pipe assembly of tubewell as per IS:2800 (part I).Supply & Laying of 200mm. Dia M.S. bail plug	1	No.	268.37	268.37
8	MR	K.S.B. make submersible pump 5H.P.	1	Set	61750.00	61750.00
9	MR	Control Pannel with 100 Amp. Main switch	1	Set	14250.00	14250.00
10	MR	Flat Copper Cable 1x3x6mm. ISI Mark	65.00	mtr.	308.75	20068.75
11	MR	Supply of 80 mm. dia M.S. column pipe of c class both side flanged type complete	40	Mtr.	4085.00	163400.00
12	MR	Supply of Steel wair robe of 1/2" size	50	mtr.	142.50	7125.00
13	18.7	Providing & Fixing of C.P.V.C. Pipe water Supply Connection at Office Buildings including all material labour complete of work.	45	mtr.	527.54	23739.30
	18.7.5	40mm Dia	40	mtr.	389.30	15572.00
	18.7.4	32 mm Dia				
Total						567760.87



 (सुबला)
 रिटेनर (तकनीकी/सिविल)
 यूपीसिडको, लखनऊ इकाई-प्रथम


 (बाबू राम)
 प्र० अधिशापी अभियन्ता
 यूपीसिडको, लखनऊ-प्रथम

Abstract of Cost**Name of Work :- Fixing of Glow Sign Board At Matsya Nideshalay 7 Campuss Ayodhya Road Babuganj Lucknow.**

Sl No.	P.W.D SI No. MR	115	Unit	Quantity	Rate	Amount
		Particulars				
1	MR	Supplying Glow Sign Board of made off Aluminum sheet (22 gauge) and framed box made off M.S. angle 50mmX50mmX4mm, and flat 20mmX4mm and fitting & fixing the same in the top wall of Kanainatsal Inspection Bungalow and fitting and fixing another M.S. angle 50mmX38mmX4mm for supporting arrangement in the in the roof by concreting (1:2:4) with necessary screws, lugs Bolt and L- type M.S. clamps etc. as required including fixing flex in the front side of the framed shutters and cutting letters on Back Lit Flex Board and laminated over flex including arrangement of light with LED Light inside the box of Glow Sign Board including all necessary Electrical fittings, fixing complete connection etc.	Sqmt	21.74	5928.00	128874.72
2	MR	Repairing of Old Existing M.S. Gate including Welding Machine & Welding Rod complete of Work.	job	3.00	9500.00	28500.00
Total						157374.72


(रिंको शुक्ला)
रिटेनर (तकनीकी/सिविल)
यूपीसिडको, लखनऊ इकाई-प्रथम


(बाबू राम)
प्र० अधिशापी अभियन्ता
यूपीसिडको, लखनऊ-प्रथम