

# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।

**GSTIN-09AAACU1932C9ZH**

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

## ई-निविदा आमंत्रण सूचना

जिलाधिकारी गौतमबुद्ध नगर के सरकारी आवासीय भवन की मरम्मत एवं रेनोवेशन के कार्य (संलग्न-विवरण/बी०ओ०क्यू०) (निविदा धनराशि रू० 27,18,738.64) को पूर्ण कराये जाने हेतु ई-टेंडर प्रक्रिया के अन्तर्गत निविदा आमंत्रित की जाती है। जिसका विवरण Website <https://etender.up.nic.in> पर उपलब्ध है। इस कार्य से सम्बन्धित किसी प्रकार की परिवर्तन आदि की सूचना उपरोक्त वेब साइट पर उपलब्ध करायी जायेगी।

इस कार्य से सम्बन्धित **नियम व शर्तें** निम्नानुसार हैं:-

1. टेंडर शुल्क रू० 1400.00 + 18% GST = रू० 1652.00
2. अर्नेष्ट मनी रू० 54,500.00
3. निविदादाता को यू०पी०सिडको से रजिस्टर्ड "D" श्रेणी गौतमबुद्ध नगर इकाई एवं अधिक श्रेणी का प्रमाण पत्र निर्गत हो, निविदा के साथ अपलोड करना आवश्यक होगा।
4. ई-पोर्टल पर अपलोड हुई निविदाओं का नियम व शर्तों के अनुसार प्रपत्रों का मिलान किया जायेगा।
5. नियम व शर्तों को पूर्ण करने वाले निविदादाताओं/फर्मों की ही फाइनेशियल बिड खोली जायेगी।
6. कार्य पूर्ण करने की अवधि कार्यादेश जारी होने की दिनांक से 04 माह होगी। कार्य पूर्ण न करने की दशा में धरोहर राशि (Earnest money) को जब्त कर लिया जायेगा।
7. निविदादाता को अंकित टेंडर फीस/धरोहर धनराशि निगम के खुले **Bank Account No 0279104000144339 IFS Code IBKL0000279, IDBI Bank, Ambedkar Road, Ghaziabad** में RTGS कराते हुये खातों में अन्तरित कराने की रसीद की छायाप्रति निविदा के साथ अपलोड करनी होगी।
8. सशर्त निविदायें मान्य नहीं होंगी।
9. निगम में पंजीकृत निविदादाता ही निविदा में प्रतिभाग करने हेतु पात्र होंगे।
10. उक्त निविदा लागत में जी०एस०टी० सम्मिलित नहीं है।
11. बिना कोई कारण बताये निविदा निरस्त करने एवं किसी भी प्रकार का संशोधन आदि करने का पूर्ण अधिकार निगम के सक्षम अधिकारी को होगा।
12. निविदादाता द्वारा निविदा आमंत्रण सूचना पत्र, तकनीकी बिड से सम्बन्धित प्रपत्र (नियम व शर्तें), निगम में पंजीयन प्रमाण-पत्र, जी०एस०टी० नं०, पैन कार्ड, आधार कार्ड, चरित्र प्रमाण पत्र, हैसियत प्रमाण पत्र, कार्य करने का अनुभव एवं श्रम विभाग पंजीकरण आदि वांछित प्रपत्रों की स्वप्रमाणित प्रति निविदा के साथ अपलोड करनी होगी।
13. निविदादाता को Litigation History (यदि कोई हो) संलग्न प्रारूप पर भरकर निविदा के साथ अपलोड करना आवश्यक होगा।



## कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि0, गौतमबुद्ध नगर।  
एस0जे0-59, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

14. निविदादाता को वांछित समस्त प्रपत्रों की हार्ड कापी मांगे जाने पर कार्यालय में उपलब्ध कराना अनिवार्य होगा।
15. निविदा खोलने की प्रक्रिया तीन चरणों में पूर्ण की जायेगी।
  1. प्रथम- जमा निविदा शुल्क एवं धरोहर राशि की पुष्टि होने पर ही तकनीकी बिड खोली जायेगी।
  2. द्वितीय- निविदादाताओं की तकनीकी बिड में अपलोड प्रपत्रों की निविदानुसार जाँच की जायेगी तथा सफल निविदादाताओं की सूची बनाते हुये प्राईस बिड खोलने हेतु संस्तुति की जायेगी।
  3. तृतीय- तकनीकी बिड में सफल निविदादाताओं की प्राईस बिड तय दिनांक एवं समय को खोली जायेगी तथा न्यूनतम दर निविदादाता को एल0ओ0आई उपर्युक्त वर्णित मूल प्रपत्र एवं उनकी प्रति/हस्ताक्षरित छायाप्रति इस कार्यालय में प्राप्त होने के पश्चात् जारी किया जायेगा।
16. यदि सफल निविदादाता द्वारा निविदा मूल्य से कम दरें उद्धरण की जाती है तो शासनादेश सं0 622/23/12-2012-2 Audit/08 T.C.-2 Dt. 08.06.2012 of UPPWD- Anubhag 12 द्वारा जारी निर्देशों के क्रम में निम्नानुसार अतिरिक्त जमानत धनराशि FDR/DD किसी भी राष्ट्रीयकृत बैंक, अथवा शैड्यूल बैंक IDBI/HDFC/ICICI के रूप में जमा करानी होगी:-
  - (i) 0.50% per 1.00% below up to 10% of BOQ Cost.
  - (ii) 1.00% per 1.00% below, more than 10% of BOQ Cost.
17. सशर्त निविदायें मान्य नहीं होगी।

अधिशासी अभियन्ता  
यूपीसिडको  
गौतमबुद्ध नगर

# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

## तकनीकी बिड (नियम व शर्तों)

1. निविदा प्रपत्र बेबसाईट <https://etender.up.nic.in> पर देखे जा सकते हैं। निविदा डाऊनलोड एवं अपलोड भी इसी बेब साईट से किया जायेगा। इच्छुक ठेकेदार/फर्म नियमित रूप से उक्त बेबसाईट का संज्ञान लेते रहे, क्योंकि प्रश्नगत निविदाओं के सम्बन्ध में परिवर्तन अथवा अन्य सूचना बेबसाईट पर उपलब्ध कराई जायेगी।
2. निविदा की स्वीकृति की दशा में अनुबन्ध गठन हेतु रु० 100.00 के नान ज्यूडिशियल स्टैम्प पेपर पर निगम द्वारा समय-समय पर जारी नियम व शर्तों के अनुसार अनुबन्ध करना होगा व भुगतान हेतु अनुमन्य बिलों की धनराशि का 5% जमानत धनराशि के रूप में कटौती की जायेगी जो कि कार्य संतोषजनक पूर्ण होने के 12 माह के पश्चात अवमुक्त की जायेगी।
3. कार्य की मात्रा अनुबन्ध की मात्रा से आवश्यकतानुसार कम या अधिक की जा सकती है।
4. परियोजना के 01 वर्ष तक देखरेख/रख रखाव का उत्तरदायित्व सम्बन्धित फर्म/ठेकेदार का होगा।
5. उपरोक्त बी०ओ०क्यू० में 05 प्रतिशत सुपरविजन चार्ज प्रत्येक रनिंग बिलों से काटा जायेगा।
6. ठेकेदार/फर्म को जी०एस०टी० में पंजीकृत होना अनिवार्य होगा, जिसकी अध्यावदिक प्रमाणित प्रति निविदा के साथ संलग्न की जानी आवश्यक है।
7. निर्धारित समयावधि में यदि निविदादाता कार्य पूर्ण नहीं करता है, तो निगम निविदा में भागीदार किसी अन्य फर्म जिसने निविदा शर्तों का पालन किया हो, से निर्माण कराये जाने हेतु स्वतन्त्र होगा, उक्त पर यदि अतिरिक्त व्यय का भुगतान किया जाना होगा तो उसे निविदादाता की जमानत धनराशि से किया जायेगा।
8. निविदादाता को कार्य संतोषजनक पाये जाने के उपरान्त ही भुगतान किया जायेगा। निविदादाता को ई-प्रकाशन व अनुबन्ध में दी गयी सभी शर्तों का पालन करना होगा। सशर्त निविदा पर कोई विचार नहीं किया जायेगा।
9. निविदादाता के निविदा स्वीकृत होने के उपरान्त यदि यह संज्ञान में आता है कि सम्बन्धित निविदादाता सक्रिय भू-माफिया गतिविधियों, असामाजिक कार्यों एवं संगठित आपराधिक गतिविधियों में लिप्त है तो उसे प्रदान किया गया कार्य आदेश निरस्त कर दिया जायेगा। इससे किसी भी क्षति की जिम्मेदारी निविदादाता की होगी।
10. निविदादाता के द्वारा निविदा के अन्तर्गत अनिवार्य प्रपत्र ऑनलाइन अपलोड किये जायेंगे। अपलोड निविदा का मिलान होने पर ही अग्रिम कार्यवाही हेतु निविदा पर विचार किया जायेगा।
11. ठेकेदार/फर्म द्वारा समस्त निर्माण कार्य उ०प्र० लोक निर्माण विभाग द्वारा जारी किये गये निर्देशों के अनुपालन में निर्धारित अनुमोदित, विशिष्टियों के अनुरूप सम्पादित कराये जायेंगे।
12. कार्यस्थल पर निर्माण कार्य हेतु अस्थायी जल एवं विद्युत की व्यवस्था ठेकेदार/फर्म द्वारा अपने व्यय पर की जायेगी।



## कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।

एस०जे०-59, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

13. ठेकेदार/फर्म द्वारा उक्त निर्माण कार्यो को कराये जाने के दौरान अथवा कार्य पूर्ण होने के पश्चात उसकी जांच ग्राम्य विकास अभिकरण/टी०ए०सी० अथवा अन्य किसी संस्था/विभागीय अधिकारी से कराये जाने के पश्चात कार्यो में यदि कोई कमी प्रकाश में आती है तो उसका निदान ठेकेदार/फर्म को अपने व्यय पर एक सप्ताह में करना होगा, जिसकी प्रतिपूर्ति निगम द्वारा नहीं की जायेगी। यदि उक्त जांच के फलस्वरूप किसी धनराशि की कटौती हेतु संस्तुति की जाती है तो उसकी प्रतिपूर्ति ठेकेदार/फर्म के बिल/जमानत धनराशि से निगम द्वारा की जायेगी।
14. ठेकेदार/फर्म द्वारा लेबर मद हेतु श्रम विभाग में पंजीकरण कराते हुए समस्त राजकीय/केन्द्रीय नियमों एवं कानूनों का अनुपालन किया जाना सुनिश्चित करना होगा। उक्त सम्पूर्ण कार्यवाही हेतु ठेकेदार/फर्म पूर्ण रूप से उत्तरदायी होगा।
15. स्वीकृत/प्राप्त धनराशि में नियमानुसार देय सभी करो आदि की कटौतियाँ करने के उपरान्त अवशेष धनराशि की सीमा तक ही भुगतान किया जायेगा।
16. बिल ऑफ क्वांटिटी में विभिन्न मदों में दर्शायी गयी मात्रा अनुमानित है तथा कार्य सम्पादन के समय किसी भी आइटम की मात्रा में किसी भी सीमा तक संशोधन हो सकता है या कोई कार्य नहीं सम्पादित कराये जाने का भी निर्णय लिया जा सकता है। औचित्यपूर्ण कारण होने पर कार्य पूर्ण करने की अवधि अधीक्षण अभियन्ता द्वारा संशोधित की जा सकती है।
17. कार्य का भुगतान सम्बन्धित ठेकेदार/फर्म द्वारा जीएसटी बिल प्रस्तुत करने व जाँच करने के उपरान्त उपलब्ध धनराशि की सीमा तक भुगतान किया जायेगा व ग्राहक विभाग द्वारा समय-समय पर जारी सभी निर्देशों का पालन किया जाना सुनिश्चित करना होगा।
18. निगम एवं ठेकेदार/फर्म के मध्य किसी प्रकार के विवाद की दशा में अधीक्षण अभियन्ता, यू०पी० स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गाजियाबाद का निर्णय अन्तिम एवं मान्य होगा।
19. निर्माण कार्य के दौरान ठेकेदार/फर्म के किसी कार्य से निगम को अन्य किसी प्रकार से हानि पहुँचती है तो उस क्षति/हानि को वहन करने का दायित्व ठेकेदार/फर्म का होगा। जिसकी वसूली ठेकेदार के बिल/जमानत धनराशि से निगम द्वारा की जायेगी।
20. सिविल कार्य हेतु निविदादाता द्वारा खनन सामग्रियों की रायल्टी भुगतान की रसीद (प्रपत्र एम०एम० 11 अथवा शासन द्वारा जारी अन्य विधिक प्रपत्र) बिल के साथ उपलब्ध करवानी होगी। विभाग द्वारा उक्त खनिज मात्रा के सापेक्ष देय रायल्टी की कटौती कर विभाग के खाते में संरक्षित कर ली जायेगी। तत्पश्चात ठेकेदार द्वारा प्रस्तुत प्रपत्रों का सत्यापन खनन विभाग की वेब साईट से कराये जाने के उपरान्त परिवहन प्रपत्र वैध/सही पाये जाने पर ठेकेदार के बिल से की गयी कटौती की धनराशि उसे वापस की दी जायेगी। परिवहन प्रपत्र के अवैध/त्रुटिपूर्ण पाये जाने पर काटी गयी रायल्टी की धनराशि भूतत्व एवं खनिकर्म विभाग के लेखाशीर्षक में जमा करायी जायेगी तथा ठेकेदार के विरुद्ध आवश्यक कार्यवाही की जायेगी।



## कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

21. निविदा प्रपत्र की सभी शर्तें मान्य होंगी यदि कोई शर्त पूर्ण नहीं की जाती है तो वह निविदा निरस्त कर दी जायेगी।
22. कार्य की प्रगति के समय कार्यस्थल पर किसी प्रकार के विवाद होने अथवा इस स्थिति में कार्य पूर्ण न होने की दशा में कार्यस्थल पर फर्म द्वारा व्यय की गयी धनराशि का उत्तरदायित्व सम्बन्धित फर्म होगा।

अधिशासी अभियन्ता  
यूपीसिडको  
गौतमबुद्ध नगर

मैंने उपरोक्त शर्तों को ध्यान से पढ़ लिया है तथा इस आधार पर मैं कार्य करने हेतु अपनी सहमति देता हूँ।

निविदादाता के हस्ताक्षर

# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

## LITIGATION HISTORY


(ON THE LETTER HEAD OF APPLICANT)

S. No.	Name of Work	Client	Type of case (Court case/ Arbitration case)	Date of registering of case	Name & Address of Court / Arbitrator	Amount involved	Present Status	Remarks (if any)
1	2	3	4	5	6	7	8	9

Signature of Applicant

With seal

**Note:** Applicant has to submit the details of last 5 years in respect of Court cases /Arbitration cases.



# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।


**GSTIN-09AAACU1932C9ZH**

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

U.P. STATE CONSTRUCTION & INFRASTRUCTURE DEVELOPMENT CORP. LTD.							
Name of Work :- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District							
BILL OF QUANTITY							
S. No	DSR 2023	Item	Qty	Unit	DSR Rate	Rate	Amount
						(111/107) X 0.757	-
1	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	1452.66	Sqm	54.65	42.90	62319.48
2	13.8.2	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	1452.66	Sqm	477.90	375.15	544967.58
3	13.91	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	2250.85	Sqm	25.15	19.74	44437.97
4	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	3703.51	Sqm	156.05	122.50	453677.20
5	13.110.1	Finishing walls with textured exterior paint of required shade : Old work (Two or more coats on existing cement paint surface applied @ 3.28 ltr/10 sqm.	1851.76	Sqm	169.20	132.82	245953.80
6	9.20.1	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	35.91	Sqm	3473.85	2726.97	97925.57
7	9.23	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	35.91	Sqm	462.35	362.94	13033.35
8	9.62.2	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250x16 mm	19.00	Each	193.70	152.05	2889.04
9	9.97.1	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : 300x10 mm	41.00	Each	130.10	102.13	4187.27
10	9.100.1	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less	19.00	Each	66.25	52.01	988.12



# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।

एस०जे०-५९, शास्त्री नगर, गाजियाबाद।


GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

		than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125mm					
11	9.148.1	Providing and fixing stainless steel (SS-304 grade) friction hinges to the side/top hung uPVC windows, of approved quality, with necessary stainless steel screws etc. as per direction of Engineer-in-charge. 200 x 19 x 1.9 mm	128.00	Each	381.30	299.32	38313.02
12	9.7.1	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :Second class teak wood	15.97	Sqm	3323.20	2608.71	41661.13
13	14.5.2	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm)	15.97	Sqm	1064.65	835.75	13346.93
14	9.135.1	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 2nd class teak wood beading 62X19 mm	30.75	Sqm	1597.15	1253.76	38553.20
15	9.101.2	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	17.00	Each	72.35	56.79	965.51
16	17.3.1	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	4.00	Each	8006.60	6285.18	25140.72
17	26.24.1	Providing and fixing in position wall panelling at all heights with integral densified calcium silicate panels/tiles of size 595 x 595 mm, having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85%	111.82	Sqm	3117.60	2447.32	273646.64



# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।


**GSTIN-09AAACU1932C9ZH**

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

		(minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity <0.043 W/m K as per ASTM 518:1991, comprising of a frame made from especially fabricated galvanised mild steel sheet 0.50 mm thick pressed section (galvanizing @120 grams per sqm including both sides) i.e.vertical studs of size 48 x 34 x 36 mm are placed at 600 mm centre to centre in a floor and ceiling channel section of size 50 x 32 mm fixed to the floor and soffit at 600 mm centre using 12 mm dia,50 mm long wedge type expanded zinc alloy dash fastner with 10 mm bolt. This same channel is then to be fixed in horizontal direction at 600 mm centre to centre so as to form a grid of 600 mm x 600 mm. Glasswool of 50 mm thickness is then to be inserted in the slots and finally calcium silicate non combustible panels/tiles are to be screw fixed with self tapping pan head nickel coated mild steel screws of size 13 x 3.2 mm on to this grid leaving an even groove of 1 mm between the panels. The joints between the panels are to be duly jointed and finished using recommended jointing calcium silicate based compound and fiber joint tape roll 50 mm wide (90 metre )roll and two coats of primer suitable for panelling as per manufacturer's specification as per direction of Engineer-in-Charge all complete. With 15 mm thick fully perforated square/butt edge light weight calcium silicate panels/ tiles.					
18	17.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	4.00	Each	2648.85	2079.35	8317.39
19	17.4.1	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern.	4.00	Each	6258.75	4913.12	19652.48
20	17.28.	Providing and fixing P.V.C. waste pipe for	20.00	Each	116.70	91.61	1832.19



# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।


**GSTIN-09AAACU1932C9ZH**

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

	1.2	sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 40 mm dia.					
21	17.73. 2	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	4.00	Each	708.95	556.53	2226.10
22	18.62. 1	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./H.P.H.D. plastic ball.15 mm nominal bore, 105 mm long, weighing not less than 138 gms	3.00	Each	182.10	142.95	428.85
23	17.71	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	4.00	Each	168.35	132.15	528.62
24	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	125.75	Sqm	1267.95	995.34	125164.10
25	11.41. 1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm	411.87	Sqm	1524.30	1196.58	492833.55
26	18.26. 1	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	60.00	Sqm	1948.25	1529.38	91762.58
27	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable	4000.00	Ltr	11.00	8.64	34540.00



# कार्यालय अधिशासी अभियन्ता

उत्तर प्रदेश स्टेट कांस्ट्रक्शन एण्ड इन्फ्रास्ट्रक्चर डेवलपमेन्ट कारपोरेशन लि०, गौतमबुद्ध नगर।  
एस०जे०-५९, शास्त्री नगर, गाजियाबाद।

GSTIN-09AAACU1932C9ZH

NIT NO: - 002/EE/GBN/E-TENDER/2026-27

DATE:- 12.05.2026

**NAME OF WORK:- Repair and Renovation work of the Residence Building of the District Magistrate in Gautam Buddha Nagar District.**

		locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.						
28	18.7.2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Internal work - Exposed on wall 20 mm nominal dia Pipes	150.00	Mtr	335.00	262.98	39446.25	
							<b>Total Rs</b>	<b>2718738.64</b>
							<b>Percentage quote by Contractor (+/-)</b>	<b>-</b>
							<b>Net Amount</b>	<b>-</b>
<b>GST Paid Extra as applicable</b>								

