

Tender Reference Number: 246/2026

Tender ID: 2026_TOUR_114732_1

Selection of an Agency for Event Management, Designing, Execution and Management of Pilgrim Facilities in Shravani Mela 2026

Corrigendum – 1

The RFP document is modified/explained (wherever applicable) as under:

Sl. No.	Clause No. & Page No.	Existing Description	Modification
1	Annexure -1: Scope of Work Page No. 24	All CCTV surveillance is to be integrated with Integrated Monitoring Control Room of District Monitoring Cell. A dedicated Control Room to be established for monitoring the entire event facilities for TDCL with high-speed Wi-Fi, monitors, desk, chairs, tower ACs, water purifiers and 24 hr power backup.	All CCTV surveillance is to be integrated with Integrated Mela Control Room (IMCR) of District Monitoring Cell. A dedicated Control Room to be established for monitoring the entire event facilities for JTDCL with high-speed Wi-Fi, monitors, desk, chairs, tower ACs, water purifiers and 24 hr power backup.
2	Annexure -1: Scope of Work Page No. 23	Toilet: One-fourth of the total number of Female Toilets is to be in the form of Bathing Room with Tap Facility. The Agency will be required to provide Tap facility in Open Area equivalent to One-Fourth of the number of Male Toilets for use as bathing points, night soil in waste storage tanks/soak pits, suction vehicle to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning of toilet on regular intervals. (70 Toilet each for 700 capacity tents (35 Male and 35 Female) (80 Toilet) (40 Male and 40 Female) for 800 capacity tents, (130 Toilets) (65 Male and 65 Female) for 1300 capacity Tent and (10 Toilets) (5 Male and 5 Female) for 100 capacities Tent. Besides these 200 extra toilets besides the roads and surroundings.	Toilet: One-fourth of the total number of Female Toilets is to be in the form of Bathing Room with Tap Facility. The Agency will be required to provide Tap facility in Open Area equivalent to One-Fourth of the number of Male Toilets for use as bathing points, night soil in waste storage tanks/soak pits, suction vehicle to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning of toilet on regular intervals. (70 Toilet each for 700 capacity tents (35 Male and 35 Female) (80 Toilet) (40 Male and 40 Female) for 800 capacity tents, (130 Toilets) (65 Male and 65 Female) for 1300 capacity Tent and (10 Toilets) (5 Male and 5 Female) for 100 capacities Tent. Besides these 200 extra toilets besides the roads and surroundings. The Agency shall

Sl. No.	Clause No. & Page No.	Existing Description	Modification
			<p>be responsible for preparing a standard engineering design, layout, and determining the appropriate depth of the toilet pits in consultation with the concerned engineer of the respective district administration. The pits shall be constructed strictly in accordance with the approved design so as to ensure prevention of water overflow and leakage throughout the duration of the Shravani Mela. The Agency shall further be responsible for the proper operation and maintenance of the same during the entire period.</p>
3	Annexure -1: Scope of Work Page No. 26	<p>Bio-Toilet (Quantity 50) Bio-Toilet/FRP moulded toilets units, single user units of size 43" X 36" X 74" (2 Male and 2 Female) from Basukinath to Deoghar (one at each 2 km distance/gap). Provide required support/facilities during the event. i.e. Night soil in waste storage tanks/soak pits, suction vehicles to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning toilets at regular intervals. Provision of Covered Toilet Pits for Bio-Toilets Maintenance: For all bio-toilets, covered toilet pits of 10 ft × 10 ft shall be excavated to support proper waste management and maintain hygiene standards. These pits must be adequately covered</p>	<p>Bio-Toilet (Quantity 50) Bio-Toilet/FRP moulded toilets units, single user units of size 43" X 36" X 74" (2 Male and 2 Female) from Basukinath to Deoghar (one at each 2 km distance/gap). Provide required support/facilities during the event. i.e. Night soil in waste storage tanks/soak pits, suction vehicles to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning toilets at regular intervals.</p> <p>The agency shall be responsible for maintaining the same throughout the Shravani Mela, ensuring it remains in good condition at all times.</p>

Sl. No.	Clause No. & Page No.	Existing Description	Modification
		and maintained to prevent odor, contamination, and environmental hazards. The selected agency shall be responsible for regular inspection and cleaning of the pits as required, ensuring safe and sanitary conditions.	
4	Annexure -1: Scope of Work Page No. 27	b) Toilet: FRP molded toilets units/ Bathroom, single user units of size 43” X 36“X 74”, night soil in waste storage tanks/soak pits, suction vehicles to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning toilets at regular intervals. (10 Toilet each for 100 capacity shed tent (7 Male and 3 Female)	b) Toilet: FRP molded toilets units/ Bathroom, single user units of size 43” X 36“X 74”, night soil in waste storage tanks/soak pits, suction vehicles to take away waste and disposed, plumbing and electrical arrangements with overhead water tanks. Housekeeping staff for cleaning toilets at regular intervals. (10 Toilet each for 100 capacity shed tent (7 Male and 3 Female). The Agency shall be responsible for preparing a standard engineering design, layout, and determining the appropriate depth of the toilet pits in consultation with the concerned engineer of the respective district administration. The pits shall be constructed strictly in accordance with the approved design so as to ensure prevention of water overflow and leakage throughout the duration of the Shravani Mela. The Agency shall further be responsible for the proper operation and maintenance of the same during the entire period.
5	Annexure -1: Scope of Work Page No. 24	Installation of Head Count Cameras in All Tent Cities: A total of 50 (10 camera in each	Installation of Head Count Cameras in All Tent Cities: A total of 50 (10 camera in each

Sl. No.	Clause No. & Page No.	Existing Description	Modification
		tent city) Head count cameras shall be installed across all five Tent Cities at key entry, exit, and circulation points to enable accurate monitoring of footfall. The system should ensure real-time data capture, support crowd management, and enhance overall safety and operational control within the Tent City areas.	tent city) Head count cameras shall be installed across all five Tent Cities at key entry, exit, and circulation points to enable accurate monitoring of footfall. The system should ensure real-time data capture, support crowd management, and enhance overall safety and operational control within the Tent City areas. Headcount camera should also be integrated with Integrated Mela Control Room (IMCR) of District Monitoring Cell.
6	Annexure -1: Scope of Work Page No. 24-25	Use of Granular Sub-Base Material for Temporary Walkways Across All Tent Cities: Granular Sub-Base (GSB) material shall be used as the foundational layer for the temporary construction of walkways across all Tent Cities. The GSB layer must be properly graded, compacted, and levelled to provide a stable, well-drained, and durable base for pedestrian movement, ensuring safety, load-bearing capacity, and resistance to weather conditions.	Agency shall use and maintain Granular Sub-Base (GSB) Material for Temporary Walkways Across All Tent Cities: Granular Sub-Base (GSB) material shall be used as the foundational layer for the temporary construction of walkways across all Tent Cities. The GSB layer must be properly graded, compacted, and levelled to provide a stable, well-drained, and durable base for pedestrian movement, ensuring safety, load-bearing capacity, and resistance to weather conditions. The agency shall be responsible for maintaining the same throughout the Shravani Mela, ensuring it remains in good condition at all times.

All other terms and conditions of the tender shall remain unchanged in view of the above modifications.

Sd-

Managing Director,
Jharkhand Tourism Development Corporation Limited