



**UTTAR PRADESH STATE BRIDGE CORPORATION
GOVT. OF UTTAR PRADESH**

**Engineering Procurement and Construction (EPC) of Yamuna
River Bridge, Approach Road, Additional Approach Road and
Protection works on Anandi Bhairon to Dera Banjara (Gijauli)
Road in Distt. Agra**

Volume2–Articles & Schedules

Apr-2026

Table of Contents

Part I		11-25
	Preliminary	
1	Definitions and Interpretations	
1.1	Definitions	
1.2	Interpretation	
1.3	Measurements and arithmetic conventions	
1.4	Priority of agreements and errors/discrepancies	
1.5	Joint and severalliability	
Part II		26-43
	ScopeofProject	
2	Scope of the Project	
2.1	Scope of the Project	
3	Obligations of the Authority	
3.1	Obligations of the Authority	
3.2	Maintenance obligations prior to the Appointed Date	
3.3	Environmental Clearances	
3.4	Deemed Termination up on delay	
4	Obligations of the Contractor	
4.1	Obligations of the Contractor	
4.2	Obligations relating to sub-contracts and any other agreements	
4.3	Employment off or eignnationals	
4.4	Contractor's personnel	
4.5	Advertisement on Project Highway	
4.6	Contractor's care of the Works	
4.7	Electricity, water, and other services	
4.8	Unforeseeable difficulties	
4.9	Co-ordination of the Works	
4.10	Environmental Measures	
4.11	Site Data	
4.12	Sufficiency of Contract Price	

4.13 Clearance of the Site

5 Representations and Warranties

5.1 Representations and warranties of the Contractor

5.2 Representations and warranties of the Authority

5.3 Disclosure

6 Disclaimer

6.1 Disclaimer

Part III

44-92

Construction and Maintenance

7 Performance Security

7.1 Performance Security

7.2 Extension of Performance Security and Additional Performance Security

7.3 Appropriation of Performance Security

7.4 Release of Performance Security

7.5 Retention Money

8 Right of Way

8.1 The Site

8.2 Procurement of the Site

8.3 Damages for delay in handing over the Site

8.4 Site to be free from Encumbrances

8.5 Protection of Site from encroachments

8.6 Special/temporary Right of Way

8.7 Access to the Authority and the Authority's Engineer

8.8 Geological and archaeological finds

9 Utilities and Trees

9.1 Existing utilities and roads

9.2 Shifting of obstructing utilities

9.3 New utilities

9.4 Felling of trees

9.5 Dismantling of structures

9.6 Development Period

10 Design and Construction of the Project Highway

- 10.1 Obligations prior to commencement of Works
- 10.2 Design and Drawings
- 10.3 Construction of the Project Highway
- 10.4 Maintenance during Construction Period
- 10.5 Extension of time for completion
- 10.6 Incomplete Works
- 10.7 Maintenance Manual
- 10.8 As-Built Records
- 10.9 Contractor's Use of Authority's Documents
- 10.10 **Quality Assurance, Monitoring and Supervision**
- 10.11 Quality of Materials and workmanship
- 10.12 Quality control system
- 10.13 Methodology
- 10.14 Inspection and technical audit by the Authority
- 10.15 External technical audit
- 10.16 Inspection of construction records
- 10.17 Monthly progress reports
- 10.18 Inspection
- 10.19 Samples
- 10.20 Tests
- 10.21 Examination of work before covering up
- 10.22 Rejection
- 10.23 Remedial work
- 10.24 Delays during construction
- 10.25 Quality control records and Documents
- 10.26 Video recording
- 10.27 Suspension of unsafe Construction Works
- 10.28 Staff and Labour

11 Completion Certificate

- 11.1 Tests on Completion
- 11.2 Completion Certificate
- 11.3 Rescheduling of Tests

- 12 Change of Scope**
 - 12.1 Change of Scope
 - 12.2 Procedure for Change of Scope
 - 12.3 Payment for Change of Scope
 - 12.4 Restrictions on Change of Scope
 - 12.5 Power of the Authority to undertake Works
- 13 Maintenance**
 - 13.1 Maintenance obligations of the Contractor
 - 13.2 Maintenance Requirements
 - 13.3 Maintenance Programme
 - 13.4 Safety, vehicle breakdowns, and accidents
 - 13.5 Lane closure
 - 13.6 Reduction of payment for non-performance of Maintenance obligations
 - 13.7 Authority's right to take remedial measures
 - 13.8 Restoration of loss or damage to Project Highway
 - 13.9 Overriding powers of the Authority
 - 13.10 Takingover Certificate
- 14 Supervision and Monitoring during Maintenance**
 - 14.1 Inspection by the Contractor
 - 14.2 Inspection and payments
 - 14.3 Tests
 - 14.4 Reports of unusual occurrence
- 15 Traffic Regulation**
 - 15.1 Traffic regulation by the Contractor
- 16 Defects Liability**
 - 16.1 Defects Liability Period
 - 16.2 Remedying Defects
 - 16.3 Cost of remedying Defects
 - 16.4 Contractor's failure to rectify Defects
 - 16.5 Extension of Defects Liability Period

17 Authority's Engineer

- 17.1 Appointment of the Authority's Engineer
- 17.2 Duties and authority of the Authority's Engineer
- 17.3 Delegation by the Authority's Engineer
- 17.4 Instructions of the Authority's Engineer
- 17.5 Determination by the Authority's Engineer
- 17.6 Remuneration of the Authority's Engineer
- 17.7 Termination of the Authority's Engineer

Part IV

93-105

Financial Covenants

18 Payments

- 18.1 Contract Price
- 18.2 Advance Payment
- 18.3 Procedure for estimating the payment for the Works
- 18.4 Stage Payment Statement for Works
- 18.5 Stage Payment for Works
- 18.6 Monthly Maintenance Statement of the Project Highway
- 18.7 Payment for Maintenance of the Project Highway
- 18.8 Payment of Damages
- 18.9 Time of payment and interest
- 18.10 Price adjustment for the Works
- 18.11 Restrictions on price adjustment
- 18.12 Price adjustment for Maintenance of Project Highway
- 18.13 Final Payment Statement
- 18.14 Discharge
- 18.15 Final Payment Certificate
- 18.16 Final payment statement for Maintenance
- 18.17 Change in law
- 18.18 Correction of Interim Payment Certificates
- 18.19 Authority's claims
- 18.20 Bonus for early completion

19 Insurance

- 19.1 Insurance for Works and Maintenance
- 19.2 Notice to the Authority
- 19.3 Evidence of Insurance Cover
- 19.4 Remedy for failure to insure
- 19.5 Waiver of subrogation
- 19.6 Contractor's waiver
- 19.7 Cross liabilities
- 19.8 Accident or injury to workmen
- 19.9 Insurance against accident to workmen
- 19.10 Application of insurance proceeds
- 19.11 Compliance with policy conditions
- 19.12 General Requirements of Insurance Policies

Part V

106-120

Force Majeure and Termination

20 Force Majeure

- 20.1 Force Majeure
- 20.2 Non-Political Event
- 20.3 Indirect Political Event
- 20.4 Political Event
- 20.5 Duty to report Force Majeure Event
- 20.6 Effect of Force Majeure Event on the Agreement
- 20.7 Termination Notice for Force Majeure Event
- 20.8 Termination Payment for Force Majeure Event
- 20.9 Dispute resolution
- 20.10 Excuse from the performance of obligations

21 Suspension of Contractor's Rights

- 21.1 Suspension upon Contractor Default
- 21.2 Authority to act on behalf of Contractor
- 21.3 Revocation of Suspension
- 21.4 Termination

- 22 Termination**
 - 22.1 Termination for Contractor Default
 - 22.2 Termination for Authority Default
 - 22.3 Termination for Authority's convenience
 - 22.4 Requirements after Termination
 - 22.5 Valuation of Unpaid Works
 - 22.6 Termination Payment
 - 22.7 Otherrights and obligations of the Parties
 - 22.8 Survival of rights
 - 22.9 Fore closure with mutual consent

Part VI

120-134

Other Provisions

- 23 Assignment and Charges**
 - 23.1 Restrictions on assignment and charges
 - 23.2 Hypothecation of Materials or Plant
- 24 Liability and Indemnity**
 - 24.1 General indemnity
 - 24.2 Indemnity by the Contractor
 - 24.3 Notice and contest of claims
 - 24.4 Defense of claims
 - 24.5 Survival on Termination
- 25 Dispute Resolution**
 - 25.1 Dispute Resolution
 - 25.2 Conciliation
 - 25.3 Arbitration
 - 25.4 Adjudication by Regulatory Authority, Tribunal or Commission
- 26 Miscellaneous**
 - 26.1 Governing law and jurisdiction
 - 26.2 Waiver of immunity
 - 26.3 Delayed payments
 - 26.4 Waiver

- 26.5 Liability for review of Documents and Drawings
- 26.6 Exclusion of implied warranties, etc.
- 26.7 Survival
- 26.8 Entire Agreement
- 26.9 Severability
- 26.10 No partnership
- 26.11 Third parties
- 26.12 Successors and assigns
- 26.13 Notices
- 26.14 Language
- 26.15 Counter parts
- 26.16 Confidentiality
- 26.17 Copyright and Intellectual Property Rights
- 26.18 Limitation of Liability
- 26.19 Care and Supply of Documents
- 26.20 Authority's Use of Contractor's Documents.
- 26.21 Contractor's Use of Authority's Documents
- 26.22 Access of the Site by Others
- 26.23 Term
- 26.24 Amendments
- 26.25 Representation and Bribes
- 26.26 No Agency

Schedules

135 onwards

Schedule-A

Schedule-B

Schedule-C

Schedule-D

Schedule-E

Schedule-F

Schedule-G

Schedule-H

Schedule -I

Schedule- J

Schedule- K

Schedule-L

Schedule-M

Schedule-N

Schedule-O

Schedule-P

Schedule-Q

Schedule-R

Part I
Preliminary

Engineering, Procurement, and Construction Agreement

THIS AGREEMENT is entered into on this the.....day of.....,20.....

Between

The General Manager/Chief Project Manager, UP State Bridge Corporation Limited (the "Authority") has decided to undertake " Design and Construction of Yamuna River Bridge, Approach Road, Additional Approach Road and Protection work on Anandi Bhairon to Dera Banjara (Gijauli) Road in Distt. Agra on EPC Mode"

(hereinafter referred to as the "Authority" which expression shall, unless repugnant to the context or meaning thereof, include its administrators, successors, and assigns) **of One Part;**

And

<insert name of party>,2 the selected bidder3 having its registered office at <insert registered office address of the party>, (hereinafter referred to as the "Contractor" which expression shall, unless repugnant to the context or meaning thereof, include its successors and permitted assigns) of the **Other Part.**

Whereas:

- A. [The Government of India] entrusted [the development, maintenance, and management of to the Authority;
- B. The Authority resolved to [rehabilitate and augment the existing road/ROB/ Bridge/Flyover (Name of Project) On an Engineering, Procurement, Construction ("EPC") basis in accordance with the terms and conditions to be set forth in an agreement to be entered into.
- C. The Authority accordingly invited the proposals (the "Request for Proposals" or "RFP") from the eligible bidders as per the technical and commercial terms and conditions prescribed in the RFP for undertaking the Project.
- D. After evaluation of the bids received, the Authority accepted the bid of the selected bidder and issued its Letter of Acceptance No. <insert details> dated <insert date> (hereinafter called the "LOA") to the selected bidder for [rehabilitation and augmentation of the above section of at the Contract Price specified hereinafter, requiring the selected bidder to inter alia:
 - (i) to give his consent to enter in to this Agreement and the enforceability of the provisions thereof, within 10 (ten) days of the date of issue of LOA;
 - (ii) submit Performance Security and Additional Performance Security (if any) as

per RFP requirements, and

(iii) execute this Agreement within 30 (thirty) days of the date of issue of LOA.

E. The Contractor has fulfilled the requirements specified in Recital (D) above;

NOW, THEREFORE, inconsideration of the foregoing and the respective covenants set forth in this Agreement, the sufficiency and adequacy of which are hereby acknowledged, the Authority hereby covenants to pay the Contractor, in consideration of the obligations specified herein, the Contract Price or such other sum as may become payable under the provisions of the Agreement at the times and in the manner specified by the Agreement and intending to be legally bound hereby, the Parties agree as follows:

Article 1

Definitions and Interpretations

1.1 Definitions

- (i) The words and expressions beginning with capital letters and defined in this Agreement shall, unless the context otherwise requires, have the meaning ascribed thereto herein, and the words and expressions defined in the Schedules and used therein shall have the meaning ascribed thereto in the Schedules.
- (ii) In this Agreement, the following words and expressions shall, unless repugnant to the context or meaning thereof, have the meaning hereinafter respectively assigned to them:

“Accounting Year” means the financial year commencing from the first day of April of any calendar year and ending on the thirty-first day of March of the next calendar year;

“Advance Payment” shall have the meaning set forth in Clause 19.2; **“Affected**

Party” shall have the meaning set forth in Clause 21.1;

“Affiliate” means, in relation to either Party {and/or Members}, a person who controls, is controlled by, or is under the common control with such Party {or Member} (as used in this definition, the expression “control” means, with respect to a person which is a company or corporation, the ownership, directly or indirectly, of more than 50% (fifty percent) of the voting shares of such person, and with respect to a person which is not a company or corporation, the power to direct the management and policies of such person, whether by operation of law or by contractor otherwise);

“Agreement” means this Agreement, its Recitals, the Schedules hereto and any amendments thereto, or any supplementary agreement made in accordance with the provisions contained in this Agreement;

“Applicable Laws” means all laws, brought into force and effect by the GOI or the State Government including rules, regulations, and notifications made thereunder, and judgments, decrees, injunctions, writs, and orders of any court of record, applicable to this Agreement and the exercise, performance and discharge of the respective rights and obligations of the Parties hereunder, as may be in force and effect during the subsistence of this Agreement;

“Applicable Permits” means all clearances, licenses, permits, authorizations, no objection certificates, consents, approvals, and exemptions required to be obtained or maintained under Applicable Laws in connection with the construction, operation, and maintenance of the Project Highway during the subsistence of this Agreement;

“Appointed Date” means the date declared by the Authority as the project commencement date with the consent of the contractor, as per the process prescribed in Articles 3 and 8 of this Agreement;

“Arbitration Act” means the Arbitration and Conciliation Act, 1996, with all its subsequent amendments;

“Authority” shall have the meaning attributed thereto in the array of Parties hereinabove as outlined in the Recitals;

“Authority Default” shall have the meaning outlined in Clause 23.2;

“Authority’s Engineer” shall have the meaning outlined in Clause 18.1;

“Authority Representative” means such person or persons as may be authorized in writing by the Authority to act on its behalf under this Agreement and shall include any person or persons having authority to exercise any rights or perform and fulfill any obligations of the Authority under this Agreement;

“Bank” means a bank incorporated in India and recognized by the Reserve Bank of India

“Base Rate” means the floor rate of interest announced by the State Bank of India for all its lending operations;

“Base Date” means the last date of the calendar month, which precedes the Bid Due Date by at least 28 (twenty eight) days;

“Bid” means the documents in their entirety comprised in the bid submitted by the [selected bidder/ Joint venture] in response to the Request for Proposal in accordance with the provisions thereof;

“Bid Security” means the bid security provided by the Contractor to the Authority in accordance with the Request for Proposal, and which is to remain in force until substituted by the Performance Security;

“Change in Law” means the occurrence of any of the following after the Base Date:

- (a) the enactment of any new Indian law;
- (b) the repeal, modification, or re-enactment of any existing Indian law;
- (c) the commencement of any Indian law which has not come into effect until the Base Date; or
- (d) a change in the interpretation or application of any Indian law by a judgment of a court of record which has become final, conclusive, and binding, as compared to such interpretation or application by a court of record before the Base Date.

“Change of Scope” shall have the meaning outlined in Article 13;

“Change of Scope Notice” shall have the meaning outlined in Clause 13.2 (i);

“Change of Scope Request” shall have the meaning outlined in Clause 13.2(ii);

“Change of Scope Order” shall have the meaning outlined in Clause 13.2(iv);

“Completion Certificate” shall have the meaning outlined in Clause 12.2;

“Construction” shall have the meaning outlined in Clause 1.2 (f);

“Construction Period” means the period commencing from the Appointed Date and ending on the date of the Completion Certificate;

“Construction Zone” shall have the meaning outlined in Clause 8.3(i);

“Contract Price” means the amount specified in Clause 19.1(i);

“Contractor” shall have the meaning attributed thereto in the array of Parties herein above as outlined in the Recitals;

“Contractor Default” shall have the meaning outlined in Clause 23.1;

“Cure Period” means the period specified in this Agreement for curing any breach or default of any provision of this Agreement by the Party responsible for such breach or default and shall:

- (a) commence from the date on which a notice is delivered by one Party to the other Party asking the latter to cure the breach or default specified in such notice;
- (b) not relieve any Party from liability to pay damages or compensation under the provisions of this Agreement; and
- (c) not in any way be extended by any period of Suspension under this Agreement; provided that if the cure of any breach default by the Contractor requires any reasonable action by the Contractor that must be approved by the Authority or the Authority’s Engineer hereunder, the applicable Cure Period shall be extended by the period taken by the Authority or the Authority’s Engineer to accord their approval;

“Damages” shall have the meaning outlined in paragraph (w) of Clause 1.2;

“Defect” means any defect or deficiency in the Construction of the Works or any part thereof, that does not conform with the Specifications and Standards, and in the case of Maintenance, means any Defect or deficiency that is specified in Schedule-E;

“Defects Liability Period” shall have the meaning outlined in Clause 17.1;

“Dispute” shall have the meaning outlined in Clause 26.1;

“Dispute Resolution Procedure” means the procedure for resolution of Disputes outlined in Article 26;

“Drawings” means all of the drawings, calculations, and documents pertaining to the Project Highway as outlined in Schedule-I, and shall include ‘as built’ drawings of the Project Highway;

“Document” or “Documentation” means documentation in printed or written form, orintapes, discs, drawings, computer programs, writings, reports,photographs, films, cassettes, or expressed in any other written, electronic, audio, or visual form;

“Emergency” means a condition or situation that is likely to endanger the safety or security of the individuals on or aboutthe ProjectHighway, including Users thereof, or which poses an immediate threat of material damage to any of the Project Assets;

“Encumbrances” means, in relation to the Project Highway, any encumbrances such as a mortgage, charge, pledge, lien, hypothecation, security interest, assignment, privilege, or priority of any kind having the effect of securityor other such obligations, and shall include any designation of loss to payees or beneficiaries or any similar arrangement under any insurance policy pertaining to the Project Highway, where applicable herein but excluding utilities referred to in Clause 9.1;

“EPC” means engineering, procurement, and construction;

“Final Payment Certificate” shall have the meaning outlined in Clause 19.15;

“Final Payment Statement” shall have the meaning outlined in Clause 19.13;

“ForceMajeure”or“ForceMajeureEvent”shall havethemeaning ascribedtoitin Clause 21.1;

“GAD” or“ General Arrangement Drawings” shall have the meaning outlined in Clause 3.1 (iii) (b);

“GOI” or“ Government” means the Government of India;

“Good Industry Practice” means the practices, methods, techniques, designs, standards, skills, diligence, efficiency, reliability, and prudence that are generally and reasonably expected from a reasonably skilled and experienced contractor engaged in the same type of undertaking as envisaged underthisAgreementandwhichwould be expectedto result inthe performanceofits obligations by theContractorunder thisAgreement,ApplicableLawsandApplicablePermitsinareliable,safe, economical and efficient manner;

“Government Instrumentality” means any department, division, or sub-division of the Government or the State Government and includes any commission, board, authority, agency, or municipal and other local authority or statutory body including panchayat under the control of the Government or the State Government, as the case maybe, and having jurisdiction overall or any part of the Project Highway or the

performance of all or any of the services or obligations of the Contractor under or pursuant to this Agreement;

“Handover Memorandum” shall have the meaning outlined in Clause 8.2;

“IRC” means the Indian Roads Congress;

“Indemnified Party” means the Party entitled to the benefit of an indemnity pursuant to Article 25;

“Indemnifying Party” means the Party obligated to indemnify the other Party pursuant to Article 25;

“Indirect Political Event” shall have the meaning outlined in Clause 21.3;

“Insurance Cover” means the aggregate of the maximum sums insured under the insurance taken out by the Contractor under Article 20, and includes all insurances required to be taken out by the Contractor under Clauses 20.1 and 20.9 but not taken, and when used in the context of any act or event, it shall mean the aggregate of the maximum sums insured and payable or deemed to be insured and payable in relation to such act or event;

“Intellectual Property” means all patents, trademarks, service marks, logos, get-ups, trade names, internet domain names, rights in designs, blue prints, programs and manuals, drawings, copyright (including rights in computer software), database rights, semi-conductor, topography rights, utility models, rights in know-how and other intellectual property rights, in each case whether registered or unregistered and including applications for registration, and all rights or forms of protection having equivalent or similar effect anywhere in the world;

“Interim Payment Certificate” or **“IPC”** means the interim payment certificate issued by the Authority’s Engineer for payment to the Contractor in respect of the Contractor’s claims for payment raised under the provisions of this Agreement;

“Joint Venture” means the group of entities which have come together for implementation of this Project;

“Lead Member” shall, in the case of a joint venture, mean the member of such joint venture who shall have the authority to bind the contractor and each member of the Joint venture; and shall be deemed to be the Contractor for this Agreement; the Lead Member shall itself undertake and perform at least 51% (fifty-one percent) of the total length of the Project Highway;

“LOA” or **“Letter of Acceptance”** means the letter of acceptance issued by the Authority as referred to in Recital (D);

“Maintenance” means the maintenance of the Project Highway as outlined in Article 14 for the period specified therein;

“Maintenance Inspection Report” shall have the meaning outlined in Clause 15.2;

“Maintenance Manual” shall have the meaning ascribed to it in Clause 10.7;

“Maintenance Programme” shall have the meaning outlined in Clause 14.3;

“Maintenance Period” shall have the meaning outlined in Clause 14.1;

“Maintenance Requirements” shall have the meaning outlined in Clause 14.2;

“Major Bridge” means a bridge having a total length of more than 60 (sixty) meters between the inner faces of the abutment walls as specified in IRC:5;

"Manual" shall be manual of standards & specifications for Project Highways as per Schedule-D;

“Material Adverse Effect” means a material adverse effect of any act or event on the ability of either Party to perform any of its obligations under and under the provisions of this Agreement and which act or event causes a material financial burden or loss to either Party;

“Materials” comprise all the supplies used by the Contractor in the Works or for the maintenance of the Project Highway;

“Monthly Maintenance Statement” shall have the meaning outlined in Clause 19.6;

“MORTH” means the Ministry of Road Transport and Highways or any substitute thereof dealing with Highways;

“Non-Political Event” shall have the meaning outlined in Clause 21.2;

“Parties” means the parties to this Agreement collectively and “Party” shall mean any of the parties to this Agreement individually;

“Performance Security” and **“Additional Performance Security”** shall have the meaning outlined in Clause 7.1;

“Plant” means the apparatus and machinery intended to form or forming part of the works;

“Political Event” shall have the meaning outlined in Clause 21.4;

“Programme” shall have the meaning outlined in Clause 10.1 (iii);

“Project” means the construction and maintenance of the Project Highway/River Bridge under the provisions of this Agreement, and includes all works, services, and equipment relating to or in respect of the Scope of the Project;

“Project Assets” means all physical and other assets relating to (a) tangible assets such as civil works and equipment including foundations, embankments, pavements,

road surface, interchanges, bridges, culverts, road over-bridges, drainage works, traffic signals, sign boards, kilometer-stones, [toll plaza(s)], electrical systems, communication systems, rest areas, relief centers, maintenance depots, and administrative offices; and (b) Project Facilities situated on the Site;

“Project Completion Date” means the date on which the Completion Certificate is issued;

“Project Completion Schedule” means the progressive Project Milestones outlined in Schedule-J for completion of the Project Highway on or before the Scheduled Completion Date;

“Project Facilities” means all the amenities and facilities situated on the Site, as described in Schedule-C;

“Project Highway” means the Site comprising the existing road {proposed bypasses and tunnels} forming part of [Name of work] and all Project Assets, and its subsequent development and augmentation under this Agreement;

“Project Milestone” means the project milestone outlined in ScheduleJ;

“Proof Consultant” shall have the meaning outlined in Clause10.2;

“Quality Assurance Plan” or **“QAP”** shall have the meaning outlined in Clause11.2;

“Re.”, “Rs.” or “Rupees” or “Indian Rupees” or “INR” means the lawful currency of the Republic of India;

“Request for Proposals” or **“RFP”** shall have the meaning outlined in Recital‘C’;

“Retention Money” shall have the meaning outlined in Clause7.5;

“Right of Way” means and refers to the total land required and acquired for the project, both in its width and length, together with all way leaves, easements, unrestricted access, and other rights of way, howsoever described, necessary for construction and maintenance of the Project Highway under this Agreement;

“Safety Consultant” shall have the meaning outlined in Clause10.1;

“Scheduled Completion Date” shall be the date outlined in Clause 10.3;

“Scheduled Construction Period” means the period commencing from the Appointed Date and ending on Scheduled Completion Date;

“Scope of the Project” shall have the meaning outlined in Clause2.1;

“Section” means apart of the Project Highway;

“Site” shall have the meaning outlined in Clause 8.1;

"Specifications and Standards" means the specifications and standards relating to the quality, quantity, capacity, and other requirements for the Project Highway, as outlined in Schedule-D, and any modifications thereof, or additions thereto, as included in the design and engineering for the Project Highway submitted by the Contractor to, and expressly approved by the Authority;

"Stage Payment Statement" shall have the meaning outlined in Clause 19.4;

"Structures" means an elevated road or a flyover, as the case may be;

"Sub-contractor" means any person or persons to whom a part of the Works or the Maintenance has been subcontracted by the Contractor and the permitted legal successors in title to such person, but not an assignee to such person;

"Suspension" shall have the meaning outlined in Article 22;

"Taking Over Certificate" shall have the meaning outlined in Clause 14.10;

"Taxes" means any Indian taxes including GST, excise duties, customs duties, value-added tax, sales tax, local taxes, cess and any impost or surcharge of like nature (whether Central, State, or local) on the goods, Materials, equipment, and services incorporated in and forming part of the Project Highway charged, levied or imposed by any Government Instrumentality, but excluding any interest, penalties and other sums in relation thereto imposed on any account whatsoever. For the avoidance of doubt, Taxes shall not include taxes on corporate income;

"Termination" means the expiry or termination of this Agreement;

"Termination Notice" means the communication issued under this Agreement by one Party to the other Party terminating this Agreement;

"Termination Payment" means the amount payable by either Party to the other upon Termination under Article 23;

"Terms of Reference" or "TOR" shall have the meaning outlined in Clause 18.2;

"Tests" means the tests outlined in Schedule-K to determine the completion of Works under the provisions of this Agreement;

"Time Extension" shall have the meaning outlined in Clause 10.5;

"User" means a person who travels or intends to travel on the Project Highway or any part thereof in/on any vehicle;

"Valuation of Unpaid works" shall have the meaning outlined in Clause 23.5;

"Works" means all works including survey and investigation, design, engineering, procurement, construction, Plant, Materials, maintenance, temporary work and sand

other things necessary to complete the Project Highway under this Agreement; and

“WPI” means the wholesale price index for various commodities as published by the Ministry of Commerce and Industry, GOI and shall include any index that substitutes the WPI, and any reference to WPI shall, unless the context otherwise requires, be construed as a reference to the WPI published for the period ending with the preceding month.

1.2 Interpretation

- (i) In this Agreement, unless the context otherwise requires,
 - (a) references to any legislation or any provision thereof shall include amendment or re-enactment or consolidation of such legislation or any provision thereof so far as such amendment or re-enactment or consolidation applies or is capable of applying to any transaction entered into hereunder;
 - (b) references to laws of India or Indian law or regulation having the force of law shall include the laws, acts, ordinances, rules, regulations, bye-laws or notifications which have the force of law in the territory of India and as from time to time may be amended, modified, supplemented, extended or re-enacted;
 - (c) references to a “person” and words denoting a natural person shall be construed as a reference to any individual, firm, company, corporation, society, trust, government, state, or agency of a state or any association or partnership (whether or not having separate legal personality) of two or more of the above and shall include successors and assigns;
 - (d) the table of contents, headings, or sub-headings in this Agreement are for convenience of reference only and shall not be used in, and shall not affect, the construction or interpretation of this Agreement;
 - (e) the words “include” and “including” are to be construed without limitation and shall be deemed to be followed by “without limitation” or “but not limited to” whether or not they are followed by such phrases;
 - (f) references to “construction” or “building” include, unless the context otherwise requires, survey and investigation, design, developing, engineering, procurement, supply of plant, materials, equipment, labor, delivery, transportation, installation, processing, fabrication, testing, and commissioning of the Project Highway, including maintenance during the Construction Period, removing of defects, if any, and other activities incidental to the construction and “construct” or “build” shall be construed accordingly;
 - (g) references to “development” include, unless the context otherwise requires, construction, renovation, refurbishing, augmentation, gradation, and other activities incidental thereto during the Construction Period, and “develop” shall be construed accordingly;

- (h) any reference to any period shall mean a reference to that according to Indian standard time;
- (i) any reference today shall mean a reference to a calendar day;
- (j) references to a “business day” shall be construed as a reference to a day (other than a Sunday) on which banks in Lucknow or other places are generally open for business;
- (k) any reference to month shall mean a reference to a calendar month as per the Gregorian calendar;
- (l) references to any date, period, or Project Milestone shall mean and include such date, period, or Project Milestone as may be extended under this Agreement;
- (m) any reference to any period commencing “from” a specified day or date and “till” or “until” a specified day or date shall include both such days or dates; provided that if the last day of any period computed under this Agreement is not a business day, then the period shall run until the end of the next business day;
- (n) the words importing singular shall include plural and viceversa;
- (o) references to any gender shall include the other and the neutral gender;
- (p) “lakh” means a hundred thousand (100,000) and “crore” means ten million (10,000,000);
- (q) “indebtedness” shall be construed to include any obligation (whether incurred as principal or surety) for the payment or repayment of money, whether present or future, actual or contingent;
- (r) references to the “winding-up”, “dissolution”, “insolvency”, or “reorganization” of a company or corporation shall be construed to include any equivalent or analogous proceedings under the law of the jurisdiction in which such company or corporation is incorporated or any jurisdiction in which such company or corporation carries on the business including the seeking of liquidation, winding-up, reorganization, dissolution, arrangement, protection or relief of debtors;
- (s) save and except as otherwise provided in this Agreement, any reference, at any time, to any agreement, deed, instrument, license, or document of any description shall be construed as a reference to that agreement, deed, instrument, license, or other documents as amended, varied, supplemented, modified or suspended at the time of such reference; provided that this Clause shall not operate to increase liabilities or obligations of the Authority hereunder or pursuant hereto in any manner whatsoever;
- (t) any agreement, consent, approval, authorization, notice, communication, information, or report required under or under this Agreement from or by any Party or the Authority’s Engineer shall be valid and effective only if it is in writing under the hand of a duly authorized representative of such Party or the Authority’s Engineer, as the case may be, in this behalf and not otherwise;

- (u) the Schedules and Recitals to this Agreement form an integral part of this Agreement and will be in full force and effect as though they were expressly set out in the body of this Agreement;
 - (v) references to Recitals, Articles, Clauses, Sub-clauses, or Schedules in this Agreement shall, except where the context otherwise requires, mean references to Recitals, Articles, Clauses, Sub-clauses, and Schedules of this Agreement, and references to a Paragraph shall, subject to any contrary indication, be construed as a reference to a Paragraph of this Agreement or of the Schedule in which such reference appears;
 - (w) the damages payable by either Party to the other of them, as outlined in this Agreement, whether on a per diem basis or otherwise, are mutually agreed on genuine pre-estimated loss and damage likely to be suffered and incurred by the Party entitled to receive the same and are not by way of penalty or liquidated damages (the "Damages"); and
 - (x) time shall be of the essence in the performance of the Parties' respective obligations. If any period specified herein is extended for the reasons specified in the Agreement; such extended time shall also be of the essence.
- (ii) Unless expressly provided otherwise in this Agreement, any Documentation required to be provided or furnished by the Contractor to the Authority shall be provided free of cost and in three copies, and if the Authority is required to return any such Documentation with its comments and/or approval, it shall be entitled to retain two copies thereof.
 - (iii) The rule of construction, if any, that a contract should be interpreted against the parties responsible for the drafting and preparation thereof, shall not apply.
 - (iv) Any word or expression used in this Agreement shall, unless otherwise defined or construed in this Agreement, bear its ordinary English meaning and, for these purposes, the General Clauses Act, 1897 shall not apply.

1.3 Measurements and arithmetic conventions

All measurements and calculations shall be in the metric system and calculations done to 2 (two) decimal places, with the third digit of 5 (five) or above being rounded up and below 5 (five) being rounded down.

1.4 Priority of agreements and errors/discrepancies

- (i) This Agreement and all other agreements and documents forming part of or referred to in this Agreement are to be taken as mutually explanatory and, unless otherwise expressly provided elsewhere in this Agreement, the priority of this Agreement and other documents and agreements forming part hereof or referred to herein shall, in the event of any conflict between them, be in the following order:
 - (a) this Agreement; and

- (b) all other agreements and documents forming part thereof or referred to herein; i.e. this Agreement at (a) above shall prevail over the agreements and documents at (b).
- (ii) Subject to the provisions of Clause 1.4 (i), in case of ambiguities or discrepancies within this Agreement, the following shall apply:
 - (a) between two or more Clauses of this Agreement, the provisions of a specific Clause relevant to the issue under consideration shall prevail over those in other Clauses;
 - (b) between the Clauses of this Agreement and the Schedules, the Clauses shall prevail and between Schedules and Annexes, the Schedules shall prevail;
 - (c) between any two Schedules, the Schedule relevant to the issue shall prevail;
 - (d) between the written description on the Drawings and the Specifications and Standards, the latter shall prevail;
 - (e) between the dimension scaled from the Drawing and its specific written dimension, the latter shall prevail; and
 - (f) between any value written in numerals and that in words, the latter shall prevail.

1.5 Joint and several liability

- (i) If the Contractor has formed a Joint Venture of two or more persons for implementing the Project:
 - (a) these persons shall, without prejudice to the provisions of this Agreement or any other agreement, be deemed to be jointly and severally liable to the Authority for the performance of the Agreement; and
 - (b) the Contractor shall ensure that no change in the composition of the Joint Venture is affected without the prior consent of the Authority.
- (ii) Without prejudice to the joint and several liability of all the members of the Joint Venture, the Lead Member shall represent all the members of the Joint Venture and shall always be liable and responsible for discharging the functions and obligations of the Contractor. The Contractor shall ensure that each member of the Joint Venture shall be bound by any decision, communication, notice, action, or inaction of the Lead Member on any matter related to this Agreement and the Authority shall be entitled to rely upon any such action, decision or communication of the Lead Member. The Authority shall have the right to release payments solely to the Lead Member and shall not in any manner be responsible or be held liable for the inter se allocation of payments among members of the Joint venture.

Part II Scope of Project

Article 2

Scope of the Project

2.1 Scope of the Project

Under this Agreement, the scope of the Project (the “**Scope of the Project**”) shall mean and include:

- (a) construction of the Project Highway on the Site outlined in Schedule- A and as specified in Schedule-B together with the provision of Project Facilities as specified in Schedule-C, and in conformity with the Specifications and Standards outlined in Schedule D;
- (b) maintenance of the Project Highway under the provisions of this Agreement and conformity with the requirements outlined in Schedule-E; and
- (c) Performance and fulfillment of all other obligations of the Contractor under the provisions of this Agreement and matters incidental thereto or necessary for the performance of any or all of the obligations of the Contractor under this Agreement.

Article 3

Obligations of the Authority

3.1 Obligations of the Authority

- (i) The Authority shall, at its own cost and expense, undertake, comply with, and perform all its obligations set out in this Agreement or arising hereunder.
- (ii) The Authority shall be responsible for the correctness of the Scope of the Project, Project Facilities, Specifications and Standards, and the criteria for testing of the completed Works.
- (iii) The Authority, upon submission of the Performance Security as per the RFP by the Contractor, shall provide to the Contractor:

(a) the required Right of Way of the Construction Zone is as follows:

S.No.	Work Detail	Date
1	90% ROW	On the appointed date.
2	Remaining 10% ROW	After 90 days from the appointed date

- (b) approval of the general arrangement drawings (the “GAD”) from Competent Authorities /railway authorities to enable the Contractor to construct road over- bridges/ under- bridges /Major River Bridge(River Ganga) at level crossings on the Project Highway under the Specifications and Standards, and subject to the terms and conditions specified in such approval, within 60 (sixty) days from the Appointed Date, and reimbursement of all the costs and expenses paid by the Contractor to the railway authorities for and in respect of the road over- bridges/ under bridges/Major River Bridge; and
- (c) All environmental clearances as required under Clause 4.3, if any.
- (iv) Delay in providing the Right of Way or approval of GAD by Competent Authorities /railway authorities, as the case may be, under the provisions of Clause 3.1 (iii) shall entitle the Contractor to Damages in a sum calculated under the provisions of Clause 8.3 of this Agreement and Time Extension under the provisions of Clause 10.5 of this Agreement. For the avoidance of doubt, the Parties agree that the Damages for the delay in the approval of GAD by the Competent Authorities /railway authorities for a particular road over-bridge/under-bridge/Bridge over River shall be deemed to be equal to the Damages payable under the provisions of Clause 8.3 for the delay in providing Right of Way for a length of 2 (two) kilometer for each such road over-bridge/ under-bridge/Major Bridge over River.

- (v) Notwithstanding anything to the contrary contained in this Agreement, the Parties expressly agree that the aggregate Damages payable under Clauses 3.1 (iv), 8.3 and 9.5 shall not exceed 1% (one percent) of the Contract Price. For the avoidance of doubt, the Damages payable by the Authority under the aforesaid Clauses shall not be additive if they arise concurrently from more than one cause but relate to the same part of the Project Highway.

Both the parties agree that payment of such Damages shall be a full and final settlement of all claims of the Contractor and such compensation shall be the sole remedy against delays of the Authority both parties further agree that the payment of Damages shall be the final cure for the Contractor against delays of the Authority, without recourse to any other payments.

- (vi) The Authority agrees to provide support to the Contractor and undertakes to observe, comply with, and perform, subject to and under the provisions of this Agreement and the Applicable Laws, the following:
 - (a) upon written request from the Contractor, and subject to the Contractor complying with Applicable Laws, provide reasonable support to the Contractor in procuring Applicable Permits required from any Government Instrumentality for implementation of the Project;
 - (b) upon written request from the Contractor, provide reasonable assistance to the Contractor in obtaining access to all necessary infrastructure facilities and utilities, including water and electricity at rates and on terms no less favorable than those generally available to commercial customers receiving substantially equivalent services;
 - (c) procure that no barriers that would have a material adverse effect on the works are erected or placed on or about the Project Highway by any Government Instrumentality or persons claiming through or under it, except for reasons of Emergency, national security, law and order or collection of inter-state taxes;
 - (d) not do or omit to do any act, deed, or thing which may in any manner violate any provisions of this Agreement;
 - (e) support, cooperate with, and facilitate the Contractor in the implementation of the Project under the provisions of this Agreement; and
 - (f) upon written request from the Contractor and subject to the provisions of Clause 4.3, provide reasonable assistance to the Contractor and any expatriate personnel of the Contractor or its Sub-contractors to obtain the applicable visas and the requisite work permits for discharge by the Contractor or its Sub-contractors of their obligations under this Agreement and the agreements with the Sub-contractors.

3.2 Maintenance obligations before the Appointed Date

The Authority shall, before the Appointed Date, maintain the Project Highway, at its own cost and expense, so that its traffic worthiness and safety are at no time materially inferior as compared to its condition 10 (ten) days before the last date for submission of the Bid, and in the event of any material deterioration or damage other than normal wear and tear, undertake repair thereof. For the avoidance of doubt, the Authority shall undertake only routine maintenance before the Appointed Date, and it shall undertake special repairs only in the event of excessive deterioration or damage caused due to unforeseen events such as floods or earthquakes.

3.3 Environmental Clearances

The Authority represents and warrants that the environmental clearances required for the construction of the Project shall be procured by the Authority before the date of issue of LOA. For the avoidance of doubt, the present status of environmental clearances is specified in Schedule-A.

3.4 Deemed Termination upon delay

Without prejudice to the provisions of Clause 8.3, and subject to the provisions of Clause 7.3, the Parties expressly agree that in the event the Appointed Date does not occur, for any reason whatsoever, within 90 days of the signing of the Agreement and submission of the full Performance Security by the Contractor, the Agreement shall be deemed to have been terminated. The Authority shall pay damages to the Contractor equivalent to 1% of the Contract Price (3% in case of stand alone bridge projects). All other rights, privileges, claims, and entitlements of the Contractor under or arising out of this Agreement shall be deemed to have been waived by, and to have ceased. The Contractor shall handover all information concerning the Highway, including but not limited to any data, designs, drawings, structures, information, plans, etc. prepared by them for the Highway, to the Authority.

Article 4

Obligations of the Contractor

4.1 Obligations of the Contractor

- (i) Subject to and on the terms and conditions of this Agreement, the Contractor shall undertake the survey, investigation, design, engineering, procurement, construction, and maintenance of the Project Highway and observe, fulfill, comply with, and perform all its obligations set out in this Agreement or arising hereunder.
- (ii) The Contractor shall comply with all Applicable Laws and Applicable Permits (including renewals as required) in the performance of its obligations under this Agreement.
- (iii) Subject to the provisions of Clauses 4.1 (i) and 4.1 (ii), the Contractor shall discharge its obligations under Good Industry Practice and as a reasonable and prudent person.
- (iv) The Contractor shall remedy all loss, defects, or damage to the Project Highway from the Appointed Date until the end of the Construction Period at the Contractor's cost, save and except to the extent that any such loss, defect, or damage shall have arisen from any willful default or neglect of the Authority.
- (v) The Contractor shall remedy all loss, defect, or damage to the Project Highway during the Defects Liability Period at the Contractor's cost to the extent that such loss, defect, or damage shall have arisen out of the reasons specified in Clause 17.3.
- (vi) The Contractor shall remedy all loss or damage to the Project Highway during the Maintenance Period at the Contractor's cost, including those stated in Clause 14.1 (ii), save and except to the extent that any such loss or damage shall have arisen on account of any willful default or neglect of the Authority or account of a Force Majeure Event.
- (vii) The Contractor shall, at its own cost and expense, in addition to and not in derogation of its obligations elsewhere set out in this Agreement:
 - (a) make, or cause to be made, necessary applications to the relevant Government Instrumentalities with such particulars and details as may be required for obtaining Applicable Permits outlined in Schedule F and obtain and keep in force and effect such Applicable Permits in conformity with the Applicable Laws;
 - (b) procure, as required, the appropriate proprietary rights, licenses, agreements, and permissions for Materials, methods, processes, and systems used or incorporated into the Project Highway;

- (c) make reasonable efforts to maintain harmony and good industrial relations among the personnel employed by it or its Sub-contractors in connection with the performance of its obligations under this Agreement;
 - (d) ensure and procure that its Sub-contractors comply with all Applicable Permits and Applicable Laws in the performance by them of any of the Contractor's obligations under this Agreement;
 - (e) not do or omit to do any act, deed, or thing which may in any manner violate any provisions of this Agreement;
 - (f) support, cooperate with, and facilitate the Authority in the implementation and operation of the Project under the provisions of this Agreement;
 - (g) ensure that the Contractor and its Sub-contractors comply with the safety and welfare measures for labor under the Applicable Laws and Good Industry Practice;
 - (h) keep, on Site, a copy of this Agreement, publications named in this Agreement, the Drawings, Documents relating to the Project, and Change of Scope orders and other communications given under this Agreement. The Authority's Engineer and its authorized personnel shall have the right of access to all these documents at all reasonable times;
 - (i) cooperate with other contractors employed by the Authority and personnel of any public authority; and
 - (j) not interfere unnecessarily or improperly with the convenience of the public, or the access to and use and occupation of all roads and footpaths, irrespective of whether they are public or in the possession of the Authority or others.
- (viii) The Contractor shall undertake all necessary superintendence to plan, arrange, direct, manage, inspect, and test the Works. The Contractor shall provide all necessary superintendence of the Works for the proper fulfilling of the Contractor's obligations under the Agreement. Such superintendence shall be given by a competent person having adequate knowledge of the operations to be carried out (including the methods and techniques required, the hazards likely to be encountered, and methods of preventing accidents) for the satisfactory and safe execution of the Works.
- (ix) The Contractor shall obtain and maintain a project-related bank account operational at the site where all transactions related to the payment of work will be done. The Contractor shall submit a monthly account statement and a detailed report on the utilization of funds transferred to this project-related bank account to the Authority's Engineer. Notwithstanding anything contrary to this agreement, the authority, in the interest of ensuring the timely completion of the work, reserves the right to audit such bank accounts to ensure that there is no diversion of funds from this project-specific account to any other project being implemented by the Contractor.

- (x) The Contractor shall provide the documents of the Contractor specified in the Agreement, and all Contractors' personnel; Goods, consumables, and other things and services, whether of a temporary or permanent nature, required in and for the execution, completion of Works, and remedying defects.
- (xi) The Contractor shall perform the Works in conformity with the Project requirements and other requirements and standards prescribed under or pursuant to the Agreement.
- (xii) The Contractor shall carry out such work incidental and contingent to the original Scope of the Project to comply with Good Industry Practices.
- (xiii) The Contractor shall maintain the required staff and necessary Contractor's equipment and materials within the reach of the Site during the Defects Liability Period so that any defects arising are promptly attended.

4.2 Obligations relating to sub-contracts and any other agreements

- (i) The Contractor, whether Joint Venture or sole, shall not sub-contract any Works in more than **49% (forty-nine percent)** of the Contract Price and shall carry out Works directly under its supervision and through its personnel and equipment **in at least 51% (fifty-one percent)** of the Contract Price. Further, in case the Contractor is a joint Venture, then the Lead Member shall carry out Works directly through its resources (men, material, machines, etc.) in **at least 51% (fifty-one percent)** of the total length of the Project Highway. Provided, however, that in respect of the Works carried out directly by the Contractor, it may enter into contracts for the supply and installation of Materials, Plant, equipment, road furniture, safety devices, and labor, as the case may be, for such Works. For the avoidance of doubt, the Parties agree that the Contractor may sub-divide the aforesaid length of **51% (fifty-one percent)** in no more than 5 (five) sections of the Project Highway. The Parties further agree that all obligations and liabilities under this Agreement for the entire project Highway shall at all times remain with the Contractor.
- (ii) In the event any sub-contract for Works, or the aggregate of such sub-contracts with any Sub-contractor, exceeds 5% (five percent) of the Contract Price, the Contractor shall communicate the name and particulars, including the relevant experience of the Sub-contractor, to the Authority before entering into any such sub-contract. The Authority shall examine the particulars of the Sub-contractor from the national security and public interest perspective and may require the Contractor, no later than 15 (fifteen) business days from the date of receiving the communication from the Contractor, not to proceed with the sub-contract, and the Contractor shall comply therewith.
- (iii) In the event any sub-contract referred to in Clause 4.2 (ii) relates to a Sub-contractor who has, over the preceding 3 (three) years, not undertaken at least one work of a similar nature with a contract value exceeding 40% (forty percent) of the value of the sub-contract to be awarded hereunder, and received payments in respect thereof for an amount equal to at least such 40% (forty percent), the Authority may, no later

than 15 (fifteen) business days from the date of receiving the communication from the Contractor, require the Contractor not to proceed with such sub-contract, and the Contractor shall comply therewith without delay or demur.

- (iv) It is expressly agreed that the Contractor shall, at all times, be responsible and liable for all its obligations under this Agreement notwithstanding anything contained in the agreements with its Sub-contractors or any other agreement that may be entered into by the Contractor, and no default under any such agreement shall excuse the Contractor from its obligations or liability under this Agreement. However, in case of non-compliance of the Contractor towards his obligations for payments to the approved Sub-contractor(s), which is likely to affect the progress of works, the authority reserves the right to intervene and direct the Contractor to release such outstanding payments to approved Sub-contractor(s) out of the payments due for the completed Works in the interest of work.

4.3 Employment of foreign nationals

The Contractor acknowledges, agrees, and undertakes that employment of foreign personnel by the Contractor and/or its Sub-contractors and their sub-contractors shall be subject to the grant of requisite regulatory permits and approvals including employment/residential vis as and work permits, if any required, and the obligation to apply for and obtain the same shall always rest with the Contractor. Notwithstanding anything to the contrary contained in this Agreement, refusal of or inability to obtain any such permits and approvals by the Contractor or any of its Subcontractors or their sub-contractors shall not constitute a Force Majeure Event, and shall not in any manner excuse the Contractor from the performance and discharge it of its obligations and liabilities under this Agreement, and the Contractor's liabilities hereunder shall remain unaffected by such failure, refusal or inability.

4.4 Contractor's personnel

- (i) The Contractor shall ensure that the personnel engaged by it or by its Sub contractors in the performance of its obligations under this Agreement are at all times appropriately and adequately qualified, skilled, and experienced in their respective functions in conformity with Good Industry Practice. The Contractor will try to hire at least 10% (ten percent) trained workmen as per the National Skills Qualifications Frame work. If necessary, the requisite workmen may be trained by the Contractor at his cost through authorized training centers of the Directorate General of Training (DGT). The Contractor will organize training at the project site/ sites for the trainees as and when required as per the training schedule finalized in consultation with the training centers. The trainees shall be paid a stipend by the Contractor (subject to a maximum of Rs. 15,000/- per person) based on minimum wages to compensate for loss of income during the training period.
- (ii) The Authority's Engineer may, for reasons to be specified in writing, direct the Contractor to remove any member of the Contractor's or Sub-contractor's personnel. Provided that any such direction issued by the Authority's Engineer shall specify the reasons for the removal of such a person.

- (iii) The Contractor shall on receiving such a direction from the Authority's Engineer order for the removal of such person or persons with immediate effect. It shall be the duty of the Contractor to ensure that such persons are evicted from the Site within 10 (ten) days of any such direction being issued in pursuance of Clause 4.4 (ii). The Contractor shall further ensure that such persons have no further connection with the Works or Maintenance under this Agreement. The Contractor shall then appoint (or cause to be appointed) a replacement.

4.5 Advertisement on Project Highway

The Project Highway or any part thereof shall not be used in any manner to advertise any commercial product or service.

4.6 Contractor's care of the Works

The Contractor shall bear full risk in, and take full responsibility for, the care of the Works, and the Materials, goods, and equipment for incorporation therein, from the Appointed Date until the date of Completion Certificate, save and except to the extent that any such loss or damage shall have arisen from any willful default or gross neglect of the Authority.

4.7 Electricity, Water, and other services

The Contractor shall be responsible for procuring all utilities as may be required, including without limitation, adequate power, water, and other services.

4.8 Unforeseeable difficulties

Except as otherwise stated in the Agreement:

- (a) the Contractor accepts complete responsibility for having foreseen all difficulties and costs of completing the Works;
- (b) the Contract Price shall not be adjusted to take account of any unforeseen difficulties or costs; and
- (c) the Scheduled Completion Date shall not be adjusted to take account of any unforeseen difficulties or costs.

4.9 Co-ordination of the Works

- (i) The Contractor acknowledges that in addition to the Agreement, it is also aware of terms of the other Project contracts and other agreements the Authority has negotiated and entered into for the performance of its obligations under the Agreement (copies of other contracts and other agreements are made available to the Contractor from time to time) and that the Contractor is fully aware of the consequences to the Authority which would or are likely to result from a breach by the Contractor of its obligations under the Agreement. In the event, that the actions of the Contractor result in the breach by the Authority of any or all of the other Project

contracts and such breach imposes any liability on the Authority, the Contractor shall: (a) undertake all steps as may be possible to mitigate or neutralize the liability that has arisen, and (b) indemnify the Authority against any such liability and compensate the Authority to that extent.

- (ii) The Contractor shall be responsible for the coordination and proper provision of the Works, including co-ordination of other Contractors or Sub-contractors for the Project. The Contractor shall co-operate with the Authority in the coordination of the Works with the works under the other Project contracts. The Contractor shall provide all reasonable support for carrying out their work to:
 - (a) any other contractors employed by the Authority;
 - (b) the workmen of the Authority;
 - (c) the workmen of any Governmental Instrumentality who may be employed in the execution of work on or near the Site; and
 - (d) such other persons as is required in the opinion of the Authority for the successful completion of the Project.

4.10 Environmental Measures

- (i) The Contractor agrees to conduct its activities in connection with the Agreement in such a manner to comply with the environmental requirements which includes, *inter alia*, all the conditions required to be satisfied under the environmental clearances and applicable law, and assumes full responsibility for measures which are required to be taken to ensure such compliance.

4.11 Site Data

- (i) The Contractor shall be deemed to have inspected and examined the Site and its surroundings and to have satisfied himself before entering into the Agreement in all material respects including but not limited to:
 - (a) the form and nature of the Site (including, inter-alia, the surface and sub-surface conditions, and geotechnical factors);
 - (b) the hydrological and climatic conditions;
 - (c) the extent and nature of the works already completed Materials necessary for the execution and completion of the Works and the remedying of any defects that include the already executed part.
 - (d) the suitability and the adequacy of the Site for the execution of the Works;
 - (e) the means of access to the Site and the accommodation the Contractor may require;
 - (f) arranging permits as required as per[.] of the Agreement.
 - (g) the requirements of operation and maintenance; and
 - (h) all other factors and circumstances affecting the Contractor's rights and obligations under the Agreement, the Contract Price, and Time for Completion.

4.12 Sufficiency of Contract Price

The Contractor shall have satisfied itself as to the correctness and sufficiency of the Contract Price. The Contract Price shall cover all its obligations under the Agreement, in addition to all risks the Contractor has agreed to undertake under the Agreement, including those associated with the performance of its obligations under the Agreement and all things necessary for the provision of the Works in a manner satisfactory to the Authority and under this Agreement.

4.13 Clearance of the Site

During the provision of the Works, and as a pre-condition to the issue of the Taking-Over Certificate, the Contractor shall clear away and remove from the Site, all Contractor's equipment, surplus material, wreckage, rubbish, and temporary Works, and shall keep the Site free from all unnecessary obstructions, and shall not store or dispose of any Contractor's equipment or surplus materials on the Site. The Contractor shall promptly clear away and remove from the Site any wreckage, rubbish, or temporary Works no longer required and leave the Site and the Works in a clean and safe condition to the sole satisfaction of the Authority.

Article 5

Representations and Warranties

5.1 Representations and warranties of the Contractor

- (i) The Contractor represents and warrants to the Authority that:
 - (a) it is duly organized and validly existing under the laws of India, and has full power and authority to execute and perform its obligations under this Agreement and to carry out the transactions contemplated hereby;
 - (b) it has taken all necessary corporate and/or other actions under Applicable Laws to authorize the execution and delivery of this Agreement and to validly exercise its rights and perform its obligations under this Agreement;
 - (c) this Agreement constitutes its legal, valid, and binding obligation, enforceable against it under the terms hereof, and its obligations under this Agreement will be legally valid, binding, and enforceable against it under the terms hereof;
 - (d) it is subject to the laws of India, and hereby expressly and irrevocably waives any immunity in any jurisdiction in respect of this Agreement or matters arising thereunder including any obligation, liability, or responsibility hereunder;
 - (e) the information furnished in the Bid, Request for Qualification, and Request for Proposals or otherwise and as updated on or before the date of this Agreement is true and accurate in all respects as on the date of this Agreement;
 - (f) the execution, delivery, and performance of this Agreement will not conflict with, or result in the breach of, or constitute a default under, or accelerate performance required by any of the terms of its memorandum and articles of association or any Applicable Laws or any covenant, contract, agreement, arrangement, understanding, decree or order to which it is a party or by which it or any of its properties or assets is bound or affected;
 - (g) there are no actions, suits, proceedings, or investigations pending or, to its knowledge, threatened against it at law or in equity before any court or before any other judicial, quasi-judicial, or other authority, the outcome of which may result in the breach of this Agreement or which individually or in the aggregate may result in any material impairment of its ability to perform any of its obligations under this Agreement;
 - (h) it does not know of any violation or default concerning any order, writ, injunction, or decree of any court or any legally binding order of any Government Instrumentality that may result in any material adverse effect on its ability to perform its obligations under this Agreement and no fact or circumstance exists which may give rise to such proceedings that would adversely affect the performance of its obligations under this Agreement;
 - (i) it has complied with Applicable Laws in all material respects and has not been subject to any fines, penalties, injunctive relief, or any other civil or criminal

liabilities which in the aggregate have or may have a material adverse effect on its ability to perform its obligations under this Agreement;

- (j) no representation or warranty by it contained herein or in any other document furnished by it to the Authority or any Government Instrumentality concerning Applicable Permits contains or will contain any untrue or misleading statement of a material fact or omits or will omit to state a material fact necessary to make such representation or warranty not misleading;
 - (k) no sums, in cash or kind, have been paid or will be paid, by it or on its behalf, to any person by way of fees, commission, or otherwise for securing the contract or entering into this Agreement or for influencing or attempting to influence any officer or employee of the Authority in connection therewith;
 - (l) nothing contained in this Agreement shall create any contractual relationship or obligation between the Authority and any Sub contractors, designers, consultants, or agents of the Contractor;
 - (m) it is adequately financed and has the requisite knowledge, expertise, technical know-how, experience, resources, infrastructure, licenses, patents, and copy rights, for designing, supplying/ procuring the goods and materials, and for providing the installation and construction services required for completing the construction of the Project Facilities; and
- (ii) it represents the Authority that:
- (a) it owns or has the right to use all **“Intellectual Property”** necessary to perform the contractual obligations and to carry on the Works without conflict with the rights of others;
 - (b) All intellectual property rights necessary to perform the contractual obligations and to carry on the Works are in full force and effect and are vested in, and beneficially owned by the Contractor, and are free from encumbrances.
 - (c) None of the intellectual property rights is being used, claimed, posed, or attacked by any other person, nor does the use of such intellectual property rights or any part of them infringe the intellectual property rights owned or enjoyed by any third party.
 - (d) None of the intellectual property rights owned or used by the Contractor is the subject of any claim, opposition, attack, assertion, or other arrangement of whatsoever nature which does or may impinge upon their use, validity, enforceability, or ownership by the Parties, and there are no grounds or other circumstances which may give rise to the same.
 - (e) No licenses registered users or other rights have been granted or agreed to be granted to any third party in respect of such intellectual property rights.
 - (f) No act has been done or has been omitted to be done to entitle any authority or person to cancel, forfeit, or modify any intellectual property rights.
 - (g) The Contractor shall notify the Authority of any adverse use of the intellectual property rights or confusingly or deceptively similar to the intellectual property rights.

- (h) The Contractor shall recognize the Authority's ownership and title to the intellectual property rights and shall not at any time, either directly or indirectly, put to issue the validity or ownership of the intellectual property rights and it will not do any act or thing, either directly or indirectly, which in any way impairs the validity and ownership of the intellectual property rights.
 - (i) The Contractor shall, promptly execute, acknowledge, and deliver all documents which are requested by the Authority to record with appropriate governmental agencies and authorities the fact that the Authority has the right to the use of the said intellectual property rights.
 - (j) The Contractor shall not, for any reason, object to, or interfere in any way with the ownership, registration, or use of the intellectual property rights by the Authority (or its licensee or assigns) for any purpose whatsoever.
- (iii) The Contractor is fully aware that the Agreement is interlinked with the other Project contracts and the non-performance or deficient performance or default by the Contractor and/or any of the Contractor's personnel or Subcontractors under one among the said contracts will have bearing on the other contracts and the evaluation of the Contractor's performance under the Agreement and the Project itself.
- (iv) If at any time during the Defects Liability Period any item of the Works or Project Facilities or any part thereof, do not conform to the Authority requirements and Specifications and Standards, on being so notified by the Authority, the Contractor shall promptly rectify/remedy such nonconformity to the satisfaction of the Authority solely at the Contractor's expense; failing which the Authority may reject or revoke Taking-Over Certificate, and the Authority may proceed to correct the Contractor's nonconforming Work by the most expeditious means available, the costs of which shall be to the Contractor's account, or the Authority may retain the non-conforming Work and an equitable adjustment reducing the total Contract Price to reflect the diminished value of such non-conforming Work will be made by written amendment.
- (v) In addition to the other warranties, the Contractor represents and warrants as follows:
- (a) The Contractor has (or, if the technology does not currently exist, will have granted at the time of passing to The Employer) in and to the technology used in the equipment, materials, goods, Works, Contractor's documents, Drawings, and Manuals ("**Technology**") -
 - i. all rights, title, and interest-free of any lien, claim, or restriction; and
 - ii. right to grant to the Authority the right to use the Technology for this contract, free of any lien, claim, or restriction and on the terms of the license as required.
 - (b) The Contractor has granted (or, if the technology does not currently exist, will grant at the time of passing to the Authority the property and title in and to the equipment, materials, goods, Works, spares, Contractor's documents, Drawings, and Manuals in which it is used) to the Authority the right to use the Technology, free of any lien, claim or restriction.

- (vi) In addition to the other Warranties, the Contractor represents and warrants as follows:
 - (a) No Technology contains any worm (i.e., a program that travels from one computer to another computer but does not attach itself to the operating system of the computer it enters), virus (i.e., a program that travels from one computer to another computer that attaches itself to the operating system it enters) or self-destruct capability.
 - (b) The Technology will not abnormally end or provide invalid or incorrect results as a result of date-dependent data.
 - (c) The Technology can accurately recognize, manage, accommodate, and manipulate date-dependent data, including single and multi-century formulas and leap years.
- (vii) No criminal proceedings were instituted against any of the employees or Directors of the Contractor.
- (viii) To date, the services of the Contractor have not been terminated by any person for any breach, non-performance, or negligence by the Contractor.

5.2 Representations and warranties of the Authority

The Authority represents and warrants to the Contractor that:

- (a) it has full power and authority to execute, deliver, and perform its obligations under this Agreement and to carry out the transactions contemplated herein and that it has taken all actions necessary to execute this Agreement, exercise its rights and perform its obligations, under this Agreement;
- (b) it has taken all necessary actions under the Applicable Laws to authorize the execution, delivery, and performance of this Agreement;
- (c) it has the financial standing and capacity to perform its obligations under this Agreement;
- (d) this Agreement constitutes a legal, valid, and binding obligation enforceable against it under the terms hereof;
- (e) it does not know of any violation or default concerning any order, writ, injunction, or decree of any court or any legally binding order of any Government Instrumentality that may result in any material adverse effect on the Authority's ability to perform its obligations under this Agreement;
- (f) it has complied with Applicable Laws in all material respects;
- (g) it has good and valid right to the Site and has the power and authority to grant the Right of Way in respect thereof to the Contractor; and
- (h) it has procured Right of Way and environment clearances such that the Contractor can commence construction forthwith on 90% (ninety percent) of the total length of the Project Highway/Bridge.

5.3 Disclosure

If any occurrence or circumstance comes to the attention of either Party that renders any of its aforesaid representations or warranties untrue or incorrect, such Party shall immediately notify the other Party of the same. Such notification shall not have the effect of remedying any breach of the representation or warranty that is untrue or incorrect nor shall it adversely affect or waive any obligation of either Party under this Agreement.

Article 6

Disclaimer

6.1 Disclaimer

- (i) The Contractor acknowledges that before the execution of this Agreement, the Contractor has, after a complete and careful examination, made an independent evaluation of the Request for Proposal, Scope of the Project, Specifications and Standards of design, construction and maintenance, Site, local conditions, physical qualities of ground, subsoil and geology, traffic volumes, suitability and availability of access routes to the Site and all information provided by the Authority or obtained, procured or gathered otherwise, and has determined to its satisfaction the accuracy or otherwise thereof and the nature and extent of difficulties, risks and hazards as are likely to arise or may be faced by it in the course of performance of its obligations hereunder. Save as provided in Clause 3.1 and Clause 5.2, the Authority makes no representation whatsoever, express, implicit, or otherwise, regarding the accuracy, adequacy, correctness, reliability, and/or completeness of any assessment, assumptions, statement, or information provided by it and the Contractor confirms that it shall have no claim whatsoever against the Authority in this regard.
- (ii) The Contractor acknowledges and hereby accepts to have satisfied itself as to the correctness and sufficiency of the Contract Price.
- (iii) The Contractor acknowledges and hereby accepts the risk of inadequacy, mistake, or error in or relating to any of the matters outlined in Clause 6.1 (i) above and hereby acknowledges and agrees that the Authority shall not be liable for the same in any manner whatsoever to the Contractor, or any person claiming through or under any of them, and shall not lead to any adjustment of Contract Price or Scheduled Completion Date.
- (iv) The Parties agree that any mistake or error in or relating to any of the matters outlined in Clause 6.1 (i) above shall not vitiate this Agreement, or render it voidable.
- (v) If either Party becomes aware of any mistake or error relating to any of the matters outlined in Clause 6.1 (i) above, that Party shall immediately notify the other Party, specifying the mistake or error.
- (vi) Except as otherwise provided in this Agreement, all risks relating to the Project shall be borne by the Contractor; and the Authority shall not be liable in any manner for such risks or the consequences thereof.

Part III
Construction and Maintenance

Article 7

Performance Security

7.1 Performance Security

- (i) (A) Within 30 (thirty) days of receipt of Letter of Acceptance, the selected Bidder shall furnish to the Authority an irrevocable and unconditional guarantee from a Bank in the form outlined in Annex- I of Schedule-G (the "Performance Security") for an amount equal to 5 % (Five percent) of its Bid Price including GST.
In case of bids mentioned below, the Selected Bidder, along with the Performance Security, shall also furnish to the Authority an irrevocable and unconditional guarantee from a Bank in the same form given at Annex-I of Schedule-G towards an Additional Performance Security (the "Additional Performance Security") for an amount calculated as under: - (Ref. to latest MoRTH Circular no. NH-37015/01/2022-H (Comp No. 208778) dated 29.02.2024.
- a. If the Bid Price offered by the Selected Bidder is lower than 20% of the estimated Project Cost/ cost put to tender, then the Additional Performance Security shall be calculated @ 20% of the difference in the (i) Estimated Project Cost (as mentioned in RFP)-20% of the Estimated Project Cost and (ii) the Bid Price offered by the selected Bidder.
- b. The Maximum limit of the Additional Performance Security shall be limited to 3% of the bid price including GST offered by the Selected Bidder.
- c. This Additional Performance Security shall be treated as part of the Performance Security.
- (B) The Performance Security shall be valid until sixty (60) days after the Defects Liability Period. The Additional Performance Security shall be valid until 28 (twenty- eight) days after the Project Completion Date.
- (ii) The Selected Bidder shall provide the Performance Security and the Additional Performance Security, if any, within 30 (thirty) days of receipt of the Letter of Acceptance, in any case before signing the Contract Agreement.
- (iii) In the event the Selected Bidder fails to provide the remaining Performance Security and Additional Performance Security, if any, as prescribed herein, it may seek an extension of time for a further period of up to 60 days by paying the Damages upfront along with the request letter seeking the extension. The Damages shall be the sum calculated at the rate of 0.01% (zero point zero one percent) of the Bid Price offered by the Selected Bidder for each day until the Performance Security and Additional Performance Security, if any, are provided in full as prescribed herein. The damages at the full rate as given above shall be applicable even if a part of the Performance Security and the Additional Performance Security is provided.

- (iv) For the avoidance of any doubt, in case of failure of submission of Performance Security and Additional Performance Security, if any, within the additional 60 days' time period, the award shall be deemed to be canceled/ withdrawn and the Bid Security shall be encashed and the proceeds thereof appropriated by the Authority. Thereupon all rights, privileges, claims, and entitlements of the Contractor under or arising out of the Award shall be deemed to have been waived by, and to have ceased with the concurrence of the Contractor, and the Award shall be deemed to have been withdrawn by the Authority

7.2 Extension of Performance Security and Additional Performance Security

The Contractor may initially provide the Performance Security for 2 (two) years; provided that it shall procure the extension of the validity of the Performance Security, as necessary, at least 2 (two) months before the date of expiry thereof. Upon the Contractor providing an extended Performance Security, the previous Performance Security shall be deemed to be released and the Authority shall return the same to the Contractor within 7 (seven) business days from the date of submission of the extended Performance Security.

7.3 Appropriation of Performance Security

- (i) Upon occurrence of a Contractor's Default, the Authority shall, without prejudice to its other rights and remedies hereunder or in law, be entitled to encash and appropriate the relevant amounts from the Performance Security as Damages for such Contractor's Default.
- (ii) Upon such encashment and appropriation from the Performance Security, the Contractor shall, within 30 (thirty) days thereof, replenish, in case of partial appropriation, to its original level the Performance Security, and in case of appropriation of the entire Performance Security provide a fresh Performance Security, as the case may be, and the Contractor shall, within the time so granted, replenish or furnish fresh Performance Security as aforesaid failing which the Authority shall be entitled to terminate the Agreement under Article 23. Upon replenishment or furnishing of a fresh Performance Security, as the case may be, as aforesaid, the Contractor shall be entitled to an additional Cure Period of 30 (thirty) days for remedying the Contractor's Default, and in the event of the Contractor not curing its default within such Cure Period, the Authority shall be entitled to encash and appropriate such Performance Security as Damages, and to terminate this Agreement under Article 23.

7.4 Release of Performance Security

- (i) The Authority shall return the Performance Security to the Contractor within 60 (sixty) days of the expiry of the Maintenance Period or the Defects Liability Period, whichever is later, under this Agreement. Notwithstanding the aforesaid, the Parties agree that the Authority shall not be obliged to release the Performance Security until all Defects identified during the Defects Liability Period have been rectified.

- (ii) The Authority shall return the Additional Performance Security to the Contractor within 28 (twenty-eight) days from the date of issue of the Completion Certificate under Article 12 of this Agreement.
- (iii) The Authority shall be liable to pay interest @ 9% (nine percent) per annum for any delay in the return of Performance Security and Additional Performance Security, if any, beyond the period prescribed above for the period of delay.

7.5 Retention Money

- (i) From every payment for Works due to the Contractor under the provisions of Clause 19.5, the Authority shall deduct 6% (six percent) thereof as guarantee money for the performance of the obligations of the Contractor during the Construction Period (the "**RetentionMoney**") subject to the condition that the maximum amount of Retention Money shall not exceed 5% (five percent) of the Contract Price.
- (ii) Upon the occurrence of a Contractor's Default, the Authority shall, without prejudice to its other rights and remedies hereunder or in law, be entitled to appropriate the relevant amounts from the Retention Money as Damages for such Contractor's Default.
- (iii) Within 15 (fifteen) days of the date of issue of the Completion Certificate, the Authority shall refund the balance of Retention Money remaining with the Authority after adjusting the amounts appropriated under the provisions of Clause 7.5 (ii).
- (iv) The Parties agree that in the event of Termination of this Agreement, the Retention Money specified in Clause 7.5 shall be treated as if they are Performance Security and shall be reckoned as such for Termination Payment under Clause 23.6.

Article 8

Right of Way

8.1 The Site

The site of the Project Highway (the “**Site**”) shall comprise the site described in Schedule-A in respect of which the Right of Way shall be provided by the Authority to the Contractor. The Authority shall be responsible for:

- (a) acquiring and providing Right of Way on the Site under the alignment finalized by the Authority, free from all encroachments and encumbrances, and free access thereto for the execution of this Agreement; and
- (b) obtaining licenses and permits for environment clearance for the Project Highway.

8.2 Procurement of the Site

- (i) The Authority Representative, the Contractor, and the Authority’s Engineer shall, within 10 (ten) days of the date of this Agreement, inspect the Site and prepare a detailed memorandum containing an inventory of the Site including the vacant and unencumbered land, buildings, structures, road works, trees and any other immovable property on or attached to the Site (hereinafter referred to as the “**Handover Memorandum**”). Subject to the provisions of Clause 8.2 (iii), the Handover Memorandum shall have appended thereto an appendix (the “**Appendix**”) specifying in reasonable detail those parts of the Site to which vacant access and Right of Way has not been given to the Contractor along with details of hindrances in the Construction Zone. For the sake of clarity, the Handover Memorandum shall specify the parts of the Site where work can be executed. The signing of the Handover Memorandum, in three counterparts (each of which shall constitute an original), by the authorized representatives of the Authority, Contractor, and Authority’s Engineer shall be deemed to constitute valid evidence of giving the Right of Way to the Contractor for discharging its obligations under and under the provisions of this Agreement and for no other purpose whatsoever.
- (ii) Whenever the Authority is ready to hand over any part or parts of the Site included in the Appendix, it shall inform the Contractor, by notice, of the proposed date and time such of handover. The Authority Representative and the Contractor shall, on the date so notified, inspect the specified parts of the Site, and prepare a memorandum containing an inventory of the vacant and unencumbered land, buildings, structures, road works, trees, and any other immovable property on or attached to the Site so handed over. The signing of the memorandum, in three (3) counterparts (each of which shall constitute an original), by the authorized representatives of the Parties shall be deemed to constitute valid evidence of giving the relevant Right of Way to the Contractor.

If the contractor fails to join for site inspection or disputes the parts of the site available for work, the Authority's Engineer shall decide the parts of the site where work can be executed and notify both parties within 3 days of the proposed date of inspection. The parties agree that such notification of the Authority's Engineer as mentioned hereinabove shall be final and binding on the parties.

- (iii) The Authority shall provide the Right of Way to the Contractor in respect of all land included in the Appendix by the date specified in Schedule-A for those parts of the Site referred to therein, and in the event of delay for any reason other than Force Majeure or breach of this Agreement by the Contractor, it shall pay to the Contractor, Damages in a sum calculated under Clause 8.3. The Contractor agrees that it shall not be entitled to claim any other damages on account of any such delay by the Authority.
- (iv) Notwithstanding anything to the contrary contained in Clause 8.2, the Authority shall specify the parts of the Site, if any, for which Right of Way shall be provided to the Contractor on the dates specified in Schedule A. Such parts shall also be included in the Appendix prepared in pursuance of Clause 8.2 (i).
- (v) The Authority further acknowledges and agrees that before the Appointed Date, it shall have procured issuance of the statutory notification under Applicable Laws for vesting of all the land comprising the Project in the Authority and has taken possession of the area for Construction Zone for at least 90% (ninety percent) of the total length of the Project Highway. The Parties also acknowledge and agree that the conditions specified in Clause 8.2 (iii) shall not be modified or waived by either Party.
- (vi) For the avoidance of doubt, the Parties expressly agree that the Appendix shall in no event contain sections of the Project Highway the cumulative length of which exceeds 10% (ten percent) of the total length of the Project Highway.
- (vii) According to the signing of the Handover Memorandum under clause 8.2 (i), the Contractor shall submit to the Authority's Engineer, a monthly land possession report till the expiry of 180 (one hundred and eighty) days from the Appointed Date, in respect of those parts of the site to which vacant access and right of way was not given to the contractor and included in Appendix to the memorandum signed under clause 8.2 (i), duly specifying the part of the site, if any, for which the right of way is yet to be handed over.

8.3 Damages for the delay in handing over the Site

- (i) In the event, that the Right of Way to any part of the Site is not provided by the Authority on or before the date(s) specified in Clause 8.2 for any reason other than Force Majeure or breach of this Agreement by the Contractor, the Authority shall pay Damages to the Contractor a sum calculated under the following formula for and in respect of those parts of the Site to which the Right of Way has not been provided:

$$\text{Amount of Damages in Rs. per day per metre} = 0.05 \times C \times \frac{1}{L} \times \frac{1}{N}$$

Where,

C= the Contract Price;

L= length of the Project Highway in meters; and

N= Completion period in days(Appointed Date to Scheduled Completion Date)

In the event that any Damages are due and payable to the Contractor under the provisions of Clause 8.3 (i) for delay in providing the Right of Way, the Contractor shall, subject to the provisions of Clause 10.5, be entitled to Time Extension equal to the period for which the Damages have become due and payable under this Clause 8.3 (i), save and except that:

- (a) if any delays involve timeover laps, the overlaps shall not be additive; and
- (b) Such time Extension shall be restricted only to the Works that are affected by the delay in providing the Right of Way.

For the avoidance of doubt, the Parties expressly agree that the Damages specified hereunder and the Time Extension specified in Clause 10.5 shall be restricted only to the failure of the Authority to provide the Right of Way for and in respect of the "Construction Zone" which shall comprise the following components:

- Main in carriageway
 - Median (for 4 lane carriage way or more)
 - Paved and earthen shoulders
 - Area for Structures including ROBs/RUBs.
 - Safety measures include Road side Drains and Furniture.
 - A parallel working space for accommodating slopes/retaining structures etc.
- (ii) Notwithstanding any thing to the contrary contained in this Agreement, the Contractor expressly agrees that Works on all parts of the Site for which Right of Way of Construction Zone is granted on the Appointed Date, or concerning the parts of the Site provided in Schedule-A, no later than the date(s) specified therein, as the case may be, shall be completed before the Scheduled Completion Date and shall not qualify for any Time Extension under the provisions of Clause 8.3 (iii).
 - (iii) (a) Notwithstanding anything to the contrary contained in this Agreement, unless covered under the deemed de-scoping in terms of sub-clause 8.3 (iii) (b), the Authority may at any time withdraw any Works forming part of this Agreement, subject to such Works not exceeding an aggregate value, such value to be determined under Schedule-H, equal to 10 (ten) percent of the Contract Price.

(b) Provided that if any Works cannot be undertaken within the municipal limits of at own or any area falling in a reserved forest or wild life sanctuary or the stretches where vacant access and Right of Way could not be handed over, as the case may be, because the requisite clearances or approvals or affected land parcels for commencing construction of Works therein have not been given within 180 (one hundred and eighty) days of the Appointed date, the affected Works shall be deemed to be withdrawn under the provisions of this Clause 8.3.3. Such Works shall not be computed for the aforesaid ceiling of 10% (ten percent) hereunder.

(c) Provided further that in case such stretches (as mentioned in Sub-Clause (b) above) can be handed over to the Contractor before the expiry of the original Scheduled Construction Period of the Project Highway, and the Contractor agrees to take up the work, the same may be allowed to be executed by him with corresponding Extension of Time, subject to the condition that the Contractor shall not be entitled to raise any claims on account of prolongation costs in this behalf.

(iv) In the event of withdrawal of Works under Clause 8.3 (iii) (a), the Contract Price shall be reduced by an amount equal to the percent of the value of the works withdrawn as mentioned in the Table below and the Contractor shall not be entitled to any other compensation or Damages for the withdrawal of Works.

Value of the Works withdrawn	Percentage of value of works to be reduced from Contract Price
upto Rs. 100 Crore	90%
Morethan Rs. 100 Crore	Rs. 90 Crore plus 95% of the amount greater than Rs. 100 Crore

Provided that If any Works are withdrawn after the commencement of the Construction of such works, the Authority shall pay to the Contractor 110% (one hundred and ten percent) of the fair value of the work done, as assessed by the Authority Engineer.

The parties expressly agree that the value of the Works withdrawn shall be determined from the details available in Schedule H. If it is impossible to determine the value from Schedule H, then the value shall be determined under the provisions of Clause 13.2 (iii).

8.4 Site to be free from Encumbrances

Subject to the provisions of Clause 8.2, the Site shall be made available by the Authority to the Contractor pursuant hereto free from all Encumbrances and occupations and without the Contractor being required to make any payment to the Authority because of any costs, compensation, expenses, and charges for the acquisition and use of such Site for the duration of the Project Completion Schedule. For the avoidance of doubt, it is agreed that the existing rights of way, easements, privileges, liberties, and appurtenances to the Site shall not be deemed to be Encumbrances. It is further agreed that, unless otherwise specified in this Agreement,

the Contractor accepts and undertakes to bear all risks arising out of the inadequacy or physical condition of the Site.

8.5 Protection of Site from encroachments

On and after signing the memorandum and/or subsequent memorandum referred to in Clause 8.2, and until the issue of the Completion Certificate, the Contractor shall maintain a round-the-clock vigil over the Site and shall ensure and procure that no encroachment takes place thereon. During the Construction Period, the Contractor shall protect the Site from all occupations, encroachments, or Encumbrances, and shall not place or create nor permit any Sub-contractor or other person claiming through or under the Agreement to place or create any Encumbrance or security threat over all or any part of the Site or the Project Assets, or on any rights of the Contractor therein or under this Agreement, save and except as otherwise expressly set forth in this Agreement. In the event of any encroachment or occupation on any part of the Site, the Contractor shall report such encroachment or occupation forthwith to the Authority and undertake its removal at its own cost and expenses.

8.6 Special/temporary Right of Way

The Contractor shall bear all costs and charges for any special or temporary right of way required by it in connection with access to the Site. The Contractor shall obtain at its cost such facilities on or outside the Site as may be required by it for the Project Highway and the performance of its obligations under this Agreement.

8.7 Access to the Authority and the Authority's Engineer

- (i) The Right of Way given to the Contractor hereunder shall always be subject to the right of access of the Authority and the Authority's Engineer and their employees and agents for inspection, viewing, and exercise of their rights and performance of their obligations under this Agreement.
- (ii) The Contractor shall ensure, subject to all relevant safety procedures, that the Authority has unrestricted access to the Site during any emergency, as decided by the Authority's Engineer.

8.8 Geological and archaeological finds

It is expressly agreed that mining, geological, or archaeological rights do not form part of this Agreement with the Contractor for the Works, and the Contractor hereby acknowledges that it shall not have any mining rights or interest in the underlying minerals, fossils, antiquities, structures or other remnants or things either of particular geological or archaeological interest and that such rights, interest and property on or under the Site shall vest in and belong to the Authority or the concerned Government Instrumentality. The Contractor shall take all reasonable precautions to prevent its workmen or any other person from removing or damaging such interest or property and shall inform the Authority forthwith of the discovery thereof and comply with such instructions as the concerned Government Instrumentality may reasonably give for the removal of such property. For the avoidance of doubt, it is agreed that any

reasonable expenses incurred by the Contractor hereunder shall be reimbursed by the Authority. It is also agreed that the Authority shall procure that the instructions hereunder are issued by the concerned Government Instrumentality within a reasonable period.

Article 9

Utilities and Trees

9.1 Existing utilities and roads

Notwithstanding anything to the contrary contained herein, it shall be the responsibility of the Contractor to ensure that the respective entities owning the existing roads, right of way, level crossings, structures, or utilities on, under, or above the Site are enabled by it to keep them in continuous satisfactory use, if necessary, by providing suitable temporary diversions with the authority of the controlling body of that road, right of way or utility.

9.2 Shifting of obstructing utilities

The Contractor shall, under Applicable Laws and with the assistance of the Authority, undertake the work of shifting any utility (including electric lines, water pipes, gas pipelines, and telephone cables) to an appropriate location or alignment, if such utility or obstruction adversely affects the execution of Works or Maintenance of the Project Highway under this Agreement. The cost of such shifting, as per estimates prepared by the entity owning the utility and approved by the Authority, shall be reimbursed by the Authority to the Contractor. The scope of work of such shifting of Utilities shall be as indicated in Schedule-B-1. In the event of any delay of such shifting on the part of the contractor, no extension of time for completion of the project and no claims, in any manner, shall be admissible on this account against the Authority.

The work of shifting Utilities can be taken up by the Contractor at any time after the signing of the Agreement.

The scope of all utility shifting works shall be expressly indicated in Schedule B-1 (Annexure).

9.3 New utilities

- (i) The Contractor shall allow, subject to permission from the Authority and such conditions as the Authority may specify, access to, and use of the Site for laying telephone lines, water pipes, electricity lines/ cables, or other public utilities. Where such access or use causes any financial loss to the Contractor, it may require the user of the Site to pay compensation or damages as per Applicable Laws. For the avoidance of doubt, it is agreed that use of the Site under this Clause 9.3 shall not in any manner relieve the Contractor of its obligation to construct and maintain the Project Highway under this Agreement and any damage caused by such use shall be restored forthwith at the cost of the Authority.
 - (ii) The Authority may, by notice, require the Contractor to connect any adjoining road to the Project Highway, and the connecting portion thereof falling within the Site shall be constructed by the Contractor at the Authority's cost under Article 10.
-

- (iii) The Authority may by notice require the Contractor to connect, through a paved road, any adjoining service station, hotel, motel, or any other public facility or amenity to the Project Highway, whereupon the connecting portion thereof that falls within the Site shall be constructed by the Contractor on payment of the cost. The cost to be paid by the Authority to the Contractor shall be determined by the Authority's Engineer. For the avoidance of doubt, in the event such a road is to be constructed for the benefit of any entity, the Authority may require such entity to make an advance deposit with the Contractor or the Authority, as the case may be, of an amount equal to the estimated cost as determined by the Authority's Engineer and such advance shall be adjusted against the cost of construction as determined by the Authority's Engineer hereunder.
- (iv) In the event construction of any Works is affected by a new utility or works under taken under Clause 9.3, the Contractor shall be entitled to a reasonable Time Extension as determined by the Authority's Engineer.

9.4 Felling of trees

The Authority shall assist the Contractor in obtaining the Applicable Permits for the felling of trees in non-forest areas to be identified by the Authority for this purpose if, and only if, such trees cause a Material Adverse Effect on the construction or maintenance of the Project Highway. The Contractor shall fell these trees as per the Permits obtained. The cost of such felling shall be borne by the Authority and in the event of any delay in felling thereof for reasons beyond the control of the Contractor; it shall be excused for failure to perform any of its obligations hereunder if such failure is a direct consequence of delay in the felling of trees. The Parties hereto agree that the felled trees shall be deemed to be owned by the Authority and shall be disposed of in such manner and subject to such conditions as the Authority may in its sole discretion deem appropriate. For the avoidance of doubt, the Parties agree that if any felling of trees hereunder is in a forest area, the Applicable Permit thereof shall be procured by the Authority within the time specified in the Agreement.

9.5 Dismantling of structures

The Contractor shall at its own cost dismantle the structures in the acquired lands including those on patta lands, Abadi lands, assigned lands, etc. the compensation for which, was paid by the Authority to the land owners and the lands were handed over to the Contractor as per Schedule B-1. The Contractor shall, at its own cost, dispose of the dismantled material in its sole discretion as deemed appropriate, while complying with all environmental guidelines and regulations and clear the Site for undertaking construction. In the event of any delay in dismantling of structures thereof for reasons beyond the control of the Contractor, the Contractor shall be entitled to Damages in a sum calculated under the formula specified in Clause 8.3 (i) for the period of delay, and to the Time Extension under Clause 10.5 for and in respect of the part(s) of the Works affected by such delay; provided that if the delays involve any time overlaps, the overlaps shall not be additive.

9.6 Development Period

The Contractor may commence pre-construction activities like utility shifting, boundary wall construction, or any other activity assigned to the Contractor by the Authority to enable construction of the Project Highway immediately after signing of the Agreement, to the extent that such work is ready for execution. The Parties agree that these works may be taken up and completed to the extent feasible by the Contractor, before declaration of the Appointed Date, but no claim against the Authority for delay shall survive during this period and that the undertaking of these works by the Contractor shall not count towards the Scheduled Construction Period of the project which starts counting only from the Appointed Date. No construction activity of the Project Highway shall be undertaken during the development period.

Article 10

Design and Construction of the Project Highway

10.1

- (i) Within 20 (twenty) days of the Appointed Date, the Contractor shall:
 - (a) appoint its representative, duly authorized to deal with the Authority in respect of all matters under or arising out of or relating to this Agreement;
 - (b) appoint a design director (the “**Design Director**”) who will head the Contractor’s design unit and shall be responsible for surveys, investigations, collection of data, and preparation of preliminary and detailed designs;
 - (c) undertake and perform all such acts, deeds, and things as may be necessary or required before commencement of Works under and under this Agreement, the Applicable Laws, and Applicable Permits; and
 - (d) make arrangements for the quarrying of materials needed for the Project Highway under and under the Applicable Laws and Applicable Permits.
- (ii) The Authority shall, appoint an engineer (the “**Authority’s Engineer**”) before the Appointed Date to discharge the functions and duties specified in this Agreement, and shall notify the Contractor of the name, address, and the date of appointment of the Authority’s Engineer forthwith.
- (iii) Within 30 (thirty) days of the Appointed Date, the Contractor shall submit to the Authority and the Authority’s Engineer a program (the “**Programme**”) for the Works, developed using networking techniques, for review and consent of the Engineer, giving the following details:
 - (a) Part I: Contractor’s organization for the Project, the general methods and arrangements for design and construction, environmental management plan, Quality Assurance Plan including design quality plan, traffic management and safety plan covering safety of users and workers during construction (including use of ‘ROBOTS’ for diversion and control of traffic), Contractor’s key personnel and equipment.
 - (b) Part II: Programme for completion of all stages of construction given in Schedule-H and Project Milestones of the Works as specified in the Project Completion Schedule outlined in Schedule-J. The Programme shall include:
 - i. the order in which the Contractor intends to carry out the Works, including the anticipated timing of design and stages of Works;
 - ii. the periods for reviews under Clause 10.2;

- iii. the sequence and timing of inspections and tests specified in this Agreement; and
- iv. the particulars for the pre-construction reviews and any other submissions, approvals, and consents specified in the Agreement.

The Contractor shall submit a revised Programme whenever the previous Programme is inconsistent with the actual progress or with the Contractor's obligations.

(c) **Part III:** Monthly cash flow forecast.

- (iv) The Contractor shall compute, based on the Drawings prepared under Clause 10.2 (iv), and provide to the Authority's Engineer, the length, area, and numbers, as the case may be, in respect of the various items of work specified in Schedule-H and comprising the Scope of the Project. The Parties expressly agree that these details shall form the basis for estimating the interim payments for the Works under the provisions of Clause 19.3. For the avoidance of doubt, the sum of payments to be computed in respect of all the items of work shall not exceed the Contract Price, as may be adjusted under the provisions of this Agreement.
- (v) The Contractor shall appoint a safety consultant (**the "Safety Consultant"**) to carry out a safety audit at the design stage of the Project Highway under the Applicable Laws and Good Industry Practice. The Safety Consultant shall be appointed after proposing to the Authority a panel of three (3) names of qualified and experienced firms from which the Authority may choose one (1) to be the Safety Consultant. Provided, however, that if the panel is not acceptable to the Authority and the reasons for the same are furnished to the Contractor, the Contractor shall propose to the Authority a revised panel of three (3) names from **the firms impaneled as safety consultants by the Ministry of Road Transport and Highways for obtaining the consent of the Authority**. The Contractor shall also obtain the consent of the Authority for the key personnel of the Safety Consultant who shall have adequate experience and qualifications in safety audit of the highway projects. The Authority shall, within 15 (fifteen) days of receiving a proposal from the Contractor hereunder, convey its decision, with reasons, to the Contractor, and if no such decision is conveyed within the said period, the Contractor may proceed with engaging the Safety Consultant.
- (vi) The safety audit under Clause 10.1 (v) shall be carried out by the Safety Consultant concerning all such design details that have a bearing on the safety of Users as well as pedestrians and animals involved in or associated with accidents. The recommendations of the Safety Consultant shall be incorporated in the design of the Project Highway and the Contractor shall forward to the Authority's Engineer a certificate to this effect together with the recommendations of the Safety Consultant. If any works required by the Safety Consultant shall fall beyond the scope of Schedule B, Schedule-C, or Schedule-D, the Contractor shall make a report thereon and seek the instructions of the Authority for Change in Scope. For the avoidance of doubt, the Safety Consultant to be engaged by the Contractor shall be independent of the design and implementation team of the Contractor.

10.2 Design and Drawings

- (i) Design and Drawings shall be developed in conformity with the Specifications and Standards outlined in Schedule D. In the event, that the Contractor requires any relaxation in design standards due to restricted Right of Way in any section, the alternative design criteria for such section shall be provided for review and approval of the Authority's Engineer.
- (ii) The Contractor shall appoint a proof check consultant (the "**Proof Consultant**") as an independent third-party Design Audit/Proof Consultant from a reputed engineering institution of IITs/NITs. The Contractor shall submit to the Authority the details of the appointed proof check consultant having adequate experience and qualifications in highways and bridges respectively. The Authority shall, within 15 (fifteen) days of receiving a proposal from the Contractor hereunder, convey its comments, with reasons, to the Contractor, and if no such comment is conveyed within the said period, the Contractor may proceed with engaging in the Proof Consultant. The Contractor shall ensure that all design Audits and proof Checking by the Proof Consultant shall not be below the rank of the Head of the Department of the institution.
- (iii) The Proof Consultant shall:
 - (a) evolve a systems approach with the Design Director to minimize the time required for final designs and construction drawings; and
 - (b) Proof-check the detailed calculations, drawings, and designs, which have been approved by the Design Director.
- (iv) In respect of the Contractor's obligations concerning the design and Drawings of the Project Highway, as outlined in Schedule-I, the following shall apply:
 - (a) The Contractor shall prepare and submit, with reasonable promptness and in such sequence as is consistent with the Project Completion Schedule, three (3) copies of each of the design and Drawings, duly certified by the Proof Consultant, to the Authority's Engineer for its approval. Provided, however, that in respect of Major Bridges and Structures, the Authority's Engineer may require additional drawings for approval under Good Industry Practice.
 - (b) by submitting the Drawings for review and approval to the Authority's Engineer, the Contractor shall be deemed to have represented that it has determined and verified that the design and engineering, including field construction criteria related thereto, conform with the Scope of the Project, the Specifications and Standards and the Applicable Laws;

- (c) within 15 (fifteen) days of the receipt of the Drawings, the Authority's Engineer shall review the same and convey its approval/observations to the Contractor with particular reference to their conformity or otherwise with the Scope of the Project and the Specifications and Standards .Provided, however, that in case of a major bridge or structure, the aforesaid period of 15 (fifteen) days may be extended up to 30 (thirty) days;
 - (d) if the aforesaid observations of the Authority's Engineer indicate that the Drawings are not in conformity with the Scope of the Project or the Specifications and Standards, such Drawings shall be revised by the Contractor in conformity with the provisions of this Agreement and resubmitted to the Authority's Engineer for review and approval. The Authority's Engineer shall give its observations, if any, within 10 (ten) days of receipt of the revised Drawings. In the event the Contractor fails to revise and resubmit such Drawings to the Authority's Engineer for review/approval as aforesaid, the Authority's Engineer may withhold the payment for the affected works under the provisions of Clause 19.5 (iv). If the Contractor disputes any decision, direction, or determination of the Authority's Engineer hereunder, the Dispute shall be resolved under the Dispute Resolution Procedure;
 - (e) no review/approval and/or observation of the Authority's Engineer and/or its failure to review/approval and/or convey its observations on any Drawings shall relieve the Contractor of its obligations and liabilities under this Agreement in any manner nor shall the Authority's Engineer or the Authority be liable for the same in any manner; and if errors, omissions, ambiguities, inconsistencies, inadequacies or other Defects are found in the Drawings, they and the construction works shall be corrected at the Contractor's cost, notwithstanding any approval under this Article 10;
 - (f) the Contractor shall be responsible for delays in submitting the Drawing as outlined in Schedule-I caused because of delays in surveys and field investigations, and shall not be entitled to seek any relief in that regard from the Authority; and
 - (g) the Contractor warrants that its designers, including any third parties engaged by it, shall have the required experience and capability under Good Industry Practice and it shall indemnify the Authority against any damage, expense, liability, loss, or claim, which the Authority might incur, sustain or be subject to arising from any breach of the Contractor's design responsibility and/or warranty set out in this Clause.
 - (h) the Contractor shall ensure that all the designs and drawings shall be approved by the Authority's Engineer within 90 days (ninety) from the Appointed Date.
- (v) Any cost or delay in construction arising from review/approval by the Authority's Engineer shall be borne by the Contractor.

- (vi) Works shall be executed under the Drawings provided by the Contractor under the provisions of Clause 10.2 and the approval of the Authority's Engineer thereon as communicated according to the provisions of Subclause(c) & (d) of Clause 10.2 (iv). Such Drawings shall not be amended or altered without prior written notice to the Authority's Engineer. If a Party becomes aware of an error or defect of a technical nature in the design or Drawings, that Party shall promptly give notice to the other Party of such error or defect.
- (vii) Within 90 (ninety)days of the Project Completion Date, the Contractor shall furnish to the Authority and the Authority's Engineer a complete set of as-built Drawings, in 2 (two) hard copies and inmicrofilm formor such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered, and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities.

10.3 Construction of the Project Highway

- (i) TheContractor shall construct the Project Highway as specified in Schedule- B and Schedule-C, and in conformity with the Specifications and Standards outlined in Schedule- D. The Contractor shall be responsible for the correct positioning of all parts of the Works and shall rectify any error in the positions, levels, dimensions, or alignment of the Works. The Actual day/date of completion as per schedule J from the Appointed Date shall be the scheduled completion date (the "Scheduled Completion Date") and the Contractor agrees and undertakes that the construction shall be completed on or before the Scheduled Completion Date, including any extension thereof.
- (ii) The Contractor shall construct the Project Highway under the Project Completion Schedule outlined in Schedule-J. In the event that the Contractor fails to achieve any Project Milestone or the Scheduled Completion Date within a period of 30(thirty)days from the date set forth in Schedule-J, unless such failure has occurred due to Force Majeureor for reasons solely attributable to the Authority, it shall pay Damages to the Authority of a sum calculated at the rate of 0.05% (zero point zero five percent) of the Contract Price for delay of each day reckoned from the date specified in Schedule -J and until such Project Milestone is achieved or the Project Highway is completed; provided that if the period for any or all Project Milestones or the Scheduled Completion Date is extended in accordance with the provisions of this Agreement, the dates set forth in Schedule-J shall be deemed to be modified accordingly and the provisions of this Agreement shall apply as if Schedule-J has been amended as above; provided further that in the event the Project Highway is completed within or before the Scheduled Completion Date including any Time Extension, applicable for that work or section, the Damages paid under this Clause 10.3 (ii) shall be refunded by the Authority to the Contractor, but withoutany interest thereon.

The Parties agree that for determining achievement or delays in completion of the Project Milestones or the Project on the due date, the works affected due to delay in providing the site for which time extension has been granted beyond the Scheduled Completion Date will be excluded. For example on the due date to achieve Project Milestone-I (i.e., Stage Payments of 10% (ten percent) of Contract Price on 180th(one hundred and eighty) day from the Appointed Date), if 5% (five percent) of the project length corresponding to the Project Milestone-I is not handed over or lately handed over resulting in the extension of completion of this 5% (five percent) length beyond Scheduled Completion Date, Stage Payment of 10% X 0.95=9.5% only is to be achieved by 180th (one hundred and eighty) day.

For the avoidance of doubt, it is agreed that recovery of Damages under this Clause 10.3(ii) shall be without prejudice to the rights of the Authority under this Agreement including the right of Termination thereof. The Parties further agree that Time Extension hereunder shall only be reckoned for and in respect of the affected Works as specified in Clause 10.5 (ii).

- (iii) The Authority shall notify the Contractor of its decision to impose Damages in pursuance with the provisions of Clause 10.3. Provided that no deduction on account of Damages shall be effected by the Authority without notifying the Contractor of its decision to impose the Damages, and taking into consideration the representation, if any, made by the Contractor within 20 (twenty) days of such notice. The Parties expressly agree that the total amount of Damages under Clause 10.3 (ii) shall not exceed 10% (ten percent) of the Contract Price. If the damages exceed 10% (ten percent) of the Contract Price, the Contractor shall be deemed to be in default of this agreement having no cure and the Authority shall be entitled to terminate this Agreement by issuing a Termination Notice under the provisions of Clause 23.1 (ii).
- (iv) If the Contractor fails to achieve the Project Completion within a period of 90 (ninety) days from the Schedule Completion Date outlined in Schedule-J unless such failure has occurred due to Force Majeure or for reasons solely attributable to the Authority, the contractor shall be deemed to be ineligible for bidding any future projects of the Authority, both as the sole party or as one of the parties of Joint Venture/ Consortium during the period from Scheduled Completion Date to issuance of Completion Certificate. This restriction is applicable if the contract value of the delayed project is not less than Rs. 300 Crore.

10.4 Maintenance during the Construction Period

- (i) During the Construction Period, the Contractor shall maintain, at its cost, the existing lane(s) of the Project Highway so that the traffic worthiness and safety thereof are at no time materially inferior as compared to their condition on Appointed Date, and shall undertake the necessary repair and maintenance works for this purpose; provided that the Contractor may, at its cost, interrupt and divert the flow of traffic if such interruption and diversion is necessary for the efficient progress of Works and conforms to Good Industry Practice; provided further that such interruption and

diversion shall be undertaken by the Contractor only with the prior written approval of the Authority's Engineer which approval shall not be unreasonably withheld. For the avoidance of doubt, it is agreed that the Contractor shall at all times be responsible for ensuring the safe operation of the Project Highway. It is further agreed that in the event the Project includes the construction of a bypass or tunnel and realignment of the existing carriageway, the Contractor shall maintain the existing highway in such sections until the new Works are open to traffic.

- (ii) Notwithstanding anything to the contrary contained in this Agreement, in the event of default by the Contractor in discharging the obligations specified in Clause 10.4 (i) above, the Authority shall get these maintenance works completed in the manner recommended by the Authority's Engineer to avoid public inconvenience at the risk and cost of the Contractor to keep the road in traffic worthy condition.

10.5 Extension of time for completion

- (i) Without prejudice to any other provision of this Agreement for and in respect of extension of time, the Contractor shall be entitled to extension of time in the Project Completion Schedule (the "**Time Extension**") to the extent that completion of any Project Milestone is or will be delayed by any of the following, namely:
 - (a) delay in providing the Right of Way of Construction Zone, environmental clearances, or approval of railway authorities, specified in Clause 3.1 (iv);
 - (b) Change of Scope(unless an adjustment to the Scheduled Completion Date has been agreed under Article 13);
 - (c) occurrence of a Force Majeure Event;
 - (d) any delay, impediment, or prevention caused by or attributable to the Authority, the Authority's personnel, or the Authority's other contractors on the Site; and
 - (e) any other cause or delay which entitles the Contractor to Time Extension under the provisions of this Agreement.
- (ii) The Contractor shall, no later than 15 (fifteen) business days from the occurrence of an event or circumstance specified in Clause 10.5 (i), inform the Authority's Engineer by notice in writing, with a copy to the Authority, stating in reasonable detail with supporting particulars, the event or circumstances giving rise to the claim for Time Extension under the provisions of this Agreement. Provided that the period of 15 (fifteen) business days shall be calculated from the date on which the Contractor became aware, or should have become aware, of the occurrence of such an event or circumstance.

Provided further that notwithstanding anything to the contrary contained in this Agreement, Time Extension shall be due and applicable only for the Works which are affected by the aforesaid events or circumstances and shall not in any manner affect the Project Completion Schedule for and in respect of the Works which are not affected hereunder.

- (iii) On the failure of the Contractor to issue to the Authority's Engineer a notice under the provisions of Clause 10.5 (ii) within the time specified therein, the Contractor shall not be entitled to any Time Extension and shall forfeit its right for any such claims in the future. For the avoidance of doubt, in the event of failure of the Contractor to issue notice as specified in clause 10.5 (iii), the Authority shall be discharged from all liability in connection with the claim.
- (iv) The Authority's Engineer shall, on receipt of the claim under the provisions of Clause 10.5 (ii), examine the claim expeditiously within the time frame specified herein. In the event the Authority's Engineer requires any clarifications to examine the claim, the Authority's Engineer shall seek the same within 15 (fifteen) days from the date of receiving the claim. The Contractor shall, on receipt of the communication of the Authority's Engineer requesting clarification, furnish the same to the Authority's Engineer within 10 (ten) days thereof. The Authority's Engineer shall, within a period of 30 (thirty) days from the date of receipt of such clarifications, forward in writing to the Contractor its determination of Time Extension.

Provided that when determining each extension of time under Clause 10.5, the Authority's Engineer shall review previous determinations and may increase, but shall not decrease the total Time Extension.

- (v) If the event or circumstance giving rise to the notice has a continuing effect:
 - (a) a fully detailed claim shall be considered interim;
 - (b) the Contractor shall, no later than 10 (ten) days after the close of each month, send further interim claims specifying the accumulated delay, the extension of time claimed, and such further particulars as the Authority's Engineer may reasonably require; and
 - (c) the Contractor shall send a final claim within 30 (thirty) days after the effect of the event or the circumstance ceases.

Upon receipt of the claim hereunder, the Authority's Engineer shall examine the same under the provisions of Clause 10.5 (iv) within 30 (thirty) days of the receipt thereof.

10.6 Incomplete Works

In the event the Contractor fails to complete the Works under the Project Completion Schedule, including any Time Extension granted under this Agreement, the Contractor shall endeavor to complete the balance work expeditiously and shall pay Damages to the Authority under the provisions of Clause 10.3(ii) for delay of each day until the Works are completed under the provisions of this Agreement. Recovery of Damages under this Clause shall be without prejudice to the rights of the Authority under this Agreement including the right to termination under Clause 23.1.

10.7 Maintenance Manual

No later than 60 (sixty) days before the Project Completion Date, the Contractor shall, in consultation with the Authority's Engineer, evolve a maintenance manual (the "**Maintenance Manual**") for the regular and preventive maintenance of the Project Highway in conformity with the Specifications and Standards, safety requirements and Good Industry Practice, and shall provide 5 (five) copies thereof to the Authority's Engineer. The Authority's Engineer shall review the Maintenance Manual within 15 (fifteen) days of its receipt and communicate its comments to the Contractor for necessary modifications, if any.

10.8 As-Built Records

The Contractor shall prepare, and keep up-to-date, a complete set of as-built records of the execution of the Works, showing the exact as-built locations, sizes, and details on the Works as executed with cross-references to all relevant specifications and data sheets. These records shall be kept on the Site and shall be used exclusively for this Sub-Clause 10.8. The Contractor shall provide 2 (two) copies of as-built records to the Authority before the commencement of the Tests on Completion.

10.9 Contractor's Use of Authority's Documents

Intellectual property in the Authority's requirements Specifications and Standards and all other documents and materials issued by the Authority or the Authority's Representative to the Contractor shall (as between the parties) remain the property of the Authority. The Contractor may, at its cost, copy, use, and communicate any such documents for the Contract. They shall not, without the consent of the Authority, be used, copied, or communicated to a third party by the Contractor, except as necessary for the Works under the Agreement.

Article 11

Quality Assurance, Monitoring and Supervision

11.1 Quality of Materials and workmanship

The Contractor shall ensure that the Construction, Materials, and workmanship are under the requirements specified in this Agreement, Specifications and Standards, and Good Industry Practice.

11.2 Quality control system

- (i) The Contractor shall establish a quality control mechanism to ensure compliance with the provisions of this Agreement (the “**Quality Assurance Plan**” or “**QAP**”).
- (ii) The Contractor shall, within 30 (thirty) days of the Appointed Date, submit to the Authority’s Engineer its Quality Assurance Plan which shall include the following:
 - (a) organization, duties and responsibilities, procedures, inspections and documentation;
 - (b) quality control mechanism including sampling and testing of Materials, test frequencies, standards, acceptance criteria, testing facilities, reporting, recording, and interpretation of test results, approvals, checklist for site activities, and proforma for testing and calibration under the Specifications for Road and Bridge Works issued by MORTH, relevant IRC specifications, and Good Industry Practice; and
 - (c) internal quality audit system.

The Authority’s Engineer shall convey its approval to the Contractor within 21 (twenty-one) days of receipt of the QAP stating the modifications, if any, required, and the Contractor shall incorporate those in the QAP to the extent required for conforming with the provisions of this Clause 11.2.

- (iii) The Contractor shall procure all documents, apparatus and instruments, fuel, consumables, water, electricity, labor, Materials, samples, and qualified personnel as are necessary for examining and testing the Project Assets and workmanship under the Quality Assurance Plan.
- (iv) The cost of testing of Construction, Materials, and workmanship under Article 11 shall be borne by the Contractor.

11.3 Methodology

The Contractor shall, at least 15 (fifteen) days before the commencement of the construction, submit to the Authority’s Engineer for review and consent the methodology proposed to be adopted for executing the Works, giving details of equipment to be deployed, traffic management, and measures for ensuring safety.

The Authority’s Engineer shall complete the review and convey its consent to the

Contractor within a period of 10(ten)days from the date of receipt of the proposed methodology from the Contractor.

11.4 Inspection and technical audit by the Authority

The Authority or any representative authorized by the Authority on this behalf may inspect and review the progress and quality of the construction of Project Highway and issue appropriate directions to the Authority's Engineer and the Contractor for taking remedial action in the event the Works are not under the provisions of this Agreement.

11.5 External technical audit

- (i) At any time during construction, the Authority may appoint an external technical auditor to conduct an audit of the quality of the Works. The Auditor in the presence of the representatives of the Contractor and the Authority's Engineer shall carry out the tests and/ or collect samples for testing in the laboratory. The timing, the testing equipment, and the sample size of this audit shall be as decided by the Authority. The findings of the audit, to the extent accepted by the Authority, shall be notified to the Contractor and the Authority's Engineer for taking remedial action under this Agreement.
- (ii) After completion of the remedial measures by the Contractor, the Auditor shall undertake a closure audit and this process will continue till the remedial measures have brought the works into compliance with the Specifications and Standards. The Contractor shall provide all assistance as may be required by the auditor in the conduct of its audit hereunder. Notwithstanding anything contained in Clause 11.5, the external technical audit shall not affect any obligations of the Contractor or the Authority's Engineer under this Agreement.

11.6 Inspection of construction records

The Authority shall have the right to inspect the records of the Contractor relating to the Works.

11.7 Monthly progress reports

During the Construction Period, the Contractor shall, no later than 10 (ten) days after the close of each month, furnish to the Authority and the Authority's Engineer a monthly report on the progress of the Works and shall promptly give such other relevant information as may be required by the Authority's Engineer.

The Contractor agrees that reporting under Clause 11.7 shall continue until the date of the completion of the Works. Each report shall include:

- (a) an executive summary;
- (b) charts showing the status of the Contractor's documents, construction and manufacturing and environmental works;

- (c) details of work sub contracted and the performance of Sub-contractors;
- (d) for the construction of each main part of the Works, the extent of progress (both quantity and percentage of the whole), the actual or expected dates of commencement, the anticipated completion date of the activity, Contractor's inspections and tests;
- (e) records of manpower and Contractor's equipment on the Site;
- (f) copies for that month of quality assurance documents, test results, and certificates;
- (g) safety statistics, accident data collection including details of any hazardous incidents and activities relating to environmental aspects and public relations;
- (h) comparisons of actual and planned progress, with details of any aspects which may jeopardize the completion under the Agreement, and the measures being (or to be) adopted to overcome such aspects;
- (i) details of any unresolved disputes or claims, concerning the Project;
- (j) details of any revision to the cash flow estimate, together with a copy of the revised cash flow estimate;
- (k) status of various Applicable Permits and compliance with conditions therein;
- (l) details of various royalty payments and insurances required to be taken by the Contractor; and
- (m) such other reports as may be required by the Authority to enable the Authority to comply with its obligations under the other Project contracts.
- (n) details of defects by the Authority;
- (o) change in emission of any sewage or effluent of any nature whatsoever, whether qualitatively or quantitatively;
- (p) any Material Adverse Effect;
- (q) declaration towards compliance with Applicable Laws including but not limited to environmental and labor legislation;
- (r) declaration specifying compliance with all Manuals provided to the Contractor; and
- (s) any change in the flow of traffic in the existing Project Highway.

11.8 Inspection

- (i) The Authority's Engineer and its authorized representative shall at all reasonable times:
 - (a) have full access to all parts of the Site and to all places from which natural Materials are being obtained for use in the Works; and

- (b) during production, manufacture, and construction at the Site and the place of production, be entitled to examine, inspect, measure, and test the Materials and workmanship, and to check the progress of the manufacture of Materials.
- (ii) The Contractor shall give the Authority's Engineer and its authorized agents access, to facilities and safety equipment for carrying out their obligations under this Agreement.
- (iii) The Authority's Engineer shall submit a monthly inspection report (the "**Inspection Report**") to the Authority and the Contractor bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. For the avoidance of doubt, such inspection or submission of the Inspection Report by the Authority's Engineer shall not relieve or absolve the Contractor of its obligations and liabilities under this Agreement in any manner whatsoever.

11.9 Samples

The Contractor shall submit the following samples of Materials and relevant information to the Authority's Engineer for pre-construction review:

- (a) manufacturer's test reports and standard samples of manufactured Materials; and
- (b) samples of such other Materials as the Authority's Engineer may require.

11.10 Tests

- (i) For determining that the Works conform to the Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out or cause to be carried out tests, at such time and frequency and in such manner as specified in this Agreement, and in accordance with Good Industry Practice for quality assurance. The test checks by the Authority's Engineer shall comprise at least 50% (fifty percent) of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (ii) In the event that the results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Contractor shall carry out remedial measures and furnish a report to the Authority's Engineer on this behalf. The Authority's Engineer shall require the Contractor to carry out or cause to be carried out tests to determine that such remedial measures have brought the Works into compliance with the Specifications and Standards, and the procedure shall be repeated until such Works conform to the Specifications and Standards. For the avoidance of doubt, the cost of such tests and remedial measures in pursuance thereof shall be solely borne by the Contractor.

11.11 Examination of work before covering up

In respect of the work which the Authority's Engineer is entitled to examine, inspect, measure, and/or test before it is covered up or put out of view or any part of the work

is placed thereon, the Contractor shall give notice to the Authority's Engineer whenever any such work is ready and before it is covered up. The Authority's Engineer shall then either carry out the examination, inspection, or testing without unreasonable delay or promptly give notice to the Contractor that the Authority's Engineer is not required to do so. Provided, however, that if any work is continuous where it is not possible or prudent to keep it uncovered or incomplete, the Contractor shall notify the schedule of carrying out such work to give sufficient opportunity, not being less than 3 (three) business days' notice, to the Authority's Engineer to conduct its inspection, measurement or test while the work is continuing. Provided further that in the event the Contractor receives no response from the Authority's Engineer within a period of 3 (three) business days from the date on which the Contractor's notice hereunder is delivered to the Authority's Engineer, the Contractor shall be entitled to assume that the Authority's Engineer would not undertake the said inspection.

11.12 Rejection

If, as a result of an examination, inspection, measurement, or testing, any Plant, Materials, design, or workmanship is found to be defective or otherwise not under the provisions of this Agreement, the Authority's Engineer shall reject the Plant, Materials, design or workmanship by giving notice to the Contractor, with reasons. The Contractor shall then promptly make good the Defect and ensure that the rejected item complies with the requirements of this Agreement.

If the Authority's Engineer requires the Plant, Materials, design, or workmanship to be retested, the tests shall be repeated under the same terms and conditions, as applicable in each case. If the rejection and retesting cause the Authority to incur any additional costs, such cost shall be recoverable by the Authority from the Contractor; and may be deducted by the Authority from any monies due to be paid to the Contractor.

11.13 Remedial work

- (i) Notwithstanding any previous test or certification, the Authority's Engineer may instruct the Contractor to:
 - (a) remove from the Site and replace any Plant or Materials which are not under the provisions of this Agreement;
 - (b) remove and re-execute any work that is not under the provisions of this Agreement and the Specification and Standards; and
 - (c) execute any work that is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event, or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (ii) If the Contractor fails to comply with the instructions issued by the Authority's Engineer under Clause 11.13(i), within the time specified in the Authority's

Engineer's notice or as mutually agreed, the Authority's Engineer may advise the Authority to have the work executed by another agency. The cost so incurred by the Authority for undertaking such work shall, without prejudice to the rights of the Authority to recover Damages under the provisions of this Agreement, be recoverable from the Contractor and may be deducted by the Authority from any monies due to be paid to the Contractor.

11.14 Delays during construction

Without prejudice to the provisions of Clause 10.3 (ii), in the event the Contractor does not achieve any of the Project Milestones or the Authority's Engineer shall have reasonably determined that the rate of progress of Works is such that Completion of the Project Highway is not likely to be achieved by the end of the Scheduled Completion Date, it shall notify the same to the Contractor, and the Contractor shall, within 15 (fifteen) days of such notice, by a communication inform the Authority's Engineer in reasonable detail about the steps it proposes to take to expedite progress and the period within which it shall achieve the Project Completion Date.

11.15 Quality control records and Documents

The Contractor shall hand over a copy of all its quality control records and documents to the Authority's Engineer before the Completion Certificate is issued under Clause 12.2 . The Contractor shall submit Road Signage Plans to the Authority Engineer for approval at least 6 (six) months before the expected completion of Project Highway.

11.16 Video recording

During the Construction Period, the Contractor shall provide to the Authority for every calendar quarter, a video recording, which will be compiled into a 3 (three)-hour compact disc or digital video disc, as the case may be, covering the status and progress of Works in that quarter. The video recording shall be provided to the Authority no later than 15 (fifteen) days after the close of each quarter after the Appointed Date.

11.17 Suspension of Unsafe Construction Works

- (i) Upon recommendation of the Authority's Engineer to this effect, the Authority may by notice require the Contractor to suspend forthwith the whole or any part of the Works if, in the reasonable opinion of the Authority's Engineer, such work threatens the safety of the Users and pedestrians.
- (ii) The Contractor shall, under the notice under Clause 11.17 (i), suspend the Works or any part thereof for such time and in such manner as may be specified by the Authority and thereupon carry out remedial measures to secure the safety of suspended works, the Users and pedestrians. The Contractor may by notice require the Authority's Engineer to inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked. Upon receiving the recommendations of the Authority's Engineer, the Authority shall either revoke such suspension or instruct the Contractor to carry out such other and further remedial measures as may be necessary in the reasonable opinion of the

Authority, and the procedure outlined in this Clause 11.17 shall be repeated until the suspension hereunder is revoked.

- (iii) Subject to the provisions of Clause 21.6, all reasonable costs incurred for maintaining and protecting the Works or part thereof during the period of suspension (the “**Preservation Costs**”), shall be borne by the Contractor; provided that if the suspension has occurred as a result of any breach of this Agreement by the Authority, the Preservation Costs shall be borne by the Authority.
- (iv) If suspension of Works is for reasons not attributable to the Contractor, the Authority’s Engineer shall determine any Time Extension to which the Contractor is reasonably entitled.

11.18 Staff and Labour

- (i) Engagement of Staff and Labor
 - (a) The Contractor shall make its arrangements for the engagement of all personnel and labor, local or otherwise, and for their payment, housing, feeding, and transport.
 - (b) The Contractor has verified/ shall verify the identity and address of all its employees and officials related to the Works by collecting necessary documentary proof.
 - (c) The Contractor shall seek a self-declaration from its employees that they have not been convicted of any criminal offense by any court and if any criminal proceedings/charge sheets have been pending/filed against them. The Contractor shall not employ persons with a criminal track record on the project. In cases where it comes to notice later that the employee concerned has concealed any such fact in his self-declaration or commits a criminal offense during his employment, the Contractor shall remove such person from the project
 - (d) Deleted.
 - (e) The employees and personnel of the Contractor shall work under the supervision, control, and direction of the Contractor and the Contractor shall be solely responsible for all negotiations with its employees and personnel relating to their salaries and benefits, and shall be responsible for assessments and monitoring of performance and for all disciplinary matters. All employees/personnel and executives engaged by the Contractor shall be in sole employment of the Contractor and the Contractor shall be solely responsible for their salaries, wages, statutory payments, etc, and under no circumstances the personnel shall be deemed to be the employees of the Authority. Under no circumstances the Authority shall be liable for any

payment or claim or compensation of any nature to the employees and personnel of the Contractor.

(ii) Returns of Labor

- (a) The Contractor shall deliver to the Authority a detailed return in such form and at such intervals as the Authority may prescribe, showing the details including names, payment details, and terms of appointment of the several classes of labor employed by the Contractor from time to time for the Works. The Contractor shall, in its returns certify that all dues of the workers or labor have been fully paid.
- (b) The Authority is entitled to witness labor payments made or to be made by the Contractor. If the Contractor defaults in its obligations for making any payments under the labor laws, the Employer may make the relevant payments. Any sum equal to any amount paid by the Employer under this Sub-Sub- Clause 9.2 shall be immediately due as a debt from the Contractor to the Employer and until payment/ set off shall carry interest at 18% per annum. For this purpose, it is agreed between the parties that debt due aforesaid shall be set off immediately out the running account bills of the Contractor under this Agreement.

(iii) Persons in the Service of Others

The Contractor shall not recruit, or attempt to recruit from amongst persons in the service of the Authority.

(iv) Labor Laws

- (a) The Contractor shall obtain all relevant labor registrations and comply with all relevant labor laws applying to its employees, and shall duly pay them and afford to them all their legal rights.
- (b) The Contractor shall make all deductions of tax at source and all contributions to the Payment of Gratuity, Provident Fund (including Employees' contribution), and Employees' State Insurance Scheme as may be required by Applicable Laws and deposit the aforesaid contributed amount with the appropriate authority/(s).
- (c) The Contractor shall require all personnel engaged in the Works to obey all Applicable Laws and regulations. The Contractor shall permit the Authority to witness labor payments for the Contractor's direct labor, or the Sub contractor's labor. The Contractor shall ensure that all its Sub contractors strictly comply with all labor laws.
- (d) Documentary evidence confirming compliance with Sub-Clause 12.4, as maybe required from time to time, shall be provided to the Employer's Representative.
- (e) The Employer shall not be liable for any delay/default of the Contractor in compliance with the labor laws.

(v) **Facilities for Staff and Labor**

The Contractor shall provide and maintain all necessary accommodation and welfare facilities for personnel engaged for the Works. The Contractor shall not permit any personnel engaged for the Works to maintain any temporary or permanent living quarters within the structures forming part of the Works.

(vi) **Health And Safety**

All necessary precautions shall be taken by the Contractor to ensure the health and safety of staff and labor engaged in the Works. The Contractor shall, in collaboration with and to the requirements of the local health authorities, ensure that para-medical staff, first aid facilities, and ambulance service are available on the Site at all times and that suitable arrangements are made for all necessary welfare and hygiene requirements and the prevention of epidemics. The Contractor shall appoint a safety officer to be responsible for the safety of personnel on the Site. This safety officer shall be qualified for his work and shall have the authority to issue instructions concerning safety and take protective measures to prevent accidents. The Contractor shall maintain records and make reports concerning the health, safety, and welfare of personnel, and damage to property, in such manner as the Authority may reasonably require.

(vii) **Contractor's Personnel**

The Contractor shall employ only personnel who are appropriately qualified, skilled, and experienced in their respective trades or occupations. The Authority may require the Contractor to remove any personnel engaged for the Works, who in the opinion of the Authority:

- (a) has engaged in any as conduct;
- (b) is in competent or negligent in the performance of his duties;
- (c) fails to conform with any provisions of the Contract;
- (d) engages in any conduct that is prejudicial to safety, health, or the protection of the environment; or
- (e) makes errors in the discharge of his functions.

If appropriate and required by the Employer, the Contractor shall then appoint (or cause to be appointed) a suitable replacement person.

(viii) **Disorderly Conduct**

The Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous, or disorderly conduct by or amongst its personnel, and to preserve peace and protection of people and property in the neighborhood of the Works.

Article 12

Completion Certificate

12.1 Tests on Completion

- (i) At least 30 (thirty) days before the likely completion of the Project Highway, or a Section thereof, the Contractor shall notify the Authority's Engineer of its intent to subject the Project Highway, or a Section thereof, to Tests. The date and time of each of the Tests shall be determined by the Authority's Engineer in consultation with the Contractor, and notified to the Authority who may designate its representative to witness the Tests. The Contractor shall either conduct the Tests as directed by the Authority's Engineer or provide such assistance as the Authority's Engineer may reasonably require for conducting the Tests. In the event of the Contractor and the Authority's Engineer failing to mutually agree on the dates for conducting the Tests, the Contractor shall fix the dates by giving not less than 10 (ten) days' notice to the Authority's Engineer.
- (ii) All Tests shall be conducted under Schedule K. The Authority's Engineer shall either conductor observe, monitor ,and review the Tests conducted by the Contractor, as the case may be, and review the results of the Tests to determine compliance of the Project Highway or a Section thereof, with Specifications and Standards and if it is reasonably anticipated or determined by the Authority's Engineer during any Test that the performance of the Project Highway or Section or any part thereof, does not meet the Specifications and Standards , it shall have the right to suspend or delay such Test and require the Contractor to remedy and rectify the Defect or deficiencies. Upon completion of each Test, the Authority's Engineer shall provide to the Contractor and the Authority copies of all Test data including detailed Test results. For the avoidance of doubt, it is expressly agreed that the Authority's Engineer may require the Contractor to carry out or cause to be carried out additional Tests, under Good Industry Practice, for determining the compliance of the Project Highway or Section thereof with the Specifications and Standards.

12.2 Completion Certificate

- (i) Upon completion of all Works forming part of the Project Highway, and the Authority's Engineer determining the Tests to be successful and after the receipt of notarized true copies of the certificate(s) of insurance, copies of insurance policies, and premium payment receipts in respect of the insurance defined in Article 20 and Schedule P of this Agreement, it shall, at the request of the Contractor forthwith issue to the Contractor and the Authority a certificate substantially in the form outlined in Schedule-L (the "Completion Certificate").

The Completion certificate is to be issued by the Authority's Engineer with the prior approval of the Authority as per Schedule N of the Contract Agreement. It should be ensured that the completion certificate is approved after verifying/confirming that all works/items including ancillary items forming part of the project are completed in all respects conforming to the standards and specifications of MoRTH. A video of

completed work on the date of completion should in variably be prepared and furnished as authentic documentary evidence of completion of work within 15 days of completion without which the completion certificate should not be issued. The authority engineer, apart from furnishing the certificate of completion and all tests as per specifications under the contract, would also certify that all NCRs issued during the contract have been closed after successful rectification of the defect within the completion date.

- (ii) Upon receiving the Completion Certificate, the Contractor shall remove its equipment, materials, debris, and temporary works from the Site within 30 (thirty) days thereof, failing which the Authority may remove or cause to be removed, such equipment, materials, debris, and temporary works and recover from the Contractor an amount equal to 120% (one hundred and twenty percent) of the actual cost of removal incurred by the Authority.
- (iii) Without prejudice to the obligations of the Contractor specified in Articles 14 and 17, the property and ownership of all the completed Works forming part of the Project Highway shall vest in the Authority.

12.3 Rescheduling of Tests

If the Authority's Engineer certifies to the Authority and the Contractor that it is unable to issue the Completion Certificate, as the case may be, because of events or circumstances on account of which the Tests could not be held or had to be suspended, the Contractor shall be entitled to re-schedule the Tests and hold the same as soon as reasonably practicable.

Article 13 Change of Scope

13.1 Change of Scope

- (i) The Authority may, notwithstanding anything to the contrary contained in this Agreement, require the Contractor to make modifications/ alterations to the Works (“**Change of Scope**”) within six months counted from the Appointed Date. Upon the Authority making its intention known to the Contractor for the specific Change of Scope, be it positive or negative, the Contractor shall submit his proposal for the said Change of Scope involving additional cost or reduction in cost. Any such Change of Scope shall be made and valued under the provisions of Article 13.
- (ii) Provided that any such Change of Scope, excluding major structures (e.g. Major River Bridge/ ROB/ RUB/ Flyover/ elevated road of more than 50 m lengths) may be required and agreed to be executed between the parties beyond the period of six months of the Appointed Date but before the expiry of 50% of the original Scheduled Construction Period of the Project Highway, subject to the condition that it shall not entail any claims (e.g. Extension of Time/ Prolongation related claims), against the Authority.
- (iii) The Change of Scope shall mean the following:
 - (a) change in specifications of any item of Work;
 - (b) omission of any work from the Scope of the Project except under Clause 8.3 (iii); provided that, subject to Clause 13.5, the Authority shall not omit any Work under this Clause to get it executed by any other authority; and/ or
 - (c) any additional Work, Plant, Materials, or services that are not included in the Scope of the Project, including any associated Tests on completion of construction.

13.2 Procedure for Change of Scope

- (i) In the event of the Authority determining that a Change of Scope is necessary, it may direct the Authority’s Engineer to issue to the Contractor a notice specifying in reasonable detail the Works and services contemplated there under (the “**Change of Scope Notice**”). The Contractor shall submit a detailed proposal as per Clause 13.2 (iii) within 15 days from the receipt of the Change of Scope Notice.
- (ii) If the Contractor determines, not later than 90 days from the Appointed Date, that a Change of Scope to the Works is required, it shall prepare a proposal with relevant details as per Clause 13.2 (iii) at its own cost and shall submit to the Authority to consider such Change of Scope (the “**Change of Scope Request**”).

- (iii) Upon receipt of a Change of Scope Notice, the Contractor shall, with due diligence, provide to the Authority and the Authority's Engineer such information as is necessary, together with the detailed proposal in support of:
- (a) the impact, if any, which the Change of Scope is likely to have on the Project Completion Schedule if the works or services are required to be carried out during the Construction Period; and
 - (b) the options for implementing the proposed Change of Scope and the effect, if any, each such option would have on the costs and time thereof, including the following details:
 - i. break-up of the quantities, unit rates, and cost for different items of work; and
 - ii. proposed design for the Change of Scope;
 - iii. proposed modifications, if any, to the Project Completion Schedule of the Project Highway.

For the avoidance of doubt, the Parties expressly agree that, subject to the provisions of Clause 13.4 (ii), the Contract Price shall be increased or decreased, as the case may be, on account of any such Change of Scope.

- (iv) The parties agree that costs and time for implementation of the proposed Change of Scope shall be determined as per the following:
- (a) For works where the Schedule of Rates (SOR) of the concerned circle of State's Public Works Department are applicable at the Base Date are available, the same shall be applicable for the determination of costs. In case of non-availability of Schedule of Rates at the Base Date, the available Schedule of Rates shall be applied by updating the same based on WPI. In case the Contract Price is lower/ higher than the Estimated Project Cost as per RFP, then the SOR rates shall be reduced/ increased in the same proportion accordingly.
 - (b) For items of Work not included in the Schedule of Rates as mentioned in sub-para (a) of Clause 13.2(iv) above, the cost of same shall be derived based on MORTH Standard Data Book, and the Authority's Engineer shall determine the prevailing market rates and discount the same considering WPI to achieve the prevailing rate at the Base Date, and for any item in respect of which MORTH Standard Data Book does not provide the requisite details, the Authority's Engineer shall determine the rate under Good Industry Practice.

For the avoidance of doubt, in case the cost as determined by the Contractor and the Authority reveals a difference of more than 10% (ten percent), the cost as determined by the Authority shall be considered final and binding on the Contractor.
 - (c) The design charges shall be considered only for new works or items (i.e. the Works or items not similar to the works or items in the original scope) @ 1% (one percent) of the cost of such new works or items.

- (d) The costs of existing works or items, which are being changed/ omitted shall also be valued as per the above procedure and only net cost shall be considered.
 - (e) The reasonable time for completion of works to be taken under Change of Scope shall be determined by the Authority's Engineer based on Good Industry Practice and if such time exceeds the Scheduled Completion Date, the issue of Completion Certificate shall not be affected or delayed on account of construction of Change of Scope items/ works remaining incomplete on the date of Tests.
- (v) Upon consideration of the detailed proposal submitted by the Contractor under Clause 13.2 (iii), the Authority, within 15 (fifteen) days of receipt of such proposal, may in its sole discretion neither accept such Change of Scope with modifications, if any and initiate proceedings thereof under this Article 13 or reject the proposal and inform the Contractor of its decision and shall issue an order (the "**Change of Scope Order**") requiring the Contractor to proceed with the performance thereof.

For the avoidance of doubt, the Parties agree that the Contractor shall not undertake any Change of Scope without the express consent of the Authority, save and except any works necessary for meeting any Emergency, that too with verbal approval of the Authority which shall be confirmed in writing in next 3 (three) days. If the Parties are unable to agree, the Authority may:

- (a) issue a Change of Scope Order requiring the Contractor to proceed with the performance thereof at the rates and conditions approved by the Authority till the matter is resolved under Article 26;
- Or
- (b) proceed under Clause 13.5.
- (vi) The provisions of this Agreement, in so far as they relate to Works and Tests, shall apply *mutatis mutandis* to the Works undertaken by the Contractor under Article 13.

13.3 Payment for Change of Scope

Payment for Change of Scope shall be made under the payment schedule specified in the Change of Scope Order.

13.4 Restrictions on Change of Scope

- (i) No Change of Scope shall be executed unless the Authority has issued the Change of Scope Order save and except any Works necessary for meeting any Emergency.
- (ii) The total value of all Change of Scope Orders shall not exceed 10% (ten percent) of the Contract Price.

- (iii) Notwithstanding anything to the contrary in this Article 13, if any change is necessitated because of any default of the Contractor in the performance of its obligations under this Agreement, the same shall not be deemed to be a Change of Scope, and shall not result in any adjustment of the Contract Price or the Project Completion Schedule.

13.5 Power of the Authority to Undertake Works

- (i) In the event the Parties are unable to agree to the proposed Change of Scope Orders under Clause 13.2, the Authority may, after giving notice to the Contractor and considering its reply thereto, award such Works or services to any person or agency based on open competitive bidding. It is also agreed that the Contractor shall provide assistance and cooperation to the person or agency who undertakes the works or services hereunder. The Contractor shall not be responsible for rectification of any Defects, but the Contractor shall carry out maintenance of such works after completion of the Defect Liability Period of work by another person or agency during the remaining period of this agreement without any extra payment.
- (ii) The Works undertaken under Clause 13.5 shall conform to the Specifications and Standards and shall be carried out in a manner that minimizes the disruption in the operation of the Project Highway. The provisions of this Agreement, insofar as they relate to Works and Tests, shall apply *mutatis mutandis* to the Works carried out under Clause 13.5.

Article 14

Maintenance

14.1

- (i) The Contractor shall maintain the Project Highway for 2(two) years, corresponding to the Defects Liability Period, commencing from the date of the Completion Certificate (the "Maintenance Period"). For the performance of its Maintenance obligations, the Contractor shall not be paid any maintenance charges.
- (ii) During the Maintenance Period, the Authority shall provide to the Contractor access to the Site for Maintenance under this Agreement. The obligations of the Contractor hereunder shall include:
 - (a) permitting safe, smooth, and uninterrupted flow of traffic on the Project Highway;
 - (b) undertaking routine maintenance including prompt repairs of potholes, cracks, joints, drains, embankments, structures, pavement markings, lighting, road signs, and other traffic control devices. For the avoidance of doubt, the electricity charges for the operation of the electrical infrastructure installed along the project length, except the infrastructure being used by the Contractor for its use, shall be borne by the Authority;
 - (c) undertaking repairs to structures;
 - (d) informing the Authority of any unauthorized use of the Project Highway;
 - (e) informing the Authority of any encroachments on the Project Highway; and
 - (f) operation and maintenance of all communication, patrolling, and administrative systems necessary for the efficient maintenance of the Project Highway under the provisions of this Agreement.
- (iii) In respect of any Defect or deficiency not specified in Schedule E, the Contractor shall, at its own cost, undertake repair or rectification under Good Industry Practice, save and except to the extent that such Defect or deficiency shall have arisen on account of any willful default or neglect of the Authority or a Force Majeure Event.
- (iv) The Contractor shall remove promptly from the Project Highway any waste materials (including hazardous materials and waste water), rubbish, and other debris (including, without limitation, accident debris) and keep the Project Highway in a clean, tidy, and orderly condition, and in conformity with the Applicable Laws, Applicable Permits and Good Industry Practice.

14.2 Maintenance Requirements

The Contractor shall ensure and procure that at all times during the Maintenance Period, the Project Highway conforms to the maintenance requirements outlined in Schedule-E (the "**Maintenance Requirements**").

14.3 Maintenance Programme

- (i) The Contractor shall prepare a monthly maintenance program (the “**Maintenance Programme**”) in consultation with the Authority’s Engineer and submit the same to the Authority’s Engineer not later than 10 (ten) days before the commencement of the month in which the Maintenance is to be carried out. For this purpose, a joint monthly inspection by the Contractor and the Authority’s Engineer shall be undertaken. The Maintenance Programme shall contain the following:
 - (a) The condition of the road in the format prescribed by the Authority’s Engineer;
 - (b) the proposed maintenance Works; and
 - (c) deployment of resources for maintenance Works.

14.4 Safety, vehicle breakdowns, and accidents

- (i) The Contractor shall ensure safe conditions for the Users, and in the event of unsafe conditions, lane closures, diversions, vehicle breakdowns, and accidents, it shall follow the relevant operating procedures for removal of obstruction and debris without delay. Such procedures shall conform to the provisions of this Agreement, Applicable Laws, Applicable Permits, and Good Industry Practice.
- (ii) The Contractor shall maintain and operate a round-the-clock vehicle rescue post with 1 (one) mobile crane having the capacity to lift a truck with a Gross Vehicle Weight of 30,000 (thirty thousand) kilograms, and such post shall be located at [****]. The Contractor shall promptly remove any damaged vehicles and debris from the Project Highway to enable safe movement of traffic and shall report all accidents to the police forthwith.

14.5 Lane closure

- (i) The Contractor shall not close any lane of the Project Highway for undertaking maintenance works except with the prior written approval of the Authority’s Engineer. Such approval shall be sought by the Contractor through a written request to be made at least 10 (ten) days before the proposed closure of the lane and shall be accompanied by particulars thereof. Within 5 (five) business days of receiving such request, the Authority’s Engineer shall grant permission with such modifications as it may deem necessary and a copy of such permission shall be sent to the Authority.
- (ii) Upon receiving the permission under Clause 14.5 (i), the Contractor shall be entitled to close the designated lane for the period specified therein, and for all lane closures extending a continuous period of 48 (forty-eight) hours, the Contractor shall, in the event of any delay in re-opening such lane, for every stretch of 250 (two hundred and fifty) meters, or part thereof, pay Damages to the Authority calculated at the rate of 0.1% (zero point one percent) of the monthly maintenance payment for each day of delay until the lane has been re-opened for traffic. In the event of any delay in re-opening such lanes or in the event of emergency decommissioning and closure to traffic of the whole or any part of the Project Highway due to failure of the Contractor, the Contractor shall pay damages to the Authority at double the above rate, without

Prejudice the rights of the Authority under this Agreement including Termination thereof.

14.6 Reduction of payment for non-performance of Maintenance obligations

- (i) If the Contractor fails to repair or rectify any Defect or deficiency outlined in Schedule-E within the period specified therein, it shall be deemed as a failure of performance of Maintenance obligations by the Contractor and the Authority shall be entitled to effect reduction in monthly lump sum payment for maintenance under Clause 19.7 and Schedule-M, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (ii) If the nature and extent of any Defect justifies more time for its repair or rectification than the time specified in Schedule E, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

14.7 Authority's right to take remedial measures

In the event the Contractor does not maintain and/or repair the Project Highway or any part thereof in conformity with the Maintenance Requirements, the Maintenance Manual, or the Maintenance Programme, as the case may be, and fails to commence remedial works within 15 (fifteen) days of receipt of the Maintenance Inspection Report under Clause 15.2 or notice in this behalf from the Authority or the Authority's Engineer, as the case may be, the Authority shall, without prejudice to its rights under this Agreement including Termination thereof, be entitled to undertake such remedial measures at the cost of the Contractor and to recover its cost from the Contractor. In addition to recovery of the aforesaid cost, a sum equal to 20% (twenty percent) of such cost shall be paid by the Contractor to the Authority as Damages.

14.8 Restoration of loss or damage to Project Highway

Save and except as otherwise expressly provided in this Agreement, if the Project Highway or any part thereof suffers any loss or damage during the Maintenance from any cause attributable to the Contractor, the Contractor shall, at its cost and expense, rectify and remedy such loss or damage forthwith so that the Project Highway conforms to the provisions of this Agreement.

14.9 Overriding powers of the Authority

- (i) If in the reasonable opinion of the Authority, the Contractor is in material breach of its obligations under this Agreement and, in particular, the Maintenance Requirements, and such breach is causing or likely to cause material hardship or danger to the Users and pedestrians, the Authority may, without prejudice to any of its rights under this Agreement including Termination thereof, by notice require the Contractor to take reasonable measures immediately for rectifying or removing such hardship or danger, as the case may be.

- (ii) If the Contractor, upon notice under Clause 14.9 (i), fails to rectify or remove any hardship or danger within a reasonable period, the Authority may exercise overriding powers under Clause 14.9 (ii) and take over the performance of any or all the obligations of the Contractor to the extent deemed necessary by it for rectifying or removing such hardship or danger; provided that the exercise of such overriding powers by the Authority shall be of no greater scope and no longer duration than is reasonably required hereunder; provided further that any costs and expenses incurred by the Authority in the discharge of its obligations hereunder shall be recovered by the Authority from the Contractor, and the Authority shall be entitled to deduct any such costs and expenses incurred from the payments due to the Contractor under Clause 19.7 for the performance of its Maintenance obligations.

- (iii) In the event of a national emergency, civil commotion, or any other circumstances specified in Clause 21.3, the Authority may take over the performance of any or all the obligations of the Contractor to the extent deemed necessary by it, and exercise such control over the Project Highway or give such directions to the Contractor as may be deemed necessary; provided that the exercise of such overriding powers by the Authority shall be of no greater scope and no longer duration than is reasonably required in the circumstances which caused the exercise of such overriding power by the Authority. For the avoidance of doubt, it is agreed that the consequences of such action shall be dealt with under the provisions of Article 21. It is also agreed that the Contractor shall comply with such instructions as the Authority may issue in pursuance of the provisions of this Clause 14.9 (iii), and shall provide assistance and cooperation to the Authority, on a best-effort basis, for the performance of its obligations hereunder.

14.10 Taking over Certificate

The Maintenance Requirements outlined in Schedule-E having been duly carried out, the Maintenance Period as outlined in Clause 14.1 (i) having expired, and the Authority's Engineer determining the Tests on Completion of Maintenance to be successful under Schedule-Q, the Authority will issue Taking Over Certificate to the Contractor substantially in the format outlined in Schedule-R.

Article 15

Supervision and Monitoring during Maintenance

15.1 Inspection by the Contractor

- (i) The Authority's Engineer shall undertake regular inspections to evaluate continuously the compliance with the Maintenance Requirements.
- (ii) The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts, and drainage systems under the guidelines contained in IRC: SP3 5. A report of this inspection together with details of proposed maintenance works as required shall be conveyed to the Authority's Engineer forthwith. The Contractor shall complete the proposed maintenance works before the onset of the monsoon and send a compliance report to the Authority's Engineer. Post-monsoon inspection shall be undertaken by the Contractor and the inspection report together with details of any damages observed and proposed action to remedy the same shall be conveyed to the Authority's Engineer forthwith.

15.2 Inspection and payments

- (i) The Authority's Engineer may inspect the Project Highway at any time, but at least once every month, to ensure compliance with the Maintenance Requirements. It shall make a report of such inspection ("**Maintenance Inspection Report**") stating in reasonable detail the Defects or deficiencies, if any, with particular reference to the Maintenance Requirements, the Maintenance Manual, and the Maintenance Programme, and send a copy thereof to the Authority and the Contractor within 10 (ten) days of such inspection.
- (ii) After the Contractor submits to the Authority's Engineer the Monthly Maintenance Statement for the Project Highway under Clause 19.6, the Authority's Engineer shall carry out an inspection within 10 (ten) days to certify the amount payable to the Contractor. The Authority's Engineer shall inform the Contractor of its intention to inspect at least 3 (three) business days in advance of such inspection. The Contractor shall assist the Authority's Engineer in verifying compliance with the Maintenance Requirements.
- (iii) For each case of non-compliance with Maintenance Requirements as specified in the inspection report of the Authority's Engineer, the Authority's Engineer shall calculate the amount of reduction in payment under the formula specified in Schedule M.
- (iv) Any deduction made on account of non-compliance will not be paid subsequently even after establishing the compliance thereof. Such deductions will continue to be made every month until the compliance is procured.

15.3 Tests

To determine that the Project Highway conforms to the Maintenance Requirements, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, Tests specified by it under Good Industry Practice. The Contractor shall, with due diligence, carry out or cause to be carried out all such Tests under the instructions of the Authority's Engineer and furnish the results of such tests forthwith to the Authority's Engineer.

At any time during the Maintenance Period, the Authority may appoint an external technical auditor to conduct an audit of the quality of the Works. The Auditor in the presence of the representatives of the Contractor and the Authority's Engineer shall carry out the Tests and/ or collect samples for testing in the laboratory. The timing, the testing equipment, and the sample size of this audit shall be as decided by the Authority. The findings of the audit, to the extent accepted by the Authority, shall be notified to the Contractor and the Authority's Engineer for taking remedial measures. After completion of the remedial measures by the Contractor, the auditor shall undertake a closure audit and this process will continue till the remedial measures have brought the maintenance works into compliance with the Specifications and Standards. The Contractor shall provide all assistance as may be required by the auditor in the conduct of its audit hereunder. Notwithstanding anything contained in Clause 15.3, the external technical audit shall not affect any obligations of the Contractor or the Authority's Engineer under this Agreement.

15.4 Reports of the unusual occurrence

The Contractor shall, during the Maintenance Period, before the close of each day, send to the Authority and the Authority's Engineer, by facsimile or e-mail, a report stating accidents and unusual occurrences on the Project Highway relating to the safety and security of the Users and Project Highway. A monthly summary of such reports shall also be sent within 3 (three) business days of the closing of the month. For this Clause 15.4, accidents and unusual occurrences on the Project Highway shall include:

- (a) accident, death, or severe injury to any person;
- (b) damaged or dislodged fixed equipment;
- (c) flooding of Project Highway; and
- (d) any other unusual occurrence.

Article 16 Traffic

Regulation

16.1 Traffic regulation by the Contractor

- (i) The Contractor shall take all the required measures and make arrangements for the safety of Users during the Construction and Maintenance of the Project Highway or a Section thereof under the provisions of MORTH Specifications. It shall provide, erect, and maintain all such barricades, signs, markings, flags, and lights as may be required by Good Industry Practice for the safety of the traffic passing through the Section under construction or maintenance.

- (ii) All works shall be carried out in a manner that creates the least interference to traffic passing through the Project Highway or a Section thereof. In sections where construction or maintenance Works on the carriageway are taken up, the Contractor shall ensure that proper passage is provided for the traffic. Where it is not possible or safe to allow traffic on part width of the carriageway, a temporary diversion of proper specifications shall be constructed by the Contractor at its own cost. 'ROBOTS' may be used for diversion and control of traffic during Construction. The Contractor shall take prior approval of the Authority's Engineer for any proposed arrangement for traffic regulation during Construction and Maintenance, which approval shall not be unreasonably withheld.

Article17

Defects Liability

17.1 Defects Liability Period

The Contractor shall be responsible for all the Defects and deficiencies, except usual wear and tear in the Project Highway or any Section thereof, till the expiry of a period of 2 (two) years from the date of completion commencing from the date of Completion Certificate (the "Defects Liability Period").

The Defects Liability Period shall commence from the date of the Completion Certificate. For the avoidance of any doubt, any repairs or restoration because of usual wear or tear in the Project Highway or any Section thereof shall form apart of the Maintenance obligations of the Contractor as specified in Article 14.

17.2 Remediating Defects

Save and except as provided in Clause 14.1 (iii), the Contractor shall repair or rectify all Defects and deficiencies observed by the Authority or Authority's Engineer during the Defects Liability Period within 15 (fifteen) days from the date of notice issued by the Authority or Authority's Engineer in this behalf, or within such reasonable period as may be determined by the Authority or Authority's Engineer at the request of the Contractor, under Good Industry Practice.

17.3 Cost of remediating Defects

Any repair or rectification undertaken under the provisions of Clause 17.2, including any additional testing, shall be carried out by the Contractor at its own risk and cost, to the extent that such rectification or repair is attributable to:

- (a) the design of the Project;
- (b) Plant, Materials, or workmanship not being under this Agreement and the Specifications and Standards;
- (c) improper maintenance during construction of the Project Highway by the Contractor; and/ or
- (d) failure by the Contractor to comply with any other obligation under this Agreement.

17.4 Contractor's failure to rectify Defects

If the Contractor fails to repair or rectify such Defect or deficiency within the period specified in Clause 17.2, the Authority shall be entitled to get the same repaired, rectified, or remedied at the Contractor's cost to make the Project Highway conform to the Specifications and Standards and the provisions of this Agreement. All costs consequent thereon shall, after due consultation with the Authority and the Contractor, be determined by the Authority's Engineer. The cost so determined and

an amount equal to 20% (twenty percent) of the cost as Damages shall be recoverable by the Authority from the Contractor and may be deducted by the Authority from any monies due to the Contractor.

17.5 Extension of Defects Liability Period

The Defects Liability Period shall be deemed to be extended till the identified Defects under Clause 17.2 have been remedied or rectified.

Article 18

Authority's Engineer

18.1 Authority's Engineer

- (i) **The Project Manager/ Dy. Project Manger of the concerned Bridge Construction Unit (herein called BCU),U. P. State Bridge Corporation(herein called UPSBC)** shall act as the "Authority's Engineer".
- (ii) **The Project Manager/Dy. Project Manger/ of the concerned BCU, UPSBC** will be responsible for the over all supervision and monitoring of the execution of the project as the representative of the owner of the project. The Authority's Engineer assists the Authority in carrying out the functions as detailed under clause 18.2. As such, an officer of the Authority is vested with all such powers and responsibilities as are enjoined upon the Authority's Engineer and is fully competent to issue any instructions for proper monitoring and supervision of the project, either by himself or through the Authority's Engineer. Instructions issued by the concerned officer of the Authority shall have the same effect as that of the Authority's Engineer interms of this Agreement. Wherever such concerned officer issues any instructions or notice to the Contractor, he shall endorse a copy thereof to the Authority's Engineer.
- (iii) The Authority shall notify the replacement of the Authority's Engineer to the Contractor, if any.
- (iv) The staff of the Authority's Engineer shall include suitably qualified engineers and other professionals who are competent to assist the Authority's Engineer in carrying out its duties.

18.2 Duties and authority of the Authority's Engineer

- (i) The Authority's Engineer shall perform the duties and exercise the authority under the provisions of this Agreement and substantially under the terms of reference ("**Terms of Reference**" or "**TOR**") outlined in Annexure-I of Schedule N, but subject to obtaining prior written approval of the Authority before determining:
 - (a) any time Extension;
 - (b) any additional cost to be paid by the Authority to the Contractor;
 - (c) the Termination Payment;
 - (d) issuance of Completion Certificate; or
 - (e) any other matter which is not specified in(a),(b),(c),or(d) above and which creates financial liability on either Party.
- (ii) No decision or communication of the Authority's Engineer shall be effective or valid unless it is accompanied by an attested true copy of the approval of the Authority for and in respect of any matter specified in Clause 18.2 (i).
- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement.

Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month. For the avoidance of doubt, the Authority's Engineer shall include in its report, compliance with the recommendations of the Safety Consultant.

18.3 Delegation by the Authority's Engineer

- (i) The Authority's Engineer may, by order in writing, delegate any of his duties and responsibilities to suitably qualified and experienced personnel who are accountable to the Authority's Engineer, or may revoke any such delegation, under intimation to the Authority and the Contractor. Provided, however, that the Authority's Engineer shall be responsible and liable for all actions and omissions of such personnel.
- (ii) Any failure of the Authority's Engineer to disapprove any work, Plant, or Materials shall not constitute approval, and shall, therefore, not prejudice the right of the Authority to reject the work, Plant, or Materials, which is not under the provisions of this Agreement and the Specifications and Standards.
- (iii) Notwithstanding anything stated in Clause 18.3 (i) above, the Authority's Engineer shall not delegate the authority to refer any matter for the Authority's prior approval wherever required under the provisions of Clause 18.2.

18.4 Instructions of the Authority's Engineer

- (i) The Authority's Engineer may issue instructions for remedying any Defect(s) to the Contractor. The Contractor shall take such instructions from the Authority's Engineer, or from an assistant to whom appropriate authority has been delegated under Clause 18.3.
- (ii) The instructions issued by the Authority's Engineer shall be in writing. However, if the Authority's Engineer issues any oral instructions to the Contractor, it shall confirm the oral instructions in writing within 2 (two) working days of issuing them.
- (iii) In case the Contractor does not receive the confirmation of the oral instructions within the time specified in Clause 18.4 (ii), the Contractor shall seek the written confirmation of the oral instructions from the Authority's Engineer. The Contractor shall obtain an acknowledgment from the Authority's Engineer of the communication seeking written confirmation. In case of failure of the Authority's Engineer or its delegated assistant to reply to the Contractor within 2 (two) days of the receipt of the communication from the Contractor, the Contractor may not carry out the instructions.
- (iv) In case of any dispute on any of the instructions issued by the delegated assistant, the Contractor may refer the dispute to the Authority's Engineer, who shall then confirm, reverse, or vary the instructions within 3 (three) business days of the dispute being referred.

18.5 Determination by the Authority's Engineer

- (i) The Authority's Engineer shall consult with each Party in an endeavor to reach an agreement wherever this Agreement provides for the determination of any matter by

the Authority's Engineer. If such agreement is not achieved, the Authority's Engineer shall make a fair determination under this Agreement having due regard to all relevant circumstances. The Authority's Engineer shall give notice to both the Parties of each agreement or determination, with supporting particulars.

- (ii) Each Party shall give effect to each agreement or determination made by the Authority's Engineer under the provisions of this Agreement. Provided, however, that if any Party disputes any instruction, decision, direction, or determination of the Authority's Engineer, the Dispute shall be resolved under the Dispute Resolution Procedure.

18.6 Remuneration of the Authority's Engineer

There muneration, costs, and expenses of the Authority's Engineer shall be paid by the Authority.

18.7 Termination of the Authority's Engineer

- (i) The Authority may, in its discretion, replace the Authority's Engineer at any time. However, the Authority shall ensure that alternative arrangements for the appointment of another Authority's Engineer or designation of its officer as the Authority Engineer for the intervening period are made simultaneously.
- (ii) If the Contractor has reasons to believe that the Authority's Engineer is not discharging its duties and functions under the provisions of this Agreement, it may make a written representation to the Authority and seek termination of the appointment of the Authority's Engineer. Upon receipt of such representation, the Authority shall hold a tripartite meeting with the Contractor and the Authority's Engineer and makes best efforts for an amicable resolution of the representation. If the appointment of the Authority's Engineer is terminated hereunder, the Authority shall appoint forthwith another Authority's Engineer under Clause 18.1 and 18.7(i).

Part IV
Financial Covenants

Article 19

Payments

19.1 Contract Price

- (i) The Authority shall make payments to the Contractor for the Works based on the lump sum price accepted by the Authority in consideration of the obligations specified in this Agreement for an amount of INR (Amount as quoted by the bidder exclusive of GST + GST amount as applicable) (the “**Contract Price**”), which shall be subject to adjustments under the provisions of this Agreement. For the avoidance of doubt, the Parties expressly agree that the Contract Price shall not include the cost of Maintenance, which shall be paid separately under the provisions of Clause 19.7. The Parties further agree that save and except as provided in this Agreement, the Contract Price shall be valid and effective until the issue of the Completion Certificate.
- (ii) The Contract Price includes all duties, taxes, royalty, cess, charges, and fees that may be levied in accordance with the laws and regulations in force as on the Base Date on the Contractor's equipment, Plant, Materials, and supplies acquired for this Agreement and on the services performed under this Agreement. Nothing in this Agreement shall relieve the Contractor from its responsibility to pay any tax including any tax that may be levied in India on profits made by it in respect of this Agreement.
- (iii) The Contract Price shall not be adjusted for any change in costs stated in Clause 19.1 (ii) above, except as stated in Clauses 19.10 and 19.17.
- (iv) The Contract Price shall not be adjusted to take account of any unforeseen difficulties or costs unless otherwise provided for in this Agreement.
- (v) Unless otherwise stated in this Agreement, the Contract Price covers all the Contractor's obligations for the Works under this Agreement and all things necessary for the Construction and the remedying of any Defects in the Project Highway.
- (vi) All payments under this Agreement shall be made in Indian Rupees.

19.2 Advance Payment

- (i) The Authority shall make an interest-bearing advance payment (the “**Advance Payment**”) @ “**Bank Rate + 3%**”, equal to 10 % (ten percent) of the Contract Price, exclusively for mobilization expenses. The Advance Payment for mobilization expenses shall be made in two installments each equal to 5% (five percent) of the Contract Price. The second 5% (five percent) mobilization advance would be released after the submission of the utilization certificate by the Contractor for the first 5% (five percent) advance already released earlier.
- (ii) In addition to the above, the Authority shall make an additional interest-bearing Advance Payment against newly purchased key Construction equipment required for

the works as per the agreed Construction program and brought to the site, if so requested by the Contractor subject to the same terms and conditions specified for Advance Payment for mobilization expenses in this Agreement. The maximum of such advance shall be 5% (five percent) of the Contract Price against Bank Guarantee. This advance shall be further subject to the condition that:

- (a) such new equipment is considered by the Authority's Engineer to be necessary for the works and
- (b) these new equipment should be procured in the name of the Contractor and be verified by the Authority's Engineer to have been brought to the site.

The Advance Payment for mobilization expenses and acquisition of key new Construction equipment would be deemed as an interest-bearing advance at the applicable interest rate (@ "Bankrate+3%"), to be compounded annually on a reducing balance basis. The interest would be recovered along with the recovery of mobilization Advance Payment as per the provision laid down for the mobilization advance recovery.

- (iii) The Contractor may apply to the Authority for the first installment of the Advance Payment at any time after the Appointed Date, along with an irrevocable and unconditional guarantee from a Bank for an amount equivalent to 110% (one hundred and ten percent) of such installment, substantially in the form provided at Annex-III of Schedule-G, to remain effective till the full repayment thereof.
- (iv) At any time, after 60 (sixty) days from the Appointed Date, the Contractor may apply to the Authority for the second installment of the Advance Payment along with an irrevocable and unconditional guarantee from a Bank for an amount equivalent to 110% (one hundred and ten percent) of such installment, substantially in the form provided at Annex-III of Schedule-G, to remain effective till the complete repayment thereof.

The Contractor has the option of splitting the Bank Guarantee against Advance Payment for mobilization expenses into parts, each not less than 2.75% (two point seven five percent) of the Contract Price. Each part of the guarantee shall remain effective till full repayment of such part advance corresponding to this bank guarantee. Such part of the Bank Guarantee shall be returned to the Contractor on recovery under the Agreement of the full amount of such part guarantee within 30 (thirty) days of the said recovery.

- (v) The Advance Payment shall be paid by the Authority to the Contractor within 15 (fifteen) days of the receipt of its respective requests under the provisions of Clause 19.2.
- (vi) The Advance Payment shall be repaid through percentage deductions from the stage payments determined by the Authority's Engineer under Clause 19.5, as follows:
 - (a) deductions shall commence in the first Stage Payment Statement;

- (b) deductions shall be made at the rate of 15% (fifteen percent) of each Stage Payment Statement until the advance payment has been repaid; provided that the advance payment shall be completely repaid before the time when 80% (eighty percent) of the Schedule Construction Period is over;
 - (c) if total certified stage payments (excluding the Advance Payment and deductions and repayments of retention) do not exceed 20% (twenty percent) of the Contract Price within [50% of the Scheduled Construction Period] from the Appointed Date then the Advance Payment including interest shall be recovered by encashment of the Bank Guarantee for the Advance Payment.
- (vii) If the Advance Payment has not been fully repaid before Termination under Clause 21.7 or Article 23, as the case may be, the whole of the balance then outstanding shall immediately become due and payable by the Contractor to the Authority. Without prejudice to the provisions of Clause 19.2 (vi), in the event of Termination for Contractor Default, the Advance Payment shall be deemed to carry interest@ “**Bank Rate+5%**” per annum from the date of Advance Payment to the date of recovery by encashment of the Bank Guarantee for the Advance Payment. For the avoidance of doubt, the aforesaid interest shall be payable on the unrecovered balance.

19.3 Procedure for estimating the payment for the Works

- (i) The Authority shall make interim payments to the Contractor as certified by the Authority's Engineer on completion of a stage, in length, number, or area as specified and valued under the proportion of the Contract Price assigned to each item and its stage in Schedule-H.
- (ii) The Contractor shall base its claim for an interim payment for the stages completed till the end of the month for which the payment is claimed, valued under Clause 19.3(i), supported with necessary particulars and documents under this Agreement.
- (iii) Any reduction in the Contract Price arising out of Change of Scope or the works withdrawn under Clause 8.3 shall not affect the amounts payable for the items or stage payments thereof which are not affected by such Change of Scope or withdrawal. For avoidance of doubt and by way of illustration, the Parties agree that if the amount assigned to Major Bridges is reduced from Rs. 100 crore to Rs. 80 crore owing to Change of Scope or withdrawal of work, the reduction in payment shall be restricted to relevant payments for Major Bridges only and the payment due in respect of all other stage payments under the item Major Bridges shall not be affected in any manner. The Parties further agree that the adjustments arising out of the aforesaid modifications shall be carried out in a manner that the impact of such modifications is restricted to the said Change of Scope or withdrawal, as the case maybe, and does not alter the payments due for and in respect of items or stage payments which do not form part of such Change of Scope or withdrawal.

19.4 Stage Payment Statement for Works

The Contractor shall submit a statement (the “**Stage Payment Statement**”), in 3 (three) copies, by the 7th (seventh) day of the month to the Authority’s Engineer in the form outlined in Schedule-O, showing the amount calculated under Clause 19.3 to which the Contractor considers himself entitled for completed stage(s) of the Works. The Stage Payment Statement shall be accompanied by the progress reports and any other supporting documents. The Contractor shall not submit any claim for payment of incomplete stages of work.

19.5 Stage Payment for Works

- (i) Within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor under Clause 19.4, the Authority’s Engineer shall broadly determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment against the Stage Payment Statement, pending issue of the Interim Payment Certificate by the Authority’s Engineer. Within 10 (ten) days of the receipt of the recommendation of the Authority’s Engineer, the Authority shall make electronic payment directly to the Contractor’s bank account.
- (ii) Within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, the Authority’s Engineer shall determine and deliver to the Authority and the Contractor an IPC certifying the amount due and payable to the Contractor, after adjusting the payments already released to the Contractor against the said statement. For the avoidance of doubt, the Parties agree that the IPC shall specify all the amounts that have been deducted from the Stage Payment Statement and the reasons therefore.
- (iii) In cases where there is a difference of opinion as to the value of any stage, the Authority’s Engineer’s view shall prevail and interim payments shall be made to the Contractor on this basis; provided that the foregoing shall be without prejudice to the Contractor’s right to raise a Dispute.
- (iv) The Authority’s Engineer may, for reasons to be recorded, withhold from payment:
 - (a) the estimated value of work or obligation that the Contractor has failed to perform under this Agreement and the Authority’s Engineer had notified the Contractor; and
 - (b) the estimated cost of rectification of work done is not under this Agreement.
- (v) Payment by the Authority shall not be deemed to indicate the Authority’s acceptance, approval, consent, or satisfaction with the work done.

19.6 Deleted.

19.7 Deleted.

19.8 Payment of Damages

- (i) The Contractor may claim Damages due and payable to it under the provisions of this Agreement.
- (ii) The Authority's Engineer shall issue the IPC within 15 (fifteen) days of the receipt of the claim under Clause 19.8 (i), after making adjustments under the provisions of this Agreement. The Authority shall pay to the Contractor the amount due under any IPC within 30 (thirty) days from the date of the submission of the claim under Clause 19.8. In the event of the failure of the Authority to make payment to the Contractor within the specified time, the Authority shall be liable to pay to the Contractor interest thereon and the provisions of Clause 19.9 shall apply *mutatis mutandis* thereto.

19.9 Deleted.

19.10 Deleted.

19.11 Deleted.

19.12 Deleted.

19.13 Final Payment Statement

- (i) Within 60 (sixty) days after receiving the Completion Certificate under Clause 12.2, the Contractor shall submit to the Authority's Engineer for consideration 6 (six) copies of a Final Payment Statement (the "**Final Payment Statement**") for Works, with supporting documents showing in detail, in the form prescribed by the Authority's Engineer:
 - (a) the summary of Contractor's Stage Payment claims for Works as submitted under Clause 19.4;
 - (b) the amounts received from the Authority against each claim; and
 - (c) any further sums which the Contractor considers due to it from the Authority.

If the Authority's Engineer disagrees with or cannot verify any part of the Final Payment Statement, the Contractor shall submit such further information as the Authority's Engineer may reasonably require. The Authority's Engineer shall deliver to the Authority:

 - i. an IPC for those parts of the Final Payment Statement that are not in dispute, along with a list of disputed items that shall then be settled under the provisions of Article 26; or
 - ii. a Final Payment Certificate under Clause 19.15 if there are no disputed items.
- (ii) If the Authority's Engineer does not prescribe the form referred to in Clause 19.13 (i) within 15 (fifteen) days of the date of issue of the Completion Certificate, the Contractor shall submit the statement in such form as it deems fit.

19.14 Discharge

Upon submission of the Final Payment Statement for Works under Clause 19.13, the Contractor shall give to the Authority, with a copy to the Authority's Engineer, a written discharge confirming that the total of the Final Payment Statement represents full and final settlement of all monies due to the Contractor in respect of this Agreement for all the Works arising out of this Agreement, except for any monies due to either Party on account of any Defect. Provided that such discharge shall become effective only after the payment due has been made under the Final Payment Certificate issued under Clause 19.15.

19.15 Final Payment Certificate

- (i) Within 30 (thirty) days after receipt of the Final Payment Statement for Works under Clause 19.13, and the written discharge under Clause 19.14, and there being no disputed items of claim, the Authority's Engineer shall deliver to the Authority, with a copy to the Contractor, a final payment certificate (the "**Final Payment Certificate**") stating the amount which, in the opinion of the Authority's Engineer, is finally due under this Agreement or otherwise. For the avoidance of doubt, before issuing the Final Payment Certificate, the Authority's Engineer shall ascertain from the Authority all amounts previously paid by the Authority and for all sums to which the Authority is entitled, the balance, if any, due from the Authority to the Contractor or from the Contractor to the Authority, as the case may be.
- (ii) The Authority shall, under the provisions of Clause 19.9, pay to the Contractor the amount which is stated as being finally due in the Final Payment Certificate.

19.16 Deleted

19.17 Change in law

- (i) If as a result of Change in Law, the Contractor suffers any additional costs in the execution of the Works or relation to the performance of its other obligations under this Agreement, the Contractor shall, within 15 (fifteen) days from the date it becomes reasonably aware of such addition in cost, notify the Authority with a copy to the Authority's Engineer of such additional cost due to Change in Law.
- (ii) If as a result of Change in Law, the Contractor benefits from any reduction in costs for the execution of this Agreement or under the provisions of this Agreement, either Party shall, within 15 (fifteen) days from the date it becomes reasonably aware of such reduction in cost, notify the other Party with a copy to the Authority's Engineer of such reduction in cost due to Change in Law.
- (iii) The Authority's Engineer shall, within 15 (fifteen) days from the date of receipt of the notice from the Contractor or the Authority, determine any addition or reduction to the Contract Price, as the case may be, due to the Change in Law.

19.18 Correction of Interim Payment Certificates

The Authority's Engineer may by an Interim Payment Certificate make any correction or modification in any previous Interim Payment Certificate issued by the Authority's Engineer.

19.19 Authority's claims

If the Authority considers itself to be entitled to any payment from the Contractor under any Clause of this Agreement, it shall give notice and particulars to the Contractor 20 (twenty) days before making the recovery from any amount due to the Contractor and shall take into consideration the representation, if any, made by the Contractor in this behalf, before making such recovery.

19.20 Deleted

Article 20

Insurance

20.1 Insurance for Works and Maintenance

- (i) The Contractor shall effect and maintain at its own cost the insurances specified in Schedule-P and as per the requirements under the Applicable Laws.
- (ii) Subject to the provisions of Clause 21.6, the Authority and the Contractor shall, under its obligations as provided for in this Agreement, be liable to bear the cost of any loss or damage that does not fall within the scope of this Article 20 or cannot be recovered from the insurers.
- (iii) Subject to the exceptions specified in Clause 20.1 (iv) below, the Contractor shall save and except as provided for in this Agreement, fully indemnify, hold harmless, and defend the Authority from and against any and all losses, damages, costs, charges and/or claims concerning:
 - (a) the death of or injury to any person; or
 - (b) the loss of or damage to any property (other than the Works);
that may arise out of or in consequence of any breach by the Contractor of this Agreement during the execution of the Works or the remedying of any defects therein.
- (iv) Notwithstanding anything stated above in Clause 20.1 (iii), the Authority shall fully indemnify the Contractor from and against any and all losses, damages, costs, charges, proceedings, and/or claims arising out of or with respect to:
 - (a) the use or occupation of land or any part thereof by the Authority;
 - (b) the right of the Authority to execute the Works, or any part thereof, on, over, under, in, or through any land;
 - (c) the damage to property which is the unavoidable result of the execution and completion of the Works, or the remedying of any Defects therein, in accordance with this Agreement; and
 - (d) the death of or injury to persons or loss of or damage to property resulting from any act or neglect of the Authority, its agents, servants, or other contractors, not being employed by the Contractor.

Provided that, in the event of any injury or damage as a result of the contributory negligence of the Contractor, the Authority shall be liable to indemnify the Contractor from and against any and all losses, damages, costs, charges, proceedings, and/or claims to the extent as may be proportionately determined to be the liability of the Authority, its servants or agents or other contractors not associated with the Contractor in such injury or damage.

- (v) Without prejudice to the obligations of the Parties as specified under Clauses 20.1 (iii) and 20.1 (iv), the Contractor shall maintain or effect such third-party insurances as may be required under the Applicable Laws.
- (vi) The Contractor shall provide to the Authority, within 30 days of the Appointed Date, evidence of professional liability insurance maintained by its Design Director and/or consultants to cover the risk of professional negligence in the design of Works. The professional liability coverage shall be for a sum of not less than [3% (three percent)] of the Contract Price and shall be maintained until the end of the Defects Liability Period.

20.2 Notice to the Authority

No, later than 15 (fifteen) days after the date of this Agreement, the Contractor shall by notice furnish to the Authority, in reasonable detail, information in respect of the insurance that it proposes to effect and maintain under Article 20. Within 15 (fifteen) days of receipt of such notice, the Authority may require the Contractor to effect and maintain such other insurances as may be necessary pursuant hereto, and in the event of any difference or disagreement relating to any such insurance, the Dispute Resolution Procedure shall apply.

20.3 Evidence of Insurance Cover

- (i) All insurance obtained by the Contractor under Article 20 shall be maintained with insurers on terms consistent with Good Industry Practice. Within 10 (ten) days from the Appointed Date, the Contractor shall furnish to the Authority notarized true copies of the certificate(s) of insurance, copies of insurance policies, and premia payment receipts in respect of such insurance, and no such insurance shall be canceled, modified, or allowed to expire or lapse until the expiration of at least 45 (forty-five) days after notice of such proposed cancellation, modification or non-renewal has been delivered by the Contractor to the Authority. The Contractor shall act under the directions of the Authority. Provided that the Contractor shall produce to the Authority the insurance policies in force and the receipts for payment of the current premia.
- (ii) The Contractor shall ensure the adequacy of the insurance at all times under the provisions of this Agreement.

20.4 Remedy for failure to insure

If the Contractor shall fail to effect and keep in force all insurances for which it is responsible pursuant hereto, the Authority shall have the option to either keep in force any such insurances, and pay such premia and recover the costs thereof from the Contractor, or in the event of computation of a Termination Payment, treat an amount equal to the Insurance Cover as deemed to have been received by the Contractor.

20.5 Waiver of subrogation

All insurance policies in respect of the insurance obtained by the Contractor under this Article 20 shall include a waiver of any and all rights of subrogation or recovery of the insurers there under against, inter alia, the Authority, and its assigns, successors, undertakings and their subsidiaries, Affiliates, employees, insurers and under writers, and of any right of the insurers to any set-off or counter claim or any other deduction, whether by attachment or otherwise, in respect of any liability of any such person insured under any such policy or in any way connected with any loss, liability or obligation covered by such policies of insurance.

20.6 Contractor's waiver

The Contractor hereby further releases assigns and waives any and all rights of subrogation or recovery against, inter alia, the Authority and its assigns, undertakings and their subsidiaries, Affiliates, employees, successors, insurers, and underwriters, which the Contractor may otherwise have or acquire in or from or in any way connected with any loss, liability or obligation covered by policies of insurance maintained or required to be maintained by the Contractor pursuant to this Agreement (other than third party liability insurance policies) or because of deductible clauses in or inadequacy of limits of any such policies of insurance.

20.7 Cross liabilities

Any such insurance maintained or affected in pursuance of Article 20 shall include a cross-liability clause such that the insurance shall apply to the Contractor and to the Authority as separately insured.

20.8 Accident or injury to workmen

Notwithstanding anything stated in this Agreement, it is hereby expressly agreed between the Parties that the Authority shall not be liable for or in respect of any damages or compensation payable to any workman or other person in the employment of the Contractor or Sub-contractor, save and except as for death or injury resulting from any act, omission or willful default of the Authority, its agents or servants. The Contractor shall indemnify and keep indemnified the Authority from and against all such claims, proceedings, damages, costs, charges, and expenses whatsoever in respect of the above save and except for those acts, omissions, or willful defaults for which the Authority shall be liable.

20.9 Insurance against accidents for workmen

The Contractor shall effect and maintain during the Agreement such insurances as may be required to insure the Contractor's personnel and any other persons employed by it on the Project Highway from and against any liability incurred in pursuance of this Article 20. Provided that for this Clause 20.9, the Contractor's personnel/any person employed by the Contractor shall include the Subcontractor and its personnel. It is further provided that, in respect of any persons employed by any Sub-contractor, the Contractor

obligations to insure as aforesaid under Clause 20.9 shall be discharged if the Sub-contractor shall have insured against any liability in respect of such persons in such manner that the Authority is indemnified under the policy. The Contractor shall require such Sub-contractor to produce before the Authority when required, such policy of insurance and the receipt for payment of the current premium within 10 (ten) days of such demand being made by the Authority.

20.10 Application of insurance proceeds

The proceeds from all insurance claims, except for life and injury, shall be applied for any necessary repair, reconstruction, reinstatement, replacement, improvement, delivery, or installation of the Project Highway and the provisions of this Agreement in respect of construction of works shall apply *mutatis mutandis* to the works under taken out of the proceeds of insurance.

20.11 Compliance with policy conditions

Each Party hereby expressly agrees to fully indemnify the other Party from and against all losses and claims arising from its failure to comply with conditions imposed by the insurance policies affected under this Agreement.

20.12 General Requirements of Insurance Policies

The Contractor must:

- (a) immediately deposit copies of the policies or certificates of any insurance which it is required to effect under the Contract, together with receipts for the premiums;
- (b) effect all insurances for which the Contractor is responsible with an insurer approved by the Authority;
- (c) make no material changes to the terms of any insurance without the Authority's approval;
- (d) in all respects comply with any conditions stipulated in the insurance policies which the Contractor is required to effect under the Agreement or which the Authority has effected in relation to the Facility and notified to the Contractor; and shall provide all assistance to the Authority in the application form, and finalization of, such comprehensive insurance package;
- (e) regardless of the extent of settlement of claims by the underwriters or the time taken for settlement of claims, the Contractor shall make good any loss, or damage at its own cost promptly;
- (f) provide all assistance to the Authority in the application form, and finalization of, such comprehensive insurance package;
- (g) pay the Contractor's share of the insurance premiums for insurance premiums allocated under such comprehensive insurance package policy to

the insurance directly to the insurance provider promptly on demand. In case the Contractor fails to make such payment in time, the Authority may elect to pay the Contractor's share and adjust it against amounts payable to the Contractor under this Agreement;

- (h) in the case of the occurrence of any event leading to an insurance claim, promptly follow the procedures specified by the insurance provider, and provide full cooperation and access to the insurance provider or its representative, to settle the claim expeditiously;
- (i) require all the Sub-Contractors providing equipment and materials or services to the Contractor or the Authority to obtain, maintain, and keep in force during the time in which they are involved in the performance of the Works hereunder insurance coverage consistent with the Contractor's insurance obligations hereunder and the Contractor shall also be responsible for fulfillment of this requirement; and
- (j) the required insurance coverage and the Contractor's obligations-referred to shall in no way affect or limit the Contractor's liability concerning its performance of the Works. Nothing in this Section shall limit or relieve the Contractor of its liabilities and obligations under this Agreement.

PartV

Force Majeure and Termination

Article 21

Force Majeure

21.1 Force Majeure

As used in this Agreement, the expression “**Force Majeure**” or “**Force Majeure Event**” shall mean the occurrence in India of any or all Non-Political Events, Indirect Political Events and Political Events, as defined in Clauses 21.2, 21.3, and 21.4 respectively, if it affects the performance by the Party claiming the benefit of Force Majeure (the “**Affected Party**”) of its obligations under this Agreement and which act or event (i) is beyond the reasonable control of the Affected Party, and (ii) the Affected Party could not have prevented or overcome by exercise of due diligence and following Good Industry Practice, and (iii) has Material Adverse Effect on the Affected Party.

21.2 Non-Political Event

A Non-Political Event shall mean one or more of the following acts or events:

- (a) act of God, epidemic, extremely adverse weather conditions, lightning, earthquake, landslide, cyclone, flood, volcanic eruption, chemical or radioactive contamination or ionizing radiation, fire or explosion (to the extent of contamination or radiation or fire or explosion originating from a source external to the Site);
- (b) strikes or boycotts (other than those involving the Contractor, Subcontractors, or their respective employees/ representatives, or attributable to any act or omission of any of them) interrupting supplies and services to the Project Highway for a continuous period of 24 (twenty-four) hours and an aggregate period exceeding 10 (ten) days in an Accounting Year, and not being an Indirect Political Event outlined in Clause 21.3;
- (c) any failure or delay of a Sub-contractor but only to the extent caused by another Non-Political Event;
- (d) any judgment or order of any court of competent jurisdiction or statutory authority made against the Contractor in any proceedings for reasons other than (i) failure of the Contractor to comply with any Applicable Law or Applicable Permit, or (ii) on account of breach of any Applicable Law or Applicable Permit or of any contract, or (iii) enforcement of this Agreement, or (iv) exercise of any of its rights under this Agreement by the Authority;
- (e) the discovery of geological conditions, toxic contamination, or archaeological remains on the Site that could not reasonably have been expected to be discovered through a site inspection; or
- (f) any event or circumstances of a nature analogous to any of the foregoing.

21.3 Indirect Political Event

An Indirect Political Event shall mean one or more of the following acts or events:

- (a) an act of war (whether declared or undeclared), invasion, armed conflict or act of a foreign enemy, blockade, embargo, riot, insurrection, terrorist or military action, civil commotion, or politically motivated sabotage;
- (b) industry-wide or State-wide strikes or industrial action for a continuous period of 24 (twenty-four) hours and exceeding an aggregate period of 10 (ten) days in an Accounting Year;
- (c) any civil commotion, boycott, or political agitation which prevents construction of the Project Highway by the Contractor for an aggregate period exceeding 10 (ten) days in an Accounting Year;
- (d) any failure or delay of a Sub-contractor to the extent caused by any Indirect Political Event;
- (e) any Indirect Political Event that causes a Non-Political Event; or
- (f) any event or circumstances of a nature analogous to any of the foregoing.

21.4 Political Event

A Political Event shall mean one or more of the following acts or events by or on account of any Government Instrumentality:

- (a) Change in Law, only if consequences thereof cannot be dealt with under and under the provisions of Clause 19.17;
- (b) compulsory acquisition in the national interest or expropriation of any Project Assets or rights of the Contractor or of the Sub-Contractors;
- (c) unlawful or unauthorized or without jurisdiction revocation of, or refusal to renew or grant without valid cause, any clearance, license, permit, authorization, no objection certificate, consent, approval or exemption required by the Contractor or any of the Sub-contractors to perform their respective obligations under this Agreement; provided that such delay, modification, denial, refusal or revocation did not result from the Contractor's or any Sub-contractors inability or failure to comply with any condition relating to grant, maintenance or renewal of such clearance, license, authorization, no objection certificate, exemption, consent, approval or permit;
- (d) any failure or delay of a Sub-contractor but only to the extent caused by another Political Event; or
- (e) any event or circumstances of a nature analogous to any of the foregoing.

21.5 Duty to report Force Majeure Event

- (i) Upon occurrence of a Force Majeure Event, the Affected Party shall by notice report such occurrence to the other Party forthwith. Any notice pursuant hereto shall include full particulars of:

- (a) the nature and extent of each Force Majeure Event which is the subject of any claim for relief under this Article 21 with evidence in support thereof;
 - (b) the estimated duration and the effect or probable effect which such Force Majeure Event is having or will have on the Affected Party's performance of its obligations under this Agreement;
 - (c) the measures which the Affected Party is taking or proposes to take for all eviating the impact of such Force Majeure Event; and
 - (d) any other information relevant to the Affected Party's claim.
- (ii) The Affected Party shall not be entitled to any relief for or in respect of a Force Majeure Event unless it shall have notified the other Party of the occurrence of the Force Majeure Event as soon as reasonably practicable, and in any event no later than 10 (ten) days after the Affected Party knew, or ought reasonably to have known, of its occurrence, and shall have given particulars of the probable material effect that the Force Majeure Event is likely to have on the performance of its obligations under this Agreement.
- (iii) For so long as the Affected Party continues to claim to be materially affected by such Force Majeure Event, it shall provide the other Party with regular (and not less than weekly) reports containing the information as required by Clause 21.5 (i), and such other information as the other Party may reasonably request the Affected Party to provide.

21.6 Effect of Force Majeure Event on the Agreement

- (i) Upon the occurrence of any Force Majeure after the Appointed Date, the costs incurred and attributable to such event and directly relating to this Agreement (the "**Force Majeure costs**") shall be allocated and paid as follows:
- (a) upon occurrence of a Non-Political Event, the Parties shall bear their respective Force Majeure costs and neither Party shall be required to pay to the other Party any costs thereof;
 - (b) upon occurrence of an Indirect Political Event, all Force Majeure costs attributable to such Indirect Political Event, and not exceeding the Insurance Cover for such Indirect Political Event, shall be borne by the Contractor, and to the extent Force Majeure costs exceed such Insurance Cover, one half of such excess amount shall be reimbursed by the Authority to the Contractor for the Force Majeure events; and
 - (c) upon occurrence of a Political Event, all Force Majeure costs attributable to such Political Event shall be reimbursed by the Authority to the Contractor.
 - (d) For the avoidance of doubt, Force Majeure costs may include costs directly attributable to the Force Majeure Event, but shall not include debt repayment obligations, if any, of the Contractor.
- (ii) Save and except as expressly provided in this Article 21, neither Party shall be liable

in any manner whatsoever to the other Party in respect of any loss, damage, cost, expense, claims, demands and proceedings relating to or arising out of the occurrence or existence of any Force Majeure Event or exercise of any right pursuant hereto.

- (iii) Upon the occurrence of any Force Majeure Event during the Construction Period, the Project Completion Schedule for and in respect of the affected Works shall be extended on a day-for-day basis for such period as the performance of the Contractor's obligations is affected on account of the Force Majeure Event or its subsisting effects.

21.7 Termination Notice for Force Majeure Event

- (i) If a Force Majeure Event subsists for 60 (sixty) days or more within a continuous period of 120 (one hundred and twenty) days, either Party may at its discretion terminate this Agreement by issuing a Termination Notice to the other Party without being liable in any manner whatsoever, save as provided in this Article 21, and upon the issue of such Termination Notice, this Agreement shall, notwithstanding anything to the contrary contained herein, stand terminated forthwith; provided that before issuing such Termination Notice, the Party intending to issue the Termination Notice shall inform the other Party of such intention and grant 15 (fifteen) days to make a representation, and may after the expiry of such 15 (fifteen) days period, whether or not it is in receipt of such representation, in its sole discretion issue the Termination Notice.

21.8 Termination Payment for Force Majeure Event

- (i) In the event of this Agreement being terminated on account of a Non-Political Event, the Termination Payment shall be an amount equal to the sum payable under Clause 23.5.

Provided that in the event Termination occurs during the Maintenance Period, the Authority's Engineer shall only determine the value of Works associated with Maintenance.

- (ii) If Termination is on account of an Indirect Political Event, the Termination Payment shall include:
 - (a) any sums due and payable under Clause 23.5; and
 - (b) the reasonable cost, as determined by the Authority's Engineer, of the Plant and Materials procured by the Contractor and transferred to the Authority for use in Construction or Maintenance, only if such Plant and Materials are in conformity with the Specifications and Standards;

Provided that in the event Termination occurs during the Maintenance Period, the Authority's Engineer shall only determine the value of Works associated with Maintenance.

- (iii) If Termination is on account of a Political Event, the Authority shall make a Termination Payment to the Contractor in an amount that would be payable under Clause 23.6 (ii) as if it were an Authority Default.

21.9 Dispute resolution

If the Parties are unable to agree in good faith about the occurrence or existence of a Force Majeure Event, such Dispute shall be finally settled under the DisputeResolution Procedure; provided that the burden of proof as to the occurrence or existence of such Force Majeure Event shall be upon the Party claiming relief and/ or excuse on account of such Force Majeure Event.

21.10 Excuse from the performance of obligations

If the Affected Party is rendered wholly or partially unable to perform its obligations under this Agreement because of a Force Majeure Event, it shall be excused from performance of such of its obligations to the extent it is unable to perform on account of such Force Majeure Event; provided that:

- (a) the suspension of performance shall be of no greater scope and no longer duration than is reasonably required by the Force Majeure Event;
- (b) the AffectedParty shall make all reasonable efforts to mitigate or limit damage to the other Party arising out of or as a result of the existence or occurrence of such Force Majeure Event and to cure the same with due diligence; and
- (c) when the Affected Party can resume the performance of its obligations under this Agreement, it shall give to the other Party notice to that effect and shall promptly resume the performance of its obligations hereunder.

Article 22

Suspension of Contractor's Rights

22.1 Suspension upon Contractor Default

Upon occurrence of a Contractor Default, the Authority shall be entitled, without prejudice to its other rights and remedies under this Agreement including its rights of Termination hereunder, to (i) suspend carrying out of the Works or Maintenance or any part thereof, and (ii) carry out such Works or Maintenance itself or authorize any other person to exercise or perform the same on its behalf during such suspension (the "Suspension"). Suspension hereunder shall be effective forthwith upon issue of notice by the Authority to the Contractor and may extend up to a period not exceeding 90 (ninety) days from the date of issue of such notice.

22.2 Authority to act on behalf of the Contractor

During the period of Suspension hereunder, all rights and liabilities vested in the Contractor under the provisions of this Agreement shall continue to vest therein and all things done or actions taken, including expenditure incurred by the Authority for discharging the obligations of the Contractor under and under this Agreement shall be deemed to have been done or taken for and on behalf of the Contractor and the Contractor undertakes to indemnify the Authority for all costs incurred during such period. The Contractor hereby licenses and sub-licenses respectively, the Authority or any other person authorized by it under Clause 22.1 to use during Suspension, all Intellectual Property belonging to or licensed to the Contractor concerning the Project Highway and its design, engineering, construction and maintenance, and which is used or created by the Contractor in performing its obligations under the Agreement.

22.3 Revocation of Suspension

- (i) In the event that the Authority shall have rectified or removed the cause of Suspension within a period not exceeding 60 (sixty) days from the date of Suspension, it shall revoke the Suspension forthwith and restore all rights of the Contractor under this Agreement. For the avoidance of doubt, the Parties expressly agree that the Authority may, at its discretion, revoke the Suspension at any time, whether or not the cause of Suspension has been rectified or removed hereunder.
- (ii) Upon the Contractor having cured the Contractor Default within a period not exceeding 60 (sixty) days from the date of Suspension, the Authority shall revoke the Suspension forthwith and restore all rights of the Contractor under this Agreement.

22.4 Termination

- (i) At any time during the period of Suspension under this Article 22, the Contractor may by notice require the Authority to revoke the Suspension and issue a Termination

Notice. The Authority shall, within 15 (fifteen) days of receipt of such notice, terminate this Agreement under and under Article 23.

- (ii) Notwithstanding anything to the contrary contained in this Agreement, if Suspension is not revoked within 90 (ninety) days from the date of Suspension hereunder, the Agreement shall, upon expiry of the aforesaid period, be deemed to have been terminated by mutual agreement of the Parties and all the provisions of this Agreement shall apply, *mutatis mutandis*, to such Termination as if a Termination Notice had been issued by the Authority upon occurrence of a Contractor Default.

Article 23

Termination

23.1 Termination for Contractor Default

- (i) Save as otherwise provided in this Agreement, if any of the defaults specified below shall have occurred, and the Contractor fails to cure the default within the Cure Period set forth below, or where no Cure Period is specified, then within a Cure Period of 60 (sixty) days, the Contractor shall be deemed to be in default of this Agreement (the “**Contractor Default**”), unless the default has occurred solely as a result of any breach of this Agreement by the Authority or due to Force Majeure. The defaults referred to herein shall include:
- (a) the Contractor fails to provide, extend, or replenish, as the case may be, the Performance Security under this Agreement;
 - (b) after the replenishment or furnishing of fresh Performance Security under Clause 7.3, the Contractor fails to cure, within a Cure Period of 30 (thirty) days, the Contractor Default for which the whole or part of the Performance Security was appropriated;
 - (c) the Contractor does not achieve the latest outstanding Project Milestone due under the provisions of Schedule-J, subject to any Time Extension, and continues to be in default for 45 (forty-five) days;
 - (d) the Contractor abandons or manifests an intention to abandon the construction or Maintenance of the Project Highway without the prior written consent of the Authority;
 - (e) the Contractor fails to proceed with the Works under the provisions of Clause 10.1 or stops Works and/or the Maintenance for 30 (thirty) days without reflecting the same in the current program and such stoppage has not been authorized by the Authority’s Engineer;
 - (f) the Project Completion Date does not occur within the period specified in Schedule-J for the Scheduled Completion Date, or any extension thereof;
 - (g) the Contractor fails to rectify any Defect, the non-rectification of which shall have a Material Adverse Effect on the Project, within the time specified in this Agreement or as directed by the Authority’s Engineer;
 - (h) the Contractor subcontracts the Works or any part thereof in violation of this Agreement or assigns any part of the Works or the Maintenance without the prior approval of the Authority;
 - (i) the Contractor creates any Encumbrance in breach of this Agreement;
 - (j) an execution levied on any of the assets of the Contractor has caused a Material Adverse Effect;

- (k) the Contractor is adjudged bankrupt or insolvent, or if a trustee or receiver is appointed for the Contractor or for the whole or material part of its assets that has a material bearing on the Project;
- (l) the Contractor has been, or is in the process of being liquidated, dissolved, wound-up, amalgamated, or reconstituted in a manner that would cause, in the reasonable opinion of the Authority, a Material Adverse Effect;
- (m) a resolution for winding up or insolvency of the Contractor is passed, or any petition for winding up or insolvency of the Contractor is admitted by a court of competent jurisdiction and a provisional liquidator or receiver or interim resolution professional, as the case may be, is appointed and such order has not been set aside within 90 (ninety) days of the date thereof or the Contractor is ordered to be wound up by court except for amalgamation or reconstruction; provided that, as part of such amalgamation or reconstruction, the entire property, assets, and undertaking of the Contractor are transferred to the amalgamated or reconstructed entity and that the amalgamated or reconstructed entity has unconditionally assumed the obligations of the Contractor under this Agreement; and provided that:
 - i. the amalgamated or reconstructed entity has the capability and experience necessary for the performance of its obligations under this Agreement; and
 - ii. the amalgamated or reconstructed entity has the financial standing to perform its obligations under this Agreement and has credit worthiness at least as good as that of the Contractor as at the Appointed Date;
- (n) any representation or warranty of the Contractor herein contained which is, as of the date hereof, found to be false or the Contractor is at any time hereafter found to be in breach or non-compliance thereof;
- (o) the Contractor submits to the Authority any statement, notice, or other document, in written or electronic form, which has a material effect on the Authority's rights, obligations, or interests and which is false in material particulars;
- (p) the Contractor has failed to fulfill any obligation, for which failure Termination has been specified in this Agreement; or
- (q) the Contractor commits a default in complying with any other provision of this Agreement if such a default causes a Material Adverse Effect on the Project or the Authority.
- (r) gives or offers to give (directly or indirectly) to any person any bribe, gift, gratuity, commission, or other thing of value, as an inducement or reward:
 - i. for doing or for bearing to do any action concerning the Contract, or
 - ii. for showing or forbearing to show favour or disfavour to any person in relation to the Contract,or if any of the Contractor's personnel, agents, or subcontractors gives or offers to give (directly or indirectly) to any person any such inducement or

reward as is described in this subparagraph (s). However, lawful inducements and rewards to the Contractor's Personnel shall not entitle termination.

- (ii) Without prejudice to any other rights or remedies which the Authority may have under this Agreement, upon occurrence of a Contractor Default, the Authority shall be entitled to terminate this Agreement by issuing a Termination Notice to the Contractor; provided that before issuing the Termination Notice, the Authority shall by a notice inform the Contractor of its intention to issue such Termination Notice and grant 15 (fifteen) days to the Contractor to make a representation, and may after the expiry of such 15 (fifteen) days, whether or not it receives such representation, issue the Termination Notice.
- (iii) The following shall apply in respect of cure of any of the defaults and/ or breaches of the Agreement:
 - (a) The Cure Period shall commence from the date of the notice by the Authority to the Contractor asking the latter to cure the breach or default specified in such notice;
 - (b) The Cure Period provided in the Agreement shall not relieve the Contractor from liability for Damages caused by its breach or default;
 - (c) The Cure Period shall not in any way be extended by any period of suspension under the Agreement;
 - (d) If the cure of any breach by the Contractor requires any reasonable action by the Contractor that must be approved by the Authority hereunder the applicable Cure Period (and any liability of the Contractor for damages incurred) shall be extended by the period taken by the Authority to accord its required approval.
- (iv) After termination of this Agreement for Contractor Default, the Authority may complete the Works and/or arrange for any other entities to do so. The Authority and these entities may then use any Materials, Plant and equipment, Contractor's documents and other design documents made by or on behalf of the Contractor.

23.2 Termination for Authority Default

- (i) If any of the defaults specified below shall have occurred, and the Authority fails to cure such default within a Cure Period of 90 (ninety) days or such longer period as has been expressly provided in this Agreement, the Authority shall be deemed to be in default of this Agreement (the "**Authority Default**") unless the default has occurred as a result of any breach of this Agreement by the Contractor or due to Force Majeure. The defaults referred to herein shall include:
 - (a) the Authority commits a material default in complying with any of the provisions of this Agreement and such default has a Material Adverse Effect on the Contractor;
 - (b) the Authority has failed to make payment of any amount due and payable to the Contractor within the period specified in this Agreement;

- (c) the Authority has failed to provide, within a period of 180 (one hundred and eighty) days from the Appointed Date, the environmental clearances required for construction of the Project Highway;
 - (d) the Authority becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compounds with its creditors, or carries on business under a receiver, trustee, or manager for the benefit of its creditors, or if any act is done or event occurs which (under Applicable Laws) has a similar effect;
 - (e) the Authority repudiates this Agreement or otherwise takes any action that amounts to or manifests an irrevocable intention not to be bound by this Agreement;
 - (f) the Authority's Engineer fails to issue the relevant Interim Payment Certificate within 60 (sixty) days after receiving a statement and supporting documents; or
 - (g) the whole work is suspended by the Authority beyond 120 (one hundred twenty) days for any reason which is not attributed to the Contractor.
- (ii) Without prejudice to any other right or remedy which the Contractor may have under this Agreement, upon occurrence of an Authority Default, the Contractor shall be entitled to terminate this Agreement by issuing a Termination Notice to the Authority; provided that before issuing the Termination Notice, the Contractor shall by a notice inform the Authority of its intention to issue the Termination Notice and grant 15 (fifteen) days to the Authority to make a representation, and may after the expiry of such 15 (fifteen) days, whether or not it receives such representation, issue the Termination Notice.

If on the consideration of the Authority's representation or otherwise, the contractor does not issue the Termination Notice on such 15th (fifteenth) day and prefers to continue with the project, it is deemed that the cause of action of the Termination Notice has been condoned by the Contractor and he would be deemed to have waived any claim and forfeited any right to any other remedy on that count or concerning such action or omission.

23.3 Termination for the Authority's convenience

Notwithstanding anything stated hereinabove, the Authority may terminate this Agreement for convenience. The termination shall take effect 30 (thirty) days from the date of notice provided to the Contractor.

23.4 Requirements after Termination

Upon Termination of this Agreement under the terms of Article 23, the Contractor shall comply with and conform to the following:

- (a) deliver all relevant records, reports, Intellectual Property, and other licenses pertaining to the Works, Maintenance, and other design documents;
- (b) transfer and/or deliver all Applicable Permits to the extent permissible under Applicable Laws; and
- (c) vacate the Site within 15 (fifteen) days.

23.5 Valuation of Unpaid Works

- (i) Within 45 (forty-five) days after Termination under Clause 23.1, 23.2, or 23.3, as the case may be, has taken effect, the Authority's Engineer shall proceed under Clause 18.5 to determine as follows the valuation of unpaid Works (the "**Valuation of Unpaid Works**"):
 - (a) value of the completed stage of the Works, less payments already made;
 - (b) reasonable value of the partially completed stages of works as on the date of Termination, only if such works conform with the Specifications and Standards; and
 - (c) value of Maintenance, if any, for completed months, less payments already made, and shall adjust from the sum thereof (i) any other amounts payable or recoverable, as the case may be, under the provisions of this Agreement; and (ii) all taxes due to be deducted at source.
- (ii) The Valuation of Unpaid Works shall be communicated to the Authority, with a copy to the Contractor, within 30 (thirty) days from the date of Termination.

23.6 Termination Payment

- (i) Upon Termination on account of Contractor's Default under Clause 23.1, the Authority shall:
 - (a) encash and appropriate the Performance Security, Additional Performance Security if any, and Retention Money, or in the event the Contractor has failed to replenish or extend the Performance Security and Additional Performance Security if any, claim the amount stipulated in Clause 7.1, as agreed pre-determined compensation to the Authority for any losses, delays, and cost of completing the Works and Maintenance, if any;
 - (b) encash and appropriate the Bank Guarantee, if any, for and in respect of the outstanding Advance Payment and interest thereon; and
 - (c) pay to the Contractor, by way of Termination Payment, an amount equivalent to the Valuation of Unpaid Works after adjusting any other sums payable or recoverable, as the case may be, under the provisions of this Agreement.
- (ii) Upon Termination on account of an Authority Default under Clause 23.2 or for the Authority's convenience under Clause 23.3, the Authority shall:

- (a) return the Performance Security, Additional Performance Security, and Retention Money forthwith;
 - (b) encash and appropriate the bank guarantee, if any, for and in respect of the outstanding Advance Payment; and
 - (c) pay to the Contractor, by way of Termination Payment, an amount equal to:
 - i. Valuation of Unpaid Works;
 - ii. the reasonable cost of temporary works, as determined by the Authority's Engineer; and
 - iii. 10% (ten percent) of the cost of the Works and Maintenance that are not commenced or not completed,and shall adjust from the sum thereof (i) any other amounts payable or recoverable, as the case may be, under the provisions of this Agreement, and (ii) all taxes due to be deducted at source.
- (iii) Termination Payment shall become due and payable to the Contractor within 30 (thirty) days of a demand being made by the Contractor to the Authority with the necessary particulars, and in the event of any delay, the Authority shall pay interest at Bank Rate + 3% per annum, on the amount of Termination Payment remaining unpaid; provided that such delay shall not exceed 90 (ninety) days. For the avoidance of doubt, it is expressly agreed that Termination Payment shall constitute full discharge by the Authority of its payment obligations in respect thereof hereunder.
- (iv) The Contractor expressly agrees that Termination Payment under this Article 23 shall constitute a full and final settlement of all claims of the Contractor on account of Termination of this Agreement and that it shall not have any further right or claim under any law, treaty, convention, contract or otherwise.

23.7 Other rights and obligations of the Parties

Upon Termination for any reason whatsoever:

- (a) property and ownership in all Materials, Plant and Works and the Project Highway shall, as between the Contractor and the Authority, vest in the Authority in whole; provided that the foregoing shall be without prejudice to Clause 23.6;
- (b) risk of loss or damage to any Materials, Plant, or Works, and the care and custody thereof shall pass from the Contractor to the Authority; and
- (c) the Authority shall be entitled to restrain the Contractor and any person claiming through or under the Agreement from entering upon the Site or any part of the Project, which have not been vested in the Authority under the provisions of this Agreement.

23.8 Survival of rights

Notwithstanding anything to the contrary contained in this Agreement any Termination under the provisions of this Agreement shall be without prejudice to the accrued rights of either Party including its right to claim and recover money damages, insurance proceeds, security deposits, and other rights and remedies, which it may have in law or Agreement. All rights and obligations of either Party under this Agreement, including Termination Payments, shall survive the Termination to the extent such survival is necessary for giving effect to such rights and obligations.

23.9 Foreclosure with mutual consent

- (i) Without prejudice to any provision of this Agreement, the Authority and Contractor may foreclose this Agreement by mutual consent in circumstances which do not constitute either party's default without any liability or consequential future liability for either party.
- (ii) Should a Party intend to foreclose this Agreement by mutual consent, the intending Party shall issue a notice to the other Party, and upon issuance of such notice, the other Party may within 15 days from receipt of such notice either agree to such foreclosure or raise objection(s) to the same by intimating either of the two possible positions to the intending Party in writing.
- (iii) In either case of the other Party agreeing to the proposed foreclosure or otherwise, the Parties may negotiate the proposed foreclosure and sign a Supplementary Agreement for foreclosure to the main Contract Agreement within 30 (thirty) days of the date agreed by both Parties. Foreclosure shall not come into effect unless and otherwise Supplementary Agreement is signed.
- (iv) Any attempt or endeavor for foreclosure by mutual agreement shall be without prejudice to the rights and obligations of the Parties herein and the factum of such an attempt or exercise shall not stop either of the Parties from discharging their contractual obligations under this Agreement.
- (v) For the avoidance of doubt, it is clarified that such foreclosure will be without prejudice to the Contractor and shall not affect the Contractor in any way if it wishes to bid in future projects of the Authority.

Part VI
Other Provisions

Article 24

Assignment and Charges

24.1 strictions on assignments and charges

This Agreement shall not be assigned by the Contractor to any person, save and except with the prior consent in writing of the Authority, which consent the Authority shall be entitled to decline without assigning any reason.

24.2 Hypothecation of Materials or Plant

Notwithstanding the provisions of Clause 24.1, the Contractor may pledge or hypothecate to its lenders, any Materials or Plant before their incorporation in the Works. Further, the Contractor may, by written notice to the Authority, assign its right to receive payments under this Agreement either absolutely or by way of charge, to any person providing financing to the Contractor in connection with the performance of the Contractor's obligations under this Agreement. The Contractor acknowledges that any such assignment by the Contractor shall not relieve the Contractor from any obligations, duty, or responsibility under this Agreement.

Article25

Liability and Indemnity

25.1 General indemnity

- (i) The Contractor will indemnify, defend, save, and hold harmless the Authority and its officers, servants, agents, Government Instrumentalities, and Government-owned and/or controlled entities/enterprises, (the “**Authority Indemnified Persons**”) against any and all suits, proceedings, actions, demands and third party claims for any loss, damage, cost and expense of whatever kind and nature, whether arising out of any breach by the Contractor of any of its obligations under this Agreement or from any negligence under the Agreement, including any errors or deficiencies in the design documents, or tort or on any other ground whatsoever, except to the extent that any such suits, proceedings, actions, demands, and claims have arisen due to any negligent act or omission, or breach or default of this Agreement on the part of the Authority Indemnified Persons.

25.2 Indemnity by the Contractor

- (i) Without limiting the generality of Clause 25.1, the Contractor shall fully indemnify, hold harmless, and defend the Authority and the Authority Indemnified Persons from and against any and all loss and/or damages arising out of or concerning:
 - (a) failure of the Contractor to comply with Applicable Laws and Applicable Permits;
 - (b) payment of taxes required to be made by the Contractor in respect of the income or other taxes of the Sub-contractors, suppliers, and representatives; or
 - (c) non-payment of amounts due because of Materials or services furnished to the Contractor or any of its Sub-contractors which are payable by the Contractor or any of its Sub-contractors.
- (ii) Without limiting the generality of the provisions of this Article 25, the Contractor shall fully indemnify, hold harmless, and defend the Authority Indemnified Persons from and against any and all suits, proceedings, actions, claims, demands, liabilities, and damages which the Authority Indemnified Persons may hereafter suffer, or pay because of any demands, claims, suits or proceedings arising out of claims of infringement of any domestic or foreign patent rights, copyrights or other intellectual property, proprietary or confidentiality rights concerning any materials, information, design or process used by the Contractor or by the Sub-contractors in performing the Contractor’s obligations or in any way incorporated in or related to the Project. If in any such suit, action, claim, or proceedings, a temporary restraint order or preliminary injunction is granted, the Contractor shall make every reasonable effort, by giving a satisfactory bond or otherwise, to secure the revocation or suspension of the injunction or restraint order. If, in any such suit, action, claim, or proceedings, the Project Highway, or any part thereof or comprised therein, is held to constitute

an infringement and its use is permanently enjoined, the Contractor shall promptly make every reasonable effort to secure for the Authority a license, at no cost to the Authority, authorizing the continued use of the infringing work. If the Contractor is unable to secure such license within a reasonable time, the Contractor shall, at its own expense, and without impairing the Specifications and Standards, either replace the affected work, or part, or process thereof with non-infringing work or part or process or modify the same so that it becomes non-infringing.

25.3 Notice and contest of claims

If either Party receives a claim or demand from a third party in respect of which it is entitled to the benefit of an indemnity under this Article 25 (the "**Indemnified Party**") it shall notify the other Party (the "**Indemnifying Party**") within 15 (fifteen) days of receipt of the claim or demand and shall not settle or pay the claim without the prior approval of the Indemnifying Party, which approval shall not be unreasonably withheld or delayed. If the Indemnifying Party wishes to contest or dispute the claim or demand, it may conduct the proceedings in the name of the Indemnified Party, subject to the Indemnified Party being secured against any costs involved, to its reasonable satisfaction.

25.4 Defense of claims

- (i) The Indemnified Party shall have the right, but not the obligation, to contest, defend, and litigate any claim, action, suit, or proceeding by any third party alleged or asserted against such Party in respect of, resulting from, related to or arising out of any matter for which it is entitled to be indemnified hereunder, and reasonable costs and expenses thereof shall be indemnified by the Indemnifying Party. If the Indemnifying Party acknowledges in writing its obligation to indemnify the Indemnified Party in respect of loss to the full extent provided by this Article 25, the Indemnifying Party shall be entitled, at its option, to assume and control the defense of such claim, action, suit or proceeding, liabilities, payments and obligations at its expense and through the counsel of its choice; provided it gives prompt notice of its intention to do so to the Indemnified Party and reimburses the Indemnified Party for the reasonable cost and expenses incurred by the Indemnified Party before the assumption by the Indemnifying Party of such defense. The Indemnifying Party shall not be entitled to settle or compromise any claim, demand, action, suit, or proceeding without the prior written consent of the Indemnified Party unless the Indemnifying Party provides such security to the Indemnified Party as shall be reasonably required by the Indemnified Party to secure the loss to be indemnified hereunder to the extent so compromised or settled.
- (ii) If the Indemnifying Party has exercised its rights under Clause 25.3, the Indemnified Party shall not be entitled to settle or compromise any claim, action, suit, or proceeding without the prior written consent of the Indemnifying Party (which consent shall not be unreasonably withheld or delayed).

- (iii) If the Indemnifying Party exercises its rights under Clause 25.3, the Indemnified Party shall nevertheless have the right to employ its counsel, and such counsel may participate in such action, but the fees and expenses of such counsel shall be at the expense of the Indemnified Party, when and as incurred, unless:
- (a) the employment of counsel by such party has been authorized in writing by the Indemnifying Party; or
 - (b) the Indemnified Party shall have reasonably concluded that there may be a conflict of interest between the Indemnifying Party and the Indemnified Party in the conduct of the defense of such action; or
 - (c) the Indemnifying Party shall not have employed independent counsel reasonably satisfactory to the Indemnified Party, to assume the defense of such action and shall have been so notified by the Indemnified Party; or
 - (d) the Indemnified Party shall have reasonably concluded and specifically notified the Indemnifying Party either:
 - i. that there may be specific defenses available to it that are different from or additional to those available to the Indemnifying Party; or
 - ii. that such claim, action, suit or proceeding involves or could have a material adverse effect upon it beyond the scope of this Agreement:

Provided that if Sub-clauses (b), (c), or (d) of this Clause 25.4 (iii) shall be applicable, the counsel for the Indemnified Party shall have the right to direct the defense of such claim, demand, action, suit or proceeding on behalf of the Indemnified Party, and the reasonable fees and disbursements of such counsel shall constitute legal or other expenses hereunder.

25.5 Survival on termination

The provisions of this Article 25 shall survive Termination.

Article 26 Dispute

Resolution

26.1 Dispute Resolution

- (i) Any dispute, difference, or controversy of whatever nature howsoever arising under or out of or concerning this Agreement (including its interpretation) between the Parties, and so notified in writing by either Party to the other Party (the “**Dispute**”) shall, in the first instance, be attempted to be resolved amicably under the conciliation procedure outlined in Clause 26.2.
- (ii) The Parties agree to use their best efforts for resolving all Disputes arising under or in respect of this Agreement promptly, equitably, and in good faith and further agree to provide each other with reasonable access during normal business hours to all non-privileged records, information, and data about any Dispute.

26.2 Conciliation

In the event of any Dispute between the Parties, either Party may call upon the Authority’s Engineer or such other person as the Parties may mutually agree upon (the “**Conciliator**”) to mediate and assist the Parties in arriving at an amicable settlement thereof. Failing mediation by the Conciliator or without the intervention of the Conciliator, either Party may require such Dispute to be referred to the Chairman of the Authority and the Chairman of the Board of Directors of the Contractor for amicable settlement, and upon such reference, the said persons shall meet no later than 7 (seven) business days from the date of reference to discuss and attempt to amicably resolve the Dispute. If such meeting does not take place within the 30 (thirty) business day period or the Dispute is not amicably settled within 30 (thirty) days of the meeting or the Dispute is not resolved as evidenced by the signing of written terms of settlement within 30 (thirty) days of the notice in writing referred to in Clause 26.1.1 or such longer period as may be mutually agreed by the Parties, either Party may refer the Dispute to arbitration under the provisions of Clause 26.3 but before resorting to such arbitration, the parties agree to explore conciliation by the Conciliation Committees of Independent Experts set up by the Authority under the procedure decided by the panel of such experts and notified by the Authority on its website including its subsequent amendments. In the event of the conciliation proceedings being successful, the parties to the dispute would sign the written settlement agreement and the conciliators would authenticate the same. Such a settlement agreement would then be binding on the parties in terms of Section 73 of the Arbitration Act. In case of failure of the conciliation process even at the level of the Conciliation Committee, either party may refer the Dispute to arbitration under the provisions of Clause 26.3.

26.3 Arbitration

- (i) Any dispute that remains unresolved between the parties through the mechanisms available/ prescribed in the Agreement, irrespective of any claimed value, which has not been agreed upon/reached settlement by the parties, will be referred to the

Arbitral Tribunal as per the Arbitration and Conciliation Act.

- (ii) Deleted
- (iii) The Arbitral Tribunal shall make are as one daward (the“Award”). Any Award made in any arbitration held under Article 26 shall be final and binding on the Parties as from the date it is made, and the Contractor and the Authority agree and undertake to carry out such Award without delay.
- (iv) The Contractor and the Authority agree that an Award may be enforced against the Contractor and/or the Authority, as the case may be, and their respective assets wherever situated.
- (v) This Agreement and the rights and obligations of the Parties shall remain in full force and effect, pending the Award in any arbitration proceedings hereunder. Further, the parties unconditionally acknowledge and agree that notwithstanding any dispute between them, each Party shall proceed with the performance of its respective obligations, pending resolution of the Dispute under this Article.
- (vi) In the event the Party against whom the Award has been granted challenges theAward for any reason in a court of law, it shall make an interim payment to the other Party for an amount equal to 75% (seventy-five percent) of the Award, pending final settlement of the Dispute. The aforesaid amount shall be paid forthwith upon furnishing an irrevocable Bank Guarantee for a sum equal to 120 % (one hundred and twenty percent) of the aforesaid amount. Upon final settlement of the Dispute, the aforesaid interim payment shall be adjusted and any balance amount due tobe paid or returned, as the case may be, shall be paid or returned with interest calculated at the rate of 10% (tenpercent) per annum from the date of interim payment to the date of final settlement of such balance.

26.4 Adjudication by Regulatory Authority, Tribunal or Commission

In the event of the constitution of a statutory regulatory authority, tribunal, or commission, as the case may be, with powers to adjudicate upon disputes between the Contractor and the Authority, all Disputes arising after such constitution shall, instead of reference to arbitration under Clause 26.3, be adjudicated upon by such regulatory authority, tribunal or commission under the Applicable Law and all references to Dispute Resolution Procedure shall be construed accordingly. For the avoidance of doubt, the Parties hereto agree that the adjudication hereunder shall not be final and binding until an appeal against such adjudication has been decided by an appellate tribunal or court of competent jurisdiction, as the case maybe, or no such appeal has been preferred within the time specified in the Applicable Law.

Article 27

Miscellaneous

27.1 Governing law and jurisdiction

This Agreement shall be construed and interpreted under and governed by the laws of India, and the courts at Lucknow shall have exclusive jurisdiction over matters arising out of or relating to this Agreement.

27.2 Waiver of immunity

Each Party unconditionally and irrevocably:

- (a) agrees that the execution, delivery, and performance of this Agreement constitute commercial acts done and performed for commercial purposes;
- (b) agrees that, should any proceedings be brought against it or its assets, property, or revenues in any jurisdiction concerning this Agreement or any transaction contemplated by this Agreement, no immunity (whether because of sovereignty or otherwise) from such proceedings shall be claimed by or on behalf of the Party concerning its assets;
- (c) waives any right of immunity which it or its assets, property, or revenues now have, may acquire in the future, or which may be attributed to it in any jurisdiction; and
- (d) consents generally in respect of the enforcement of any judgment or award against it in any such proceedings to the giving of any relief or the issue of any process in any jurisdiction in connection with such proceedings (including the making, enforcement, or execution against it or in respect of any assets, property or revenues whatsoever irrespective of their use or intended use of any order or judgment that may be made or given in connection therewith).

27.3 Delayed payments

The Parties hereto agree that payments due from one Party to the other Party under the provisions of this Agreement shall be made within the period set forth therein, and if no such period is specified, within 30 (thirty) days of receiving a demand along with the necessary particulars. In the event of a delay beyond such period, the defaulting Party shall pay interest for the period of delay calculated at a rate equal to Base Rate plus 2 (two) percent, calculated at quarterly rests, and recovery thereof shall be without prejudice to the rights of the Parties under this Agreement including Termination thereof.

27.4 Waiver

- (i) Waiver, including partial or conditional waiver, by either Party of any default by the other Party in the observance and performance of any provision of or obligations under this Agreement: -

- (a) shall not operate or be construed as a waiver of any other or subsequent default hereof or of other provisions of or obligations under this Agreement;
 - (b) shall not be effective unless it is in writing and executed by a duly authorized representative of the Party; and
 - (c) shall not affect the validity or enforceability of this Agreement in any manner.
- (ii) Neither the failure by either Party to insist on any occasion upon the performance of the terms, conditions, and provisions of this Agreement or any obligation thereunder nor time or other indulgence granted by a Party to the other Party shall be treated or deemed as a waiver of such breach or acceptance of any variation or the relinquishment of any such right hereunder.

27.5 Liability for review of Documents and Drawings

Except to the extent expressly provided in this Agreement:

- (a) no review, comment, or approval by the Authority or the Authority's Engineer of any Document or Drawing submitted by the Contractor nor any observation or inspection of the construction, or maintenance of the Project Highway nor the failure to review, approve, comment, observe or inspect hereunder shall relieve or absolve the Contractor from its obligations, duties, and liabilities under this Agreement, the Applicable Laws and Applicable Permits; and
- (b) the Authority shall not be liable to the Contractor because of any review, comment, approval, observation, or inspection referred to in Sub-clause (a) above.

27.6 Exclusion of implied warranties etc.

This Agreement expressly excludes any warranty, condition, or other undertaking implied at law or by custom or otherwise arising out of any other agreement between the Parties or any representation by either Party not contained in a binding legal agreement executed by both Parties.

27.7 Survival

- (i) Termination shall:
 - (a) not relieve the Contractor or the Authority, as the case may be, of any obligations hereunder which expressly or by implication survive Termination hereof; and
 - (b) except as otherwise provided in any provision of this Agreement expressly limiting the liability of either Party, not relieve either Party of any obligations or liabilities for loss or damage to the other Party arising out of, or caused by, acts or omissions of such Party before the effectiveness of such Termination or arising out of such Termination.

- (ii) All obligations surviving Termination shall only survive for 3 (three) years following the date of such Termination.

27.8 Entire Agreement

This Agreement and the Schedules together constitute a complete and exclusive statement of the terms of the agreement between the Parties on the subject hereof, and no amendment or modification hereto shall be valid and effective unless such modification or amendment is agreed to in writing by the Parties and duly executed by persons especially empowered in this behalf by the respective Parties. All prior written or oral understandings, offers, or other communications of every kind about this Agreement are abrogated and withdrawn. For the avoidance of doubt, the Parties hereto agree that any obligations of the Contractor arising from the Request for Qualification or Request for Proposals, as the case may be, shall be deemed to form part of this Agreement and treated as such.

27.9 Severability

If for any reason whatever, any provision of this Agreement is or becomes invalid, illegal, or unenforceable or is declared by any court of competent jurisdiction or any other instrumentality to be invalid, illegal, or unenforceable, the validity, legality, or enforceability of the remaining provisions shall not be affected in any manner, and the Parties will negotiate in good faith to agree to one or more provisions which may be substituted for such invalid, unenforceable or illegal provisions, as nearly as is practicable to such invalid, illegal or unenforceable provision. Failure to agree upon any such provisions shall not be subject to the Dispute Resolution Procedure set forth under this Agreement or otherwise.

27.10 No partnership

This Agreement shall not be interpreted or construed to create an association, joint venture, or partnership between the Parties, or to impose any partnership obligation or liability upon either Party, and neither Party shall have any right, power, or authority to enter into any agreement or undertaking for, or act on behalf of, or to act as or be an agent or representative of, or to otherwise bind, the other Party.

27.11 Third parties

This Agreement is intended solely for the benefit of the Parties and their respective successors and permitted assigns, and nothing in this Agreement shall be construed to create any duty to, the standard of care concerning, or any liability to, any person not a Party to this Agreement.

27.12 Successors and assigns

This Agreement shall be binding upon, and inure to the benefit of the Parties and their respective successors and permitted assigns.

27.13 Notices

Any notice or other communication to be given by any Party to the other Party under or in connection with the matters contemplated by this Agreement shall be in writing and shall:

- (a) in the case of the Contractor, be given by facsimile or e-mail and by letter delivered by hand to the address given and marked for the attention of the person set out below or to such other person as the Contractor may from time to time designate by notice to the Authority; provided that notices or other communications to be given to an address outside [Delhi] may, if they are subsequently confirmed by sending a copy thereof by registered acknowledgment due, air mail or by courier, be sent by facsimile or e-mail to the person as the Contractor may from time to time designate by notice to the Authority;

[***]

- (b) in the case of the Authority, be given by facsimile or e-mail and by letter delivered by hand and be addressed to the [Chairman] of the Authority with a copy delivered to the Authority Representative or such other person as the Authority may from time to time designate by notice to the Contractor; provided that if the Contractor does not have an office in [Delhi] it may send such notice by facsimile or e-mail and by registered acknowledgment due, air mail or by courier; and
- (c) any notice or communication by a Party to the other Party, given in accordance herewith, shall be deemed to have been delivered when in the normal course of post it ought to have been delivered and in all other cases, it shall be deemed to have been delivered on the actual date and time of delivery; provided that in the case of facsimile or e-mail, it shall be deemed to have been delivered on the working day following the date of its delivery.

27.14 Language

All notices required to be given by one Party to the other Party and all other communications, Documentation, and proceedings which are in any way relevant to this Agreement shall be in writing and English language.

27.15 Counterparts

This Agreement may be executed in two counterparts, each of which, when executed and delivered, shall constitute an original of this Agreement.

27.16 Confidentiality

The Parties shall treat the details of this Agreement as private and confidential, except to the extent necessary to carry out obligations under it or to comply with Applicable Laws. The Contractor shall not publish, permit to be published, or disclose any

particulars of the Works in any trade or technical paper or else where without the previous agreement of the Authority.

27.17 Copyright and Intellectual Property rights

- (i) As between the Parties, the Contractor shall retain the copy right and other Intellectual Property rights in the Contractor's documents and other design documents made by (or on behalf of) the Contractor. The Contractor shall be deemed (by signing this Agreement) to give to the Authority a non-terminable transferable non-exclusive royalty-free license to copy, use, and communicate the Contractor's documents, including making and using modifications of them. This license shall:
 - (a) apply throughout the actual or intended working life (whichever is longer) of the relevant parts of the Works;
 - (b) entitle any person in proper possession of the relevant part of the Works to copy, use, and communicate the Contractor's documents to complete, operate, maintain, alter, adjust, repair, and demolish the Works; and
 - (c) in the case of Contractor's documents which are in the form of computer programs and other software, permit their use on any computer on the Site and other places as envisaged by this Agreement, including replacements of any computers supplied by the Contractor.
- (ii) The Contractor's documents and other design documents made by (or on behalf of) the Contractor shall not, without the Contractor's consent, be used, copied, or communicated to a third party by (or on behalf of) the Authority for purposes other than those permitted under this Clause 27.17.
- (iii) As between the Parties, the Authority shall retain the copyright and other intellectual property rights in this Agreement and other documents made by (or on behalf of) the Authority. The Contractor may, at its cost, copy, use, and obtain communication of these documents for this Agreement. They shall not, without the Authority's consent, be copied, used, or communicated to a third party by the Contractor, except as necessary for the contract.

27.18 Limitation of Liability

- (i) Neither Party shall be liable to the other Party for loss of use of any Works, loss of profit, loss of any contract, or for any indirect or consequential loss or damage which maybe suffered by the other Party in connection with this Agreement, save and except as provided under Articles 23 and 25.
- (ii) The total liability of one Party to the other Party under and under the provisions of this Agreement, save and except as provided in Articles 23 and 25, shall not exceed the Contract Price. For the avoidance of doubt, this Clause shall not limit the liability in any case of fraud, deliberate default, or reckless misconduct by the defaulting Party.

27.19 Care and Supply of Documents

- (i) Each of the Contractor's documents shall be in the custody and care of the Contractor, unless and until taken over by the Authority. Unless otherwise stated in the Agreement, the Contractor shall supply to the Authority 2 (two) copies of each of the Contractor's documents.
- (ii) The Contractor shall keep, on the Site, a copy of the Agreement, publication named in the Authority's requirements, the Contractor's documents, and variations and other communications given under the Agreement. The Authority's personnel shall have the right of access to all these documents at all reasonable times.
- (iii) If a Party becomes aware of an error or defect of a technical nature in a document which was prepared for use in executing the Works, the Party shall promptly give notice to the other party of such error or defect.

27.20 Authority's Use of Contractor's Documents.

- (i) As between the Parties, the Contractor shall retain the copyright and other Intellectual Property rights in the Contractor's Documents and other design documents made by (or on behalf of) the Contractor.
- (ii) The Contractor hereby gives to the Authority a non-terminable transferable nonexclusive royalty-free license to copy, use, and communicate the Contractor's Documents, including making and using modifications of them. This license shall:
 - (a) apply throughout the actual or intended working life (whichever is longer) of the relevant parts of the Works,
 - (b) entitle any person in proper possession of the relevant part of the Works to copy, use, and communicate the Contractor's Documents to complete, operate, maintain, alter, adjust, repair, and demolish the Works, and
 - (c) in the case of Contractor's Documents which are in the form of computer programs and other software, permit their use on any computer on the Site and other places as envisaged by the Contractor, including replacements of any computers supplied by the Contractor.
- (iii) The Contractor's Documents and other design documents made by or on behalf of the Contractor shall not, without the Contractor's consent, be used, copied, or communicated to a third party by (or on behalf of) the Authority for purposes other than those permitted under this Sub-Clause.

27.21 Contractor's Use of Authority's Documents

As between the Parties, the Authority shall retain the copyright and other intellectual property rights in the Authority's requirements and other Documents made by (or on behalf of) the Authority. The Contractor may, at its cost copy, use, and obtain

communication of these documents for the Agreement. They shall not without the Authority's consent, be copied, used, or communicated to a third party by the Contractor, except as necessary for the Agreement.

27.22 Access to the Site by Others

The Contractor shall, at all times, afford access to the Site to the authorized representatives of the Authority, the Authority's Engineer, and anyone else authorized by the Authority to access the site and to the persons duly authorized by any Governmental Agency having jurisdiction over the Project, including those concerned with safety, security or environmental protection to inspect the Project Highway and to investigate any matter within their authority and upon reasonable notice, the Contractor shall provide to such persons reasonable assistance necessary to carry out their respective duties and functions with minimum disruption to the construction, operation and maintenance of the Project Highway consistent with the purpose for which such persons have gained such access to the Site.

27.23 Term

This Agreement shall come into force and effect from the date first hereinabove written and shall remain in force and effect till the Termination Date i.e. the Parties perform all their respective obligations or is terminated by any of the Parties for the reasons and in the manner provided for in the Agreement.

27.24 Amendments

The Agreement may not be supplemented, amended, modified, or changed except by an instrument in writing signed by the Contractor and the Authority and expressed to be a supplement, modification, or change to the Agreement.

27.25 Representation and Bribes

The Contractor represents and warrants to the Authority that:

- (a) No representation or warranty by the Contractor contained herein or in any other document furnished by it to the Authority, or to any Governmental Instrumentality concerning Applicable Permits contains or will contain any untrue statement of material fact or omits or will omit to state a material fact necessary to make such representation or warranty not misleading; and
- (b) It warrants that no sums, in cash or kind, have been paid or will be paid by or on behalf of the Contractor, to any person by way of fees, commission, or otherwise for securing or entering into the Contractor for influencing or attempting to influence any officer or employee of the Authority or GOI in connection therewith.

27.26 No Agency

The Agreement does not constitute either Party as the agent, partner, or legal representative of the other for any purposes whatsoever, and neither Party shall have any express or implied right or authority to assume or to create any obligation or responsibility on behalf of or in the name of the other Party.

Schedules

Schedule-A

The Site

- (i) Site of the Two-Lane Project Highway/ Bridge shall include the land and road works as described in Annex-I of this Schedule-A.
- (ii) The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.
- (iii) An inventory of the Site including the land, Utility shifting, road works, any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2 (i) of this Agreement.
- (iv) The GAD of the Two-Lane Project Highway/Bridge are specified in Annex-III. The proposed profile of the Project Highway/Bridge shall be followed by the contractor with minimum FRL as indicated in the GAD. The Contractor, however, improve/ upgrade the Road/Bridge Profile as indicated in Annex-III based on site/design requirement.
- (v) The status of the environment clearances obtained or awaited is given in Annex-IV.

Annex-I
(Schedule-A)

Site

1. Site

The Site of the “Engineering Procurement and **Construction of Yamuna River Bridge, Approach Road, Additional Approach Road and Protection work on Anandi Bhairon to Dera Banjara (Gijauli) Road in Distt. Agra (on EPC Mode)**” is in the State of Uttar Pradesh.



2. Land

The Site of the Project Highway/Bridge comprises the land (sum total of land already in possession and land to be possessed) as described below:

S.No.	Description of item	Length (m)	Breadth (m)	Quantity (Ha) (Approximate)	Remarks
1	Main Bridge	525.94 M	-	-	-
2	Approach Viaduct	191.50 M			
3	Approach Road	200 M (Dera Banjara side)	-	-	
4	Add. Approach Road	1608.17 Dera banjara Side- 1324.86 M Agra Side- 283.31 M	-	-	
5	Protection Work	1 Job			
6	Retaining Wall	283.31 M (Agra Side)			

3. Old Major Bridges-NIL

4. Roadover-bridges (ROB)/ Roadunder-bridges (RUB):NIL

5. Grade separators: NIL

6. Minor bridges: NIL

7. Railway level Crossings:NIL

8. Underpasses (vehicular, non-vehicular): NIL

9. Culverts: Box Culvert

10. Bus-bays: NIL

11. Truck Lay byes: NIL

12. Road side drains: NIL

13. Major junctions: NIL

14. Minor junctions: NIL

15. Bypasses: NIL

Annex-II*(As per Clause 8.3 (i))***(Schedule-A)****Dates for providing Right of Way of Construction Zone**

S.No.	Work Detail	Date
1	90% ROW	On the appointed date
2	Remaining 10% ROW	After 90 days from appointed date

Annex- III

(Schedule-A)


Alignment Plans/GAD

The alignment of the Project Highway/bridge is enclosed as GAD. Finished road level/formation level of the bridge indicated in the GAD shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the GAD. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement.

Encl: GAD/Alignment

NOTES:

1. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SPECIFIED.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITIES.
3. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AND UTILITIES AT ALL TIMES.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING UTILITIES AND STRUCTURES.
5. THE CONTRACTOR SHALL MAINTAIN ADEQUATE DRAINAGE AND EROSION CONTROL MEASURES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION AND RESTORATION OF THE ENVIRONMENT.
7. THE CONTRACTOR SHALL MAINTAIN ADEQUATE SAFETY MEASURES AND SIGNAGE DURING CONSTRUCTION.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION AND RESTORATION OF ALL ADJACENT PROPERTIES AND UTILITIES.
9. THE CONTRACTOR SHALL MAINTAIN ADEQUATE RECORDS OF ALL CONSTRUCTION ACTIVITIES.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION AND RESTORATION OF ALL ADJACENT PROPERTIES AND UTILITIES.



GENERAL ELEVATION OF BRIDGE STRUCTURE

APPROACH ROAD - 7% SLOPE

APPROACH ROAD - 1.5% SLOPE


FORMATION LEVEL (M)

GROUND LEVEL (M)

CHIMNEY (M)

VERTICAL PROFILE

SCALE: 1:100



SECTIONAL ELEVATION OF P.S.C. BEAM


REINFORCEMENT DETAILS

SCALE: 1:20



GENERAL ELEVATION OF SUBSTRUCTURE

SCALE: 1:50



PLAN AT MID BEAM

SCALE: 1:100



PLAN AT ABUTMENT

SCALE: 1:100



PLAN AT ABUTMENT W/ LOG

SCALE: 1:100



DETAIL OF CHAIR BAR

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT W/ LOG

SCALE: 1:20

DETAIL OF JOINT OF P.S.C. BEAM

SCALE: 1:20

DETAIL OF JOINT OF SUBSTRUCTURE

SCALE: 1:20

DETAIL OF JOINT OF ABUTMENT

SCALE: 1:20

Annex-IV
(Schedule-A)

Environment Clearances

NO clearance required

Schedule-B

(See Clause 2.1)

Development of the Project Highway/Major Bridge

1. Development of the Project Highway/Bridge

Development of the Project Highway/Bridge shall include design and construction of the Project Highway/Bridge as described in this Schedule-B and in Schedule-C. The GAD of the Project on the location is specified as appended in **Annex-III of Schedule A** and shall be deemed to be part of this Schedule B.

2. Work

The work shall include “**Engineering Procurement and Construction of Yamuna River Bridge, Approach Road, Additional Approach Road and Protection works on Anandi Bhairon to Dera Banjara (Gijauli) Road in Distt. Agra. on EPC Mode**” and installation of road furniture/metal crash barrier etc. as described in Annex-I of this Schedule-B and in Schedule-C.

3. Specifications and Standards

The Project Highway/Bridge shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.

Annex-I
(Schedule-B)

Description of Project

include “Design and Construction of Yamuna River Bridge, Approach Road, Additional Approach Road and Protection work on Anandi Bhairon to Dera Banjara (Gijauli) Road in Distt. Agra” **on EPC Mode**

1.1 The Project shall be constructed as per the alignment plan as specified in Annex-III of Schedule-A, unless otherwise specified by the Authority. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for plain/rolling terrain to the extent land is available.

1.2 Length/Width of Carriageway/Formation width

The width of the structures shall be as specified in the following table:

S. No.	Type of Structure / Road	Length of Structure/ Road	Formation width	Carriageway width	Remark
1	Bridge portions	525.94 m	11.50 m	7.50 m	(1.5 m footpath + RCC crash barrier) on each side
2A	Approach Viaduct	191.50 m	11.50 m	7.5 m	
2B	Approaches Dera Banjara Side	200 m		7.00 m	
2C	Add. Approaches Both Side	1608.17 m Dera banjara Side- 1324.86 M Agra Side- 283.31 M		5.50 m	
2D	Retaining Wall	283.31 M Agra Side			

1. GEOMETRIC DESIGN AND GENERAL FEATURES

(i) General

Geometric design and General features of the Project Highway shall be in accordance with Section 2 of the Manual of Specification and Standards as specified in Schedule D.

(ii) Design Speed

The design speed shall be as specified in Schedule D.

(iii) Improvement of the existing road geometrics

In the stretches, where improvement of the existing road geometrics to the prescribed standards is not possible, the existing road geometrics shall be improved to the extent possible within the given right of way and proper road signs and safety measures shall be provided.

(iv) Right of way

The right of way is available as per the Plan & profile.

Note: No additional land will be provided than above, as such wherever required Toe wall/ Retaining wall of suitable heights shall be provided to confine free side slopes of highway embankment for main carriageway/service road, etc. on either side to accommodate the typical cross sections as given in Schedule – B within the proposed RoW without any additional cost to the Authority.

3 Design parameters of the Project

3.1 General

All structures and Approach/Culverts etc. shall be designed and constructed in accordance with the Manual as specified in Schedule D and shall conform to the cross-sectional and other features specified below:

As structure (Bridge) is to be constructed on Yamuna River Bridge by the EPC contractor.

1	Major River Bridge		
A	Structural Arrangement including Viaduct		
(i)	Span Arrangement	7 x 24.00m+ 1x23.50+ 8x58.50 + 1x57.40 m c/c	Refer GAD Superstructure- PSC girders for viaduct PSC Box Girder for Main river bridge
(ii)	The total length of the Bridge including viaduct	525.94 m + 191.50 m = 717.44 m	
(iii)	Minimum Vertical Clearance over HFL	3.235 m	
(iv)	Formation Width of Major Bridge	11.50 m	(7.5 m main carriageway + 2x1.5m footpath+ 2x 0.5 RCC Crash Barrier)
(v)	Abutment/Pier Well Foundation	Minimum Outer dia 8 m	Refer GAD
(vi)	Foundation for Viaduct	1.2 m dia Pile	Minimum Length of Pile 26 m
B	Hydraulics & levels		
(i)	Tentative design Discharge (Based on U/S and D/S bridges)	9500 cumecs	Refer to Enclosed GAD
(ii)	H.F.L	RL 157.00 m	Minimum level Refer GAD

(iii)	L.W.L	RL 147.00 m	Refer GAD
(iv)	Maximum Scour Level for pier	RL 134.293 m	Can't be higher than this level whatever is the reason
(v)	Maximum Scour Level for Abutment	RL 134.293 m	
C	A minimum grade of Concrete		
(i)	Cast in Situ P.S.C. Box Girder with Deck Slab	M 50	Minimum exposure grade Refer GAD
(ii)	RCC Substructure	M 35	
(iii)	RCC Crash barrier	M 40	
(iv)	RCC Well Foundation	M 30	
(v)	RCC Pier Well	M 30	
(vi)	Abutment Cap	M 35	
(vii)	Well Curb	M 30	
D	Seismic Parameters		
(i)	Importance Factor	1.5	
(ii)	Seismic Zone	III	
E	Silt factor (scour Zone)	1.10	Can't be higher than this whatever is the reason
F	Type of Expansion Joint	Modular Type	As per directions of Engineer incharge
G	Type of Bearing	Spherical Bearings	As per directions of Engineer incharge
H	RCC Crash barrier	each side M-40	
I	Wearing Coat (CC)	75 mm thick Asphaltic Wearing Coat	
2	Approach Road (Dera Banjara side only)		
(i)	Formation Width	10.50 m	7.0m Carriageway +1.5 m *2 paver blocks both sides
(ii)	Paved Carriageway	7.00 m	
(iii)	Total Length	200 m	Minimum Crust Composition as per Section 4 of Schedule B
3	Additional Approach Road (both sides)		
(i)	Formation Width	8.50 m	
(ii)	Paved Carriageway	5.50 m	
(iii)	Total Length	1608.17 m	
a)	Dera Banjara Side	1324.86 m	
b)	Agra Side	283.31 m	

4	Protection work all round abutment and along approaches under flood zone	As per IRC 89	
5	Total length of Retaining Wall	283.31 m	Towards Agra side
6	Approx. Minimum Length of Metal crash barrier/safety Jali	As per Schedule D	
7	BOX Culvert/Minor Bridge	Minimum length 55.50 m	Formation width 11.50 m Refer GAD for details -
8	Length of K.C.Drain + CHUTE Drain	As per Relevant IRC codal provisions	As per site requirement and direction of Engineer in charge
9	Lighting Arrangements	Main Bridge+ Approaches+ Additional Approaches	As per the requirements of Manual

Note:

(i) Any change in the span arrangement or type of superstructure, as indicated in the tentative GAD appended in Annex III of Schedule A, due to site constraints, shall require prior approval of the Authority. Any additional financial implications arising from such changes shall be borne by the EPC Contractor. **Notwithstanding the above, any cost savings arising from the implementation of such changes shall be treated as a Negative Change of Scope and shall be assessed and valued in accordance with Article 13 of the Contract Agreement.**

(ii) Any variation in the length specified in this Clause of Schedule-B shall not constitute a Change of Scope, save and except any variations in the length arising out of a Change of Scope expressly undertaken in accordance with the provisions of Article 13.

(iii) The formation level indicated in the GAD shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the GAD. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirements.

(iv) Both banks of the river shall be protected using appropriate measures as recommended in the relevant IRC codes/manuals. These measures shall be implemented around each abutment and along each approach, including provisions such as KC drains, chutes, etc., in accordance with codal provisions and/or design requirements and specifications, while utilizing the existing embankment to the extent possible.

3.2 Foundation

All piers shall be supported on well/Pile foundations in accordance with IRC: 78, as indicated in the General Arrangement Drawing (GAD). Any change in the type of superstructure, as indicated in the tentative GAD appended in Annex III of Schedule A, due to site constraints, shall require prior approval of the Authority.

3.3 Substructure/Superstructure

The Substructure/Superstructure shall be designed and constructed in accordance with section 7 of the Manual and shall conform to the cross-sectional features and other details specified therein. Pavement design of Approach/Service Road.

4 Pavement design of Approach/Additional Approach

4.1 Type of Pavement

The flexible pavement shall be designed for the Main carriageway as per section 5 of the Manual and in conformity with the IRC: 37-2018 for the minimum **design life of 20 years**. The crust composition for the Main carriageway & service road, entry/ exit ramps shall be not less than as given below:

Sr. No.	Description of item	Minimum pavement Composition of Flexible Pavement (mm) for the Main Carriageway
1	GSB	150 mm
2	WMM	250 mm
3	DBM	50 mm
4	BC	30 mm

4.2 Design Traffic

Notwithstanding anything to the contrary contained in this Agreement or the Manual, the concessionaire shall design the pavement for the Main Carriageway minimum design traffic of 10 MSA or as per the actual traffic at the time of construction whichever is higher.

5 RETAINING/RE WALLS & PROTECTION WORKS

Provide Retaining/RE walls in approaches to structures and at any other locations as per site conditions to contain the project facility within the available right of way as per the cross section provisions mentioned in Schedule-B conforming to Schedule "D".

In any case no free slope will be permitted then Approaches shall be confined by Retaining walls only (due to land/utility/space constraint) and in addition, RCC Breast wall of suitable dimensions (Length, width, height) shall be designed and provided to facilitate slip roads within the available right of way.

Providing and laying Protection works including Filter Material, Pitching and Boulder apron for river protection against river scour and also embankment protection shall be as per provisions of IRC:89 -2019. Efficient drainage system on approaches including Chute drains etc shall be as per provisions of IRC:89 -2019.

Note: Any additional length required as per site conditions shall not constitute a Change of Scope, save and except any variations arising out of a Change of Scope expressly under taken in accordance with the provisions of Article 13.

6 DRAIN AGE SYSTEM FOR BRIDGE DECKS

An effective drainage system for bridge decks shall be provided as specified in the Manual.

7 TRAFFIC CONTROL DEVICES AND ROAD SAFETY WORKS

The traffic control devices and road safety works shall be provided in accordance with Section 9 of the Manual. The reflective sheeting shall be provided in accordance with section 9.2.3 of the Manual and in conformity with the IRC: 67-2022.

8 ROAD SIDE FURNITURE

Roadside furniture like Road Boundary Stones, km/Hectometer Stones, Railings, Traffic Impact Attenuators, and Delineators shall be provided in accordance with the provisions of Section 9 of the manual.


9 USE OF FLY-ASH

Use of fly-ash shall be considered in the construction as per latest NHAI guidelines/Policy circular's/MOEF guidelines dated 27/08/2018, No. 24028/14/2018-H.

10 CHANGE OF SCOPE

Any variations in the lengths specified in this Schedule-B shall not constitute a Change of Scope, save and except any variations in the length arising out of a Change of Scope expressly undertaken in accordance with the provisions of Article 13.

Typical Section



**TYP. CROSS SEC. OF PIER
FOR 58.50M PIER SPAN**

Schedule B-1

1. The shifting of utilities and felling of trees shall be carried out by the Contractor. The cost of the same shall be borne by the Authority. The details of utilities are as follows:

Sr. No	Type of Utility	Unit	Quantity	Location/stretch (LHS/RHS)
A	Electrical Utilities			
A1	Electrical Poles	Nos.	37	
A2	Electrical cables	meters	Req As per Specification	
A3	Transformers	Nos.	-	
-	-----	--		
-	-----	--		
B	Water/Sewage pipeline		-	
	Sewage	meters	-	
B2	Water supply	meters	-	
-	-----	--		
-	-----	--		
C	Felling of Trees	Nos.	Nil	

Schedule-C

(See Clause 2.1)

Project Facilities

1. Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) Toll plaza [s]; Nil
- (b) Road side furniture; **as per manual**
- (c) Pedestrian facilities; Nil
- (d) Tree plantation; Nil
- (e) Trucklay-byes; Nil
- (f) Bus-bays and bus shelters; Nil
- (g) Rest areas; and others to be specified: Nil

SCHEDULE-D

SPECIFICATIONS AND STANDARDS

1 Construction

The Contractor shall comply with the Specifications and Standards outlined in Annex-I of this Schedule-D for the construction of the Project Highway.

2 Design Standards

The Project Highway including Project Facilities shall conform to the design requirements set out in the following documents:

- Manual of Specifications and Standards for Two Laning of Highways (IRC: SP: 73) referred to herein as the **Manual** as applied to the proposed highway and IWAI guidelines.
- IRC:SP: 88-2019
- **IRC:SP: 90-2010**
- IRC: 99-2018 & IRC:SP102-2014
- IRC:SP21-2009
- IRC:SP55-2014
- IRC:SP:113-2018
- IRC:SP119-2015

Design standards are included in the tables below.

S. No	Description	Design Code
1.	Geometric Designs & standards	IRC:38 Guide lines for the design of horizontal curves
		IRC:SP-23–Vertical curves for Highways
		IRC:39–Standards for Road rail level crossings
		IRC:64–Capacity of Roads in Rural Areas
		IRC:66– Sight Distance on Rural Highways
		IRC:73– Geometric Design Standards for Rural (non-urban) Highways
		IRC:75–Guidelines for design of High Embankment
		IRC:86–Geometric Design standards for urban roads in plains
		IRC:106–Guidelines on the capacity of urban roads in plain areas
2.	Design of Pavement	IRC:37–Guidelines for Design of Flexible Pavement
		IRC:58–Guidelines for Design of Rigid Pavements
		IRC:115–Guidelines for strengthening of flexible pavements
3.	Junctions/Intersections/ interchanges	IRC:65-Traffic Rotaries
		IRC:92- Guidelines for Design of Inter changes
		IRC:SP:41– Design of At grade junctions
4.	Kilometer stones, 200m stones, and boundary pillar	IRC:81–Type Design for Highway kilometer stones
		IRC:26-Type design for 200 m stones
		IRC:25-Type design for boundary stones
5.	Traffic Signs	IRC:31–Route marker signs for state routes
		IRC:67–Code of practice for road signs
		IRC:79–Recommended practice for Road Traffic signs
		IRC:SP:31–Road Traffic signs

S. No	Description	DesignCode
6.	Road Markings	IRC:35–Code of practice for road markings, road delineators
7.	Ancillary Works	IRC:80–Type design for pick-upbus stops on Rural Highways IRC:SP:12–Guidelines on the provision of parking areas.
8.	Drainage	IRC:SP:42–Guidelines on Road Drainage IRC:SP:50–Guidelines on urban drainage
9.	Safety Measures	IRC:103–Guidelines for pedestrian facilities IRC:SP:44–Highway Safety Code IRC:SP:55–Guidelines for safety in construction zones
10.	Bridges and Structures	IRC:5– Standard Specification and Code of Practice for Road Bridges, Section 1 – General Features of Design IRC:6–Standard specifications and code of practice for Road bridges (Section:II) Loads and Load combinations IRC:21–Standard Specification and Code of Practice for Road bridges, Section III–Cement Concrete (Plain and reinforced) IRC:112–Code of practice for concrete road bridges IRC:SP:13–Guidelines for the design of small bridges and culverts IRC:78–Standard Specification and Code of Practice for Road Bridges, Section VII–Foundation and Substructure IRC: 83-(PartI)– Standard Specification and Code of Practice for Road bridges, Section IX–Bearing,Part I: Roller & Rocker Bearing IRC:83-(PartII)– Standard Specification and Code of Practice for Road bridges, Section IX – Bearing, Part II: Elastomeric Bearings IRC:83-(PartIII)–Standard Specification and Code of Practice for Road bridges, Section IX–Bearings, Part III: POT, PIN, Metallic Guide and Plane Sliding Bearings IRC:89- Guidelines for design and construction of River Training and Control Works for Road Bridges IRC:SP:35–Guidelines for inspection and Maintenance of Bridges IRC:SP:40–Guidelineson Repair, Strengthening, and Rehabilitation of Concrete Bridges. IRC:SP:114–Guidelines for seismic design of road bridges
		IRC:65-2018:Guidelines for Design and Construction of Segmental Bridges (First Revision)
		-2016: Guidelines for Design of Continuous Bridges (First Revision)

Annex-I**(Schedule-D)****Specifications and Standards for Construction****1 Specifications and Standards**

All Materials, works, and construction operations shall conform to the Manual, and MORTH Specifications for Road and Bridge Works 5thRevision 2013. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Employer's Representative.

2 Deviations from the Specifications and Standards

2.1 The terms "Concessionaire", "Independent Engineer" and "Concession Agreement" used in the Manual shall be deemed to be substituted by the terms "EPC Contractor", "Employer's Representative" and "Agreement" respectively.

2.2 Notwithstanding anything to the contrary contained in Paragraph 1 above, the following specifications and standards shall apply to the project highway, and for purposes of this agreement; the aforesaid specifications and standards shall be deemed to be amended to the extent set forth below. Measures shall be provided to mitigate safety and other hazards arising from each of the following deviations from the Specifications and Standards. Measures to mitigate safety hazards shall address any recommendations contained in the Road Safety Audit Reports.

Sl. No.	Clause No. of manual	Description	Deviation
1	Clause 2.2 of Manual	Design Speed: Ruling or minimum Design speed shall be followed	The minimum design speed shall be 80 kmph and as per Plan & Profile drawing as appended in Schedule A.
2	Clause 2.6 of Manual	Type and width of Shoulders	The type and Width of shoulders shall be as per the Typical cross sections appended in Schedule B.
3	Clause 2.17 of IRC:SP: 87-2019	Typical Cross Sections	Typical Cross Sections shall be as per the Typical cross sections as appended in Schedule B.
4	Clause 2.9.3	Super elevation shall be limited to 7 Percent	Super elevation shall be limited to 4% (four Percent) in built-up areas
5	Clause 2.9.4	Radius of Horizontal Curves	The minimum radius of Horizontal curves shall be as per the alignment plan shown in the Plan and profile drawings as appended in Schedule A.
6	Clause 2.9.5	Sight distance, stopping sight distance, and overtaking sight distance	Where sight distance requirements cannot be met as per the Manual, proper road signs and safety measures shall be provided for safe regulation of fast-moving, slow-moving, and pedestrian traffic.
	Clause 2.9.6.2	Gradient	As per manual

8	Clause 3.2	At grade junction	The junction shall be designed to the maximum extent as per the typical layout plan within RoW as appended in Schedule A.
9	Clause 4.2	Road Embankment: Principles for the height of the embankment	The minimum FRL shall be followed as per the drawing appended in Schedules A & B.
10	Clause 5.2 & 5.2.1	Provision of Flexible or Rigid pavement	The type of Pavement shall be flexible.
11	Clause 5.4.1(i)	Design period of Flexible Pavement	Flexible Pavement shall be designed for a minimum design period of 20 years.
12	Clause 5.11	Earthen Shoulders	Earthen Shoulders on either side of the road shall be of selected earth with MDD not less than 17.5 kN/cu.m. and 4-day soaked CBR of min 9% at min 97% of dry density, placed on top of granular sub-base (that is an extension from pavement upto the daylight). The PI and LL shall not exceed 6 and 25 respectively. The remaining portion shall conform to section 300 of MoRTH Specifications.
13	Clause 7.3(ii)	Deck Width of bridges	The deck width of bridges shall be as per TCS appended in Schedule B.
14	Clause 9.8	Pedestrian facilities	As per TCS annexed with schedule B.
15	Clause 12.11, 12.10 & 12.15	Location	As directed and finalized by the Authority.
16	MoRTH Specification no. 501.3, 505 & 507	Hot mix plant for Bituminous Mixes	All bituminous courses (bituminous base course/wearing course) shall be carried out using a type Hot Mix Plant of 100-120 TPH capacity having a minimum output of 75 TPH.

- 1.3 Any deviations from standards shall require advanced approval by the Authority's Engineer. The Contractor shall also prepare a Table of Deviations for deviations from standards which lists each deviation, location, justification, and other relevant information.
- 1.4 In the absence of any definite provisions on any particular issue in the aforesaid Specifications, reference may be made to the latest codes and Specifications of IRC, BIS, BS, ASTM, AASHTO, and CAN/CSA in that order. Where even these are silent, the construction and completion of the works shall conform to sound engineering practice as approved by the Authority Engineer / Authority.

Schedule-E

(See Clauses 2.1 and 14.2)

Maintenance Requirements

1. Maintenance Requirements

- (i) The Contractor shall, at all times maintain the Project Highway under the provisions of this Agreement, Applicable Laws, and Applicable Permits.
- (ii) The Contractor shall repair or rectify any Defect or deficiency outlined in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfillment of the Maintenance obligations by the Contractor. Upon the occurrence of any breach hereunder, the Authority shall be entitled to effect a reduction in monthly lump sum payment as outlined in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (iii) All Materials works, and construction operations shall conform to the MORTH Specifications for Road and Bridge Works and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

[Specify all the relevant documents]

2. Repair/rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration concerning the Specifications and Standards and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

5. Emergency repairs/restoration

Notwithstanding any thing to the contrary contained in this Schedule-E, if any Defect, deficiency, or deterioration in the Project Highway poses a hazard to safety or risk of property damage, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in the safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

7. Pre-monsoon inspection/Post-monsoon inspection

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts, and drainage systems before [1st June] every year under the guidelines contained in IRC: SP35. A report of this inspection together with details of proposed maintenance works as required based on this inspection shall be sent to the Authority's Engineer before the [10th of June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post-monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

8. Repairs on account of natural calamities

All damages occurring to the Project Highway on account of a Force Majeure Event or willful default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.

Annex-I

(Schedule-E)

Repair/rectification of Defects and deficiencies

The Contractor shall repair and rectify the Defects and deficiencies specified in this Annex-I of Schedule-E within the time limit setforth in the table below.

Table-1: Maintenance Criteria for Pavements:

Asset Type	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
Flexible Pavement (Pavement of MCW, Service Road, Service Road, approach)	Potholes	Nil	<0.1 % of area and subject to limit of 10 mm in depth	Daily	Length Measurement Unit like Scale, Tape, odometer etc.	IRC82:2015 and Distress Identification Manual for Long Term Pavement Performance Program, FHWA 2003 (http://www.tfhr.com/pavement/ltp/reports/03031/)	24-48 hours	MORT&H Specification 3004.2

Asset Types	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
of Grade structure, approaches of connecting roads, slip roads, lay byes etc. as applicable)	Cracking	Nil	<5% subject to limit of 0.5 sqm for any 50m length	Daily			7-15 days	MORT&H Specification 3004.3
	Rutting	Nil	< 5mm	Daily	Straight Edge		15-30 days	MORT&H Specification 3004.2
	Corrugations and Shoving	Nil	<0.1% of area	Daily	Length Measurement Unit like		2-7 days	IRC:82-2015

AssetType	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
	Bleeding	Nil	<1%ofarea	Daily	Scale, Tape, odo meter etc.		3-7days	MORT&H Specification 3004.4
	Raveling /Stripping	Nil	<1%ofarea	Daily			7-15days	IRC:82-2015 read with IRCSP81
	Edge Deformation/ Breaking	Nil	<1m for any 100 m section and width < 0.1 m at any location, restricted to 30 cmfrom the edge	Daily			7-15 days	IRC:82-2015

Asset Type	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
	Roughness BI	2000 mm /km	2400 mm/km	Bi-Annually	Class I Profilometer SCRIM (Sideway-force Coefficient Routine Investigation Machine or equivalent)	Class I Profilometer: ASTM E950(98) : 2004 –Standard Test Method for measuring Longitudinal Profile of Travelled Surfaces with Accelerometer Established Inertial Profiling Reference ASTM E1656 -94: 2000- Standard Guide for Classification of Automatic Pavement Condition Survey Equipment	180days	IRC:82-2015
	Skid Number	60SN	50SN	Bi-Annually			180days	BS:7941-1: 2006
	Pavement Condition Index	3	2.1	Bi-Annually			180days	IRC:82-2015

AssetType	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
	Other Pavement Distresses			Bi-Annually			2-7days	IRC:82-2015
	Deflection/ Remaining Life			Annually	Falling Weight Deflectometer	IRC115: 2014	180days	IRC:115-2014
Rigid Pavement (Pavement of MCW, Service Road, Grade structure,	Roughness BI	2200m m/km	2400mm / km	Bi-Annually	Class I Profilometer	ASTM E950 (98) :2004 and ASTM E1656 - 94: 2000	180days	IRC:SP:83-2008
	Skid	Skid Resistance no. at different speed of vehicles		Bi-Annually	SCRIM (Sideway-force	IRC:SP:83-2008	180days	IRC:SP:83-2008

	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
Asset Type approaches of connecting roads, slip roads, lay byes etc. as applicable)		Minimum SN	Traffic Speed (Km/h)		Coefficient Routine Investigation Machine or equivalent)			
		36	50					
		33	65					
		32	80					
		31	95					
		31	110					

AssetType	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
Embankment /Slope	Edgedropat shoulders	Nil	40mm	Daily	Length Measurement Unit like Scale, Tape, odometer etc.	IRC	7-15days	MORT&H Specification 408.4
	Slope of camber /cross fall	Nil	<2% variationin prescribed slope of camber /crossfall	Daily			7-15days	MORT&H Specification 408.4
	Embankment Slopes	Nil	<15% variationin prescribe	Daily			7-15days	MORT&H Specification 408.4

Asset Type	Performance Parameter	Level of Service (LOS)		Frequency of Inspection	Tools/ Equipment	Standards and References for Inspection and Data Analysis	Timelimit for Rectification/ Repair	Maintenance Specifications
		Desirable	Acceptable					
			sideslope					
	Embankment Protection	Nil	Nil	Daily	NA		7-15days	MORT&H Specification
	Rain Cuts/ Gullies in slope	Nil	Nil	Daily Specially During Rainy Season	NA		7-15days	MORT&H Specification

In addition to the above performance criterion, the contractor shall strictly maintain therigid pavements as per requirements in the following table

Table -2: **Maintenance Criteria for Rigid Pavements:**

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
CRACKING						
1	Single Discrete Cracks intersecting with any joint	w= widthofcrack L=length of crack d=depth of crack D = depth of slab	0	Nil,notdiscernible	No Action	Notapplicable
			1	w<0.2mm. haircracks		
			2	w=0.2-0.5mm,discernible from slow-moving car	Seal without delay	Seal, and stitch if L>lm.
			3	w=0.5-1.5 mm, discerniblefrom fast-moving car		

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased $D/2$	For the cased >math>D/2</math>
2	Single Transverse (or Diagonal) Crack intersecting with one or more joints	w= width of crack L=length of crack d=depth of crack D = depth of slab	4	w= 1.5-3.0mm	Seal, and stitch if L>lm.	Staple or Dowel Bar Retrofit, FDR for affected portion.
			5	w>3mm.	Within 7 days	
			0	Nil, not discernible	No Action	
			1	w<0.2mm, hair cracks	Route and seal with epoxy.	Staple or Dowel Bar Retrofit.
2	w = 0.2- 0.5mm, discernible from slow vehicle	Within 7 days	Within 15 days			
			3	w = 0.5- 3.0mm, discernible from fast vehicle	Route, seal and stitch, if L > 1 m.	
					Within 7 days	

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
			4	w=3.0-6.0 mm	Dowel Bar Retrofit. Within 15 days	Full Depth Repair Dismantle and reconstruct affected. Portion with norms and specifications See Para 5.5 & 9.2
			5	w > 6 mm, usually associated with spalling, and/or slab rocking under traffic	Not Applicable, as it may be full depth	Within 15 days
			0	Nil, not discernible	No Action	
3	Single Longitudinal Crack intersecting with one or more joints	w = width of crack l = length of crack d = depth of crack D = depth of slab	1	w < 0.5 mm, discernible from slow moving vehicle	Seal with epoxy, if L > 1 m. Within 7 days	Staple or dowel bar retrofit. Within 15 days

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the case $< D/2$	For the case $> D/2$
			2	w = 0.5- 3.0mm, discernible from fast vehicle	Routeseal and stitch, if L > 1m. Within 15 days	-
			3	w=3.0-6.0mm	Staple, if L > 1m. Within 15 days	Partial Depth Repair with stapling.
			4	w=6.0 -12.0 mm, usually associated with spalling	Not Applicable, as it may be full depth	Within 15 days
			5	w > 12 mm, usually associated with spalling, and/or slab rocking under traffic		Full Depth Repair Dismantle and reconstruct affected portion as per norms and specifications-

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
						See Para 5.6.4 Within 15 days
4	Multiple Cracks intersecting with one or more joints	w=width of crack	0	Nil, not discernible	No Action	-
			1	w < 0.2mm, hair cracks	Seal, and stitch if L > 1m.	
			2	w = 0.2 - 0.5mm, discernible from slow vehicle	Within 15 days	
			3	w = 0.5 - 3.0mm, discernible from fast vehicle	Full depth repair within 15 days	
			4	w = 3.0 - 6.0mm panel broken into 2 or 3 pieces		
			5	w > 6mm and/or panel broken		
					Dismantle, Reinstall subbase, Reconstruct whole slab as per specifications within 30 days	

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the case $<D/2$	For the case $>D/2$
				into more than 4 pieces		
5	Corner Break	w=width of crack L=length of crack	0	Nil, not discernible	No Action	-
			1	w<0.5mm; only 1 corner broken	Seal with low viscosity epoxy to secure broken parts	Seal with epoxy seal with epoxy
			2	w<1.5mm; L<0.6m, only one corner broken	Within 7 days	Within 7 days
			3	w<1.5mm; L<0.6m, two corners broken	Partial Depth (Refer Figure 8.3 of IRC:SP:83-2008)	Full depth repair
			4	w>1.5mm; L>0.6m or three corners broken		
			5	three or four corners broken	Within 15 days	Reinstate sub-base, and reconstruct the

S. No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
						slab as per norms and specifications within 30 days
	Punchout (Applicable to Continuous Reinforced Concrete Pavement (CRCP) only)	w = width of crack L=length (m/m ²)	0	Nil, not discernible		No Action
			1	w < 0.5mm; L < 3m/m ²	Not Applicable, as it may be full depth	Seal with low viscosity epoxy to secure broken parts. Within 15 days
			2	either w > 0.5mm or L < 3m/m ²		
			3	w > 1.5mm and L < 3m/m ²		
			4	w > 3mm, L < 3m/m ² and deformation		
			5	w > 3mm, L > 3m/m ² and deformation		

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased<D/2	For the cased>D/2
Surface Defects						
7	Ravelling Honeycomb surface	r=area damaged or surface/total surface of slab (%) h=maximum depth of damage	0	Nil, not discernible	Short Term	Long Term
					Noaction.	NotApplicable
			1	r<2%	Local repair of areas damaged	
			2	r=2-10 %	and liable to be damaged. Within 15 days	
			3	r=10-25%	Bonded Inlay, 2 or 3 slabs if affecting.	
			4	r=25- 50%		

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased<D/2	For the cased>D/2
					Within 30 days	
			5	r>50% and h>25 mm	Reconstruct slabs, 4 or more slabs if affecting. Within 30 days	
8	Scaling	r = damaged surface / total surface of slab (%) h=maximum depth of damage	0	Nil, not discernible	Short Term	Long Term
					Noaction.	Not Applicable
			1	r<2%	Local repair of areas damaged	
			2	r=2-10%	and liable to be damaged. Within 7 days	

S. No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the case $D/2$	For the case >math>D/2</math>
9	Polished Surface/Glazing	t=texture depth, sand patch test	0		Bonded Inlay within 15 days	Not Applicable
			1	t>1mm		
			2'	t=1- 0.6mm	Monitor rate of deterioration	
			3	t=0.6-0.3mm		
			4	t=0.3-0.1mm		

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
			5	t<0.1 mm	Diamond Grinding if affecting 50% or more slabs in a continuous stretch of minimum 5km. Within 30 days	
10	Popout (Small Hole) Pothole Refer Para 8.4	n=number/m ² d=diameterh = maximum depth	0	d<50mm;h<25mm;n<1per 5 m ²	Noaction.	Not Applicable
			1	d=50-100mm;h<50mm;n<1 per5m ²	Partial depth repair65 mm deep.	
			2	d=50-100mm;h>50mm;n<1 per5m ²	Within 15 days	

S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	Repair Action	
					For the cased <D/2	For the cased >D/2
			3	d=100-300mm;h<100mm;n< 1 per 5 m ²	Partial depth repair 110mm	
			4	d=100-300mm;h>100mm; n< 1 per 5 m ²	i.e.10mm more than the depth of the hole. Within 30 days	
			5	d>300mm;h>100mm:n>1per 5 m ²	Full depth repair. Within 30 days	

Joint Defects							
11	Joint Seal Defects	loss or damage L = Length as % total joint length	0	Difficult to discern.	Short Term	Long Term	
						Noaction.	Not Applicable
			1	Discernible, L< 25% but of little immediate consequence with regard to ingress of water or trapping incompressible material.	Cleanjoint, inspect later.		
			3	Notable. L > 25% insufficient protection against ingress of water and trapping incompressible material.	Clean and reapply sealant in selected locations. Within 7 days		
5	Severe; w > 3 mm negligible\protection against ingress of water and trapping incompressible material	Clean, widen and reseal the joint. Within 7 days					

12	Spalling of Joints	w = width on either side of the joint L = length of spalled portion (as % joint length)	0	Nil , not discernible	Noaction.	Not Applicable
			1	w<10mm	Apply low viscosity epoxy resin/ mortar in cracked portion.	
			2	w=10-20mm, L <25%	Within 7 days	
			3	w=20-40mm, L >25%	Partial Depth Repair. Within 15 days	
			4	w=40-80 mm, L >25%	30-50 mmdeep, h=w+20%of w, within 30 days	
			5	w> 80mm,and L>25%	50-100 mm deep repair. H = w + 20% of w. Within 30 days	

13	Faulting (or Stepping) in Cracks or Joints	f=difference of level	0	not discernible,<1 mm	Noaction.	Noaction.
			1	f<3mm		
			2	f=3-6mm	Determinec a use and observe, take action for diamond grinding	Replace the slabas appropriate. Within 30 days
			3	f=6-12mm	Diamond Grinding	
			4	f=12-18mm	Raise sunkens lab.	Replace the slabas appropriate. Within 30 days
			5	f>18 mm	Strengthen subgrade and sub-base by grouting and raising sunken slab	
14	Blowup or Buckling	h = vertical displacement from normal profile	0	Nil, not discernible	Short Term	Long Term
			1	h<6mm	No Action	
			2	h=6-12 mm	Install Signs to Warn Traffic	

			3	h=12-25mm	within 7 days	
			4	h>25mm	Full Depth Repair. Within 30 days	
			5	shattered slabs, ie 4 or more pieces	Replace broken slabs. Within 30 days	
15	Depression	h = negative vertical displacement from normal profile L = length	0	Not discernible, h<5mm	No action.	Not Applicable
			1	h=5-15mm		
			2	h=15-30mm, Nos <20% joints	Install Signs to Warn Traffic within 7 days	
			3	h=30-50 mm		
			4	h >50mm or >20% joints	Strengthen sub grade. Reinstate pavement at normal level	

			5	h>100 mm	if L< 20 m. Within 30 days	
16	Heave	h = positive vertical displacement from normal profile. L=length	0	Not discernible. h < 5 mm	Short Term	Long Term scrabble
					Noaction.	
			1	h=5-15mm	Followup.	
			2	h=15-30mm, Nos <20% joints	Install Signs toWarn Traffic within 7 days	
			3	h=30-50mm		
			4	h >50mmor>20% joints	Stabilise subgrade. Reinstate pavement at normal level if length <20m. Within30days	
			5	h>100 mm		
17	Bump	h = vertical	0	h<4mm	Noaction	

		displacement from normal profile	1	h=4-7mm	Grind, in case of new construction within 7 days	Construction Limit for New Construction.
			3	h=7-15mm	Grind, in case of ongoing Maintenance within 15 days	Replace in case of new construction. Within 30 days
			5	h>15mm	Full Depth Repair. Within 30 days	Full Depth Repair. Within 30 days
18	Lane Shoulder Dropoff	to f=difference of level	0	Nil, not discernible <3mm	Short Term	Long Term
					No action.	
			1	f= 3-10mm	Spot repair of shoulder within 7 days	
			2	f=10-25mm		
			3	f=25-50mm	Fill up shoulder	

			4	f=50-75 mm	within 7day ss	Forany100m stretchReconstruct shoulder, if affecting 25% or more of stretch. Within 30 days
			5	f>75 mm		
Drainage						
19	Pumping	quantity of fines andwaterexpelled through open joints and cracks Nos	0	not discernible	No Action	
			1to2	slight/ occasional Nos <10%	Repair cracks and joints Without delay.	Inspect and repair sub-drainage at distressed sections and upstream.
			3to4	appreciable/ Frequent 10 - 25%	Lift or jacks lab within 30 days.	
		Nos/100mstretch	5	abundant, crack development > 25%	Repair distressed pavement sections. Strengthen subgrade and subbase. Replace slab. Within30days	

20	Ponding	Ponding on slabs due to blockage of drains	0-2	No discernible problem	Noaction.	Action required to stop water damaging foundation within 30 days.
			3to 4	Blockages observed in drains, but water flowing	Clean drains etc within 7 days, Follow up	
			5	Ponding, accumulation of water observed	-do-	

Table-3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

Asset Type	Performance Parameter	Level of Service(LOS)			Frequency of Measurement	Testing Method	Recommended Remedial measures	Timelimit for Rectification	Specifications and Standards
Highway		As per IRC SP :84-2014, a minimum of safe stopping sight distance shall be available throughout.				Manual Measurements with Odo meter along with video / image backup	Removal of obstruction within 24 hours, in case of sight line affected by temporary objects such as trees, temporary encroachments. In case of permanent structure or design deficiency: Removal of obstruction/ improvement of deficiency at the earliest Speed Restriction boards and suitable traffic calming measures such as transverse bar marking, blinkers, etc. shall be applied during the period of rectification.		IRC:SP 84-2014
	Availability of Safe Sight Distance	Design Speed, kmph	Desirable Minimum Sight Distance (m)	Safe Stopping Sight Distance (m)	Monthly				
		100	360	180					
		80	260	130					
Pavement Marking	Wear	<70% of marking remaining			Bi-Annually	Visual Assessment as per Annexure-F of IRC:35-2015	Re-painting	Cat-1 Defect- within 24 hours Cat-2 Defect within 2 months	IRC:35-2015

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Timelimit for Rectification	Specifications and Standards	
	Day time Visibility	During expected life Service Time Cement Road - 130 mcd/m ² /lux Bituminous Road- 100 mcd/m ² /lux	Monthly	As per Annexure-D of IRC:35-2015	Re-painting	Cat-1 Defect - within 24 hours Cat-2 Defect - within 2 months	IRC:35-2015	
	Night Time Visibility	<u>Initial and Minimum Performance for Dry Retro reflectivity during night time:</u>		As per Annexure-E of IRC:35-2015	Re-painting	Cat-1 Defect - within 24 hours Cat-2 Defect - within 2 months	IRC:35-2015	
		Design	(RL) Retro					
		Speed	Reflectivity (mcd/m ² /lux)					
			Initial (7days)					Minimum Threshold level (TL)&warranty period required up to 2 years
		Upto65	200					80
		65- 100	250					120
		Above 100	350					150
	<u>Initial and Minimum Performance for Night Visibility under wet condition (Retro reflectivity):</u>							

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specifications and Standards
		Initial 7 days Retroreflectivity: 100 mcd/m ² /lux Minimum Threshold Level: 50 mcd/m ² /lux					
	Skid Resistance	Initial and Minimum performance for Skid Resistance: Initial (7 days): 55BPN Min. Threshold: 44BPN *Note: shall be considered under urban /city traffic condition encompassing the locations like pedestrian crossings, bus bay, bus stop, cycle track inter section delineation, transverse bar markings etc	Bi-Annually	As per Annexure-G of IRC:35-2015		Within 24 hours	IRC:35-2015
Road Signs	Shape and Position	Shape and Position as per IRC:67-2012. Sign board should be clearly visible for the design speed of the section.	Daily	Visual with video /image backup	Improvement of shape, in case if shape is damaged. Relocation as per requirement	48 hours in case of Mandatory Signs, Cautionary and Informatory Signs (Single and Dual post signs) 15 Days in case of Gantry/ Cantilever Sign boards	IRC:67-2012
	Retro reflectivity	As per specifications in IRC:67-2012	Bi-Annually	Testing of each	Change of signboard	48 hours in case of Mandatory	IRC:67-2012

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Timelimit for Rectification	Specifications and Standards
				sign board using Retro Reflectivity Measuring Device. In accordance with AST MD 4956-09.		Signs, Cautionary and Informatory Signs (Single and Dual postsigns) 1 Month in case of Gantry / Cantilever Sign boards	
Kerb	Kerb Height	Asper IRC86:1983 depending upon type of Kerb	Bi-Annually	Use of distance measuring tape	Raising Kerb Height	Within 1 Month	RC86:1983
	Kerb Painting	<u>Functionality:</u> Functioning of Kerb painting as intended	Daily	Visual with video/ image backup	Kerb Repainting	Within 7-days	RC35:2015
Other Road Furniture	Reflective Pavement Markers (Road Studs)	Numbers and Functionality as per specificationsin IRC:SP:84-2014 and IRC:35-2015,unless specified in Schedule-B.	Daily	Counting	NewInstallation	Within 2 months	IRC:SP:84-2014,IRC:35-2015
	Pedestrian Guardrail	<u>Functionality:</u> Functioning of guardrail as intended	Daily	Visual with video/ image backup	Rectification	Within 15 days	IRC:SP:84-2014
	Traffic Safety Barriers	<u>Functionality:</u> Functioning of Safety Barriers as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP:84-2014, IRC:119-2015
	End Treatment of	<u>Functionality:</u> Functioning of End Treatment as intended	Daily	Visual with video /image	Rectification	Within 7 days	IRC:SP:84-2014,

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specifications and Standards
	Traffic Safety Barriers			backup			IRC:119-2015
	Attenuators	Functionality: _____ Functioning of Attenuators as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP-2014, IRC:119-2015
	Guard Posts and Delineators	Functionality: Functioning of Guard Posts and Delineators as intended	Daily	Visual with video/ image backup	Rectification	Within 15 days	IRC: 79 - 1981
	Overhead Sign Structure	Overhead sign structures shall be structurally adequate	Daily	Visual with video /image backup	Rectification	Within 15 days	IRC:67-2012
	Traffic Blinkers	Functionality: Functioning of Traffic Blinkers as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP:84-2014
Highway Lighting System	Highway Lights	Illumination: Minimum 40 Lux illumination on the road surface	Daily	The illumination level shall be measured with luxmeter	Improvement in Lighting System	24 hours	IRC:SP:84-2014
		No major failure in the lighting system	Daily	-	Rectification of failure	24 hours	IRC:SP:84-2014
		No minor failure in the lighting system	Monthly	-	Rectification of failure	8 hours	IRC:SP:84-2014
	Toll Plaza Canopy Lights	Minimum 40 Lux illumination on the road surface	Daily	The illumination level shall be measured with luxmeter	Improvement in Lighting System	24 hours	IRC:SP:84-2014
		No major/minor failure in the lighting system	Daily	-	Rectification of failure	8 hours	IRC:SP:84-2014

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Timelimit for Rectification	Specifications and Standards
Trees and Plantation including median plantation	Obstruction in a minimum head-room of 5.5 m above carriageway or obstruction in visibility of road signs	No obstruction due to trees	Monthly	Visual with video/ image backup	Removal of trees	Immediate	IRC:SP:84-2014
	Deterioration in health of trees and bushes	Health of plantation shall be as per requirement of specifications & instructions issued by Authority from time to time	Daily	Visual with video/image backup	Timely watering and treatment . Or Replacement of Trees and Bushes.	Within 90 days	IRC:SP:84-2014
	Vegetation affecting sight line and road structures	Sight line shall be free from obstruction by vegetation	Daily	Visual with video/ image backup	Removal of Trees	Immediate	IRC:SP 84-2014
Rest Areas	Cleaning of toilets	-	Daily	-	-	Every 4 hours	
	Defects in electrical, water and sanitary installations	-	Daily	-	Rectification	24 hours	

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specifications and Standards
Other Project Facilities and Approach roads	Damage or deterioration in Approach Roads, pedestrian facilities, trucklay-bys,bus-bays, bus-shelters,cattle crossings,Traffic Aid Posts, Medical Aid Posts and other works		Daily	-	Rectification	15 days	IRC:SP 84-2014

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specifications and Standards
Pipe/box/slab culverts	Free waterway/unobstructed flow section	85% of culvert normal flow area to available.	2 times in a year (before and after rainy season)	Inspection by Bridge Engineer as per IRC SP:35-1990 and Recording of depth of silting and area of vegetation.	Cleaning silt up soils and debris in culvert barrel after rainy season, removal of bushes and vegetation, U/s of barrel, under barrel and D/s of barrel before rainy season.	15 days before onset of monsoon and within 30 days after endofrainy season.	IRC5-2015, IRC SP:40-1993 and IRC SP:13-2004
	Leak-proof expansion joints if any	No leakage through expansion joints	Bi-Annually	Physical inspection of expansion joints as per IRC SP: 35-1990 if any, for leakage strains on walls at joints.	Fixing with sealant suitably	30 days or before onset of rains whichever comes earlier	IRC SP:40-1993 andIRC SP:69-2011
	Structurally sound	Spalling of concrete not more than 0.25 sqm Delamination of concrete not more than 0.25 sq.m. Cracks wider than 0.3 mm not more than 1m aggregate length	Bi-Annually	Detailed inspection of all components of culvert as per IRC SP:35-1990and recording the defects	Repairs to spalling, cracking, delamination, rusting shall be followed as per IRC:SP:40-1993.	15days	IRCSP 40-1993 and MORTH Specifications clause 2800

	Protection works in good condition	Damaged of rough stone apron or bank revetment not more than 3 sqm, damage to solid apron (concrete apron) not more than 1 sqm	2 times in a year (before and after rainyseason)	Condition survey as per IRCSP:35-1990	Repairs to damaged aprons and pitching	30 days after defect observation or 2 weeks before on set of rainy season whichever is earlier.	IRC:SP40-1993 and IRC: SP: 13 - 2004.
Bridges including ROB's Flyover etc. as applicable	Riding quality or user comfort	No pothole in wearing coat on bridge deck	Daily	Visual inspection as per IRCSP:35-1990	Repairs to BC or wearing coat	15days	MORT&H Specification 2811
Bridge -Super Structure	Bumps	No bump at expansion joint	Daily	Visual inspection as per IRC SP:35- 1990	Repairs to BC on either side of expansion joints, profile correction course on approach slab in case of settlement to approach embankment	15days	MORT&H Specification 3004.2 & 2811.
	Usersafety (condition of crash barrier andguard rail)	No damaged or missing stretch of crash barrier or pedestrian hand railing	Daily	Visual inspection and detailed condition survey as per IRC SP: 35-1990.	Repairs and replacement of safety barriers as the case may be	3days	IRC:5-1998, IRCSP:84-2014 and IRCSP:40-1993.

	Rusted reinforcement	Notmore than 0.25 sq.m	Bi-Annually	Detailed condition survey as per IRCSP: 35-1990 using Mobile Bridge Inspection Unit	All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anti-corrosive coating before carrying out the repairs to affected concrete portion with Epoxy mortar/concrete.	15days	IRCSP:40-1993 and MORTH Specification 1600.
	Spalling of Concrete	Notmore than 0.50 sq.m					
	Delamination	Notmorethan0.50 sq.m					
	Cracks wider than 0.30mm	Not more than 1 m total length	Bi-Annually	Detailed condition survey as per IRCSP: 35-1990 using Mobile Bridge Inspection Unit	Grouting with epoxy mortar, investigating causes for cracks development and carryout necessary Rehabilitation.	48Hours	IRCSP:40-1993 and MORTH Specification 2800.
	Rainwater seepage through deck slab	Leakage-nil	Quarterly	Detailed condition survey as per IRCSP: 35-1990 using Mobile Bridge Inspection Unit	Grouting of decks labat leakage areas, water proofing, repairs to drainage spouts	1months	MORTH Specifications 2600&2700.
	Deflection due to permanent loads and	Within design limits.	Once in every 10 years for spans more	Load test method	Carry out major rehabilitation works on bridge to retain original design loads capacity	6 months	IRCSP: 51-1999.

	liveloads		than40m				
	Vibrations in bridge deck due to moving trucks	Frequency of vibrations shall not be more than 5 Hz	Once in every 5 years for spans morethan 30m and every 10 years for spans between 15 to 30m	Laser displacement sensors or laser vibro-meters	Strengthening of super structure	4months	AASHTOLRFD specifications
	Leakage in Expansion joints	No damage to elastomeric sealant compound in strip seal expansion joint, no leakage of rain water through expansion joint in case of buried and asphalt plug and copper strip joint.	Bi-Annually	Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge Inspection Unit	Replace of seal in expansion joint	15days	MORTH specifications 2600 and IRC SP:40-1993.
	Debris and dust in strip seal	No dust or debris in expansion joint	Monthly	Detailed condition survey as per IRC SP:35-1990 using	Cleaning of expansion joint gaps thoroughly	3days	MORTH specification s2600 and

	expansion joint	gap.		Mobile Bridge Inspection Unit			IRCSP:40-1993.
	Drainage spouts	No down take pipe missing/ broken belows of fit of the deck slab. No silt, debris, clogging of drainage spout collection chamber.	Monthly	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	Cleaning of drainage spouts thoroughly. Replacement of missing/ broken downtake pipes with a minimum pipe extension of 500 mm below soffit of slab. Providing sealant around the drainage spout if any leakages observed.	3days	MORTH specification 2700.
Bridge-substructure	Cracks/spalling of concrete/ rusted steel	No cracks, spalling of concrete and rusted steel	Bi-Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anti-corrosive coating before carrying out repairs to substructure by grouting/guniting and micro concreting depending on type of defect noticed	30days	IRCSP:40-1993 and MORTH specification 2800.

	Bearings	Delamination of bearing reinforcement not more than 5%, cracking or tearing of rubber not more than 2 locations per side, nor rupture of reinforcement or rubber	Bi-Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	In case of failure of even one bearing on any pier/ abutment, all the bearing on that pier / abutment shall be replaced, in order to get uniform load transfer onto bearings.	3 months	MORTH specification 2810 and IRCSP:40-199.
Bridge Foundations	Scouring around foundations	Scouring shall not be lower than maximum scour level for the bridge	Bi-Annually	Condition survey and visual inspection as per IRCSP:35-1990 using Mobile Bridge Inspection Unit. In case of doubt, use Underwater camera for inspection of deep wells in major Rivers.	Suitable protection works around pier/ abutment	1 month	IRCSP:40-1993, IRC 83-2014, MORTH specification 2500
	Protection works in good condition	Damaged of rough stone apron or bank revetment not more than 3	2 times in a year (before and after rainy season)	Condition survey as per IRC SP: 35-1990	Repairs to damaged aprons and pitching.	30 days after defect observation or 2	IRC:SP40-1993 and IRC:SP:13-2004.

		sq.m,damageto solid apron (concreteapron)				weeks before onset of rainy season whichever is earlier.	
<p>Note: Any Structure during the entire contract period which is found that does not comply with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor.</p>							

Table4: Maintenance Criteria for Structures and Culverts:

Table 5: Maintenance Criteria for Hill Roads

In addition to above, for hill roads the following provisions for maintenance is also to done.

Hill Roads		
(i)	Damage to Retaining wall/ Breast wall	7 (Seven) days
(ii)	Land slides requiring clearance	12 (Twelve) hours
(iii)	Snow requiring clearance	24 (Twenty-Four) hours

Note: For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith) along with MoRTH specifications shall be binding for all maintenance activities.

A. Flexible Pavement

Nature of Defect or deficiency		Time
		limit for repair/ rectification
(b) Granular earth shoulders, side slopes, drains and culverts		
(i)	Variation by more than 1 % in the prescribed slope of camber/cross fall (shall not be less than the camber on the main carriageway)	7 (seven) days
(ii)	Edged road shoulders exceeding 40 mm	7 (seven) days
(iii)	Variation by more than 15% in the prescribed side (embankment) slopes	30 (thirty) days
(iv)	Raincuts/gullies in slope	7 (seven) days
(v)	Damage to or silting of culverts and side drains	7 (seven) days
(vi)	Desilting of drains in urban/semi-urban areas	24 (twenty-four) hours
(vii)	Railing, parapets, crash barriers	7 (seven) days (Restore immediately if causing safety hazard)
(c) Road side furniture including road sign and pavement marking		
(i)	Damage to shape or position, poor visibility or loss of retro-reflectivity	48 (forty-eight) hours
(ii)	Painting of km stone, railing, parapets, crash barriers	As and when required/ Once every year
(iii)	Damaged/missing signs road requiring replacement	7 (seven) days
(iv)	Damage to road markings	7 (seven) days
(d) Road lighting		
(i)	Any major failure of the system	24 (twenty-four) hours
(ii)	Faults and minor failures	8 (eight) hours
(e) Trees and plantation		

Nature of Defector deficiency		Time limit for repair/rectification
(i)	Obstruction in a minimum head- room of 5 m above carriageway or obstruction in visibility of road signs	24 (twenty-four) hours
(ii)	Removal of fallen trees from carriageway	4(four) hours
(iii)	Deterioration in health of trees and bushes	Timely watering and treatment
(iv)	Trees and bushes requiring replacement	30 (thirty) days
(v)	Removal of vegetation affecting sight lineand road structures	15 (fifteen) days
(f) Rest area		
(i)	Cleaning of toilets	Every 4 (four) hours
(ii)	Defects in electrical, water and sanitary installations	24 (twenty-four) hours
(g) [Toll Plaza]		
(h) Other Project Facilities and Approach roads		
(i)	Damage in approach roads, pedestrian facilities, truck lay- byes, bus-bays, bus-shelters, cattle crossings, [Traffic Aid Posts, Medical Aid Posts] and service roads	15 (fifteen) days
(ii)	Damaged vehicles or debris on the road	4 (four) hours
(iii)	Malfunctioning of the mobile crane	4 (four)hours
Bridges		
(a) Super structure		
(i)	Any damage, cracks, spalling/ scaling Temporary measures Permanent measures	within 48 (forty-eight) hours within 15 (fifteen) days or as specified by the Authority's Engineer
(b) Foundations		

Nature of Defect or deficiency		Timelimit for repair/ rectification
(i)	Scouring and/or cavitation	15 (fifteen) days
(c) Piers, abutments, return walls and wing walls		
(i)	Cracks and damages including settlement and tilting, spalling, scaling	30 (thirty) days
(d) Bearings (metallic) of bridges		
(i)	Deformation, damages, tilting or shifting of bearings	15 (fifteen) days Greasing of metallic bearings once in a year
(e) Joints		
(i)	Malfunctioning of joints	15 (fifteen) days
(f) Other items		
(i)	Deforming of pads in elastomeric bearings	7 (seven) days
(ii)	Gathering of dirt in bearings and joints; or clogging of spouts, weep holes and vent-holes	3 (three) days
(iii)	Damage or deterioration in kerbs, parapets, hand rails and crash barriers	3 (three) days (immediately within 24 hours if posing danger to safety)
(iv)	Rain-cuts or erosion of banks of the side slopes of approaches	7 (seven) days
(v)	Damage to wearing coat	15 (fifteen) days
(vi)	Damage or deterioration in approach slabs, pitching, apron, toes, floor or guide bunds	30 (thirty) days
(vii)	Growth of vegetation affecting the structure or obstructing the waterway	15 (fifteen) days
(g) Hill Roads		
(i)	Damage to retaining wall/breast wall	7 (seven) days
(ii)	Land slides requiring clearance	12 (twelve) hours

Nature of Defector deficiency		Time limit for repair/ rectification
(iii)	Snow requiring clearance	24 (twenty-four) hours

[Note: Where necessary, the Authority may modify the time limit for repair/rectification, or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

Schedule – F
(See Clause 4.1 (vii))

Applicable Permits

1. Applicable Permits

- (i) The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:
 - (a) Permission of the State Government for extraction of boulders from quarry;
 - (b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
 - (c) license for the use of explosives;
 - (d) Permission of the State Government for drawing water from river/reservoir;
 - (e) license from the inspector of factories or other competent Authority for setting up the batching plant;
 - (f) Clearance of Pollution Control Board for setting up batching plant;
 - (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
 - (h) Permission of Village Panchayats and State Government for borrowing earth; and
 - (i) Any other permits or clearances required under Applicable Laws.
- (ii) Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority under the provisions of this Agreement.

Schedule-G

(See Clauses 7.1 and 19.2)

Annex-I

(See Clause 7.1)

Form of Bank Guarantee

[Performance Security/Additional Performance Security]

[GM/CPM UPSBC] WHEREAS:

- (A) _____ [name and address of contractor] (hereinafter called the "**Contractor**") and [name and address of the authority], (hereinafter called the "**Authority**") have entered into an agreement (hereinafter called the "**Agreement**") for the construction of the on Engineering, Procurement, and Construction (the "**EPC**") basis, subject to and under the provisions of the Agreement
- (B) The Agreement requires the Contractor to furnish a Performance Security for due and faithful performance of its obligations, under and under the Agreement, during the {Construction Period/ Defects Liability Period and Maintenance Period} (as defined in the Agreement) in a sum of Rs..... cr. (Rupees crore)(the "**Guarantee Amount**").
- (C) We,.....through our branch at(the "**Bank**") have agreed to furnish this bank guarantee (*hereinafter called the "**Guarantee**"*) by way of Performance Security.

NOW, THEREFORE , the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor's obligations during the {Construction Period/ Defects Liability Period and Maintenance Period} under and under the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and any referenceto the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
2. A letter from the Authority, under the hand of an officer not below the rank of

[CPM/GM UPSBC], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final, and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor, and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfillment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the
6. rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
7. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfillment, compliance, and/or performance of all or any of the obligations of the Contractor under the Agreement.
8. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority shall be forfeited and

the Bank shall be relieved from its liabilities hereunder.

9. The Guarantee shall cease to be in force and effect on ****\$. Unless a demand or claim under this Guarantee is made in writing before the expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
10. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
11. Any notice by way of request, demand, or otherwise hereunder may be sent by post addressed to the Bank at its above-referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
12. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority under the provisions of the Agreement.

Signed and sealed thisday of....., 20..... at..... SIGNED,
SEALED AND DELIVERED

For and on behalf of the Bank by:
(Signature)
(Name)
(Designation)
(Code Number)
(Address)

NOTES:

- (i) The bank guarantee should contain the name, designation, and code number of the officer (s) signing the guarantee.
- (ii) The address, telephone number, and other details of the head office of the Bank as

Annex – II

(Schedule - G)

(See Clause 19.2)

Form for Guarantee for Advance Payment

[GM/CPMUP SBC]

WHERE AS:

- (A) [name and address of contractor] (hereinafter called the “**Contractor**”) has executed an agreement (hereinafter called the “**Agreement**”) with the [name and address of the authority],(hereinafter called the “**Authority**”) for the construction of the on Engineering, Procurement and Construction (the “**EPC**”) basis, subject to and under the provisions of the Agreement
- (B) Under Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @*Bank Rate + 3%* advance payment (hereinafter called “**Advance Payment**”) equal to 10% (ten percent) of the Contract Price; and that the Advance Payment shall be made in two installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the full repayment of the installment of the Advance Payment as security for compliance with its obligations under the Agreement. The amount of {first/second}installment of the Advance Payment is Rs ----- cr. (Rupees crore) and the amount of this Guarantee is Rs.-----cr.(Rupees -----crore)(the “**Guarantee Amount**”)\$.
- (C) We,.....through our branch at(the “**Bank**”) have agreed to furnish this bank guarantee (*hereinafter called the “Guarantee*”) for the Guarantee Amount.

NOW, THEREFORE , the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment ontime of the aforesaid installment of the Advance Payment under and under the Agreement, and agrees and undertakes to pay to the Authority,upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
A letter from the Authority, under the hand of an officer not below the rank of [GM/CPM UPSBC], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for there payment of the

installment of the Advance Payment under and under the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

- 2 To give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor, and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 3 It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 4 The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or for bear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other for bearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 5 This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Advance Payment.
- 6 Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- 7 The Guarantee shall cease to be in force and effect on ****. Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.

- 8 The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 9 Any notice by way of request, demand, or otherwise hereunder may be sent by post addressed to the Bank at its above-referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 10 This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority under the provisions of the Agreement.

Signed and sealed thisday of.....,20..... at..... SIGNED,
SEALED AND DELIVERED

For and on behalf of

the Bank by:
(Signature)
(Name)
(Designation)
(Code Number)
(Address)

NOTES:

- (i) The bank guarantee should contain the name, designation, and code number of the officer(s) signing the guarantee.

^sInsert a date being 90 (ninety) days after the end of one year from the date of payment of the Advance payment to the Contractor (under Clause 19.2 of the Agreement).

- (ii) The address, telephone number, and other details of the head office of the Bank as well as of the issuing branch should be mentioned on the cover letter of the issuing branch.
- _____

SCHEDULE-H

See Clauses 10.1(iv) and 1 9.3

Contract Price Weightages

- 1.1 The Contract Price for this Agreement is Rs.....
- 1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

Item	Weightages in Percentage to the contract Price	Stage of Payment	Percentage Weights
1	2	3	4
1. Approach Road & Add. Approach Road	4.00%	i)-Earth work & Subgrade (GSB)	50%
		ii) WMM	10%
		iii) DBM	10%
		iv) Bituminous Concrete	30%
2. Major Bridge	75.00%	(i) Foundation	40%
		(ii) Sub Structure	10%
		(iii) Super Structure	47%
		(iv) Expansion Joint	1%
		(v) Miscellaneous work (Crash Barrier + Hand Rail + Weep Holes + Drainage Spout + Drain Pipe + Wearing Coat etc.)	2%

Item	Weightages in Percentage to the contract Price	Stage of Payment	Percentage Weights
1	2	3	4
4. Approach Viaduct	12.00%	(i) Foundation	40%
		(ii) Sub Structure	10%
		(iii) Super Structure	47.00%
		(iv) Expansion Joint	1.00%
		(v) Miscellaneous work (Railing over Crash Barrier + Drainage Spout+ Wearing Coat etc.)	2.00%
5.Otherworks	9.00%	(i) Protection Work + Chutes on Embankments	10%
		(ii) Box Culvert	34%
		(iii) Retaining Wall	50%
		(iv) Kc drains etc.	03%
		(iv) Lighting Arrangements	2.5%
		(v) Road markings, Road Signage, Overhead Sign Board,Paintingon (Crash Barrier & Kerb) and km stones etc.	0.5%

1.1 The procedure for estimating the value of work done:

1.3.1 Road Works:

Stage of Payment	Payment Procedure
1	2
Construction of Approach Road	
i)-Earth work & Subgrade	The unit of measurement is linear length. Payment of each stage shall be made on a pro-rata basis on completion of a stage in full length.
ii) - WMM	
iii) - DBM	
iv) BC	

For example, if the total length of bituminous work to be done is 100 km, the cost perkm of bituminous work shall be determined as follows:

$$\text{Cost per km} = P \times \text{Weightages for road work} \times \text{Weightage for bituminous work} \times (1/L)$$

Where P= Contract Price

L= Total length in Km

Similarly, the rates per km for other stages shall be worked out accordingly.

Note: The length affected due to law and order problems or litigation during execution due to which the Contractor is unable to execute the work, may be deducted from the total project length for payment purposes. The total length calculated here is only for payment purposes and will not affect and refer to other clauses of the Contract Agreement.

1.3.2 Major Bridge

Stage of Payment	Payment Procedure
1	2
(i) Foundation	The cost of each foundation shall be determined on a pro-rata basis with respect to the total number of foundations. Payment against the foundation shall be made on a pro-rata basis on completion of one foundation lift, on prorated basis of no of lifts to constructed, min 2 m lift, in case of well foundation, and 20 % on well cap foundation In case load testing is required for the foundation, the trigger of the first payment shall include load testing where specified.
(ii) Sub Structure i/c Bearing	Payment against Sub-structure shall be made on a pro-rata basis on completion of one pier lift, on prorated basis of no of lifts to constructed, min 2 m lift, in case of well foundation, and 20 % on pier cap complete
(iii) Super Structure	Payment shall be made on a pro-rata basis on completion of a stage i.e. completion of super - structure including bearings of at least one span in all respects as specified. 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be on completion of stage as above.

(iv) Expansion Joint	Payment shall be made on completion of the wearing coat including expansion joints complete in all respects as specified.
(v) Miscellaneous work (Crash Barrier + Hand Rail + Weep Holes + Drainage Spout + Drain Pipe + Wearing Coat etc.)	Payments shall be made on completion of all miscellaneous works like hand rails, crash barriers, road markings, etc. complete in all respects as specified.

1.3.3 Otherworks

Stage of Payment	Payment Procedure
1	2
Other works	
(i) Protection Work + Chutes on Embankments	Payment shall be made on a pro-rata basis on completion of a stage of not less than 50 % (Fifty percent) of the total scope.
(ii) Box bridge	The unit of measurement is linear length. Payment shall be made on a pro-rata basis on completion of a stage in a length of not less than 50 % (Fifty percent) of the total length.
(iii) Retaining wall	The unit of measurement is linear length. Payment shall be made on a pro-rata basis on completion of a stage in a length of not less than 50 % (Fifty percent) of the total length.
(iv) KC drains etc.	The unit of measurement is linear length. Payment shall be made on a pro-rata basis on completion of a stage in a length of not less than 50 % (Fifty percent) of the total length.
(v) Lighting Arrangements	The unit of measurement is linear length. Payment shall be made on a pro-rata basis on completion of a stage in a length of not less than 50 % (Fifty percent) of the total length.
(v1) Roadmarkings + Road Signage + Overhead Sign Board + Painting on (Crash Barrier & Kerb) + km stones etc.	The unit of measurement is linear length/ square unit as the case may be. Payment shall be made on a pro-rata basis on completion of a stage in a length of not less than 50 % (Fifty percent) of the total length.

Schedule-I

(See Clause 10.2 (iv))

Drawings

1. Drawings

In compliance with the obligations outlined in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

2. Additional Drawings

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

Annex-I

(Schedule-I)

List of Drawings

A minimum list of the drawings of the various components/ elements of the Project Highway and project facilities required to be submitted by the Contractors is given below:

- a) Drawings of horizontal alignment, vertical profile, and detailed cross sections.
- b) Drawings of cross-drainage works.
- c) Drawings of Major intersections, **Major bridges**, Grade Separated Structures, Viaducts, etc.
- d) Drawing of road furniture including traffic signage, marking, safety barriers, etc.
- e) Drawing of traffic diversion plan.
- f) Drawing as per instruction of Authority's Engineer.
- g) General arrangement showing the area of base camp and administrative block.
- h) General arrangement showing electrical works.

Schedule-J

(See Clause 10.3 (ii))

Project Completion Schedule

1. Project Completion Schedule

During the Construction period, the Contractor shall comply with the requirements outlined in this **Schedule-J** for each of the Project Milestones and the Scheduled Completion Date. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

2. Project Milestone-I

- (i) Project Milestone-I shall occur on the date falling on the **[30% of the Scheduled Construction Period]** day from the Appointed Date (the "**Project Milestone- I**").
- (ii) Before the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than **10% (ten percent)** of the Contract Price.

3. Project Milestone-II

- (i) Project Milestone-II shall occur on the date falling on the **[60% of the Scheduled Construction Period]** day from the Appointed Date (the "**Project Milestone- II**").
- (ii) Before the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than **40% (forty percent)** of the Contract Price.

4. Project Milestone-III

- (i) Project Milestone-III shall occur on the date falling on the **[85% of the Scheduled Construction Period]** day from the Appointed Date (the "**Project Milestone- III**").
- (ii) Before the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than **70% (seventy percent)** of the Contract Price.

5. Scheduled Completion Date

- (i) The Scheduled Completion Date shall occur on **1095th** days from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction under this Agreement.

6. Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and under the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

Schedule-K

(See Clause 12.1 (ii))

Tests on Completion

1. Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days before the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10(ten) days before the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted under Article 12 and this Schedule-K.

2. Tests

- (i) Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [***].
- (ii) Riding quality test: The riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with the latest equipment and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometer.
- (iii) Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted under the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Nondestructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) meters or more shall also be subjected to load testing.
- (iv) Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, under Good Industry Practice, for determining the compliance of the Project Highway with Specifications and Standards, except tests as specified in clause 5, but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.

- (v) Environmental audit: The Authority’s Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements outlined in Applicable Laws and Applicable Permits.
- (vi) Safety Audit: The Authority’s Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

3. Agency for Conducting Tests

All Tests outlined in this Schedule-K shall be conducted by the Authority’s Engineer or such other agency or person as it may specify in consultation with the Authority.

4. Completion Certificate

Upon successful completion of Tests, the Authority’s Engineer shall issue the Completion Certificate under the provisions of Article 12.

- 5. The Authority Engineer will carry out tests with the following equipment at his own cost in the presence of the contractor’s representative.

Sr. No.	Key metrics of Asset	Equipment to be used	Frequency of condition survey
1	Surface defects of pavement	Network Survey Vehicle (NSV)	At least twice a year (As per survey months defined for the state basis rainy season)
2	Roughness of pavement	Network Survey Vehicle(NSV)	At least twice a year (As per survey months defined for the state basis rainy season)
3	Strength of pavement	Falling Weight De-flectometer (FWD)	At least once a year
4	Bridges	Mobile Bridge Inspection Unit(MBU)	At least twice a year (As per survey months defined for the state basis rainy season)
5	Roadsigns	Retro-reflectometer	At least twice a year (As per survey months defined for the state basis rainy season)

The first testing with the help of NSV shall be conducted at the time of issue of the Completion Certificate.

Schedule-L

(See Clause 12.2)

Completion Certificate

- 1 I,.....(Name of the Authority’s Engineer),acting as the Authority’s Engineer, under and under the Agreement dated (the “Agreement”), for [Construction of the.....](the “Project Highway”) on Engineering, Procurement, and Construction(EPC) basis through (Name of Contractor), hereby certify that the Tests under Article 12 of the Agreement have been successfully undertaken to determine compliance of the Project Highway with the provisions of the Agreement,and I am satisfied that the Project Highway can be safely and reliably placed in service of the Users thereof.

- 2 It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the day of..... 20..., Scheduled Completed Date for which was the.....day of.....20.....

SIGNED,SEALED AND DELIVERED

For and on behalf of the Authority’s Engineer by:

(Signature)

(Name)

(Designation)(Address)

Schedule-M

(See Clauses 14.6, 15.2 and 19.7)

Payment Reduction for Non-Compliance

2. Payment reduction for non-compliance with the Maintenance Requirements

- (i) Monthly lump sum payments for maintenance shall be reduced in the case of non-compliance with the Maintenance Requirements outlined in Schedule E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority’s Engineer shall calculate the amount of payment reduction based on weightage in percentage assigned to non-conforming items as given in Paragraph 2.

3. Percentage reductions in lump sum payments on a monthly basis

- (i) The following percentages shall govern the payment reduction:

S.No.	Item/Defect/Deficiency	Percentage
(a)	Carriageway/Pavement	
(i)	Potholes, cracks, and other surface defects	15%
(ii)	Repairs of Edges, Rutting	5%
(b)	Road,Embankment,Cuttings,Shoulders	
(i)	Edgedrop,in adequate crossfall, undulations, settlement, potholes, ponding, obstructions	10%
(ii)	Deficient slopes, raincuts, disturbed pitching, vegetation growth, pruning of trees	5%
(c)	Bridges and Culverts	
(i)	De-silting, cleaning, vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations	20%
(ii)	Any Defects in superstructures ,bearings, and sub-structures	10%

S.No.	Item/Defect/Deficiency	Percentage
(iii)	Painting, repairs/replacement kerbs, railings, parapets, guideposts/crash barriers	5%
(d)	Road side Drains	
(i)	Cleaning and repair of drains	5%
(e)	Road Furniture	
(i)	Cleaning, painting, and replacement of road signs, delineators, road markings, 200 m/km/5 th km stones	5%
(f)	Miscellaneous Items	
(i)	Removal of dead animals, broken down/accident vehicles, fallen trees, road blockades, or malfunctioning mobile crane	10%
(ii)	Any other Defects under paragraph 1.	5%
(g)	Defects in Other Project Facilities	5%

- (ii) The amount to be deducted from the monthly lump-sum payment for non-compliance with a particular item shall be calculated as under:

$$R = \frac{P}{100} \times (M1 \text{ or } M2) \times \frac{L1}{L}$$

Where,

P= Percentage of particular item/Defect/deficiency for deduction

M1=Monthly lump-sum payment under para 1.2 above of this Schedule

M2=Monthly lump-sum payment under para 1.2 above of this Schedule

L1=Non-complying length L= Total length of the road,

R= Reduction (the amount to be deducted for non-compliance for a particular item/Defect/deficiency)

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non-compliance.

For any Defect in part of one kilometer, the non-conforming length shall be taken as one kilometer.

Schedule-N

(See Clause 18.1 (i))

TOR of Authority's Engineer

1. Terms of Reference

The Terms of Reference for the Authority's Engineer (the "**TOR**") shall substantially conform with Annex 1 to this Schedule N.

Annex-I

(Schedule-N)

Terms of Reference for Authority's Engineer

1. Scope

- (i) This TOR shall apply to the construction and maintenance of the Project Highway.

2. Definitions and interpretation

- (i) The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- (ii) References to Articles, Clauses, and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses, and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- (iii) The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

3. General

- (i) The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- (ii) The Authority's Engineer shall perform the duties and exercise the authority under the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:
 - (a) any Time Extension;
 - (b) any additional cost to be paid by the Authority to the Contractor;
 - (c) the Termination Payment; or
 - (d) issuance of Completion Certificate or
 - (e) any other matter which is not specified in (a),(b),(c),or (d) above and which creates a financial liability on either Party.
- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- (iv) The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's

prior approval under the provisions of Clause 18.2.

- (v) The Authority's Engineer shall aid and advise the Authority on any proposal for a Change of Scope under Article 13.
- (vi) In the event of any disagreement between the Parties regarding the meaning, scope, and nature of Good Industry Practice, as outlined in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope, and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

4. Construction Period

- (i) During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geotechnical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant under the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however, that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended up to 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.
- (ii) The Authority's Engineer shall review and approve any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- (iii) The Authority's Engineer shall review and approve the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within 21 (twenty-one) days stating the modifications, if any, required thereto.
- (iv) The Authority's Engineer shall complete the review and approval of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- (v) The Authority's Engineer shall grant written approval to the Contractor, where necessary, for the interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period under the provisions of Clause 10.4.
- (vi) The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- (vii) The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies.

In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.

- (viii) The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- (ix) To determine that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and under Good Industry Practice for quality assurance. For purposes of this Paragraph 4 (ix), the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.
- (x) The Authority's Engineer shall test check at least 50 (fifty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (xi) The timing of tests referred to in Paragraph 4 (ix) and the criteria for acceptance/rejection of their results shall be determined by the Authority's Engineer under the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its quality assurance under Good Industry Practice.
- (xii) If the results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.
- (xiii) The Authority's Engineer may instruct the Contractor to execute any work that is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event, or otherwise ; provided that incase of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (xiv) In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen)days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.
- (xv) The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificateis issued under Clause 12.2.

- (xvi) The authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measures, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.
- (xvii) If the Contractor carries out any remedial measures to secure the safety of suspended works and Users and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.
- (xviii) The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate, as the case may be. For carrying out its functions under Paragraph 4 (xviii) and all matters incidental thereto, the Authority's Engineer shall act under and under the provisions of Article 12 and Schedule K.

5. Maintenance Period

- (i) The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- (ii) The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.
- (iii) The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, to determine that the Project Highway conforms with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor on this behalf.
- (iv) In respect of any defect or deficiency referred to in Paragraph 3 of Schedule- E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration concerning the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.
- (v) The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

6. Determination of costs and time

- (i) The Authority's Engineer shall determine the costs, and/or their reasonableness, that

are required to be determined by it under the Agreement.

- (ii) The Authority's Engineer shall determine the period Extension that is required to be determined by it under the Agreement.
- (iii) The Authority's Engineer shall consult each Party in every case of determination under the provisions of Clause 18.5.

7. Payments

- (i) The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer under the provisions of Clause 10.2 (iv) (d).
- (ii) Authority's Engineer shall-
 - (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor under Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
 - (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments under the provisions of Clause 19.10.
- (iii) The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor under Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor under the provisions of the Agreement.
- (iv) The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance under the provisions of Clause 19.16.

8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

9. Miscellaneous

- (i) A copy of all communications, comments, instructions, Drawings, or Documents sent by the Authority's Engineer to the Contractor under this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- (ii) The Authority's Engineer shall retain at least one copy of each of all Drawings and Documents received by it, including 'as-built' Drawings, and keep them in its safe custody.

- (iii) Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and micro film form or such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- (iv) The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.
- (v) The Authority's Engineer shall inform the Authority and the Contractor of any event of the Contractor's Default within one week of its occurrence.

Schedule-O

(See Clauses 19.4(i), 19.6(i), and 19.8 (i))

Forms of Payment Statements

1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed under Clause 19.3(i) after the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope order executed after the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above under the provisions of Clause 13.2 (iii) (a);
- (e) total of (a),(b),(c), and (d)above;
- (f) Deductions:
 - i. Any amount to be deducted under the provisions of the Agreement except taxes;
 - ii. Any amount towards deduction of taxes;and
 - iii. Total of (i) and (ii) above.
- (g) Net claim:(e)-(f) (iii);
- (h) The amounts received by the Contractor upto the last claim:
 - i. For the Works executed (excluding Change of Scope orders);
 - ii. For Change of Scope Orders, and
 - iii. Taxes deducted

2. Monthly Maintenance Payment Statement

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible under the provisions of the Agreement;
- (b) the deductions for maintenance work not done;
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause19.12; and
- (e) amount towards the deduction of taxes

3. Contractor's claim for Damages

Note: The Contractor shall submit its claims in a form acceptable to the Authority.

Schedule - P

(See Clause 20.1)

Insurance

2. Insurance during the Construction Period

- (i) The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non-Political Event of Force Majeure, malicious act, accidental damage, explosion, fire, and terrorism:
 - (a) insurance of Works, Plant, and Materials and an additional sum of [15 (fifteen)] percent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
 - (b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.
- (ii) The insurance under sub-para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks that are not insurable at commercial terms.

3. Insurance for Contractor's Defects Liability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring before the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and Good Industry Practice.

4. Insurance against injury to persons and damage to property

- (i) The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not **less than Rs.15 lacs**.

- (ii) The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
 - (a) the Authority's right to have the construction works executed on, over, under, in, or through any land, and to occupy this land for the Works; and
 - (b) damage which is an unavoidable result of the Contractor's obligations to execute the Works.
- (iii) **Insurance to be in jointnames**

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.

Schedule-Q

(See Clause 14.10)

Tests on Completion of Maintenance Period

1. Riding Quality test:

Riding quality test: The riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometer.

2. Visual and physical test:

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping, and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.

Schedule-R

(See Clause 14.10)

Taking Over Certificate

I, (Name and designation of the Authority's Representative) under and under the Agreement dated(the "**Agreement**"),for [Construction of the] (the"**Project Highway**") on Engineering, Procurement, and Construction (EPC) basis through.

(Name of Contractor), hereby certify that the Tests on completion of Maintenance Period under Article 14 of the Agreement has been successfully under taken to determine compliance of the Project Highway with the provisions of the Agreement and I hereby certify that the Authority has taken over the Project Highway from the Contractor on this day.....

SIGNED, SEALED AND DELIVERED

(Signature)

(Name and designation of Authority's Representative)

(Address)

******* End of the Document*******