

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

Chief Administrative Officer / CON acting for and on behalf of The President of India invites E-Tenders against Tender No **29-CAO-C-SC-2026** Closing Date/Time 30/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	SCR Construction Organisation - Secunderabad Division: Construction of Rail Over Rail (ROR) at Dornakal station: Construction of Viaductt bridge at Ch.7185 m of 25 x 30.50m Composite Girder and Rail Over Rail Bridge at Ch.7909m of 3 x 61.00 m Open Web Girder, Execution of Earth work in embankment and blanketing on approaches,Laying & Linking of BG Track on ROR portion and execution of miscellaneous Civil works in connection with Rail Over Rail at Dornakal Junction connecting Dornakal-Bhadrachalam Road Branch Line		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Two Packet System
Tender Closing Date Time	30/06/2026 15:00	Date Time Of Uploading Tender	26/05/2026 17:28
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	901721086.02	Tendering Section	GENERAL
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	18034400.00	Validity of Offer (Days)	90
Tender Doc. Cost (Rs.)	0.00	Period of Completion	24 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	16/06/2026		
Are JV allowed to bid	Yes	Number of JV Member Allowed	3
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-IRUSSOR-2021 ITEMS FOR EARTHWORK							16490315.00	Above/ Below/P ar
1	011031	70000.00	cum	220.94	15465800.00	AT Par	15465800.00	
	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, platforms etc. with contractor's own earth conforming to Soil Quality Class SQ1/SQ2/SQ3, after preparation of foundations as applicable, benching in existing banks wherever required, spreading in layers with motor grader, bringing the moisture content to OMC, mechanical compaction to specified density and dressing of bank to final profile as per RDSO Specifications: RDSO/2020/GE: IRS-0004 with latest correction slips. Note: 1) Foundation preparation, Benching including additional earthwork on account of this, wherever required, shall be paid extra under relevant schedule item for benching. 2) Payment for Earthwork under this item shall be made based on the cross section measurements calculated (i) with original ground profile of existing bank based on initial ground levels before doing benching and (ii) final profile of the bank worked out with final levels as per prevailing guidelines. Using Soil Class SQ1							
2	011032	600.00	cum	268.50	161100.00	AT Par	161100.00	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, platforms etc. with contractor's own earth conforming to Soil Quality Class SQ1/SQ2/SQ3, after preparation of foundations as applicable, benching in existing banks wherever required, spreading in layers with motor grader, bringing the moisture content to OMC, mechanical compaction to specified density and dressing of bank to final profile as per RDSO Specifications: RDSO/2020/GE: IRS-0004 with latest correction slips. Note: 1) Foundation preparation, Benching including additional earthwork on account of this, wherever required, shall be paid extra under relevant schedule item for benching. 2) Payment for Earthwork under this item shall be made based on the cross section measurements calculated (i) with original ground profile of existing bank based on initial ground levels before doing benching and (ii) final profile of the bank worked out with final levels as per prevailing guidelines. Using Soil Class SQ2							
3	012030	500.00	cum	1726.83	863415.00	AT Par	863415.00	
	Description:- Mechanical manufacturing of blanketing material by using only hard and durable stone crushed in mechanical crusher to different gradations, wet mixing of the same in designed proportion in Pug mill or wet mix plant to have uniform gradation including all incidental transportation, laying over finished formation in uniform layer(s) with motor grader, compaction with suitable vibratory roller to specified density and finishing to correct profile, complete as per RDSO Specification No. RDSO/2020/GE: IRS-0004 with latest correction slips. Note: This item shall be used only when entire constituent of blanketing material is mechanically manufactured by crushing of hard and durable stone into desired gradation of designed proportion.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-IRUSSOR-2021 ITEMS FOR SOIL EXPLORATION							3908053.20	Above/ Below/P ar
1	021011	300.00	Metre	1065.00	319500.00	AT Par	319500.00	
	Description:- Exploratory drilling of boreholes down to required depth, drilling of 150mm dia. boreholes in all type of soils except hard rock & large boulders (boulder core more than 30cm) including refilling, reinstating surface and disposing off surplus material including use of mechanical rigs with power operated winches as well as percussion/chiselling tool for advancing through occasional seams of hard strata to be employed, where necessary in Dry area. 0m to 10m							
2	021012	300.00	Metre	1118.52	335556.00	AT Par	335556.00	
	Description:- Exploratory drilling of boreholes down to required depth, drilling of 150mm dia. boreholes in all type of soils except hard rock & large boulders (boulder core more than 30cm) including refilling, reinstating surface and disposing off surplus material including use of mechanical rigs with power operated winches as well as percussion/chiselling tool for advancing through occasional seams of hard strata to be employed, where necessary in Dry area. 10m to 20m							
3	021051	300.00	Metre	3055.85	916755.00	AT Par	916755.00	
	Description:- Drilling of NX size borehole (75mm dia.) in all types of hard rock and collection of rock core samples from boreholes and preserving in boxes. 0m to 10m							
4	021052	150.00	Metre	3209.71	481456.50	AT Par	481456.50	
	Description:- Drilling of NX size borehole (75mm dia.) in all types of hard rock and collection of rock core samples from boreholes and preserving in boxes. 10m to 20m							
5	021110	100.00	Each	137.81	13781.00	AT Par	13781.00	
	Description:- Taking out 100mm dia. & 450mm long undisturbed samples of soil from bore holes, including provision of air tight containers for packing and, labeling incl. transporting the samples to laboratory. Piston sampler shall be used for extracting undisturbed samples where necessary. Samples shall be collected as per IS:2720.							
6	021120	100.00	Each	147.17	14717.00	AT Par	14717.00	
	Description:- Taking out 100mm dia. & 450mm long disturbed samples of soil from bore holes, including provision of air tight containers for packing, labeling and transporting the samples to laboratory. Samples shall be collected as per IS:2720.							
7	021130	100.00	Each	802.76	80276.00	AT Par	80276.00	
	Description:- Conducting standard penetration test as per IS:2131 at approximate 1.5m intervals in bore holes, as directed by the Engineer in charge							
8	021151	100.00	Each	267.59	26759.00	AT Par	26759.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Moisture Content/Dry Density							
9	021152	100.00	Each	535.18	53518.00	AT Par	53518.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Atterberg Limits							
10	021153	100.00	Each	535.18	53518.00	AT Par	53518.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Specific Gravity							

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

11	021154	100.00	Each	735.87	73587.00	AT Par	73587.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Grain size analysis including Hydrometer analysis							
12	021155	100.00	Each	2006.91	200691.00	AT Par	200691.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Direct Shear Test							
13	021156	100.00	Each	602.07	60207.00	AT Par	60207.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Natural Density							
14	021157	100.00	Each	6689.69	668969.00	AT Par	668969.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Consolidation Test							
15	021158	100.00	Each	2006.91	200691.00	AT Par	200691.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Unconfined Compression Test							
16	021159	100.00	Each	2006.91	200691.00	AT Par	200691.00	
	Description:- Conducting laboratory Tests on collected soil samples as per relevant IS code Tri-axial Test							
17	021161	75.00	Each	267.59	20069.25	AT Par	20069.25	
	Description:- Conducting Laboratory tests on collected ROCK SAMPLES as per relevant IS code Density Test							
18	021162	75.00	Each	267.59	20069.25	AT Par	20069.25	
	Description:- Conducting Laboratory tests on collected ROCK SAMPLES as per relevant IS code Water Absorption & Porosity							
19	021163	75.00	Each	133.79	10034.25	AT Par	10034.25	
	Description:- Conducting Laboratory tests on collected ROCK SAMPLES as per relevant IS code Hardness							
20	021164	75.00	Each	2006.91	150518.25	AT Par	150518.25	
	Description:- Conducting Laboratory tests on collected ROCK SAMPLES as per relevant IS code Unconfined Compression Test							
21	021170	5.00	Each	1337.94	6689.70	AT Par	6689.70	
	Description:- Conducting chemical analysis of ground water samples to determine suitability for concreting and aggressiveness in relation to attack on concrete / reinforcement including determination of pH value.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-IRUSSOR-2021 ITEMS FOR BRIDGE WORKS - FOUNDATION & SUB-STRUCTURE							95440537.02	Above/ Below/ Par
1	022011	7880.00	cum	189.63	1494284.40	AT Par	1494284.40	
	Description:- Earthwork in excavation by mechanical means (Hydraulic Excavator)/Manual Means for foundations and floors of the bridges, retaining walls etc. including setting out, dressing of sides, ramming of bottom, getting out the excavated material, back filling in layers with approved material and consolidation of the layers by ramming and watering etc. including all lift, disposal of surplus soil up to a lead of 300m, all types of shoring and strutting with all labour and material complete as per drawing and technical specification as directed by Engineer in charge. Note: This item will be used for excavation work in connection with other miscellaneous works also like side drains, foundation for OHE masts and other miscellaneous structures in connection with Gauge Conversion, Doubling, New lines. All kinds of soils							
2	022012	985.00	cum	387.70	381884.50	AT Par	381884.50	
	Description:- Earthwork in excavation by mechanical means (Hydraulic Excavator)/Manual Means for foundations and floors of the bridges, retaining walls etc. including setting out, dressing of sides, ramming of bottom, getting out the excavated material, back filling in layers with approved material and consolidation of the layers by ramming and watering etc. including all lift, disposal of surplus soil up to a lead of 300m, all types of shoring and strutting with all labour and material complete as per drawing and technical specification as directed by Engineer in charge. Note: This item will be used for excavation work in connection with other miscellaneous works also like side drains, foundation for OHE masts and other miscellaneous structures in connection with Gauge Conversion, Doubling, New lines. Soft rock (not requiring blasting)							
	022013	500.00	cum	708.17	354085.00	AT Par	354085.00	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

3	Description:- Earthwork in excavation by mechanical means (Hydraulic Excavator)/Manual Means for foundations and floors of the bridges, retaining walls etc. including setting out, dressing of sides, ramming of bottom, getting out the excavated material, back filling in layers with approved material and consolidation of the layers by ramming and watering etc. including all lift, disposal of surplus soil up to a lead of 300m, all types of shoring and strutting with all labour and material complete as per drawing and technical specification as directed by Engineer in charge. Note: This item will be used for excavation work in connection with other miscellaneous works also like side drains, foundation for OHE masts and other miscellaneous structures in connection with Gauge Conversion, Doubling, New lines. Hard rock (requiring blasting)						
4	022032	410.00	cum	2593.05	1063150.50	AT Par	1063150.50
	Description:- Providing and laying in position Plain cement concrete of specified Nominal Mix for miscellaneous works like side drains, foundation for OHE masts and other miscellaneous structures excluding the cost of Cement, centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)						
5	024020	105.00	cum	2646.72	277905.60	AT Par	277905.60
	Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Design Mix Cement Concrete, mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants, of specified grade (cast in-situ) using 20mm graded crushed stone aggregate and coarse sand of approved quality in Drop and curtain wall and alike structures below bed level, complete in all respect as per drawings and technical specifications to the satisfaction of Engineer-in-Charge. Note: Payment for cement, reinforcement and shuttering shall be made extra.						
6	022040	4690.00	cum	2646.72	12413116.80	AT Par	12413116.80
	Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality in RCC raft foundation & Pile cap including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Note: 1. Payment for cement, reinforcement and shuttering shall be made extra under relevant item. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons for not using plasticiser at the stage of Mix Design and in that case deduction shall be made as per relevant item.						
7	022051	5360.00	cum	2718.70	14572232.00	AT Par	14572232.00
	Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the following Reinforced cement concrete structural elements up to height of 9.0 m from foundation top level, including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Note: 1. Payment for cement, reinforcement and shuttering shall be made extra under relevant item. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons for not using plasticiser at the stage of Mix Design and in that case deduction shall be made as per relevant item. Abutment & Pier						
8	022052	2680.00	cum	2718.70	7286116.00	AT Par	7286116.00
	Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the following Reinforced cement concrete structural elements up to height of 9.0 m from foundation top level, including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Note: 1. Payment for cement, reinforcement and shuttering shall be made extra under relevant item. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons for not using plasticiser at the stage of Mix Design and in that case deduction shall be made as per relevant item. Wing wall and Return wall						
	022053	1060.00	cum	2754.70	2919982.00	AT Par	2919982.00

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

9	<p>Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the following Reinforced cement concrete structural elements up to height of 9.0 m from foundation top level, including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Note: 1. Payment for cement, reinforcement and shuttering shall be made extra under relevant item. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons for not using plasticiser at the stage of Mix Design and in that case deduction shall be made as per relevant item. Abutment cap, Pier Cap, Inspection Platform & Pedestal over Pier cap, Fender wall, Diaphragm wall etc.</p>						
10	022054	25.00	cum	2682.71	67067.75	AT Par	67067.75
10	<p>Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the following Reinforced cement concrete structural elements up to height of 9.0 m from foundation top level, including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Note: 1. Payment for cement, reinforcement and shuttering shall be made extra under relevant item. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons for not using plasticiser at the stage of Mix Design and in that case deduction shall be made as per relevant item. Approach slab at formation level, Dirt wall/ ballast wall at formation level</p>						
11	022060	100.00	cum	2599.66	259966.00	AT Par	259966.00
11	<p>Description:- Providing and laying Plain Cement Concrete 1:3:6 with graded stone aggregate of 40mm nominal size, in foundation and floors, retaining walls of bridges including mechanical mixing, vibrating, pumping and bailing out water where ever required with all materials and labour complete but excluding the cost of cement and shuttering as per drawings and technical specifications as directed by Engineer.</p>						
12	022070	1550.00	Metre	231.77	359243.50	AT Par	359243.50
12	<p>Description:- Providing and fixing Weep Holes in Abutments, Wing walls and Return walls etc., of new bridges with 110mm dia UPVC pipe Type A ISI marked with all contractor's men, material, transportation, all taxes as per specifications and as directed by Engineer-in-Charge.</p>						
13	023021	15.00	Each	57722.11	865831.65	AT Par	865831.65
13	<p>Description:- Providing and constructing Temporary Earthen Island / coffer dam for construction of well foundations of dia. up to 10m (longest dimension) , including bailing and pumping out of water, provision of sand bags, wooden ballies, sheet piling, earth, sand or any other suitable material, as required with all labour and material complete job. For water depth up to 1.00m</p>						
14	023022	45.00	Each	88284.17	3972787.65	AT Par	3972787.65
14	<p>Description:- Providing and constructing Temporary Earthen Island / coffer dam for construction of well foundations of dia. up to 10m (longest dimension) , including bailing and pumping out of water, provision of sand bags, wooden ballies, sheet piling, earth, sand or any other suitable material, as required with all labour and material complete job. Extra for every 1.00m additional depth and part thereof over item 023021 up to water depth of 4.00m.</p>						
15	023023	770.00	RM	3953.17	3043940.90	AT Par	3043940.90
15	<p>Description:- Providing and constructing Temporary Earthen Island / coffer dam for construction of well foundations of dia. up to 10m (longest dimension) , including bailing and pumping out of water, provision of sand bags, wooden ballies, sheet piling, earth, sand or any other suitable material, as required with all labour and material complete job. Providing and constructing 10m wide service road to reach island location from one pier location to another pier location.</p>						
16	025031	17900.00	Sqm	605.99	10847221.00	AT Par	10847221.00
16	<p>Description:- Centering and shuttering including strutting, propping etc. and removal of form for : All types of bridge sub-structures, e.g. pier, abutment, wing wall, retaining wall, RCC box type foundations, Abutment cap, Pier Cap, Inspection Platform & Pedestal over Pier cap, Fender wall, Diaphragm wall etc. up to 5m above ground level</p>						
17	025032	7390.00	Sqm	788.17	5824576.30	AT Par	5824576.30
17	<p>Description:- Centering and shuttering including strutting, propping etc. and removal of form for : All types of bridge super-structures, e.g. slabs, I-girders, T-girders, Box girders etc. up to 5m above ground level.</p>						
	031012	1350.00	cum	2862.67	3864604.50	AT Par	3864604.50

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

18	<p>Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for cast in-situ Prestressed (Post-tensioned) concrete girder / Box girders/Slabs for different spans including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per drawings, specifications and direction of the Engineer in-charge. Note: 1. Payment for Staging, Shuttering, Cement, reinforcement, HTS cables, sheathing, anchorage cones, stressing of cables and grouting of the ducts shall be made extra under relevant items. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons at the stage of Mix Design and in that case deduction shall be made as per relevant item. With Soffit level From 9m above Bed Level to 12m above Bed Level</p>						
19	031090	6198880.00	Cubic Centimetre	1.20	7438656.00	AT Par	7438656.00
19	<p>Description:- Design, manufacturing, supplying and fixing in position elastomeric bearing true to line and level conforming to IS:3400, IS:226, BS-5400 under prestressed concrete girders/ Steel Girders, for Pre-cast as well as cast-in-situ girders as per approved drawing. The rate shall include cost of load test of one no. bearing from Railway approved firms and all fixing materials, equipments, machineries, labour, taxes, loading, unloading, leading, lifting etc. complete. Rates include getting the drawing approved from Railway and cost of inspection during manufacturing from railway approved organization. Note : 1. The rate is for finished item complete and paid only after fixing in position below the girder. 2. The volume shall be as given in the drawing and no deduction shall be made for inserted steel plates etc.</p>						
20	031101	260.00	Metre	6148.89	1598711.40	AT Par	1598711.40
20	<p>Description:- Providing and fixing in position of standard preformed sealed and slab type or strip seal elastomeric type expansion joints for Railway bridge or Road Over Bridges as per approved drawings and latest MORTH/IRC specifications complete in all respect as directed by Engineer in-charge. For 40mm expansion</p>						
21	031111	14.00	Each	75665.73	1059320.22	AT Par	1059320.22
21	<p>Description:- Load testing of one or more spans of bridge as selected by the Engineer as per approved load test procedure following relevant IS/IRC/Railway codes with contractor's labour, deflection measuring instruments, loading materials, recording and analyzing the load testing results including all lead & lift, etc. complete as required. The rates are all inclusive and will be paid after load test is finished and girder is cleared of the kentledges/loading material etc. The load shall be 1.25 times the stipulated design load. For Span design load up to 100 MT</p>						
22	031112	600.00	MT	263.43	158058.00	AT Par	158058.00
22	<p>Description:- Load testing of one or more spans of bridge as selected by the Engineer as per approved load test procedure following relevant IS/IRC/Railway codes with contractor's labour, deflection measuring instruments, loading materials, recording and analyzing the load testing results including all lead & lift, etc. complete as required. The rates are all inclusive and will be paid after load test is finished and girder is cleared of the kentledges/loading material etc. The load shall be 1.25 times the stipulated design load. Extra for every increase of 1 MT or part thereof over 100 MT in the span design load capacity up to 800 MT</p>						
23	031192	100.00	Metre	1142.50	114250.00	AT Par	114250.00
23	<p>Description:- Providing and fixing in position GI Drainage Spouts of required length with Grating in RCC slab and filling bitumen along kerb as shown in drawing with contractor's pipes, bitumen, tools, equipment, lead, lifts etc. complete as per specifications and as directed by Engineer in-charge. 100mm dia. Drainage Spouts</p>						
24	031210	1200.00	Metre	525.51	630612.00	AT Par	630612.00
24	<p>Description:- Supplying and laying 160mm dia. PVC Pipes Class-I, capable for a pressure of 2.5 kg/sqm in footpath of ROB for laying cable with all contractor's materials labour, tools, plant, machinery, vehicles, consumables, lead, lift etc. complete as per specifications and as directed by Engineer in-charge.</p>						
25	052140	300.00	Metre	338.30	101490.00	AT Par	101490.00
25	<p>Description:- Providing and fixing of Drainage Spouts of 110mm UPVC Type A ISI marked (Working pressure 4 kg/sqcm) using suitable clamps and adhesive etc., complete.</p>						
26	137105	3.00	Sqm	116.55	349.65	AT Par	349.65
26	<p>Description:- Painting 2 coats to Bridge Reference / Boards, Structures etc. along track with enamel paint of approved make with different colours & letters, as directed by Engineer in-charge. Miscellaneous General Boards, Jurisdiction Boards, Structures etc.</p>						
27	041207	3.00	Day	241163.26	723489.78	AT Par	723489.78
27	<p>Description:- Providing road crane of specified lifting capacity with specified jib length revolving type for material handling, assembly & erection of girders/slab/RCC Box etc. 200 MT capacity</p>						
	013051	200.00	RM	134.69	26938.00	AT Par	26938.00

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

28	Description:- Provision of barricading with contractor's bamboos / ballies vertical post of 100mm dia. planted at every 2m interval, projecting at least 1.5m above ground level and driven firmly (minimum 0.5m) inside ground and including painting verticals & horizontals with red luminous paints / strips at alternative bay on barricade. Barricades shall be maintained through out the execution of the work and shall be removed in workman like manner on completion of the work only after instruction of Engineer in-Charge. Note: (1) 60% payment shall be made on provision of barricading at work-site and balance 40% payment after removal of barricades. (2) The released bamboos / ballies shall be the property of the Contractor. With 3 horizontal bamboo / balli members of minimum 50mm dia. spaced equally
	013052 200.00 RM 79.28 15856.00 AT Par 15856.00
29	Description:- Provision of barricading with contractor's bamboos / ballies vertical post of 100mm dia. planted at every 2m interval, projecting at least 1.5m above ground level and driven firmly (minimum 0.5m) inside ground and including painting verticals & horizontals with red luminous paints / strips at alternative bay on barricade. Barricades shall be maintained through out the execution of the work and shall be removed in workman like manner on completion of the work only after instruction of Engineer in-Charge. Note: (1) 60% payment shall be made on provision of barricading at work-site and balance 40% payment after removal of barricades. (2) The released bamboos / ballies shall be the property of the Contractor. Joining with strong nylon rope in one cross and one horizontal pattern of minimum 5mm dia.
	124031 360.00 Each 1068.34 384602.40 AT Par 384602.40
30	Description:- Providing Caution Watchman at a location where caution order is imposed and ensuring to be on continuous vigil and exhibit necessary hand signals to the trains for their passage over caution spot. Note: 1) Prescribed protection equipment shall be supplied by Railways and the same shall be returned after work is over. 2) If Contractor fails to post watchman at any time during one day, penalty at double the accepted rates will be levied and 3) The watchman nominated by the contractor will be screened for suitability as per Railway norms. For one shift (12 Hrs)
	211201 120.00 Hour 870.14 104416.80 AT Par 104416.80
31	Description:- Hiring of machinery for minor miscellaneous works for short duration including operator/driver, fuel, lubricants and consumable. The contractor shall arrange all statutory permits as required by rules and regulations prevailing in the area of work. Payment shall be made for actual working hours at site. JCB Backhoe Loaders 3DX Plus or similar with minimum 1.10 cum bucket capacity
	211210 1800.00 Day 606.09 1090962.00 AT Par 1090962.00
32	Description:- Arranging labour as and when required by the Engineer in charge, for various works under SSE/P.Way, with contractor's T&P, equipments, hand signal flags, etc. as per specifications, special conditions and detailed scope of work as furnished in the tender and as directed by the Engineer in charge. Note: Item shall be operated with prior approval of concerned Sr. DEN / DEN in charge.
	013080 1000.00 Sqm 847.69 847690.00 AT Par 847690.00
33	Description:- Shoring with 'Z' section MS sheet piles side by side in all kinds of soil mechanically or manually as per approved drawing with contractor's own arrangement complete in all respects and removal of sheet piles after completion of the work as directed by engineer in-charge Note: Payment will be made as per actual driven length of pile.
	031020 41.00 cum 2646.72 108515.52 AT Par 108515.52
34	Description:- Providing and launching in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the Precast Prestressed (Post-tensioned) Concrete Girder/Box Girders/Slabs in contractor's casting yard in the vicinity of worksite, including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability, complete as per drawings, specifications and direction of the Engineer. Note: 1. Payment for Shuttering, Cement, Reinforcement, HTS cables, Sheathing, Anchorage Cones, stressing of cables, grouting of the ducts and launching of girder/slab in position shall be made extra under relevant items. However, deduction shall be made in case of slab as per relevant item. 2. For pre-cast item, loading in transport vehicle in casting yard is included and shall not be paid extra. 3. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons at the stage of Mix Design and in that case deduction shall be made as per relevant item.
	022014 500.00 cum 1058.31 529155.00 AT Par 529155.00
35	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

	<p>Description:- Earthwork in excavation by mechanical means (Hydraulic Excavator)/Manual Means for foundations and floors of the bridges, retaining walls etc. including setting out, dressing of sides, ramming of bottom, getting out the excavated material, back filling in layers with approved material and consolidation of the layers by ramming and watering etc. including all lift, disposal of surplus soil up to a lead of 300m, all types of shoring and strutting with all labour and material complete as per drawing and technical specification as directed by Engineer in charge. Note: This item will be used for excavation work in connection with other miscellaneous works also like side drains, foundation for OHE masts and other miscellaneous structures in connection with Gauge Conversion, Doubling, New lines. Hard rock (blasting prohibited)</p>							
36	022033	100.00	cum	2533.99	253399.00	AT Par	253399.00	
	<p>Description:- Providing and laying in position Plain cement concrete of specified Nominal Mix for miscellaneous works like side drains, foundation for OHE masts and other miscellaneous structures excluding the cost of Cement, centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size)</p>							
37	025012	7420.00	cum	-183.97	-1365057.40	AT Par	-1365057.40	
	<p>Description:- Deduct if Plasticiser has not been used in Design Mix Concrete of any grade as per approved mix design or use of 40mm graded stone aggregate in place of 20mm graded stone aggregate in any grade of concrete. Note: Deduction to be made for quantity of concrete. Deduction for using 40mm graded stone aggregate in place of 20mm graded stone aggregate in any grade of concrete.</p>							
38	025033	73900.00	Sqm	97.90	7234810.00	AT Par	7234810.00	
	<p>Description:- Centering and shuttering including strutting, propping etc. and removal of form for : Extra for additional height over item no. 025031 & 025032 wherever required with adequate bracing, propping etc. over initial height of 5 metres for every additional height of 1 metre or part thereof.</p>							
39	031013	1350.00	cum	3078.62	4156137.00	AT Par	4156137.00	
	<p>Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for cast in-situ Prestressed (Post-tensioned) concrete girder / Box girders/Slabs for different spans including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per drawings, specifications and direction of the Engineer in-charge. Note: 1. Payment for Staging, Shuttering, Cement, reinforcement, HTS cables, sheathing, anchorage cones, stressing of cables and grouting of the ducts shall be made extra under relevant items. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons at the stage of Mix Design and in that case deduction shall be made as per relevant item. With Soffit level From 12m above Bed Level to 15m above Bed Level</p>							
40	031014	1350.00	cum	71.98	97173.00	AT Par	97173.00	
	<p>Description:- Providing and laying in position machine batched, machine mixed and machine vibrated Cement Concrete of specified grade as per approved Design Mix (mixed in Mobile Concrete Batching/Mixing Plant at site or RMC from approved plants) using 20mm graded crushed stone aggregate and coarse sand of approved quality for cast in-situ Prestressed (Post-tensioned) concrete girder / Box girders/Slabs for different spans including finishing, using Plasticiser in approved proportions (as per IS:9103), to modify workability without impairing strength and durability complete as per drawings, specifications and direction of the Engineer in-charge. Note: 1. Payment for Staging, Shuttering, Cement, reinforcement, HTS cables, sheathing, anchorage cones, stressing of cables and grouting of the ducts shall be made extra under relevant items. 2. Plasticiser shall invariably be used in approved proportion to increase workability with minimum possible quantity of cement for all grade of Design Mix Concrete unless it is specifically approved citing reasons at the stage of Mix Design and in that case deduction shall be made as per relevant item. Extra over USSOR Item no. 031013 for Soffit level beyond 15m above Bed Level for every 1m or part thereof</p>							
41	137101	2.00	Each	150.25	300.50	AT Par	300.50	
	<p>Description:- Painting 2 coats to Bridge Reference / Boards, Structures etc. along track with enamel paint of approved make with different colours & letters, as directed by Engineer in-charge. Bridge Board</p>							
42	137104	30.00	Each	640.87	19226.10	AT Par	19226.10	
	<p>Description:- Painting 2 coats to Bridge Reference / Boards, Structures etc. along track with enamel paint of approved make with different colours & letters, as directed by Engineer in-charge. HFL, FSL & DL on Bridge Pier / Abutment</p>							
43	052260	6000.00	HP Hour	40.58	243480.00	AT Par	243480.00	
	<p>Description:- Dewatering of natural or accumulated water from any location. Payment to be done for Horse power of pump multiplied by pumping hours.</p>							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

Schedule () D-IRUSSOR-2021 ITEMS FOR SUPER STRUCTURE-STEEL & BEARINGS							461770457.26	Above/ Below/P ar
1	041011	1985.00	MT	142444.59	282752511.15	AT Par	282752511.15	
	Description:- Supplying, fabrication, assembling of all types of steel girders of specified spans with structural steel conforming to Quality "B0" Grade Designation E250 conforming to IS:2062, erection / slewing / end launching of steel girders with cranes or any other approved launching methods as per site conditions (not requiring traffic block) on sub-structure including provision of trolley refuges etc., complete as per approved QAP and drawings conforming to IRS-B1-2001 and other relevant codes and specifications. Note: 1. Detailed fabrication and erection drawings & launching methodology will be prepared by the contractor and got approved from Railway. 2. The rate is all inclusive including launching in position, complete in all respect except cost of (i) Painting / Metalising; (ii) Bearings & (iii) HSFG bolts which shall be paid extra under relevant item. 3. The payment shall be made on the theoretical weight of main components and gusset plates only. 4. Payment Schedule: (i) Receipt of material at site: 40% (ii) Fabrication of girders: 20% (iii) Erection/Launching: 20% (iv) Completion in all respects: 20% Plate Girder/Semi Through Girder/Composite Girder (Steel Work)							
2	041012	670.00	MT	158482.82	106183489.40	AT Par	106183489.40	
	Description:- Supplying, fabrication, assembling of all types of steel girders of specified spans with structural steel conforming to Quality "B0" Grade Designation E250 conforming to IS:2062, erection / slewing / end launching of steel girders with cranes or any other approved launching methods as per site conditions (not requiring traffic block) on sub-structure including provision of trolley refuges etc., complete as per approved QAP and drawings conforming to IRS-B1-2001 and other relevant codes and specifications. Note: 1. Detailed fabrication and erection drawings & launching methodology will be prepared by the contractor and got approved from Railway. 2. The rate is all inclusive including launching in position, complete in all respect except cost of (i) Painting / Metalising; (ii) Bearings & (iii) HSFG bolts which shall be paid extra under relevant item. 3. The payment shall be made on the theoretical weight of main components and gusset plates only. 4. Payment Schedule: (i) Receipt of material at site: 40% (ii) Fabrication of girders: 20% (iii) Erection/Launching: 20% (iv) Completion in all respects: 20% Open web Girder							
3	041013	2650.00	MT	3839.88	10175682.00	AT Par	10175682.00	
	Description:- Supplying, fabrication, assembling of all types of steel girders of specified spans with structural steel conforming to Quality "B0" Grade Designation E250 conforming to IS:2062, erection / slewing / end launching of steel girders with cranes or any other approved launching methods as per site conditions (not requiring traffic block) on sub-structure including provision of trolley refuges etc., complete as per approved QAP and drawings conforming to IRS-B1-2001 and other relevant codes and specifications. Note: 1. Detailed fabrication and erection drawings & launching methodology will be prepared by the contractor and got approved from Railway. 2. The rate is all inclusive including launching in position, complete in all respect except cost of (i) Painting / Metalising; (ii) Bearings & (iii) HSFG bolts which shall be paid extra under relevant item. 3. The payment shall be made on the theoretical weight of main components and gusset plates only. 4. Payment Schedule: (i) Receipt of material at site: 40% (ii) Fabrication of girders: 20% (iii) Erection/Launching: 20% (iv) Completion in all respects: 20% Extra for using steel conforming to Grade Designation E350 instead of Grade Designation E250 of Quality "B0" as per IS: 2062							
4	041020	37590.00	Kg	311.31	11702142.90	AT Par	11702142.90	
	Description:- Supplying and fixing HSFG bolts of any dia and any length with suitable nuts including DTI washers conforming to IRS-B1-2001 for bridges and steel structures with contractors labour, tools and plants and lead and lift etc., complete.							
5	041041	53000.00	Sqm	630.31	33406430.00	AT Par	33406430.00	
	Description:- Metallizing of steel work of girders with sprayed aluminium after surface preparation by Sand/grit blasting, followed by one coat of etch primer (IS:5666) & one coat of Zinc Chrome primer (IS:104) and two coats of aluminium paint (IS:2339) with all labour, T&P and material as a complete job duly conforming to all relevant specifications and process given under Clause 39 of IRS-B1-2001. Note: Nominal Thickness of sprayed Aluminium coating shall be 150 microns. DFT of Zinc chrome primer shall be 25-30 microns and DFT of each coat of Aluminium paint shall be 12-14 microns. On new girder during fabrication							
6	041050	3660.00	Kg	105.11	384702.60	AT Par	384702.60	
	Description:- Providing and fixing railing used in rows for footpath or anti-crash barrier railing with B class G.I. pipe 65/50 mm nominal dia including cost of M.S. angle and channels in vertical posts, welding / bolting, priming painting with one coat ready mix Zinc Chromate conforming to IS:104 with DFT of 25-30Microns, followed by one coat of Zinc Chrome red oxide conforming to IS:2074 with DFT of 25 Microns with all material, labour, T&P as a complete job. Note: Cost of painting shall be paid extra under relevant item.							
7	041080	29.00	MT	110904.69	3216236.01	AT Par	3216236.01	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

	Description:- Supplying, Fabricating and fixing access ladders, inspection platforms, Trolley refuges etc., on bridges with structural steel conforming to IS:2062 including welding / bolting, priming painting with one coat of ready mixed paint of Zinc Chromate (IS:104) with DFT of 25-30 microns followed by one coat of Zinc Chrome Red Oxide (IS:2074) with DFT of 25 microns with all material, labour, T&P as a complete job. Note: Painting shall be paid separately under relevant item.							
8	041090	4800.00	MT	566.14	2717472.00	AT Par	2717472.00	
	Description:- Supplying, fitting and fixing in position true to line and level cast steel rocker/roller bearing of different load bearing capacity conforming to IS :7666, IS:9565, IS:1030, IS:919, IS:3073 and IRS Bridge Code including all accessories as per drawing and Technical Specifications with all material, labour, T&P as a complete job. The payment shall be made for the load bearing capacity in Metric Tonne as per approved drawing.							
9	041370	90.00	MT	124797.68	11231791.20	AT Par	11231791.20	
	Description:- Supplying fabricating and erecting welded and/or bolted and/or riveted steel work in built up sections, trusses and framed work, staging, racks, Height Gauge etc. for Steel Structures other than bridge girders, using RSJ, tees, angles and channels/flats, plates, gussets, round or square bars, cleats, bolts etc., with contractors own steel including cutting, bending, straightening, drilling, riveting, hoisting, fixing, erecting, welding, bolting etc., with Providing stiffeners wherever required as per approved drawing including applying a priming coat of a approved steel primer with all contractor's materials, labour, tools & plants, lead & lift including crossing of tracks if required etc., complete as per specification and as directed by Engineer-in-charge. Note: The payment shall be made on the theoretical weight of main components and gusset plates only.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () E-IRUSSOR-2021 ITEMS FOR MISCELLANEOUS BRIDGE WORKS							27665274.96	Above/ Below/ Par
1	013100	340.00	Sqm	680.89	231502.60	AT Par	231502.60	
	Description:- Supplying & laying of drainage composite for use behind abutments, wing walls, return walls and Retaining walls Geocomposite drain (Vertical) as per RDSO Specification No. RDSO/2018/GE:IRS-0006 latest version with all material, labour, equipment, tools and plants, lead, lift etc. complete in all respects as per the direction of Engineer-in-Charge.							
2	051070	1340.00	cum	2494.46	3342576.40	AT Par	3342576.40	
	Description:- Providing and laying Pitching with Stone Boulders, weighing not less than 35kg each with voids filled with cement sand mortar 1:4 on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and Technical Specifications (filter media to be paid separately under the relevant item). Rate is excluding cost of cement which shall be paid extra under relevant item.							
3	051010	500.00	cum	1627.55	813775.00	AT Par	813775.00	
	Description:- Providing and laying boulders apron on river bed for protection against scour with stone boulders weighing not less than 35 kg each with voids filled with spalls complete as per drawing and Technical Specification.							
4	051030	2080.00	cum	1003.45	2087176.00	AT Par	2087176.00	
	Description:- Supplying of stone boulders weighing not less than 35 kg each at specified bridge locations.							
5	052020	50.00	cum	1940.44	97022.00	AT Par	97022.00	
	Description:- Providing and laying 300mm thick (average) Dry Stone flooring with boulders of not less than 35kg each in weight, hand packed with surface levelled off to the correct section with hammer dressing as necessary on the ground including filling the gaps with quarry spalls and ordinary sand complete including cost of supply of all materials, labour, lead, lift, tools, plants, crossing of tracks and the like as per drawing and technical specification as directed by Engineer in charge.							
6	052150	7730.00	cum	2355.72	18209715.60	AT Par	18209715.60	
	Description:- Providing and laying of filter media consisting of granular materials of GW, GP, SW groups as per IS:1498 (latest) in required profile behind boulder filling of abutments, wing walls / return walls etc. above bed level with all labour and material complete job as per drawing and technical specification of RDSO Guidelines.							
7	052200	17.00	Each	258.36	4392.12	AT Par	4392.12	
	Description:- Painting the HFL mark and Danger level mark, year of HFL on bridge abutments and piers with ready mixed paint as per standard in two coats over one coat of primer with all materials, labour, tools, scaffolding, all lead and lift etc. including writing complete.							
	052210	2.00	Each	744.16	1488.32	AT Par	1488.32	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

8	Description:- Providing cast in situ bridge number plaques as per Railway drawing in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm notch in Bridge parapet coping duly engraving the letter and figures and an arrow indicating the direction of flow and finishing the top exposed surface with cement mortar 1:3, painting letters and figures with two coats of black enamel paint on two coats of white background with all labour, tools, cement, paint etc. with all leads and lifts.														
9	052220	21.00	Each	1148.22	24112.62	AT Par	24112.62								
	Description:- Providing cast in-situ plaques for bridge foundations details of size 45cmx45cmx5cm in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm deep notch over abutment & piers, engraving the letters & figures with CM 1:3 and finished smooth including painting letters and figures with 2 coats of black enamel and plaque with white enamel with all labour, tools, cement, paint, curing etc. as a complete job.														
10	052240	500.00	cum	2109.60	1054800.00	AT Par	1054800.00								
	Description:- Supplying, spreading and filling coarse sand (no cohesive materials to be used) of approved quality including watering and ramming in foundation, behind the abutment, wing wall, retaining wall in layers not exceeding 150mm thick including its compaction as per direction of Engineer-in-charge. The rate includes all lead, lift, ascent, descent, crossing of Railway line etc. complete with contractor's labour, materials, tools and plant.														
11	053011	2.00	Set	24417.36	48834.72	AT Par	48834.72								
	Description:- Designing and developing Detailed structural and working Drawings for following items for ROB/RUB/Bridge based on Railway's approved GADs, duly collecting necessary data from Railways and R&B authorities, duly designing members and submission of check plot duly getting proof-checked by Railway approved institutes, submitting for Railway's verification and approval, making corrections duly incorporating suggestions in drawings/designs, further submission of original in transparent film paper and soft copy (CD) for Railways approval etc. with contractor's technical expertise and instruments, labour, consumables, repeatedly attending till final approval etc., complete as directed by Engineer in-charge. Open / Pile / Well Foundation for piers/abutments														
12	053012	2.00	Set	7592.80	15185.60	AT Par	15185.60								
	Description:- Designing and developing Detailed structural and working Drawings for following items for ROB/RUB/Bridge based on Railway's approved GADs, duly collecting necessary data from Railways and R&B authorities, duly designing members and submission of check plot duly getting proof-checked by Railway approved institutes, submitting for Railway's verification and approval, making corrections duly incorporating suggestions in drawings/designs, further submission of original in transparent film paper and soft copy (CD) for Railways approval etc. with contractor's technical expertise and instruments, labour, consumables, repeatedly attending till final approval etc., complete as directed by Engineer in-charge. RCC Bed Block														
13	053013	2.00	Set	23748.39	47496.78	AT Par	47496.78								
	Description:- Designing and developing Detailed structural and working Drawings for following items for ROB/RUB/Bridge based on Railway's approved GADs, duly collecting necessary data from Railways and R&B authorities, duly designing members and submission of check plot duly getting proof-checked by Railway approved institutes, submitting for Railway's verification and approval, making corrections duly incorporating suggestions in drawings/designs, further submission of original in transparent film paper and soft copy (CD) for Railways approval etc. with contractor's technical expertise and instruments, labour, consumables, repeatedly attending till final approval etc., complete as directed by Engineer in-charge. Foundation and sub-structure for RCC retaining wall, abutment and approach slab														
14	052250	2080.00	cum	334.09	694907.20	AT Par	694907.20								
	Description:- Providing Boulder Backing behind wing wall, return wall, retaining wall with hand packed boulders & cobbles with smaller size boulders toward the back including all lead, lift, labour & other incidental charges as complete work in all respect. Payment for boulder/cobbles will be done extra.														
15	052040	500.00	cum	1984.58	992290.00	AT Par	992290.00								
	Description:- Supply and laying of coarse sand including consolidation with all labour, lead, lift, tools, plants, crossing of tracks as per drawing and technical specification as directed by the Engineer in charge in case loose slush is encountered at site of foundation before casting the foundation or laying the filtering media.														
S.No.								Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () F-IRUSSOR-2021 ITEMS FOR REINFORCEMENT STEEL													238363712.00	Above/ Below/P ar	
1	025082	2425600.00	Kg	98.27	238363712.00	AT Par	238363712.00								

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

Description:- Supply of steel reinforcement of approved brands/makes for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars of grade Fe-500D or more of approved brands/makes.								
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () G-IRUSSOR-2021 ITEMS FOR CEMENT							41735282.50	Above/ Below/ Par
1	025072	5750.00	MT	7258.31	41735282.50	AT Par	41735282.50	
Description:- Supply and using Cement at Worksite Ordinary Portland Cement 53 grade of approved brands/makes								
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () H-IRUSSOR-2021 ITEMS FOR P-Way							10246883.08	Above/ Below/ Par
1	171032	25.00	MT	427.47	10686.75	AT Par	10686.75	
Description:- Loading, leading and unloading of 52Kg / 60Kg rail up to 13 metre length by Railway's Rail Dolly / Dip Lorry to the nominated location under traffic with line protection in case road carriage is not possible with different lead with a lift up to 5 metre during block period. For lead beyond 500 metre and up to 1 Km.								
2	171033	25.00	MT	50.80	1270.00	AT Par	1270.00	
Description:- Loading, leading and unloading of 52Kg / 60Kg rail up to 13 metre length by Railway's Rail Dolly / Dip Lorry to the nominated location under traffic with line protection in case road carriage is not possible with different lead with a lift up to 5 metre during block period. Extra to Items no. 171032 for lead beyond 1 Km for every subsequent Km or part thereof and up to 10 Km								
3	194010	2.00	Set	3509.41	7018.82	AT Par	7018.82	
Description:- Manufacture of flared portion of Guard Rail by cutting and bending to required shape & RDSO's approved drawings. Note: (1) Rails shall be supplied by Railways. (2) One set consists of two rails i.e. both left and right.								
4	194020	2.00	Set	3189.64	6379.28	AT Par	6379.28	
Description:- Providing and fixing of flared portion of guard rails of any rail section over PSC sleepers including fixing of with all fittings, including leading of rails and fittings, squaring and adjusting spacing of sleepers as required, providing nose blocks duly cutting wooden blocks supplied by railways and fixing it with bolts of 16mm dia as directed complete and finished as per RDSO's approved drawing. Note: 1.One set consists of LH & RH side rails of one end. 2.Required P.Way fittings will be supplied at SSE stores depot.								
5	194030	50.00	Each	64.86	3243.00	AT Par	3243.00	
Description:- Drilling holes 25mm to 40mm dia. with drill twist in the foot of guard rails for fixing guard rails on bridge as directed.								
6	202021	2.00	Each	6231.22	12462.44	AT Par	12462.44	
Description:- Manufacturing, fabricating and supplying retro-reflective Engineering Indicator boards, made of 2mm thick aluminium sheet or 3mm thick aluminium composite sheet, face to be fully covered with high intensity encapsulated type heat activated retro-reflective sheeting conforming to type-IV of ASTM-D4956-01 in yellow & black or other colour combination including subject matter, message, symbols, borders etc. as approved by Engineer In-charge or as per IRPWM guidelines, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class-2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back-support frame of M.S. angle iron of size 25mm x25mm x 3mm provided all along the edges of board with theft resistant measures back side of board shall be with non-peelable weatherproof paint, consisting of one coat of zinc chromate primer and two coats of epoxy paint. Vertical post shall have black & white anti-corrosive paint or powder coating complete, as directed. Caution Indicator Board of size 1400mmx400mm with back support frame fixed to vertical post of MS angle of size 50mmx50mmx6mm of 3650 mm long								
	202022	2.00	Each	5388.98	10777.96	AT Par	10777.96	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

7	<p>Description:- Manufacturing, fabricating and supplying retro-reflective Engineering Indicator boards, made of 2mm thick aluminium sheet or 3mm thick aluminium composite sheet, face to be fully covered with high intensity encapsulated type heat activated retro-reflective sheeting conforming to type-IV of ASTM-D4956-01 in yellow & black or other colour combination including subject matter, message, symbols, borders etc. as approved by Engineer In-charge or as per IRPWM guidelines, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class-2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back-support frame of M.S. angle iron of size 25mm x25mm x 3mm provided all along the edges of board with theft resistant measures back side of board shall be with non-peelable weatherproof paint, consisting of one coat of zinc chromate primer and two coats of epoxy paint. Vertical post shall have black & white anti-corrosive paint or powder coating complete, as directed. Speed Indicator Board of equilateral triangular shape having each side of 1000mm with back support frame fixed to vertical post of MS angle of size 50mmx50mmx6mm of 3650 mm long</p>						
	202024	2.00	Each	7524.70	15049.40	AT Par	15049.40
8	<p>Description:- Manufacturing, fabricating and supplying retro-reflective Engineering Indicator boards, made of 2mm thick aluminium sheet or 3mm thick aluminium composite sheet, face to be fully covered with high intensity encapsulated type heat activated retro-reflective sheeting conforming to type-IV of ASTM-D4956-01 in yellow & black or other colour combination including subject matter, message, symbols, borders etc. as approved by Engineer In-charge or as per IRPWM guidelines, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class-2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back-support frame of M.S. angle iron of size 25mm x25mm x 3mm provided all along the edges of board with theft resistant measures back side of board shall be with non-peelable weatherproof paint, consisting of one coat of zinc chromate primer and two coats of epoxy paint. Vertical post shall have black & white anti-corrosive paint or powder coating complete, as directed. Termination Indicator Board of Circular shape having diameter of 1000mm with back support frame welded to vertical post of MS angle of size 50mmx50mmx6mm of 3950 mm long</p>						
	195020	45.00	MT	128900.15	5800506.75	AT Par	5800506.75
9	<p>Description:- Fabrication & supply of Galvanized H-beam Sleepers made out of the materials conforming to IS 2062 of standard Rolled sections as per approved drawing Nos RDSO/B/1636/4/R,5&9 complete and as directed by Engineer-in charge. Note: Cost of steel fittings and GRSP shall be paid separately.</p>						
	195041	9600.00	Kg	108.99	1046304.00	AT Par	1046304.00
10	<p>Description:- Supplying & fixing of Anti-Skid MS / Stainless Steel chequered plates on un- ballasted deck bridge as per approved drawings, with matching grade stainless steel fasteners as directed by Engineer-in- Charge, on new bridge or replacement of existing chequered plates on old bridge including removal of old chequered plates and stacking near approaches of bridge, clear from all infringement. Note: Joints of chequered plates shall not fall in between sleepers MS chequered plates 6 to 8mm thick on new bridge</p>						
	201040	320.00	Set	1801.58	576505.60	AT Par	576505.60
11	<p>Description:- Manufacture & supply of a set of 2 Nos of Elastomeric Pads 25mm / 30mm thick and 4 nos of Grooved rubber pads as per RDSO drawing No. B/1636/5 alt 2 to suit Insulated H Beam sleepers from RDSO approved sources with all contractor's material, lead, lift, labour, tools, plant and transportation etc. complete as per approved drawings and as instructed by Engineer in-charge. Note: One Set consists of 2 nos. Elastomeric Pad 25mm/30mm and 4 nos. Grooved Rubber Pad.</p>						
	201080	320.00	Set	4835.12	1547238.40	AT Par	1547238.40
12	<p>Description:- Supplying of Zero toe load fixtures for H Beam sleepers of 52/60Kg Rails procured from RDSO approved firms as per RDSO approved drawing with up-to-date correction slips and specifications with all contractor's lead, lift, labour, tools, plant, transportation etc. complete as per instructions of Engineer in-charge. Note: Complete fixture for 1 sleeper shall constitute 1 set.</p>						
	123070	200.00	TRM	507.75	101550.00	AT Par	101550.00
13	<p>Description:- Linking of track on Girder Bridge with Steel Channel/H-beam sleepers as per approved drawings including leading of running and guard rails, sleepers and fittings, bending of guard rails, notching, drilling of holes, cutting of rails etc. as per IRPWM with latest correction slips and making track structure fit for normal speed. Note: 1) Rails, Steel Channel/H-beam sleeper and all fittings will be supplied by Railways. 2)Transportation of track material if supplied beyond 250m of bridge approaches, shall be paid separately under relevant item.</p>						
	195090	2.00	Set	42629.37	85258.74	AT Par	85258.74
14	<p>Description:- Bending the inner and outer 52 Kg/60Kg/90R rails available at site suitable for V portion along bulb of rerailing ramp as per RDSO Drg No T-8259 drilling of holes and cutting to the required length and shape all lead, lifts, labour, tools and plants machinery and all other required materials for bending etc, and as directed by Engineer In charge at site.</p>						
	195100	500.00	cu dm	47.11	23555.00	AT Par	23555.00

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

15	Description:- Supplying providing and fixing country kali wood/hard wood (Non teak) sleepers of various thickness and length as per the RDSO re railing ramp Drg No T-8259 for fixing bent rails and MS plates including cutting the wood in saw mills, transporting to site of work with all leads and lifts, labour, tools and plant etc. as directed by Engineer In-charge.							
16	195110	2.00	Each	16292.07	32584.14	AT Par	32584.14	
16	Description:- Fixing of 60Kg/52 Kg/90R rails for Re railing ramp as per RDSO Drg No T-8259 on bridge approaches on wooden/PSC sleepers including fixing railways fishplates, bolts, nuts, MS bearing plates, screws, check blocks of re-railing ramp etc, levelling after drilling of holes in rails wherever necessary under block with contractor's labour, tools and plants, machinery all etc, complete and as directed by Engineer in charge at site.							
17	201020	320.00	Set	238.44	76300.80	AT Par	76300.80	
17	Description:- Manufacture & supply of 10mm thick Grooved Rubber Pads as per drg. No. RDSO/T-5199 & RDSO's Spec. no. IRS-T-47-2006 (Prov.) from RDSO approved sources with all contractor's lead, lift, labour, tools, plant and transportation etc. complete as instructed by Engineer in-charge. Note: One set constitutes two nos.							
18	201060	320.00	Set	2781.85	890192.00	AT Par	890192.00	
18	Description:- Manufacture, supply & fixing of galvanised steel fittings of insulated galvanised steel channel sleeper for 60 Kg running rails & 52 Kg Guard Rail as per RDSO drawing no. RDSO/T-5155 to 5164 with up-to-date correction slips and specifications from RDSO approved sources with all contractor's lead, lift, labour, tools, plant, transportation etc. complete and instructions of Engineer in-charge.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () I-NS ITEMS							6100571.00	Above/ Below/P ar
1	NCON10004	4100.00	Sqm	1287.83	5280103.00	AT Par	5280103.00	
1	Description:- Designing, supplying, fabricating & providing of Trapezoidal roll formed deck sheeting profiles made of galvanised steel troughed metal decking plate over cross girders /supports for cast-in-situ deck slab of ROB, thickness of deck plate shall be 1.00mm (minimum) and shall serve as permanent shuttering to deck slab of 250mm(maximum) thickness measured over crest of metal decking and shall have adequate strength to support to the weight of green concrete and imposed loads during concreting over a span of 2000mm between supports, deck sheets to be embossed to facilitate enhanced sheet to concrete bonding with contractors all materials, men, equipment, tools & plant, fixing arrangements, all lead & lift and the work to be carried out above railway properties as directed by the Engineer-in-charge.							
2	NCON10002	50.00	Each	15950.00	797500.00	AT Par	797500.00	
2	Description:- Providing sheet piling with Railway's released rails and contractor's MS Sheet of 6mm thick, transportation of rails from stacks within Yard to site of work including loading and unloading, cutting the rails to required length, making the nosing at one end of the rail piece with Contractor's gas and equipment, cutting the MS sheet to required size of 0.42m x 6.40m (overall length of sheet pile is 7.00m), welding the MS sheet to rail post at 10 cm intervals on both sides of the rail and driving the sheet piles at locations where required by the side of the existing bridge alignment with the help of contractor's crawler crane, guide hammer and equipment, vehicles, consumables with all lead and lifts etc., complete as per dimensions and specifications mentioned in the approved drawings and as directed by the Engineer-in-charge. Note: i) The work is to be carried out in the proximity of electrified territory and running railway tracks and busy road traffic nearby. So, the contractor should take all pre-cautionary measures for ensuring safety of his workmen and his machinery from running trains/road vehicles. ii) The above item will be operated based on the necessity as per site conditions for ensuring safety of the adjoining bridge structures. The decision of Engineer will be final and no claims will be entertained with regard to operation of item.							
3	NCON17001	2.00	Each	6480.00	12960.00	AT Par	12960.00	
3	Description:- Preparation and submission of Completion drawings of Major / Minor bridges showing plan, elevation, section, notes and other relevant particulars to appropriate scale as per Railway Engineering code, prepared in AUTO CAD on 75 Micron thickness film, including submission of check print for proof check, to incorporate corrections and modifications as suggested by the Railway administration. Showing the exg. particulars in Indian ink and completed in Red ink as per the details given by Railways, with contractor's materials, labour, tools, plant etc., in the following sizes as per special conditions and as directed by the Engineer-in-charge.c) A-0 Size and size in between A1 and A0.							
	NCON02009	2.00	Each	5004.00	10008.00	AT Par	10008.00	

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

4	<p>Description:- Preparation and supply of drawings for major /RUBs/ROBs/ minor bridges with general arrangements, new / extension to BG standards (based on completion drawing of existing bridges/ rough sketches supplied by Railway), prepared on Auto CAD on 75 Micron Polythene film with Indian ink with different colour i.e. existing particulars in black & proposed in red colour with contractor's computer, stationery / staff, tools & equipment etc., complete as per specifications and as directed by the Engineer-in-charge. The name of the drawing shall be written bilingual language both in English & Hindi. Note: Total 6 sets of approved copies of plans shall be supplied by the contractor free of cost to the Railways in addition to the original drawing in tracing cloth or film and soft copy in CD.</p>
---	--

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Important All documents uploaded and remarks / confirmation entered by the bidders against any : eligibility condition shall be opened as part of technical bid only

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)
1.1	If JV firms are allowed to participate, Financial eligibility of the JV Firm shall be adjudged based on satisfactory fulfillment of the Para No.17.15.2 of Part-I of IRSGCC-2022 [including upto ACS no.11]	No	No	Not Allowed
1.2	NOTE: If the tender is not accompanied by the certificate(s) in support of financial eligibility as above, the tender shall be rejected. No post-tender correspondence will be entertained.	No	No	Not Allowed

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	(a)The tenderer must have successfully completed or substantially completed any of the following categories of works during last 07 (seven) years, ending last day of month previous to the one in which tender is invited[Even though the work might have commenced before the qualifying period]: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work each costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)
1.1	The total value of similar nature of work completed during the qualifying period and not the payments received within qualifying period alone, shall be considered. In case, final Bill of similar nature of work has not been passed and final measurements have not been recorded, the paid amount including statutory deductions will be considered. If final measurements have been recorded and work has been completed with negative variation, then also the paid amount including statutory deductions will be considered. However, if final measurements have been recorded and work has been completed with positive variation but variation has not been sanctioned, original agreement value or last sanctioned agreement value whichever is lower shall be considered for judging eligibility.	No	No	Not Allowed

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

1.2	In case JV firms are allowed to participate, Technical Eligibility of the JV Firm shall be adjudged based on satisfactory fulfillment of the Para No.17.15.1 of Part-I of IRSGCC-2022 [including upto ACS no.11]	No	No	Not Allowed
1.3	The works executed by tenderer for any Govt. / Govt. bodies / PSUs and public listed company (as detailed in Note for Para No.10.1 of part-I of IRSGCC 2022 including upto ACS no.11) shall only be considered for fulfilling of Technical Eligibility Criteria.	No	No	Not Allowed
1.3.1	The work experience certificate shall be in the name and style of the tenderer participating or as per provisions under Clause 17.15 of Part-I of IRSGCC 2022 (including upto ACS no.11) for JV Firm, if eligible to participate. However, in case the tenderer is submitting the certificate issued to a JV firm of which the tenderer is a member, the credentials proportionate to his share in the JV will be considered. The tenderer shall submit an attested copy of relevant JV Agreement along with the Tender.	No	No	Not Allowed
1.3.2	The work experience certificate shall be issued by an officer not below the rank of JA Grade or Bill passing Officer in Railways and Bill passing Officer/Executive In-charge of work in other Govt. / Govt. bodies / PSUs. The certificate should bear the signature and seal of the issuing officer, name of the department etc.	No	No	Not Allowed
1.3.3	Note for Para No.10.1 of Part-I of IRSGCC (including upto ACS no.11); Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated / registered atleast 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Allowed (Mandatory)
1.4	Defination of Similar Work :- Any "Railway /Metro /Road Bridge work having Steel Composite/Bowstring girder and / or PSC girder in super structure". NOTE: Foot over bridges, pipe line crossing, etc. will not be considered for similar nature of work for eligibility consideration.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Important All documents uploaded and remarks / confirmation entered by the bidders against any : compliance condition shall be opened as part of technical bid only.

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The Bid Security shall be deposited either in cash through e-payment gateway or submitted as Bank Guarantee bond from a scheduled commercial bank of India. The Bank Guarantee bond shall be as per Annexure- VIA and shall be valid for a period of 90 days beyond the bid validity period. Tenderers may refer Para 5 of IRSGCC -2022 -Part-I (including up to ACS no.11) for other details in regard to payment of bid security. The original Bank Guarantee should be delivered in person to Dy.CE/C/Plg./SC, Room no.206A, 2nd floor, Rail Nirman Nilayam, S.C. Railway, Secunderabad -500025. Note: As per ACS no.5 issued by Railway Board vide letter No.2022/CE-I/CT/GCC-2022/Policy dt.20.10.2023, "The original Bank Guarantee should be delivered in person to the oficial nominated as indicated in the tender document before closing date for submission of bids (i.e., excluding the last date of submission of bids (Authority: PCE/SC's Ir.no.W.496/Policy/Vol.IX, dt:31.05.2024).	Yes	Yes	Allowed (Mandatory)
2	Following documents shall be enclosed	No	No	Not Allowed
2.1	In case of Sole Proprietorship Firm, the documents to be attached with the tender are: (i)An undertaking that he is not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as a member of the partnership firm or JV in which he was / is a partner/member. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract.(ii) All documents in terms of Para 10 of the Tender Form (Second Sheet) of IRSGCC 2022(Including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

2.2	In case, the tenderer is bidding on behalf of HUF the documents to be attached with the tender are : (i) A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. (ii)An undertaking that the HUF is not blacklisted or debarred by Railways or any other Ministry/Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as member of JV in which the HUF was / is a member. Concealment/wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract.(iii) All other documents in terms of Para 10 of the Tender Form (Second Sheet) of IRSGCC 2022 (Including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)
2.3	In case, the Tenderer is a Partnership Firm, the following documents shall be submitted: (i)A notarized copy of the Partnership Deed or a copy of the Partnership Deed registered with the Registrar. (ii)A notarized or registered copy of Power of Attorney in favour of the individual to tender for the work, sign the agreement etc. and create liability against the firm.(iii)An undertaking by all partners of the partnership firm that they are not blacklisted or debarred by Railways or any other Ministry / Department of the Govt. of India from participation in tenders/contracts as on the date of submission of bids, either in their individual capacity or in any firm/LLP in which they were/are partners/members. Any concealment/wrong information in regard to above shall make the bid ineligible or the contract shall be determined under Clause 62 of the General Conditions of Contract.(iv)All other documents as mentioned in Para 18 of the tender form (second sheet) of IRSGCC-2022(Including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)
2.4	In case tenderer is a LLP Firm registered under LLP Act-2008, the following documents shall be submitted: (i)A copy of LLP Agreement (ii)A copy of Certificate of Incorporation (iii)A copy of Power of Attorney/Authorization issued by the LLP in favour of the individual to sign the tender on behalf of the LLP and create liability against the LLP. (iv)An undertaking by all partners of the LLP that they are not blacklisted or debarred by Railways or any other Ministry / Department of the Govt. of India from participation in tenders / contracts as on the date of submission of bids, either in their individual capacity or in any firm/LLP or JV in which they were / are partners/members. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the Standard General Conditions of Contract (v)All other documents in terms of Para 10 of Tender form(2nd sheet) of IRSGCC- April-2022 Part-I(Including upto ACS no.11). (vi) All other documents as per Clause 14 of IRSGCC -April -2022- Part I (including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)
2.5	In case the Tenderer is a Company registered under Companies Act-2013:-The tenderer(s) shall submit the following documents: (i)The copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company (ii)A copy of Certificate of Incorporation (iii)A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. (iv)An undertaking that the Company is not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as a member of the partnership firm or JV in which the Company was / is a partner/member. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract. (v)All other documents in terms of para 10 of tender form (2nd Sheet) of IRSGCC-2022(Including ACS no.11) (vi) All other documents as per Clause 14 of IRSGCC -April -2022- Part I(including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

2.6	In case the Tenderer is a Registered Society & Registered Trust, the following documents shall be submitted: (i)A copy of Certificate of Registration (ii)A copy of Memorandum of Association of Society / Trust Deed (iii)A copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust.(iv) A Copy of rules and regulations of the society (v)All other documents in terms of Para 10 of Tender form(2nd sheet) of IRSGCC- April-2022 Part-I(Including upto ACS no.11). (v) All other documents as per Clause 14 of IRSGCC -April -2022- Part-I(Including upto ACS no.11).	Yes	Yes	Allowed (Mandatory)
2.7	In case JV Firms are allowed to participate: JV firm should upload Memorandum of Understanding [MOU] as per the format attached as annexure to the tender in DOCUMENTS. Submission of all other documents by JV firm / Members of JV should also be as per Cl.No.17.14 of Part-I of IRSGCC-2022(Including upto ACS no.11)	Yes	Yes	Allowed (Mandatory)
3	Uploading of other relevant documents connected to the tender; such as Declaration regarding employment of Retired Engineer/ Retired Railway officer, NEFT Form, List of Personnel/Organization, List of Plant/ machinery, (As per the formats attached in the list of Documents whatever attached and remaining in their own format to be submitted)etc	No	No	Allowed (Optional)
4	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The successful bidder shall submit "Performance Guarantee" amounting to FIVE percent (5%) of contract value after award of the work. Note: If Bid quoted 5% below the advertised tender value, "Additional Performance Guarantee" amounting to FIVE percent (5%) of contract value shall be submitted after award of the work as per ACS No.11 of IRS GCC-2022.	No	No	Not Allowed
2	The General Conditions of Contract governing the performance of the works covered by this tender are the IRS GCC-2022 [including upto ACS no.11]. A soft copy of the Indian Railway Standard General conditions of Contract is uploaded in the attached documents to the tender for reference. Hard copy of IRSGCC (with up-to-date correction slip) may be perused in the office of the Chief Administrative Officer/ Construction/ South Central Railway / Secunderabad - 500071. The tenderer/s is/are deemed to have kept himself/themselves fully Informed of the provisions of the IRS General conditions of Contract including all corrections and Amendments issued up to date (as on date, IRS GCC-2022 upto ACS no.11 shall be considered) while submission of offer and any claim that he/they is/are not aware of any amendment or correction slip to the IRSGCC shall not be entertained.	No	No	Not Allowed

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

3	STUDY OF DRAWINGS AND LOCAL CONDITIONS: The drawings for the works can be seen in the office of the Chief Administrative Officer, Construction, S.C.Railway, Secunderabad - 500071 or in the office of the concerned field Deputy Chief Engineer / Construction / S.C.Railway . It should be noted that these drawings are meant for general guidance only and Railway may suitably modify them during the execution of work according to the circumstances without making the Railways liable for any claims on account of such changes. If there is any variation between the description in the tender and the detailed plans, the Engineer-in-Charge will operate the correct description and his decision is final and binding on the tenderer/ Contractor. The Tenderer/Contractor is required to inspect the sites of works and acquaint himself with the site conditions, availability of approaches for transporting of men and materials, space and other factors relating to the works, availability of labour, electricity and water, etc., before quoting his rates. The extent of lead and lift involved in the execution of works and any difficulties involved in the execution of work should also be examined before formulating the rates for complete items of works described in the schedule. The Tender submitted will be deemed to have been made after such inspection.	No	No	Not Allowed
4	DRAWINGS FOR WORKS: The percentage rates for the schedule items and itemized rates for the non-scheduled items quoted by the tenderer as may be accepted by the railways will, hold good irrespective of any changes, modifications, alterations, additions, omissions in the locations of structures and detailed drawings, specifications and/or the manner of executing the work. It should be specifically noted that some of the detailed drawings may not have been finalised by the Railway and will, therefore, be supplied to the contractor as and when they are finalised on demand. No compensation whatsoever on this account shall be payable by the Railway Administration. No claim whatsoever will be entertained by the Railway on account of any delay or hold up of the works arising out of delay in approval of drawings, changes, modifications, alterations, additions, omission and the site layout plans or detailed drawings and design and/or late supply of such material as are required to be arranged by the Railway or due to any other factor on Railway Accounts.	No	No	Not Allowed
5	Manual tenders, supporting documents etc., sent by Post/FAX/Courier or in Person SHALL NOT BE ACCEPTED.	No	No	Not Allowed
5.1	All requisite documents are to be properly submitted online only and the bidders should ensure that the content of the documents uploaded is distinctly legible/readable.	No	No	Not Allowed
6	CORRIGENDUM NOTICE ON IREPS: [I]Railway may modify the tender document by issuing online corrigendum through "www.ireps.gov.in" 15 days prior to the tender closing date. For the purpose of CORRIGENDUM in the tender, NIT period is splitted as under: (a) ADVERTISEMENT PERIOD: The time during which all information pertaining to tender shall be available but offers cannot be submitted (b) OFFER SUBMISSION PERIOD: 15 days prior to closing of tender, during which tenderers can submit their offer.	No	No	Not Allowed
7	If the Bid of a Tenderer is seriously unbalanced in relation to the Engineer's estimate of the cost of work to be performed under the contract, the Railways may require the tenderer to produce detailed price analysis for any or all items of the Tender Schedule, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed.	No	No	Not Allowed
8	Applicable for the tenders with eligibility criteria: The offer of Tenderer(s) who do not enclose Work Experience Certificate & Financial eligibility Certificate with requisite details, and supporting documents along with their Tender to establish their credentials shall be summarily rejected, even though they are working contractors or contractors on approved list.	No	No	Not Allowed
8.1	The offer shall be evaluated only from the certificates/documents submitted along with the tender offer.	No	No	Not Allowed

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

8.2	Any Certificate /Documents offered / submitted / received after the tender opening shall not be given any credit and shall not be considered.	No	No	Not Allowed
8.3	Attestation of documents may be self attested or attested by a Gazetted Officer.	No	No	Not Allowed
8.4	Railway reserves the right to verify the authenticity of the documents/information furnished.	No	No	Not Allowed
9	TAXES: if rates of existing GST or cess on GST for Works Contract is increased or any new tax /cess on Works Contract is imposed by Statute after the date of opening of tender but within the original date of completion/date of completion extended under clause 17 & 17A of Part-II of IRSGCC-2022 (including upto ACS no.11) and the Contractor thereupon properly pays such taxes/cess, the Contractor shall be reimbursed the amount so paid. Further, if rates of existing GST or cess on GST for Works Contract is decreased or any tax/cess on Works Contract is decreased / removed by Statute after the date of opening of tender, the reduction in tax amount shall be recovered from Contractor's bills/Security Deposit or any other dues of Contractor with the Government of India.	No	No	Not Allowed
10	This tender complies with PUBLIC PROCUREMENT POLICY ORDER-2017 dated 19.07.2024. Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	No	Not Allowed
11	Tenderer(s) shall note that conditional/alternate offer will not be considered and will summarily be rejected, even though such condition makes them as the lowest tenderer.	No	No	Not Allowed
12	After opening of the tender, any document pertaining to the constitution of sole proprietorship Firm/Partnership Firm/ Registered Company/ Registered Trust/ Registered Society/ HUF/LLP etc. shall be neither asked nor considered, if submitted. Further, no suo moto cognizance of any document available in public domain (i.e, on internet etc) or in Railway's record/office files etc. will be taken for consideration of the tender, if no such mention is available in the tender offer submitted{Asper clause no. 14(iv) Part I of IRSGCC 2022 including upto ACS no.11}	No	No	Not Allowed
13	As per clause no.5 part I of IRSGCC 2022 (including upto ACS no.11) the details of exemptions/discount of Bid Security payment is as follows:	No	No	Not Allowed
13.1	i) Any firm recognized by Department of Industrial Policy and Promotion (DIPP) as 'Startups' shall be exempted from payment of Bid Security.	No	No	Not Allowed
13.2	iii) Labour Cooperative Societies shall deposit only 50% of Bid Security as mentioned in the tender	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Bidders should carefully read all the conditions and the Special Conditions alongwith Special Conditions - General & Technical, which are annexed to the tender document in the DOCUMENTS attached to the tender. These special conditions form part of the tender document and will supplement to the conditions of IRSGCC-2022 [including upto ACS no.11]. Where the provisions of these special conditions are at variance with IRSGCC and other documents mentioned above, these Special Conditions shall prevail.	No	No	Not Allowed
2	IN CASE OF ADVERTISED TENDER VALUE IS MORE THAN RS. 10 CRORES, JOINT VENTURE (JV) FIRMS ARE ALSO CONSIDERED FOR ELIGIBILITY.	No	No	Not Allowed

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

3	IN CASE OF ADVERTISED TENDER VALUE IS MORE THAN RS.10 CRORES, The tender/technical bid will be evaluated based on bid capacity formula detailed as Annexure-VI of IRSGCC 2022 (including upto ACS no.11). NOTE: i)The Tenderer(s) shall furnish the details of existing commitments and balance amount of ongoing works with tenderer as per the prescribed proforma of Railway for statement of all works in progress and also the works which are awarded to tenderer but yet not started upto the date of opening of tender. In case of no works in hand, a 'NIL' statement should be furnished. This statement should be submitted duly verified by Chartered Accountant.(ii) The available bid capacity of tenderer shall be assessed based on the details submitted by the tenderer. In case, the available Bid Capacity is lesser than estimated cost of work put to tender, his offer shall not be considered even if he has been found eligible in other eligibility criteria/tender requirement. (iii) In case, the tenderer/s failed to submit the above statement along with offer, their/his offer shall be considered as incomplete and will be rejected summarily.	No	No	Not Allowed
4	This work involves measurement of works by contractor (cost of tender is more than Rs. 5 crs). Contractor has to make his own arrangements for recording measurements from time to time. No additional payments will be in this regard.	No	No	Not Allowed
5	The tenderer on successful award, while submitting its on-account/final bills, shall certify that the personnel who have been deployed under this contract are not in engagement with any other contract on full time basis. In correct/false declarations will be dealt as per agreement conditions (Authority : Railway Board letter No.2022/SD-II/22/01/4 Pt.1 dt.07-11-2022)	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed
2	[1]I/We have read the various conditions of the tender attached hereto and hereby agree to abide by the said conditions. I/We also agree to keep this tender open for acceptance for the period mentioned in the tender document [NIT HEADER] from the date fixed for opening the same and in default thereof, I/We will be liable for forfeiture of my/our Bid Security submitted. [2] I/We offer to do the work at the percentage rates quoted by me/us in the attached schedule and bind myself/ourselves to complete the work within the period of completion given in this tender document[NIT HEADER] from the date of issue of letter of acceptance of this tender. I/We also hereby agree to abide by the IRS GCC (including upto ACS no.11) and Special Conditions of contract and to carry out the works according to the IRU Standard Specifications for formation works, Bridge works and P.Way Works 2021 laid down by Indian Railway, CPWD Specifications 2020 for Horticulture, Land scaping and CPWD Specifications 2019 Volume 1 and Volume 2 laid down by Central Public Works Department, New Delhi for DSR-2023 items for the present contract. [3]. The full value of the earnest money paid shall stand forfeited without prejudice to any other rights or remedies of the railway if [a]I/We do not submit the Performance Guarantee within the time specified in the Tender document; [b] I/We do not execute the contract document within seven days after receipt of notice issued by the Railway that such documents are ready; and [c] I/We do not commence the work within fifteen days after receipt of orders to that effect. [4]. Until a formal agreement is prepared and executed, acceptance of this tender shall constitute a binding contract between us subject to modifications, as may be mutually agreed to between us and indicated in the letter of acceptance of my/our offer for this work.	No	No	Not Allowed

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

3	I/We understand that no post-tender correspondence will be entertained. However, if any clarification is required by the Railway, the same will be sought from the tenderer. Also, I/We are aware that any Certificate/ Documents offered after the tender opening shall not be given any credit and shall not be considered.	No	No	Not Allowed
4	I/we do hereby solemnly affirm and state on behalf of the tenderer including its constituents as under:	No	No	Not Allowed
4.1	[i] I/We the tenderer(s) am/are signing this document after carefully reading the contents. [ii]I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.[iii]I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us. [iv] I/We declare and certify that I/We have not made any misleading or false representation in the documents, forms, statements attached in proof of the qualification requirements. [v] I/We also understand that my/our offer will be evaluated based on the documents/credentials uploaded along with the offer and the same shall be binding upon me/us. [vi] I/We declare that the information and the documents attached alongwith the tender by me/us are correct and I/We are fully responsible for the correctness of the information and the documents submitted by us.	No	No	Not Allowed
5	I/We indemnify and save harmless the Railway from and against all actions, suit proceedings losses, costs, damages, charges, claims and demands of every nature and description brought or recovered against the Railways by reason of any act or omission of the Contractor, his agents or employees, in the execution of the works or in his guarding of the same. All sums payable by way of compensation under any of these conditions shall be considered as reasonable compensation to be applied to the actual loss or damage sustained, and whether or not any damage shall have been sustained.	No	No	Not Allowed
6	I/We are aware that: Should the Railway decide to negotiate with a view to bring down the rates, the tenderer called for negotiations should furnish the following form of declaration before commencement of negotiations. I/We ----- do declare that in the event of failure of contemplated negotiations relating to Tender No., dt..... Item No. opened on dt:..... my original tender shall remain open for acceptance on its original terms and condition. I also declare that I am aware that during this negotiations, I cannot increase the originally quoted rates against any of the individual items and that in the event of my doing so the same would not be considered at all i.e., reduction in rates during negotiation alone would be considered and for some items if I/we increase the rates, the same would not be considered and in lieu my originally quoted rates alone would be considered and my offer would be evaluated accordingly. I/We are also aware that the validity of such negotiated offer will be 30 days from the date of negotiations or the validity of original offer, whichever is later.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	IRGCC-2022-uptoACS-11updated-13.03.2026.pdf	IRGCC2022 with ACS11
2	ACS11toGCC.pdf	ACS11 IRGCC
3	DETAILSOFPERSONNELPLANTANDMACHINERYWORKSONHANDFORMATS.pdf	Details of personnel
4	EMPLOYMNTOFRETIREDRAILWAYOFFICERSCERTIFICATEFORMAT.pdf	employment of retired officers

**SCR-CONST-HQ-ENGG/SOUTH CENTRAL RLY
TENDER DOCUMENT**

Tender No: 29-CAO-C-SC-2026

Closing Date/Time: 30/06/2026 15:00

5	26.02.2026_RevisedApprovedlistofBrands.pdf	Approved brands
6	AFFIDAVIT_ANNEXURE-Vwith_ACS-4_GCC-2022.pdf	affidavit
7	Agt_format_for_JV_withACS-3_GCC-2022.pdf	agr format
8	FormatforBankGuarantee11.10.2019ver-2.pdf	BG format
9	MOUFormatforJVfirms_1.pdf	MOU for JV
10	NEFT_FORM_GCC_2022.pdf	NEFT form
11	PROFORMA_for_BIDCAPACITYcorrected22.08.2022.pdf	bid capacity proforma
12	PublicProcurementPolicy19.07.2024.pdf	public procerment policy
13	SpecialConditions-Measurementofworksbycontractor28.08.21-Ver-1.pdf	contractor measurement
14	SPECIALCONDITIONSTECHNICAL_1.pdf	special tech cond
15	SPLCONDITIONSTECHNICALOWG.pdf	special tech cond OWG
16	TSSpecialConditionsGeneralwithIRGCC-2022.pdf	TS special general conditions
17	Repliestoqueries_RORDKJ.pdf	Replies to queries
18	CorrectedRORconditions.pdf	Mile stone for RORDKJ Viaduct
19	scheduleofbiddingprocess.pdf	schedule of bidding process
20	proformaforBGforBidsecurity.pdf	BG format for BidSecurity

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: ANIL KUMAR ADEPU

Designation : Dy.CE/C/PIg/SC